AGENDA PACKET

AUGUST 15, 2023 MEETING

<u>Part 1 of 2</u>

	CAL#	PAGE
AGENDA		2
LEWISBORO COMMONS (WILDER BALTER), 100 BEEKMAN LANE, GOLDENS BRIDGE	Cal #10-15 PB	Cal #20-17WP
Town Board Resolution, dated July 24, 2023	Cal #5-17SW	4
Public hearing materials		5
WACCABUC COUNTRY CLUB PICKLEBALL COURTS, 74 MEAD STREET, WACCABUC	Cal #01-23PB	
Cover letter from Insite Engineering, dated July 25, 2023		11
Planning Board and Stormwater applications, dated July 25, 2023		14
NOI, undated		18
Site plan, Insite Engineering, dated July 25, 2023		34
MERCHAN AND VALENCIA RESIDENCE, 1324 ROUTE 35, SOUTH SALEM	Cal #02-23WV	
No new materials		-
BERNABO VACANT LAND, 96 POST OFFICE ROAD, WACCABUC	Cal #29-23WP	Cal #09-23SW
Kellard Sessions review memo, dated August 10, 2023		36
CAC review memo, dated August 7, 2023		41
Wetland and Stormwater applications, dated June 26, 2023		42
Site plan, P.W. Scott Engineering & Architecture, dated May 25, 2023		64
Architectural drawings, SD Design, dated June 28, 2023		65
Engineering plans, P.W. Scott Engineering & Architecture, dated May 8, 2023		66
IRSP, P.W. Scott Engineering & Architecture, dated March 28, 2023		68
Septic plan and report, P.W. Scott Engineering & Architecture, dated May 8, 2023		176

TOWN OF LEWISBORO Westchester County, New York



Tel: (914) 763-5592 Fax: (914) 875-9148 Email: planning@lewisborogov.com

Planning Board 79 Bouton Road South Salem, New York 10590

AGENDA

Tuesday, August 15, 2023

Courtroom at 79 Bouton Road

Meeting will start at 7:30 p.m. and end at or before 11:00 p.m.

I. PUBLIC HEARING

Cal #10-15 PB, Cal #20-17WP, Cal #5-17SW

Lewisboro Commons (Wilder Balter), 100 Beekman Lane, Goldens Bridge, NY 10526; Sheet 5, Block 10776, Lots 19, 20 & 21 (Lewisboro Commons Housing Development Fund Co., Inc., owner of record) - Request for a partial release of the apartments' construction performance bond.

II. SITE DEVELOPMENT PLAN REVIEW

Cal #01-23PB, Cal #11-23SW

Waccabuc Country Club pickleball courts, 74 Mead Street, Waccabuc, NY 10597; Sheet 22, Block 10802, Lot 23 (Waccabuc Country Club Co., owner of record) - Application for a Waiver of Site Development Plan Procedures for the installation of four pickleball courts on an existing residence's tennis court.

III. WETLAND PERMIT REVIEWS

Cal #22-23WP, Cal #02-23WV

Merchan and Valencia Residence, 1324 Route 35, South Salem, NY 10590; Sheet 39, Block 10543, Lot 22 (Lina Merchan and Fabio Valencia, owners of record)

Cal #29-23WP, Cal #09-23SW

Bernabo vacant land, 96 Post Office Road, Waccabuc, NY 10597; Sheet 25, Block 10812, Lot 3; (Alex Bernabo, owner of record) – Application for a new well, septic and house.

Cal #30-23WP

Bisset Residence, 65 Lake Shore Drive, South Salem, NY 10590; Sheet 36G, Block 11174, Lot 3 (Patricia & Paul Bisset, owners of record) – Application for a new patio and walls, walkways

Cal #31-23WP

Long Pond Preserve channel, 0 Tarry-A-Bit Drive, Waccabuc, NY 10597; Sheet 22, Block 11155, Lots 143 & 145 and Sheet 25, Block 11155 Lot 139 (Three Lakes Council, owner of record) – Application for an East of Hudson Watershed Corporation stormwater retrofit/channel stabilization project on Long Pond Preserve.

IV. SPECIAL USE PERMIT

Cal #02-10PB

Bedford Audubon Society, 35 Todd Road, Katonah, NY 10536; Sheet 5, Block 10776, Lots 7 & 30 and Sheet 5, Block 10777, Lot 3 (Bedford Audubon Society, owner of record)– Application for the renewal of a Special Use Permit or a private nature preserve.

V. SITE VISIT REPORT

<u>Cal #26-23WP</u>

Scott's Dam Reservoir Rehabilitation, 0 Wakeman Road, South Salem, NY 10590; Sheet 47, Block 10057, Lot 11 (Norwalk City First Taxing District, owner of record) - Application for dam improvements and a temporary accessway.

VI. CORRESPONDENCE

Delaware County Department of Planning and Watershed Affairs – Lead Agency Notification for land acquisition in the EOH and WOH water sheds.

Ridgefield, CT Planning and Zoning Commission to amend its Town Code § 2.2 - renewable energy systems.

- VII. MINUTES OF July 18, 2023.
- VIII. NEXT MEETING DATE: September 19, 2023.
- IX. ADJOURN MEETING.

RESOLUTION ADOPTED BY THE TOWN BOARD OF THE TOWN OF LEWISBORO AT A MEETING HELD ON JULY 24, 2023

RESOLVED, that the Town Board authorizes the Planning Board to hold a public hearing and act upon Insite Engineering's request for a partial release of a performance security in connection with Lewisboro Commons.

STATE OF NEW YORK COUNTY OF WESTCHESTER

I, JANET L. DONOHUE, Town Clerk of the Town of Lewisboro, County of Westchester, State of New York, do hereby certify that I have compared the preceding copy of a Resolution adopted by the Town Board of the Town of Lewisboro at a meeting held on the 24th day of July, 2023, to the original thereof, and that the same is a true and exact copy of said original and of the whole thereof.

Town Clerk

Dated at South Salem, New York this 25th day of July, 2023

Affidavit of Proof of Mailing

The undersigned being duly sworn deposes and says: I, <u>Christopher Hahn</u> being over 18 years of age, work at <u>WBP Development LLC</u>. On <u>Suly 27,2023</u>, deponent mailed the attached notice of a public hearing (ATTACH A COPY OF NOTICE LETTER) for <u>HSO Barford Rod</u> <u>Chapping NY 10579</u> (application address) before the Town of Lewisboro attached as Exhibit A, to the following individuals and organizations, attached, as Exhibit B, by depositing a true copy of the aforesaid documents in a post-paid properly addressed envelope for delivery to a United States Postal Service Post Office.

his John

Signature

christophe Hehn

Print

State of New York) County of Westchester)

Sworn to before me this $2\eta^{4}h$

July 2023 ... Manstron Q. Cuser Day of _ Notary Public (

Christine A. Crisci Notary Public, State of New York LIC # 01CR6365109 Qualified in Westchester County Comm. Exp. September 25, 20 35

TOWN OF LEWISBORO NOTICE OF PUBLIC HEARING

NOTICE IS HEREBY GIVEN that the Planning Board of the Town of Lewisboro,

Westchester County, New York will convene a Public Hearing on Tuesday, August 15, 2023 at 7:30 p.m., or soon thereafter at the Town Offices at 79 Bouton Road, South Salem, New York, regarding the following:

Cal #10-15 PB, Cal #20-17WP, Cal #5-17SW

Request for partial release of a performance security posted by Wilder Balter Partners; Route 22 and Beekman Lane, Goldens Bridge, NY 10526; Sheet 5, Block 10776, Lots 19, 20 & 21 (Lewisboro Commons Housing Development Fund Co., Inc.; owner of record) established to guarantee the completion of infrastructure associated with a 42-unit multifamily residential development. The subject property consists of approximately 35.4 acres and is located within R-4A One-Family Residential and CC-20 Campus Commercial Districts.

A copy of materials pertaining to the requested partial release of the performance security may be inspected at the office of the Planning Board Administrator, 79 Bouton Road, South Salem, New York during regular Planning Board hours. Persons wishing to object to this request should file a notice of objection with the Planning Board together with a statement of the grounds of objection prior to the closing of the Public Hearing. All interested parties are encouraged to attend the Public Hearing and all will be provided an opportunity to be heard.

> PLANNING BOARD TOWN OF LEWISBORO By: Janet Andersen Chair

Dated: July 25, 2023

The Town of Lewisboro is committed to equal access for all citizens. Anyone needing accommodations to attend or participate in this meeting is encouraged to notify the Administrator to the Planning Board in advance.





P-1 Affidavit of Exemption to Show Specific Proof of Workers' Compensation Insurance coverage for a 1, 2, 3 of 4 Family, Owner-Occupied Residence (mus meet orten specified in the affidavit – does not require submittal to Compensation Board – MUST BE SUBMITTED FOR EACH PERMIT)

Except for the BP-1 form, all forms are valid for the coverage period shown, one year from the date of the Workers' Companisation Board stamp or, in the absence of either, one year from the date of the signed document.

Copy of the BP-4 exemption affidavit form is attached for your convenience.

Village office personnel are not permitted to assist you in completing any andavit

Affidavit of Public Hearing Notice

In the matter of an application for a Partial Performance Bond Release by WB Lewisboro LLC in the Town of Lewisboro, New York and Designated on the official tax map as Sheet 5, Block 10776, Lots 19, 20 & 21.

The undersigned being duly sworn deposes and says: I, <u>Christopher</u> Hahn, being over 18 years of age, work at <u>WBP</u> <u>Development LLC</u>. On <u>8/8/23</u>, deponent posted the sign provided by the Town of Lewisboro Planning

Department for the public hearing for Lewisboro Commons.

Ten tak

Signature

Hshn

Print

State of New York)County of Westchester)

Sworn to before me this δ Day of August Elizabeth D George Notary Public, State of New York Notary Public LIC # 01GE6365190 Qualified in Putnam County Commission Exp. Oct 2, 20

COMING SOON · LEWISBORO COMMONS 42-UNIT MULTIFAMILY AFFORDABLE COMMUNITY



and I



NOTICE

This property is the subject of an application before the Lewisboro Planning Board. A public hearing has been scheduled at which time all interested parties will be afforded an opportunity to be heard.

Please contact the Planning Board Secretary at 914-763-5592 or visit

www.lewisborogov.com for additional information

(Total)



July 25, 2023

Town of Lewisboro Planning Board 79 Bouton Road South Salem, NY 10590

RE: Waccabuc Country Club Pickleball 74 Mead Street Waccabuc, NY TM# Block 42.2, Lot 1, Sheet 10

Dear Chair Anderson and Members of the Board:

Please find enclosed four (4) copies of the following plans and documents in support of an application for site development plan approval and stormwater permit approval the above referenced project:

- Stormwater Permit Application, dated July 18, 2023.
- Site Development Plan Application, dated July 18, 2023.
- Affidavit of Ownership.
- SP-1 Site Plan, last revised July 25, 2023.
- SP-2 Erosion & Sediment Control Plan & Details, last revised July 25, 2023.
- Draft NYSDEC Notice of Intent.
- Draft MS4 SWPPP Acceptance Form.

To be provided under separate cover:

• Check for \$865.00 for Step1 and Step 2 application fee and stormwater permit fee, under separate cover.

Based on discussion with the Board at their July 18, 2023 meeting, the grading of the berm has been clarified, additional information has been added on the site plans and the applications for Step 1 and Step 2 Site Development Plan Approval and Stormwater Permit have been prepared for the project and included as part of this submission package.

Based on comments from the Jan Johannessen, AICP from Kellard Sessions memorandum dated July 13, 2023, we offer the following:

Required Approvals and Referrals

- 1. We defer to the Building Inspector for whether this application requires site plan approval by the Planning Board. As requested, the Site Development Plan Application Step 1 and Step 2 has been prepared and included as part of this submission with the requisite fees. Unless waived by the Planning Board, a public hearing is required to be held on the Site Development Plan.
- 2. It is acknowledged that a Town Stormwater Permit is required from the Planning Board.

- 3. The applicant reviewed the project with the ACARC on March 15, 2023 and received their approval for the project plan. Based on discussion at the meeting, we have confirmed that the proposed improvements are greater than 400 feet from the front lot line, therefore, it is our understanding that we do not need to go back to the ACARC.
- 4. The Zoning Board of Appeals has approved the expansion of a nonconforming use and two (2) area variances for the project.
- 5. It is understood that coverage under NYSDEC SPDES General Permit for Stormwater Discharges from Construction Activity (GP-0-20-001) will be required.

Comments

- 1. It is understood that this project requires the filing of a Notice of Intent (NOI) and MS4 Acceptance Form with the NYSDEC. A Town Stormwater Permit application has been provided with this submission and draft copies of the NOI and SWPPP Acceptance Form have also been provided for review.
- 2. Drawing SP-1 has been updated to provide a grass swale between the court and the berm, with relevant spot elevations to clarify how the area will be drained.
- 3. All proposed silt fencing has been incorporated within the limits of land disturbance; the soil stockpile is also located within the limits of disturbance.
- 4. The stabilized construction entrance as shown on the Enlarged Site Plan now conforms to our detail.
- 5. A note has been added to the Drawing SP-1 stating that all soil imported to the site shall constitute unrestricted clean fill, free of non-soil constituent. A signed soil manifest for any imported soil shall be provided to the Town.
- 6. Drawing SP-1 has been updated to include a photo of the privacy fence on the Fisher property at 68 Mead Street. In addition, the fence detail has been updated to note the color and reference the photo of the neighbor's fence.
- 7. The proposed improvements are greater than 400' from the front property line, as depicted on Drawing SP-1, therefore we believe we do not need to return to the Architecture and Community Appearance Review Council.
- 8. It is understood that the Building Inspector will need to confirm whether the application still qualifies for a Waiver of Site Development Plan Procedures, with the needed variances and incorporation of a landscaping berm. As requested, the applicant has submitted Steps 1 and 2 of the Site Plan Application. It is understood that the Planning Board may still elect to waive a public hearing. As noted at the July 18th, 2023 meeting by their shared attorney, the two eastern, adjacent neighbors have no objection to the current plan.

We look forward to meeting with the Board at their August 15, 2023 meeting. It is our understanding that a resolution of approval will be drafted for that meeting. We respectfully request approval of the Stormwater Permit for the project, Site Development Plan Approval if the Building Inspector determines that it is still required and a waiver of public hearing.

Should you have any questions or comments regarding this information, please feel free to contact our office.

Very truly yours,

INSITE ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C.

By:

Zachary M. Pearson, PE Principal Engineer

ZMP/dlm/sr

Enclosures

cc: Michael Sirignano, Esq., via email John Assumma, via email

Insite File No. 23105.100

TOWN OF LEWISBORO PLANNING BOARD

.

Site Development Plan/Subdivision Plat Application - Check all that apply:

Waiver of Site Development Plan ProceduresStep ISite Development Plan ApprovalStep ISpecial Use Permit ApprovalStep ISubdivision Plat ApprovalStep IStep IStep I	Step III
Project Information	
Project Name:	
Project Address:74 Mead Street, Waccabuc, NY	
Gross Parcel Area: ^{6,1 AC +/-} Zoning District: <u>R-4A</u> Sheet(s): ^{42,2}	Block (s): 1 Lot(s): 10
Project Description: -resurfacing the existing asphalt, infilling asphalt at the corners of th south sides of the existing court perimeter fence. To mitigate sound on the east, south, and west sides of the courts. A 6' high privacy fr constructed on top of the berm. A proposed wood chip path will lea pickleball courts.	urt into (4) pickleball courts. This will include ne court and installing wind cloth on the east and d, a 3' - 6' high earthen berm will be constructed fence with noise dampening fabric will be ad from the neighboring Club property to the
s the site located within 500 feet of any Town boundary? s the site located within the New York City Watershed? s the site located on a State or County Highway?	YES NO V YES NO V YES NO V
Does the proposed action require any other permits/approvals from other agencies/ Town Board ZBA Set Building Dept. ACARC Set NYSDEC NYCDEP NYSDOT Town Wetland Town Stormwate	/departments? Town Highway WCDH
Other	
wner's Information	•
ame: Waccabuc Country Club Email:	dassumma extention
ddress: 90 Mead Street, PO Box 400, Waccabuc NY 10597	Phone: 914-763-3144
oplicant's Information (if different)	
ame: same as owner Email	
ldress:	Phone:
uthorized Agent's Information	
ime: Zachary Pearson, P.E. Senior Project Engineer Email: zpearson@	@insite-eng.com
dress: "Insite Engineering, Surveying, and Landscape Architecture, P.C., 3 Garrett Place, Carm 10512	nel, NY Phone: 845-225-9690 —
THE APPLICANT understands that any application is considered complete only when all information and received by the Planning Board. The applicant further understands that the applicant is responsible for incurred by the Planning Board.	d documents required have been submitted and the payment of all application and review fees
THE UNDERSIGNED WARRANTS the fruth of all statements contained herein and in all supporting docu and belief, and authorizes visitation and inspection of the subject property by the Town of Lewisboro an	ments according to the best of his/her knowledge nd its agents.
APPLICANT'S SIGNATURE TOP & MULLING	DATE 7-18-2023
DWNER'S SIGNATURE THE DE AMUNING	DATE 7-18-2023

TOWN OF LEWISBORO PLANNING BOARD

÷

79 Bouton Road, South Salem, NY 10590 Email: planning@lewisborogov.com Tel: (914) 763-5592 Fax: (914) 875-9148

Affidavit of Ownership

State of: New Costo
County of:
JOHN D. ASSUMMA , being duly sworn, deposes and says that he/she
resides at
in the County ofWESTCHESTERState ofState ofYOR
and that he/she is (check one) \checkmark the owner, or \Box the
Name of corporation, partnership, or other legal entity
which is the owner, in fee of all that certain log, piece or parcel of land situated, lying and being in the
Town of Lewisboro, New York, aforesaid and know and designated on the Tax Map in the Town of
Lewisboro as:
Block <u>42.2</u> , Lot <u>1</u> , on Sheet <u>10</u> .
Joh D. Alunnus owner's Signature GENERAL MANIAGED
Sworn to before me this
<u>18</u> day of July , 2023
NOTARY PUBLIC, State of New York
Notary Public Condition Stand Dian. 31, 20

TOWN OF LEWISBORO PLANNING BOARD

79 Bouton Road, South Salem, NY 10590 Email: <u>planning@lewishorogov.com</u> Tel: (914) 763-5592 Fax: (914) 875-9148

Tax Payment Affidavit Requirement

This form must accompany all applications to the Planning Board.

Under regulations adopted by the Town of Lewisboro, the Planning Board may not accept any application unless an affidavit from the Town of Lewisboro Receiver of Taxes is on file in the Planning Board office. The affidavit must show that all amounts due to the Town of Lewisboro as real estate taxes and special assessments on the total area encompassed by the application, together with all penalties and interest thereon, have been paid.

Under New York State law, the Westchester County Clerk may not accept any subdivision map for filing unless the same type of affidavit from the Town of Lewisboro Receiver of Taxes is submitted by the applicant at the time of filing.

This form must be completed by the applicant and must accompany all applications to the Planning Board. Upon receipt, the Planning Board Secretary will send the form to the Receiver of Taxes for signature and notarization. If preferred, the applicant may directly obtain the signature of the Receiver of Taxes and notarization prior to submission.

То	Be Completed by Applicant (Please type or print)		
Waccabuc Country Club Compe	Project Name	Courts	
Property Description : 74 Neod Sheelv	Property Assessed to:		
Tax Block(s): <u>1080え</u>	Warcobuc Coup	fry Club	
Tax Lot(s): <u>23</u>	PO Box 400	ı 	
Tax Sheet(s): J J	City	New York State	(0597 Zip

The undersigned, being duly sworn deposes and says that a search of the tax records in the office of the Receiver of Taxes, Town of Lewisboro, reveals that all amounts due to the Town of Lewisboro as real estate taxes and special assessments, together with all penalties and interest thereon, affecting the premises described below, have been paid.

Signature - Receiver of Taxes: Sworn to before me this JANET L. DONOHUE NOTARY PUBLIC, STATE OF NEW YORK No. 01DC6259627 Qualified in Westchester County Commission Expires April 16, 202 Signature - Notary Public (affix stamp)

	Application No.:
	Fee: Date:
TOWN OF LEWISBORG	0
STORMWATER PERMIT APPL	ICATION
79 Bouton Road, South Salem,	NY 10590
Phone: (914) 763-5592	2
Fax: (914) 875-9148	
Project Address: 74 Mead St, Waccabuc, NY 10597	
Sheet: Block: _1 Lot(s): _10	
Project Description (describe overall project including all propo	sed land development activities):
Waccabuc Country Club proposes to convert an existing tennis court in	to (4) pickleball courts. This will include resurfacing th
existing asphalt, infilling asphalt at the corners of the court and installing	ig wind cloth on the east and south sides of the existing
court perimeter fence. To mitigate sound, a 3' - 6' high earthen berm wi	ill be constructed on the east, south, and west sides of
the courts, A 6' high privacy fence with noise dampening fabric will be c	constructed on top of the berm. A proposed wood chip
path will lead from the neighboring Club property to the pickleball courts	s. Adama and antialing and
	jaassumme optortline net
Owner's Address: 90 Mead Street, PO Box 400, Waccabuc, NY 10597	Email:
Applicant's Name (if different): same as owner	Phone:
Applicant's Address:	Email:
Zachary Pearson, P.E. Senior Project	Phone: (BAE) and occo
	_ 11016: (845) 225-9690
Agent's Address, Insite Engineering, Surveying, and Landscape	En este de la companya de la company
Agent's Address: Architecture, P.C., 3 Garrett Place, Carmel, NY 10512	Email: _zpearson@insite-eng.com
TO BE COMPLETED BY OWNER/A	APPLICANT
The approval authority is? (see §189-5 of the Town Code)	
Town Engineer and Stormwater Managem	ent Officer Planning Board
Is the project located within the NYCDEP Watershed? Yes	No
Total area of proposed disturbance: ビ 5,000 s.f < 1 acre	≥1 acre

Will the project require coverage under the NYSDEC General Permit for Stormwater Discharges from Construction Activity? Yes D No D Requires post-construction stormwater practice

Does the proposed action require any other permits/approvals from other agencies/departments? (Wetland Inspector, Planning Board, Town Board, Zoning Board of Appeals, Building Department, Town Highway, ACARC, NYSDEC, NYCDEP, WCDOH, NYSDOT, etc): Identify all other permits/approvals required: ^{ZBA}, Building Dept., ACARC, NYSDEC

Note: The applicant, owner and/or agent is responsible for reviewing and complying with Chapter 189, "Stormwater Management and Erosion and Sediment Control," of the Town Code. This application must be submitted with all applicable plans, reports and documentation specified under §189-B, "SWPPP requirements," of the Town Code; all SWPPP's shall be prepared in conformance with Chapter 189 and shall be prepared by a qualified professional, as defined therein. The provision for obtaining a Town Stormwater Permit is in addition to the requirement of obtaining coverage under the SPDES General Permit for Stormwater Discharges from Construction Activity, if applicable."

Owner Signature:

uno

Date: 7-18-2023

NOTICE OF INTENT



New York State Department of Environmental Conservation

Division of Water

625 Broadway, 4th Floor



Albany, New York 12233-3505

Stormwater Discharges Associated with <u>Construction Activity</u> Under State Pollutant Discharge Elimination System (SPDES) General Permit # GP-0-20-001 All sections must be completed unless otherwise noted. Failure to complete all items may result in this form being returned to you, thereby delaying your coverage under this General Permit. Applicants must read and understand the conditions of the permit and prepare a Stormwater Pollution Prevention Plan prior to submitting this NOI. Applicants are responsible for identifying and obtaining other DEC permits that may be required.

-IMPORTANT-

RETURN THIS FORM TO THE ADDRESS ABOVE

OWNER/OPERATOR MUST SIGN FORM

	Owner/Operator Information																																				
Owne	r/C	pe	ra	toi	<u>(</u>	Co	mpa	any	7 N	Iam	e/I	Pri	va	te	٥v	me	r	Nai	me/	Mu	nic	cip	pal	it	y 1	Jan	ie)			_				1			
Wa	C	С	a	b	u	С		С	0	u	n	t	r	У		C	1	u	b																		
Owne	Dwner/Operator Contact Person Last Name (NOT CONSULTANT)																																				
As	S	u	m	a																																	
Owne	Owner/Operator Contact Person First Name																																				
JC	h	n																																			
Owne	r/C	pe	ra	toi		lai	lir	ng	Ad	ldr	ess	3	1 1			1	1	1	1	r	1		1	r	1	1	1	-	1	-	1	r	1	1	1	 	
90		М	e	a	d		S	t	r	e	е	t																									
City		1				1	1	1		1	1	1						1		1	1		1	1		1				1		1		1	1		
Wa	C	C	a	d	u	С																															
Stat N Y	e					ip L () 5	5 9) 7	7 -	. [
Dhor		01-1	no	r 10			tor	~)						Г.		(01		م <i>د</i> ا	(O D	020	nt o	r)															
9 1	4] -	7	6	3	-	3	1	4	4]			[_																
Emai	1 (Ow	ne	r/(pe	era	tor	<u>-</u>)		1										1				1				1	1	_					1		
jd	a	S	S	u	m	a	@	0	p	t	0	n	1	i	n	e	·	n	e	t																	
FED	FED TAX ID																																				
	- (not required for individuals)																																				
																																				_	

Project Site Informa	ation
Project/Site Name W a c c a b u c C o u n t r y C l u b P	i c k l e b a l l
Street Address (NOT P.O. BOX) 7 4 M e a d S t r e e t i	
Side of Street O North O South O East Ø West	
City/Town/Village (THAT ISSUES BUILDING PERMIT)	
State Zip County N Y 1 0 5 9 7 - Westches	ter
Name of Nearest Cross Street	
Distance to Nearest Cross Street (Feet)	Project In Relation to Cross Street O North O South O East Ø West
Tax Map Numbers Section-Block-Parcel	Tax Map Numbers

1. Provide the Geographic Coordinates for the project site in NYTM Units. To do this you **must** go to the NYSDEC Stormwater Interactive Map on the DEC website at:

www.dec.ny.gov/imsmaps/stormwater/viewer.htm

Zoom into your Project Location such that you can accurately click on the centroid of your site. Once you have located your project site, go to the tool boxes on the top and choose "i"(identify). Then click on the center of your site and a new window containing the X, Y coordinates in UTM will pop up. Transcribe these coordinates into the boxes below. For problems with the interactive map use the help function.

х	Coo	rdi	rdinates (Eas							
	6	1	7	5	9	5				

чc	loor	dina	(N	ortł	ning)	
4	5	7	1	6	8	5	

2. What is the nature of this construction project?
O New Construction
Redevelopment with increase in impervious area
Chedevelopment with increase in impervious area
@ Redevelopment with no increase in impervious area
e Redevelopment with no increase in impervious area

3. Select the predominant land use for SELECT ONLY ONE CHOICE FOR EACH	both pre and post development conditions.
Pre-Development Existing Land Use	Post-Development Future Land Use
⊖ FOREST	○ SINGLE FAMILY HOME Number of Lots
\bigcirc PASTURE/OPEN LAND	○ SINGLE FAMILY SUBDIVISION
\bigcirc Cultivated Land	○ TOWN HOME RESIDENTIAL
\bigcirc SINGLE FAMILY HOME	○ MULTIFAMILY RESIDENTIAL
\bigcirc SINGLE FAMILY SUBDIVISION	○ INSTITUTIONAL/SCHOOL
\bigcirc TOWN HOME RESIDENTIAL	\bigcirc INDUSTRIAL
\bigcirc MULTIFAMILY RESIDENTIAL	○ COMMERCIAL
\bigcirc INSTITUTIONAL/SCHOOL	○ MUNICIPAL
\bigcirc INDUSTRIAL	○ ROAD/HIGHWAY
○ COMMERCIAL	© RECREATIONAL/SPORTS FIELD
\bigcirc ROAD/HIGHWAY	○ BIKE PATH/TRAIL
⑦ RECREATIONAL/SPORTS FIELD	\bigcirc LINEAR UTILITY (water, sewer, gas, etc.)
○ BIKE PATH/TRAIL	○ PARKING LOT
\bigcirc LINEAR UTILITY	○ CLEARING/GRADING ONLY
\bigcirc PARKING LOT	\bigcirc DEMOLITION, NO REDEVELOPMENT
○ OTHER	○ WELL DRILLING ACTIVITY *(Oil, Gas, etc.)

*Note: for gas well drilling, non-high volume hydraulic fractured wells only

4.	In accordance with the larger enter the total project site a existing impervious area to be activities); and the future in disturbed area. (Round to the	common plan of development or sa area; the total area to be distu- e disturbed (for redevelopment apervious area constructed withis nearest tenth of an acre.)	ale, rbed; n the
	Total Site AreaTotal Area61	Co Existing Impervious d Area To Be Disturbed 3 0.1	Future Impervious Area Within Disturbed Area
5.	Do you plan to disturb more t	nan 5 acres of soil at any one t	ime? Yes 'No
6.	Indicate the percentage of ear B	ch Hydrologic Soil Group(HSG) at c D % 1 0 %	the site.
7.	Is this a phased project?		⊖Yes ⊘No
8.	Enter the planned start and e dates of the disturbance activities.	$\begin{array}{c} \text{Start Date} \\ \hline 0 & 8 \\ \end{array} / \begin{array}{c} 0 & 1 \\ \end{array} / \begin{array}{c} 2 & 0 \\ \end{array} 2 & 3 \\ \end{array} - \end{array}$	End Date 0 9 / 3 0 / 2 0 2 3

9.	I	den	tify	the	e n	eai	res	st	sur	fa	ce	wat	ce	rbc	bdy	/(i	.es	5)	to	wł	nic	ch	cc	ons	sti	ru	ct	io	n	si	.te	r	run	of	f	wi	11		
Nam	a	isci	large	•																																			
T	0	w r	. c	f		L	e	w	i	s	b	01	:	0		W	е	t	1	a	n	d									Τ								
																													<u> </u>		Ť								
													_		_													L	_										
9a	ι.	Ty	vpe o	fw	ate	erk	bod	y :	ide	ent	if	ied	i	n Q	jue	st	io	n	9?																				
	V	Vetl	and	/ S	tat	e	Jui	ris	sdi	ct	ior	n Or		Sit	е	(A:	ns	we	r !	9b)																			
	V	Vetl	and	/ S	tat	e	Jui	ris	sdi	ct	ior	n Of	f	Si	te																								
	V	Vetl	and	/ F	ede	era	11	Jur	is	dio	cti	ion	01	n S	it	е	(A:	ns	we:	r 9	b)																		
	V	Vetl	and	/ F	ede	era	13	Jur	is	dio	cti	ion	01	££	Si	te																							
	S	Stre	am /	Cr	eek	c 0	n s	Sit	e																														
	S	Stre	am /	Cr	eek	s 0	ff	Si	te																														
	F	Rive	r On	Si	te														01-			·	_			- 1-			. 7		-7				£ !	10	-		
	F	Rive	r Of:	E S	ite	9													90	••	H	low	W	as	5 T		3	we	τı	ar	la	10	len	.t1	I1(ea	?		
	I	lake	On s	Sit	е																F	Reg	u]	Lat	203	ry	М	ap											
	I	Lake	Off	Si	te																/ I	Del	ir	nea	at	ed	b	У	Co	ns	sul	ta	ant						
	C)the	r Tyj	pe	On	Si	te														Γ	Del	ir	iea	at	ed	b	У	Ar	my	γ C	lo1	rps	s c	f	En	gir	iee	rs
)the	r Tyj	pe	Off	E S	ite	e)th	.er	-	(i)	de	nt	if	y)										
10	•	На 3(as th)3(d)	e s se	uri egme	fac ent	ce ti	wat n <i>i</i>	ter App	bo	dy di:	(ies x E	3) 0	in f G	ıç P-	ine 0-	st 20	io -0	n 01	9 k ?	bee	en	ic	ler	nt:	if	ie	d	as	ē	L		0	Ye	s) No	5	
11	•	I: Ap	s thi opend	s p ix	c o	jec of	ct GP	100	cat -20	ed)-0	01	n or ?	ne	of	t	he	W	lat	er	she	eds	s i	de	ent	:i:	Ei	ed	i	n				Ø	Ye	es	() No	D	

12.	Is the project located in one of the watershed		
	areas associated with AA and AA-S classified	🕑 Yes	\bigcirc No
	waters?		
	If no, skip question 13.		

13.	Does this construction activity disturb land with no existing impervious cover and where the Soil Slope Phase is identified as an E or F on the USDA Soil Survey? If Yes, what is the acreage to be disturbed?	\bigcirc Yes	Ø No

14.	Will the project disturb soils within a State		
	regulated wetland or the protected 100 foot adjacent	\bigcirc Yes	🖉 No
	area?		

•	6403089820	

15.	Does the site runoff enter a separate storm sewer system (including roadside drains, swales, ditches, O Yes @ N culverts, etc)?	io ()	Unknown
16.	What is the name of the municipality/entity that owns the separate s system?	storm	sewer
17.	Does any runoff from the site enter a sewer classified \bigcirc Yes \oslash N as a Combined Sewer?	io ()	Unknown
18.	Will future use of this site be an agricultural property as defined by the NYS Agriculture and Markets Law?	0 Ye	es 🖉 No
19.	Is this property owned by a state authority, state agency, federal government or local government?	0 Ye	es 🕐 No
20.	Is this a remediation project being done under a Department approved work plan? (i.e. CERCLA, RCRA, Voluntary Cleanup Agreement, etc.)	<u>)</u> Уе	es 🕐 No
21.	Has the required Erosion and Sediment Control component of the SWPPP been developed in conformance with the current NYS Standards and Specifications for Erosion and Sediment Control (aka Blue Book)?	© ¥6	es O No
22.	Does this construction activity require the development of a SWPPP that includes the post-construction stormwater management practice component (i.e. Runoff Reduction, Water Quality and Quantity Control practices/techniques)? If No, skip questions 23 and 27-39.	() ¥e	es 🌒 No
23.	Has the post-construction stormwater management practice component of the SWPPP been developed in conformance with the current NYS Stormwater Management Design Manual?	• Ye	es () No

	02	251	.08	98	25	,																																
(24.		Th	e :	Sto	orn	nwa	te	r 1	Po]	llu	ıti	on	Pr	rev	en	ti	on	Ρ	la	n	(S	WP	ΡP) (vas	p p	rej	pai	red	b	y:						\searrow
	•	Pr	of	es	si	ona	al	En	gi	nee	er	(1	••E	.)																								
		So	il	a	nd	Wa	ate	er	Co	nse	erv	vat	io	n I	Dis	str	ic	t	(5	SWC	CD))																
		Re	gi	st	er	ed	La	nd	sc	ape	e A	Arc	hi	te	ct	(R	. I	. A	.)																			
		Ce	rt	if	ie	d I	Pro	fe	ss	io	nal	Li	n	Ero	ວຣ	lon	L đ	ind	5	Sec	lin	ner	nt	Co	nt	ro	L (CP	ES	C)								
		Ow	me	r/0	Op	era	ato	r																														
		<u>ot</u>	he	r		—		T						Т										1														
				-				_																_														
SW	ppp	₽ı	rer	ar	er																																	
I	n	s	i	t	e		Е	n	g	i	n	e	e	r	i	n	g	ſ	Т	Τ																	Γ	
Co	ntad	ct	Na	ime	(La	st	, 5	Spa	ice	,	Fi	rst	;)																								
P	e	a	r	s	0	n	,		Ζ	a	С	h	a	r	У																							
Ma	ilir	ng	Ac	ldr	es	s					-	1	1	1	r –	1	1										1		1	-	1	-	_	-	-	 _		
3		G	a	r	r	е	t	t		P		a	C	e																								
Ci	ty	r	m		1																	_																
Q+		- -	 7 i r		-												_																					
N	Y		1	0	5	1	2	-]																									
Ph	one																				F	Tax	2											_				
8	4 5	5	-	2	2	5	-	9	6	9	0											8	4	5	-	2	2	5	-	9	7	1	7					
Em	ail	_						0				•	1.				1			_																		
Z	p	e	a	r	S	0	n	@	1	n	S			e	-	e	n		ſ	•	C	0	m								<u> </u>	-					Ļ	

SWPPP Preparer Certification

I hereby certify that the Stormwater Pollution Prevention Plan (SWPPP) for this project has been prepared in accordance with the terms and conditions of the GP-0-20-001. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of this permit and the laws of the State of New York and could subject me to criminal, civil and/or administrative proceedings.

Fi:	rst	= N	Iam	e												MI
Ζ	a	С	h	а	r	У										Μ
La	st	Na	me													
Ρ	e	a	r	s	0	n	,	Ρ	•	Е	•					
	Sig	gna	atu	re									 		1	
																Date

Temporary Structural

Check Dams

Construction Road Stabilization

- ✔ Dust Control
 - Earth Dike
 - Level Spreader

Perimeter Dike/Swale

Pipe Slope Drain

Portable Sediment Tank

Rock Dam

Sediment Basin

- Sediment Traps
- Silt Fence
- Stabilized Construction Entrance Storm Drain Inlet Protection Straw/Hay Bale Dike Temporary Access Waterway Crossing Temporary Stormdrain Diversion Temporary Swale

Turbidity Curtain

Water bars

Biotechnical

Brush Matting Wattling

Other

Vegetative Measures

Brush Matting
Dune Stabilization
Grassed Waterway

Mulching
Protecting Vegetation
Recreation Area Improvement

Seeding
Sodding
Straw/Hay Bale Dike
Streambank Protection
Temporary Swale

Topsoiling
 Vegetating Waterways

Permanent Structural

Debris Basin

Diversion

Grade Stabilization Structure

✔ Land Grading

Lined Waterway (Rock)

Paved Channel (Concrete)

Paved Flume

Retaining Wall

Riprap Slope Protection

Rock Outlet Protection

Streambank Protection

Post-construction Stormwater Management Practice (SMP) Requirements

<u>Important</u>: Completion of Questions 27-39 is not required if response to Question 22 is No.

27.	Identify all site planning practices that were used to prepare the final site plan/layout for the project.
	Preservation of Undisturbed Areas
	Preservation of Buffers
	Reduction of Clearing and Grading
	Locating Development in Less Sensitive Areas
	Roadway Reduction
	Sidewalk Reduction
	Driveway Reduction
	Cul-de-sac Reduction
	Building Footprint Reduction
	Parking Reduction

- 27a. Indicate which of the following soil restoration criteria was used to address the requirements in Section 5.1.6("Soil Restoration") of the Design Manual (2010 version).
 - All disturbed areas will be restored in accordance with the Soil Restoration requirements in Table 5.3 of the Design Manual (see page 5-22).
 - O Compacted areas were considered as impervious cover when calculating the WQv Required, and the compacted areas were assigned a post-construction Hydrologic Soil Group (HSG) designation that is one level less permeable than existing conditions for the hydrology analysis.
- 28. Provide the total Water Quality Volume (WQv) required for this project (based on final site plan/layout).

Total	WQV	Requi	ired
	-		acre-feet

29. Identify the RR techniques (Area Reduction), RR techniques(Volume Reduction) and Standard SMPs with RRv Capacity in Table 1 (See Page 9) that were used to reduce the Total WQv Required(#28).

Also, provide in Table 1 the total impervious area that contributes runoff to each technique/practice selected. For the Area Reduction Techniques, provide the total contributing area (includes pervious area) and, if applicable, the total impervious area that contributes runoff to the technique/practice.

Note: Redevelopment projects shall use Tables 1 and 2 to identify the SMPs used to treat and/or reduce the WQv required. If runoff reduction techniques will not be used to reduce the required WQv, skip to question 33a after identifying the SMPs.

7738089822

Table	1	-
-------	---	---

Runoff Reduction (RR) Techniques and Standard Stormwater Management Practices (SMPs)

	Total Contributing	Т	'ota	al Co	nt	ri	buting
RR Techniques (Area Reduction)	Area (acres)	Imp	erv	vious	A	rea	a(acres)
Conservation of Natural Areas (RR-1) .		'or					
Sheetflow to Riparian Buffers/Filters Strips (RR-2)		'or].		
Tree Planting/Tree Pit (RR-3)		'or			-		
Disconnection of Rooftop Runoff (RR-4)		'or			•		
RR Techniques (Volume Reduction)					٦		
Vegetated Swale (RR-5)	••••••	•••			•		
Rain Garden (RR-6)		••					
Stormwater Planter (RR-7)		••					
Rain Barrel/Cistern (RR-8)		••					
Porous Pavement (RR-9)		••].		
Green Roof (RR-10)	• • • • • • • • • • • • • • • • • • • •	• •					
Standard SMPs with RRv Capacity					_		
Infiltration Trench (I-1) ·····		••					
Infiltration Basin (I-2) ·····		••					
Dry Well (I-3)		•					
Underground Infiltration System (I-4)							
Bioretention (E-5)].		
Dry Swale $(0-1)$					1.		
				II			
Standard SMPs					-		
Micropool Extended Detention (P-1)		••					
Wet Pond (P-2)		•					
Wet Extended Detention (P-3) ·····	• • • • • • • • • • • • • • • • • • • •	••					
Multiple Pond System (P-4)		•					
Pocket Pond (P-5) ·····		•					
Surface Sand Filter (F-1) •••••••••		••].		
Underground Sand Filter (F-2)		• •].		
Perimeter Sand Filter (F-3) ·····		•			1.		
Organic Filter (F-4)					1.		
Shallow Wetland (W-1)		-			1		
Extended Detention Wetland (W-2)		•			1		
Bond /Notland Suster (M.2)	• • • • • • • • • • • • • • • • • • • •	••			1		
Portet Netler & (W. 4)	• • • • • • • • • • • • • • • • • • • •	••			1		
POCKET WETLAND (W-4)		•			-		

Wet Swale (0-2)

0762089822	
Table 2 -	Alternative SMPs (DO NOT INCLUDE PRACTICES BEING USED FOR PRETREATMENT ONLY)
Alternative SMP	Total Contributing Impervious Area(acres)
 Hydrodynamic Wet Vault Media Filter Other 	
Provide the name and manufacturer proprietary practice(s)) being us Name Manufacturer Manufacturer Manufacturer Note: Redevelopment projects which use questions 28, 29, 33 and WQv required and total WQv p	<pre>b of the Alternative SMPs (i.e. d for WQv treatment. b do not use RR techniques, shall d 33a to provide SMPs used, total provided for the project.</pre>
30. Indicate the Total RRv prov. Standard SMPs with RRv capac Total RRv provided	ided by the RR techniques (Area/Volume Reduction) and city identified in question 29.
31. Is the Total RRv provided (stotal WQv required (#28). If Yes, go to question 36. If No, go to question 32.	#30) greater than or equal to the \bigcirc Yes \bigcirc No
32. Provide the Minimum RRv required = (P) Minimum RRv Required Minimum RRv Required	uired based on HSG. (0.95)(Ai)/12, Ai=(S)(Aic)] t
 32a. Is the Total RRv provided (a Minimum RRv Required (#32)? If Yes, go to question 33. Note: Use the space proves specific site limitations 100% of WQv required (#2 specific site limitations 100% of the WQv required SWPPP. If No, sizing criteria has a processed. SWPPP preparer materia. 	#30) greater than or equal to the ided in question #39 to <u>summarize</u> the s and justification for not reducing 8). A <u>detailed</u> evaluation of the s and justification for not reducing (#28) must also be included in the not been met, so NOI can not be ust modify design to meet sizing

1766089827

33. Identify the Standard SMPs in Table 1 and, if applicable, the Alternative SMPs in Table 2 that were used to treat the remaining total WQv(=Total WQv Required in 28 - Total RRv Provided in 30).

Also, provide in Table 1 and 2 the total <u>impervious</u> area that contributes runoff to each practice selected.

Note: Use Tables 1 and 2 to identify the SMPs used on Redevelopment projects.

33a. Indicate the Total WQv provided (i.e. WQv treated) by the SMPs identified in question #33 and Standard SMPs with RRv Capacity identified in question 29. WQv Provided acre-feet Note: For the standard SMPs with RRv capacity, the WQv provided by each practice = the WQv calculated using the contributing drainage area to the practice - RRv provided by the practice. (See Table 3.5 in Design Manual) Provide the sum of the Total RRv provided (#30) and 34. the WQv provided (#33a). Is the sum of the RRv provided (#30) and the WQv provided 35. (#33a) greater than or equal to the total WQv required (#28)? 🔾 Yes 🔷 No If Yes, go to question 36. If No, sizing criteria has not been met, so NOI can not be processed. SWPPP preparer must modify design to meet sizing criteria. Provide the total Channel Protection Storage Volume (CPv) required and 36. provided or select waiver (36a), if applicable. CPv Required CPv Provided acre-feet acre-feet 36a. The need to provide channel protection has been waived because: O Site discharges directly to tidal waters or a fifth order or larger stream. \bigcirc Reduction of the total CPv is achieved on site through runoff reduction techniques or infiltration systems.

37. Provide the Overbank Flood (Qp) and Extreme Flood (Qf) control criteria or select waiver (37a), if applicable.

Total Overbank Flood Control Criteria (Qp)

Pre-Development	Post-development
Total Extreme Flood Control	Criteria (Qf)
Pre-Development	Post-development
CFS	CFS

37a.	The need to meet the Qp and Qf criteria has been waived because:
	\bigcirc Site discharges directly to tidal waters
	or a fifth order or larger stream.
	\bigcirc Downstream analysis reveals that the Qp and Qf
	controls are not required

38. Has a long term Operation and Maintenance Plan for the post-construction stormwater management practice(s) been
O Yes
No developed?

If Yes, Identify the entity responsible for the long term Operation and Maintenance

39. Use this space to summarize the specific site limitations and justification for not reducing 100% of WQv required(#28). (See question 32a) This space can also be used for other pertinent project information.

4285089826

40. Identify other DEC permits, existing and new, that are required for this project/facility.

Air Pollution Control Coastal Erosion Hazardous Waste Long Island Wells Mined Land Reclamation Solid Waste Navigable Waters Protection / Article 15 Water Quality Certificate Dam Safety Water Supply Freshwater Wetlands/Article 24 Tidal Wetlands Wild, Scenic and Recreational Rivers Stream Bed or Bank Protection / Article 15 Endangered or Threatened Species(Incidental Take Permit) Individual SPDES SPDES Multi-Sector GP NYR Other ✓ _{None}

41.	Does this project require a US Army Corps of Engineers Wetland Permit? If Yes, Indicate Size of Impact.	O Yes	🕐 No
42.	Is this project subject to the requirements of a regulated, traditional land use control MS4? (If No, skip question 43)	🕑 Үез	() No
43.	Has the "MS4 SWPPP Acceptance" form been signed by the principal executive officer or ranking elected official and submitted along with this NOI?	Ø Yes	○ No
44.	If this NOI is being submitted for the purpose of continuing or transcoverage under a general permit for stormwater runoff from constructi activities, please indicate the former SPDES number assigned. $\boxed{N \mid Y \mid R}$	ferring on	

Owner/Operator Certification

I have read or been advised of the permit conditions and believe that I understand them. I also understand that, under the terms of the permit, there may be reporting requirements. I hereby certify that this document and the corresponding documents were prepared under my direction or supervision. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations. I further understand that coverage under the general permit will be identified in the acknowledgment that I will receive as a result of submitting this NOI and can be as long as sixty (60) business days as provided for in the general permit. I also understand that, by submitting this NOI, I am acknowledging that the SWPPP has been developed and will be implemented as the first element of construction, and agreeing to comply with all the terms and conditions of the general permit for which this NOI is being submitted.

MI
Date

NYS Department of Environmental ConservationDivision of Water625 Broadway, 4th FloorAlbany, New York 12233-3505								
MS4 Stormwater Pollution Prevention Plan (SWPPP) Acceptance Form for Construction Activities Seeking Authorization Under SPDES General Permit *(NOTE: Attach Completed Form to Notice Of Intent and Submit to Address Above)								
I. Project Owner/Operator Information								
1. Owner/Operator Name: Waccabuc Country Club								
2. Contact Person: John Assuma								
3. Street Address: 90 Mead St								
4. City/State/Zip: Waccabuc, NY 10597								
II. Project Site Information								
5. Project/Site Name: Waccabuc Country Club Pickleball								
6. Street Address: 74 Mead St								
7. City/State/Zip: Waccabuc, NY 10597								
III. Stormwater Pollution Prevention Plan (SWPPP) Review and Acceptance Information								
8. SWPPP Reviewed by:								
9. Title/Position:								
10. Date Final SWPPP Reviewed and Accepted:								
IV. Regulated MS4 Information								
11. Name of MS4: Town of Lewisboro								
12. MS4 SPDES Permit Identification Number: NYR20A								
13. Contact Person:								
14. Street Address:								
15. City/State/Zip:								
16. Telephone Number:								

MS4 SWPPP Acceptance Form - continued

V. Certification Statement - MS4 Official (principal executive officer or ranking elected official) or Duly Authorized Representative

I hereby certify that the final Stormwater Pollution Prevention Plan (SWPPP) for the construction project identified in question 5 has been reviewed and meets the substantive requirements in the SPDES General Permit For Stormwater Discharges from Municipal Separate Storm Sewer Systems (MS4s). Note: The MS4, through the acceptance of the SWPPP, assumes no responsibility for the accuracy and adequacy of the design included in the SWPPP. In addition, review and acceptance of the SWPPP by the MS4 does not relieve the owner/operator or their SWPPP preparer of responsibility or liability for errors or omissions in the plan.

Printed Name:

Title/Position:

Signature:

Date:

VI. Additional Information

(NYS DEC - MS4 SWPPP Acceptance Form - January 2015)



<u>R4–A ZONE REQUIREMENTS</u>											
	<u>REQUIRED/</u> <u>PERMITTED</u>	<u>EXISTING</u>	PROPOSE								
Minimum Lot Size:	4 AC	6.1 AC	6.1 AC								
Minimum Front Yard:											
From street center line	75'	215'	215'								
From front lot line	50'	183'	183'								
Minimum Side Yard:	50'	52'	51'								
Minimum Rear Yard:	50'	436'	436'								
Recreation Facility Setback:	2 x 50'=100'	52.8' to north	51'± *								
		99.6' to south	98'± *								
Maximum Building Height:	2.5 stories/ 35'	2.5 stories/ 35'	2.5 stori 35'								
Maximum Building Coverage:	6%	2%	2%								



xxx
<u></u>
100
× ^{568.9} × ^{568.9}

2–14–23

AS NOTED

BY

CHECKED

DATE

SCALE

J.J.S.

D.L.M.

<u>SITE PLANT LIST</u>											
QTY.	BOTANICAL/COMMON NAME	SIZE	ROOT/SPACING								
	EVERGREEN TREES										
4	llex opaca / American Holly	6' HT. (MIN.)	B & B								
9	Picea abies/ Norway Spruce	6' HT. (MIN.)	B & B								
3	Thuja 'Green Giant' / Green Giant Arborvitae	6' HT. (MIN.)	B & B								

- 1. All proposed planting beds to receive a 12" min. depth of topsoil. No fertilizer is to be used. Nutrient requirements shall be met by incorporation of suitable organic material. Soil amendments based on specific testing of topsoil material.
- 2. Any new soils added will be amended as required by results of soil testing and placed using a method that will not
- 4. Plants shall conform with ANSI Z60.1 American Standard for Nursery Stock in all ways including dimensions.
- 5. Plant material shall be taken from healthy nursery stock.
- 6. All plants shall be grown under climate conditions similar to those in the locality of the project.
- 8. The location and layout of landscape plants shown on the site plan shall take precedence in any discrepancies between the quantities of plants shown on the plans and the quantity of plants in the Plant List. 9. Provide a 3" layer of shredded bark mulch (or as specified) over entire watering saucer at all tree pits or over entire
- 10. All landscape plantings shall be maintained in a healthy condition at all times. Any dead or diseased plants shall

- 1. All proposed seeded areas to receive 4" min. depth of topsoil. Soil amendments shall be determined based on specific testing of topsoil material. Topsoil shall be placed using a method that will not cause compaction.
- vegetation cover in combination with suitable mulch as follows:
- no fertilizer is to be for seeded areas. Nutrient requirements shall be met by incorporation of acceptable organic matter based on results of soil testing. mulch: salt hay or small grain straw applied at a rate of 90 lbs./1000 s.f. or 2 tons/acre, to be applied and anchored according to New York State Standards and Specifications for Erosion and Sediment Control, - if the season prevents the establishment of a permanent vegetation cover, the disturbed areas will be
- 3. Seeding should begin immediately upon completion of finish grading and seed bed preparation while soil is still friable and before weeds can emerge. If seeding area is crusted or compacted, it should be loosened by discing or tilling. If weeds are present, they should be mowed short and removed or tilled under before seed is applied.
- 4. Seed mixtures shall be planted between March 21 and May 20, or between August 15, and October 15 or as directed by project representative. The seed mixes as specified on these drawings are as follows: A. Seed Mix for disturbed areas shall be (ERNMX-114) 5311 Conservation Mix at a rate of 3-5 lbs / 1,000 square





REQUIRED EROSION CONTROL SWPPP CONTENTS:

Pursuant to the NYSDEC "SPDES General Permit for Stormwater Discharges from Construction Activity" (GP-0-20-001), all Stormwater Pollution Prevention Plan's (SWPPP) shall include erosion and sediment control practices designed in conformance with the most current version of the technical standard, "New York Standards and Specifications for Erosion and Sediment Control." Where erosion and sediment control practices are not designed in conformance with this technical standard, the owner or operator must demonstrate equivalence to the technical standard. The following list of required SWPPP components is provided in accordance with Part III.B.1a–I of General Permit GP-0-20-001:

- a. Background Information: The subject project consists of the installation of a berm and privacy fence surrounding a pickleball court. b. Site map / construction drawing: These plans serve to satisfy this SWPPP
- requirement. c. Description of the soils present at the site: Onsite soils located within the
- proposed limits of disturbance consist of Paxton Fine Sandy Loam (PnB), as identified on the Soil Conservation Service Web Soil Survey. This soil type belongs to the Hydrologic Soil Group "C."
- d. Construction phasing plan / sequence of operations: The Construction Sequence and phasing found on these plans provide the required phasing. A Construction Sequence and Erosion and Sediment Control Maintenance Schedule has been provided. The Erosion and Sediment Control Notes contained hereon outline a general sequence of operations for the proposed project. In general all erosion and sediment control facilities shall be installed prior to commencement with land disturbing activities, and areas of disturbance shall be limited to the shortest period of time as practicable.
- e. Description of erosion and sediment control practices: This plan, and details / notes shown hereon serve to satisfy this SWPPP requirement. f. Temporary and permanent soil stabilization plan: The Sedimentation and Erosion Control Notes and Details provided heron identify temporary and permanent
- project, and at the various stages of development. g. Site map / construction drawing: This plan serves to satisfy this SWPPP requirement.
- h. The dimensions, material specifications, installation details, and operation and maintenance requirements for all erosion and sediment control practices: The details, Erosion and Sediment Control Notes, and Erosion and Sediment Control Maintenance Schedule serve to satisfy this SWPPP requirement.
- *i.* An inspection schedule: Inspections are to be performed twice weekly and by a qualified professional as required by the General Permit GP-0-20-001. In addition the NYSDEC Trained Contractor shall perform additional inspections as cited in the Sedimentation and Erosion Control Notes.
- j. A description of pollution prevention measures that will be used to control litter, construction chemicals and construction debris: In general, all construction litter / debris shall be collected and removed from the site. The general contractor shall supply either waste barrels or dumpster for proper waste disposal. Any construction chemicals utilized during construction shall either be removed from site daily by the contractor or stored in a structurally sound and weatherproof building. No hazardous waste shall be disposed of onsite, and shall ultimately be disposed of in accordance with all federal, state and local regulations. Material Safety Data Sheets (MSDS), material inventory, and emergency contact numbers shall be maintained by the general contractor for all construction chemicals utilized onsite. Finally, temporary sanitary facilities (portable toilets) shall be provided onsite during the entire length of construction, and inspected weekly for evidence of leaking holding tanks.
- k. A description and location of any stormwater discharges associated with industrial activity other than construction at the site: There are no known industrial stormwater discharges present or proposed at the site.
- I. Identification of any elements of the design that are not in conformance with the technical standard, "New York Standards and Specifications for Erosion and Sediment Control." All proposed elements of this SWPPP have been designed in accordance with the "New York Standards and Specifications for Erosion and Sediment Control."



INSTALLATION NOTES 1. STONE SIZE - USE 3" STONE

- 2. LENGTH AS REQUIRED, BUT NOT LESS THAN 30 FEET.
- 3. THICKNESS NOT LESS THAN SIX (6) INCHES.
- 4. WIDTH 12 FOOT MINIMUM, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS OR EGRESS OCCUR. 5. FILTER CLOTH - WILL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING OF
- STONE. FILTER CLOTH WILL NOT BE REQUIRED ON A SINGLE FAMILY RESIDENCE LOT. 6. SURFACE WATER - ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CONSTRUCTION ENTRANCES SHALL BE PIPED ACROSS THE ENTRANCE. IF PIPING
- IS IMPRACTICAL, A MOUNTABLE BERM WITH 5:1 SLOPES WILL BE PERMITTED. MAINTENANCE - THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHT OF WAY
- THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHT OF WAY MUST BE REMOVED IMMEDIATELY.
- WASHING WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHT OF WAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE AND WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.
- 9. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN.

STABILIZED CONSTRUCTION ACCESS DETAIL (N. T. S.)

- stabilization measures to be employed with respect to specific elements of the

- EROSION & SEDIMENT CONTROL NOTES:
- 1. The owner's field representative (O.F.R.) will be responsible for the implementation and maintenance of erosion and sediment control measures on this site prior to and during construction. 2. All construction activities involving the removal or disposition of soil are to be provided with
- appropriate protective measures to minimize erosion and contain sediment disposition within. Minimum soil erosion and sediment control measures shall be implemented as shown on the plans and shall be installed in accordance with "New York Standards and Specifications For Erosion and Sediment Control," latest edition.
- 3. Wherever feasible, natural vegetation should be retained and protected. Disturbance shall be minimized in the areas required to perform construction. No more than 5 acres of unprotected soil shall be exposed at any one time.
- 4. When land is exposed during development, the exposure shall be kept to the shortest practical period of time. In the areas where soil disturbance activity has temporarily or permanently ceased, the application of soil stabilization measures must be initiated by the end of the next business day and completed within seven (7) days from the date the current soil disturbance activity ceased. Disturbance shall be minimized to the areas required to perform construction.
- 5. Silt fence shall be installed as shown on the plans prior to beginning any clearing, grubbing or earthwork. 6. All topsoil to be stripped from the area being developed shall be stockpiled and immediately
- seeded for temporary stabilization. Ryegrass (annual or perennial) at a rate of 30 lbs. per acre shall be used for temporary seeding in spring, summer or early fall. 'Aristook' Winter Rye (cereal rye) shall be used for temporary seeding in late fall and winter. 7. Any disturbed areas not subject to further disturbance or construction traffic, permanent or
- temporary, shall have soil stabilization measures initiated for permanent vegetation cover in combination with a suitable mulch within 1 business day of final grading. All seeded areas to receive a minimum 4" topsoil (from stockpile area) and be seeded and mulched as follows: • Seed mixture to be planted between March 21 and May 20, or between August 15 and October 15 or as directed by project representative at a rate of 100 pounds per acre in the following proportions: Kentucky Bluegrass 20%
- Creeping Red Fescue 40% Perennial Ryegrass 20% Annual Ryegrass • Mulch: Salt hay or small grain straw applied at a rate of 90 lbs./1000 S.F. or 2
- tons/acre, to be applied and anchored according to "New York Standards and Specification For Erosion and Sediment Control," latest edition.
- 8. Grass seed mix may be applied by either mechanical or hydroseeding methods. Seeding shall be performed in accordance with the current edition of the "NYSDOT Standard Specification. Construction and Materials, Section 610–3.02, Method No. 1". Hydroseeding shall be performed using materials and methods as approved by the site engineer.
- 9. Cut or fill slopes steeper than 3:1 shall be stabilized immediately after grading with Curlex I Single Net Erosion Control Blanket, or approved equal.
- 10. Paved roadways shall be kept clean at all times.

suitably stabilized.

- 11. The site shall at all times be graded and maintained such that all stormwater runoff is diverted to soil erosion and sediment control facilities.
- 12. All storm drainage outlets shall be stabilized, as required, before the discharge points become operational.
- 13. Stormwater from disturbed areas must be passed through erosion control barriers before discharge beyond disturbed areas or discharged into other drainage systems.
- 14. Erosion and sediment control measures shall be inspected and maintained on a daily basis by the O.F.R. to insure that channels, temporary and permanent ditches and pipes are clear of
- debris, that embankments and berms have not been breached and that all straw bales and silt fences are intact. Any failure of erosion and sediment control measures shall be immediately repaired by the contractor and inspected for approval by the O.F.R. and/or site engineer. 15. Dust shall be controlled by sprinkling or other approved methods as necessary, or as directed
- by the O.F.R. 16. Cut and fills shall not endanger adjoining property, nor divert water onto the property of others.
- 17. All fills shall be placed and compacted in 6" lifts to provide stability of material and to prevent settlement.
- 18. The O.F.R. shall inspect downstream conditions for evidence of sedimentation on a weekly basis and after rainstorms.
- 19. As warranted by field conditions, special additional erosion and sediment control measures, as specified by the site engineer and/or the Town Engineer shall be installed by the contractor. 20. Erosion and sediment control measures shall remain in place until all disturbed areas are





<u>NOTES</u>:





- 1. AREA CHOSEN FOR STOCKPILE LOCATION SHALL BE DRY AND STABLE.
- 2. MAXIMUM SLOPE OF STOCKPILE SHALL BE 2:1.
- 3. UPON COMPLETION OF SOIL STOCKPILING, EACH PILE SHALL BE IMMEDIATELY SEEDED WITH K31 PERENNIAL TALL FESCUE.
- 4. ALL STOCKPILES SHALL BE PROTECTED WITH SILT FENCING INSTALLED ON THE DOWNGRADIENT SIDE.

TEMPORARY SOIL STOCKPILE DETAIL (N.T.S.)



CONSTRUCTION SEQUENCE:

- 1. Install stabilized construction entrance/anti-tracking pad at driveway entrance. Install silt fence in general locations indicated on the plan. Begin shrub relocation.
- Strip and stockpile topsoil on site for later use in lawn and landscape areas. Begin grading of berm.
- Install fence on top of berm. Upon completion of grading operations, install evergeen trees.
- Erosion and Sediment Control Notes contained on this page.

EROSION AND SEDIMENT CONTROL MAINTENANCE SCHEDULE						
MONITORING REQUIREMENTS				MAINTENANCE REQUIREMENTS		
PRACTICE	DAILY	WEEKLY	AFTER RAINFALL	DURING CONSTRUCTION	AFTER CONSTRUCTION	
SILT FENCE BARRIER	_	Inspect	Inspect	Clean/Replace	Remove	
STABILIZED CONSTRUCTION ENTRANCE	Inspect	_	Inspect	Clean/Replace Stone and Fabric	Remove	
*VEGETATIVE ESTABLISHMENT	_	Inspect	Inspect	Water/Reseed/ Remulch	Reseed to 80% Coverage	
SOIL STOCKPILES	_	Inspect	Inspect	Mulching/ Silt Fence Repair	Remove	

after construction is:

Waccabuc Country Club 90 Mead Street

Waccabuc, NY 10597 and/or the current owner(s) of the subject property.



PROVIDE STAKING AND GUYING FOR TREES PLANTED ON S THAN 3H: 1V, IN EXPOSED, WINDY AREAS AND AS SPECIFIED ARCHITECT. GUY WIRES AND STAKES SHALL BE REMOVED TWELVE MONTHS OF PLANTING.





<u>LEGEND</u>	
EXISTING PROPERTY LINE	
— EXISTING EASEMENT	
EXISTING ZONING DISTRICT BOUNDARY	
EXISTING BUILDING	
EXISTING STONE RETAINING WALL	
EXISTING STONE WALL	
EXISTING GRAVEL TRAIL	
— EXISTING CHAIN LINK FENCE	
EXISTING POST & RAIL FENCE	
EXISTING CONCRETE CURB	
EXISTING WETLAND	
– – EXISTING APPROXIMATE LIMITS OF WETL	AND
EXISTING 100 YR. FLOODPLAIN BOUNDA	RY
EXISTING WETLAND BUFFER	
EXISTING STREAM BUFFER	
EXISTING 10' CONTOUR	
– – EXISTING 2' CONTOUR	
EXISTING SPOT GRADE	
PROPOSED SPOT ELEVATION	
PROPOSED 10' CONTOUR	
PROPOSED 2' CONTOUR	
PROPOSED SILT FENCE PROPOSED LIMITS OF DISTURBANCE	
PROPOSED TEMPORARY SOIL STOCKPILE	-
PROPOSED STABILIZED CONSTRUCTION ENTRANCE	

8. Topsoil, seed, and mulch all disturbed areas as soon as practical in accordance with the

* Permanent vegetation is considered stabilized when 80% of the plant density is established. Erosion control measures shall remain in place until all disturbed areas are permanently stabilized. <u>Note:</u> The party responsible for implementation of the maintenance schedule during and

A TTAG WIRE HOSE CONT	CH No. 10 GALV. ANNEALED GUYS TO TRUNK. USE RUBBER COVER WHERE WIRES ARE IN ACT WITH BRANCHES.				
PROV SPECI SAUC OVER PLACI	-PROVIDE 3" LAYER OF MULCH AS SPECIFIED OVER ENTIRE WATERING SAUCER AT ALL TREE PITS, OR OVER ENTIRE TREE BED. DO NOT PLACE MULCH WITHIN 3" OF TRUNK.				
/ TRUNK FLARE TO BE COMPLETELY EXPOSED. SET 1" TO 2" ABOVE ESTABLISHED FINISH GRADE.					
3' LO (SPAC BE DI TENSI	NG CEDAR STAKES, MIN. 3" DIA., CED 120° IN PLAN). STAKES TO RIVEN IN AFTER ATTACHING TO ION WIRE.				
	FORM 4" HIGH TOPSOIL LIP AT EDGE OF TREE PIT TO FORM WATERING SAUCER				
	CUT AND REMOVE BINDING FROM TRUNK AND FROM AROUND AS MUCH OF BALL AS POSSIBLE. CUT AND REMOVE BURLAP AT UPPER 1/3 OF ROOT BALL. IF SYNTHETIC WRAP IS USED, REMOVE COMPLETELY.				
	SIT ROOT BALL ON EXISTING UNDISTURBED SOIL OR ON COMPACTED SUBGRADE. DO NOT DIG DEEPER THAN THE DEPTH OF ROOT BALL.				
LOPES GREATER D BY LANDSCAPE WITHIN					

REVISED FOR PLANNING BOARD SUBMISSION				
REVISION				
S / T / ERING, SURVEYING PE ARCHITECTURE,	G & <i>P.C.</i>	3 Garrett Place Carmel, NY 105 (845) 225–9690 (845) 225–9717 www.insite–eng.c	12 7 fax com	
<u>OUNTRY CLUB</u> EBALL ORO, WESTCHESTER CTY, NEV ON & CONTROL D DETAILS	N YORK	CSTILL OF NEW) CSTILL	F JUNEER X	
PROJECT MANAGER Z.	М.Р.	DRAWING NO.	SHEET	
DRAWN BY S.	<i>M.R</i> .	SP-2	2	
CHECKED D.	.L.M.		/ 2	



MEMORANDUM

TO:	Chairperson Janet Andersen and Members of Lewisboro Planning Board
CC:	Ciorsdan Conran
	Kevin Kelly, Building Inspector
FROM:	Jan K. Johannessen, AICP Joseph M. Cermele, P.E., CFM Town Consulting Professionals
DATE:	August 10, 2023
RE:	Alex Bernabo 96 Post Office Road Sheet 25, Block 10812, Lot 3

PROJECT DESCRIPTION

The subject property consists of ± 4 acres of land and is located at 96 Post Office Road within the R-4A Zoning District. The subject property is currently vacant land. The applicant is proposing a two (2) bedroom dwelling with attached garage. Improvements include a gravel driveway, septic system, well and associated stormwater treatment system.

SEQRA

The proposed action is a Type II Action and is categorically exempt from the State Environmental Quality Review Act (SEQRA).

REQUIRED APPROVALS

- 1. A Wetland Activity Permit and Town Stormwater Permit is required from the Planning Board; a public hearing is required to be held on the Wetland Permit.
- 2. Work proposed within the Town right-of-way will require a Driveway Opening Permit from the Town Highway Superintendent.

CIVIL ENGINEERING | LANDSCAPE ARCHITECTURE | SITE & ENVIRONMENTAL PLANNING
Chairperson Janet Andersen Bernabo – 96 Post Office Road August 10, 2023 Page 2 of 5

- 3. The proposed potable water well and sanitary sewage treatment system require approval from the Westchester County Department of Health (WCDH).
- 4. The subject property is located within the NYC East of Hudson Watershed and proposed land disturbance exceeds 5,000 s.f. Coverage under New York State Department of Environmental Conservation (NYSDEC) SPDES General Permit for Stormwater Discharges from Construction Activity (GP-0-20-001) will be required.
- 5. The applicant has received New York City Department of Environmental Conservation (NYCDEP) Individual Residential Stormwater Plan Determination approval.

COMMENTS

- 1. The application should be referred to the Building Inspector for review of zoning compliance.
- 2. The wetland boundary shall be delineated by a qualified wetland scientist, in accordance with Chapter 217, Wetlands and Watercourse, of the Town Code. Wetland flags shall be survey located and shall appear on the plan, along with the Town's 150-foot regulated wetland buffer line. In accordance with the Town's wetland ordinance, the wetland delineation must have been conducted within one (1) year of the date of application and this office must confirm the wetland boundary line.
- 3. There appears to be an off-site wetland on the opposite side of the street at 101 Post Office Road; off-site wetlands shall be shown, as should the 150-foot buffer.
- 4. The applicant shall submit a Wetland Report, which shall contain the information required under Sections 217-5 and 6 of the Town's Wetland Ordinance.
- 5. The applicant shall develop a Wetland Mitigation Plan, which provides, at a minimum, mitigation at a ratio of 1:1 (for every s.f. of wetland or wetland buffer disturbance proposed, an equal or greater amount of mitigation shall be provided). Reference is made to the Town's mitigation guidelines provided in Chapter 217, Appendix B. Note that stormwater mitigation does not count toward satisfying the wetland mitigation requirement.
- The plan shall illustrate and identify the location, specie type and diameter at breast height (dbh) of all trees with a dbh of eight (8) inches or greater and located within the limits of disturbance and 25 feet beyond. Indicate trees to be removed and/or protected.
- 7. Drawing SY1 shall be revised to include the drawing scale and a north arrow.

Chairperson Janet Andersen Bernabo – 96 Post Office Road August 10, 2023 Page 3 of 5

- 8. The plan shall be revised to dimension all required minimum zoning setbacks lines (front, rear, side yard setbacks).
- 9. In the Zoning Table, the distance from the structure to the street centerline is shown to be 713'. When measuring on the plan, it appears this separation is 71'. Please correct.
- 10. Show any proposed contours and/or spot grades at the southern side of the proposed dwelling.
- 11. Provide fence and gate details, including height, material, color, etc. The detail provided is not legible and the leaders and text are cut off.
- 12. Provide construction details for all proposed improvements, including but not limited to, driveway, walkways, walls, fencing, septic and water service, etc.
- 13. Identify the limits of the existing stone wall removal at the driveway entrance.
- 14. In accordance with Section 195-24A of the Subdivision Regulations, the applicant shall demonstrate that the driveway grade does not exceed 3% within 30 feet of the edge of street pavement or 14% at any other point. Further, we question the use of a gravel surface at 12% grade. Provide a driveway profile.
- 15. All walls greater than or equal to four (4) feet in height shall be designed by a NYS Licensed Professional Engineer. Provide construction details and specifications on the plan for the Planter Wall.
- 16. The plan shall note that the construction of all walls greater than or equal to four (4) feet in height shall be certified by the Design Professional prior to issuance of a Certificate of Occupancy/Completion.
- 17. The applicant shall provide a copy of the WCDH Approval, including signed plans and permits, related to the proposed wastewater treatment system and potable water well.
- 18. The plan shall illustrate the location of the proposed septic laterals (Primary and Expansion). Demonstrate that the minimum required WCDH separation distances to the septic system, well, structures, drainage improvements, etc. are maintained.
- 19. The site plan shall quantify the limits of disturbance (s.f.). The plan shall note that disturbance limits shall be staked in the field prior to construction.

Chairperson Janet Andersen Bernabo – 96 Post Office Road August 10, 2023 Page 4 of 5

- 20. The limits of disturbance line should be revised to include all the split rail fence installation and proposed plantings.
- 21. Silt fence should be shown to be installed parallel to the contours.
- 22. Land disturbance is proposed to exceed ≥5,000 s.f. and will therefore require conformance with NYSDEC SPDES General Permit (GP-0-20-001) and filing of a Notice of Intent (NOI) and MS4 Acceptance Form with the NYSDEC. Submit draft copies to this office for review.
- 23. The applicant shall provide stormwater mitigation and design calculations for the runoff generated by the net increase in impervious surface for the 100-year, 24-hour storm event.
- 24. Stormwater planter sizing calculations shall be provided and shall follow the NYS Stormwater Design Manual, accounting for ponding, soil media and gravel layer volumes. Provide planting requirements for the stormwater planter.
- 25. The roof leaders for the garage should be shown on the plan to clarify how stormwater will be conveyed to the storm water planter.
- 26. The plan shall illustrate the footing drain location on the site plan. Include the size, slope, and material of drainage pipe and provide outlet protection details.
- 27. Clarify what the thick line with the "WL" symbol is which is shown across the property. The legend shows it as a water line.
- 28. Note #21 in the sequence of construction found on sheet SY1 is not legible. The same applies for the Erosion Control Maintenance note 9.3.1. Please correct.
- 29. It is recommended that the Planning Board conduct a site visit.

In order to expedite the review of subsequent submissions, the applicant should provide annotated responses to each of the comments outlined herein.

PLANS REVIEWED, PREPARED BY P.W. SCOTT ENGINEERING & ARCHITECTURE, P.C., DATED MAY 25, 2023:

- Cover Sheet (CS)
- IRSP Erosion Control Plan (SY1)
- Concrete Planter Details (SY2)

Chairperson Janet Andersen Bernabo – 96 Post Office Road August 10, 2023 Page 5 of 5

DOCUMENTS REVIEWED:

- Wetland Permit Application
- Stormwater Permit Application
- Short EAF, dated April 5, 2023
- NYCDEP Individual Residential Stormwater Plan Determination, dated June 13, 2023
- Proposed Ground Level Floor Plan and Elevations (A-1.0), prepared by SD Design, dated June 28, 2023

JKJ/dc

https://kellardsessionsconsulti.sharepoint.com/sites/Kellard/Municipal/Lewisboro/Correspondence/2023-08-10_LWPB_Bernabo - 96 Post Office Road_Review Memo.docx

TO:	The Town of Lewisboro Planning Board
FROM:	Lewisboro Conservation Advisory Council
SUBJECT:	Bernabo vacant land, 96 Post Office Road, Waccabuc, NY 10597
DATE:	August 7, 2023

The Conservation Advisory Council (CAC) has reviewed the materials submitted by the applicant for a new well, septic and house.

The entire project is in the wetland buffer. The CAC would like to see the wetland and the 150 foot buffer lines clearly marked. Given the closeness to the wetland, the CAC would like to see:

- A calculation of the disturbance and the association mitigation planting plan size to meet the 1 to 1 criteria
- A detailed list of any tree removals including size and type and their position on the plan to determine if their removal is necessary
- A stormwater management plan
- A soil report both for the septic area and to determine if there are wet areas in the buffer that may be disturbed.

Fee: <u>\$50.00</u> Date: <u>06/20/20</u>23

TOWN OF LEWISBORO ENVIRONMENTAL QUESTIONNAIRE

The purpose of this Questionnaire is to determine whether a Town Wetland Permit, a Town Stormwater Permit and/or coverage under the NYSDEC SPDES General Permit for Stormwater Discharges from Construction Activity is required. This form does not provide authorization to commence work.

Project Address:	96 Post Office Rd, Waccabuc, NY		
Sheet:	<u>.25</u> Block: <u>10812</u> Lot(s): <u>3</u>		,
Project Descriptio	n: <u>Construction of new residence, OWTS</u>	and Well	,
This questionnaire mu dimensions of the pro and the approximate	ust be accompanied with a Site Plan or, at a minimum, poosed activity. Said plans must include a line which e area of disturbance must be calculated (square feet). F	a Plot Plan w ncircles the to ailure to subn	hich clearly illustrates the location and otal area of proposed land disturbance nit these items will delay review.
Owner's Name:	wDesigne, Inc. / Alex Bernabo	Phone:	(914) 906-1336
Owner's Address:	3867 Danbury Rd, Brewster, NY 10509	_ Email:	info@wdesigne.com
Agent's Name (if a	PW Scott Engineering & Architectur applicable): <u>Peder Scott, P.E., R.A.</u>	e, PC _ Phone:	845-278-2110
Agent's Address: _	3871 Danbury Rd, Brewster, NY 10509	_ Email:	pwscott@pwscott.com

FOR TOWN USE - PLEASE DO NOT WRITE BELOW THIS LINE

- 1. The use of the property is?
- Is a Town Wetland Permit required? Yes
 If Yes, what type of Wetland Permit is required? Planning Board
- 3. Is the project located within the NYCDEP Watershed? Yes
- 4. Area of proposed disturbance: **5000 SqFt to Less than 1 acre**
- 5. Is a Town Stormwater Permit required? Yes If Yes, the approval authority will be? Planning Board
- 6. Will the project require coverage under the NYSDEC General Permit for Stormwater Discharges from Construction Activity? **Yes**

Application Fee (if required):Wetland Permit \$: \$255 plus \$2,000 escrowStormwater Permit \$: 155

Notes: ____

Signature:	Jan K. Johannessen
0	Wetland Inspector/Consultant

Date: 06/20/2023

Application	No.:	
••		
Foo		Data

TOWN OF LEWISBORO WETLAND PERMIT APPLICATION

79 Bouton Road, South Salem, NY 10590 Phone: (914) 763-5592 Fax: (914) 875-9148

Project Address: 96 Post Office Rd, Waccabuc, NY

Sheet: <u>25</u> Block: <u>10812</u> Lot(s): <u>3</u>

Project Description (Identify the improvements proposed within the wetland/wetland buffer and the approximate amount of wetland/wetland buffer disturbance): <u>Construction of 2,800 house + 600 sf garage</u> plus well disturbance .213 acres in wetlands, SSTS & driveway in buffer - Buffer Disturbance: .309

Owner's Name:	wDesigne / Alex Bernabo	_Phone: _	(914) 906-1336
Owner's Address: _	3867 Danbury Rd, Brewster, NY 10509	Email:	info@wdesigne.com
Applicant's Name (f different):	Phone: _	
Applicant's Address	::	Email:	
Agent's Name (if ap	plicable):Peder Scott, P.E., R.A W Scott Engineering & Architecture_PC	Phone: _	845-278-2110
Agent's Address: <u>3</u>	871 Danbury Rd, Brewster, NY 10509	Email:	pwscott@pwscott.com

TO BE COMPLETED BY OWNER/APPLICANT

What type of Wetland Permit is required? (see §217-5C and §217-5D of the Town Code)

🔏 Administrative 🛛 🗆 Planning Board

Is the project located within the NYCDEP Watershed? X Yes \Box No

Total area of proposed disturbance: $\Box < 5,000 \text{ s.f.}$ X 5,000 s.f. - < 1 acre $\Box \ge 1 \text{ acre}$

Note: Initially, all applications shall be submitted with a plan that illustrates the existing conditions and proposed improvements. Said plan must include a line which encircles the total area of proposed land disturbance and the approximate area of disturbance must be calculated (square feet). The Planning Board and/or Town Wetland Inspector may require additional materials, information, reports and plans, as determined necessary, to review and evaluate the proposed action. If the proposed action requires a Planning Board Wetland Permit, the application materials outlined under §217-7 of the Town Code must be submitted, unless waived by the Planning Board. The Planning Board may establish an initial escrow deposit to cover the cost of application/plan review and inspections conducted by the Town's consultants.

For administrative wetland permits, see attached Administrative Wetland Permit Fee Schedule.

Owner Signature:

Date:	June	27,	2023
-------	------	-----	------

Application No.:

Fee: ____ Date:

TOWN OF LEWISBORO STORMWATER PERMIT APPLICATION

79 Bouton Road, South Salem, NY 10590 Phone: (914) 763-5592 Fax: (914) 875-9148

Project Address:96 Post Office Rd	
Sheet: <u>10812</u> Block: <u>003</u> Lot(s): <u>0025</u>	
Project Description (describe overall project including all propo Construct new residence, OWTS & Well	sed land development activities):
Owner's Name:wDesigne / Alex Bernabo	_ Phone: (914) 906-1336
Owner's Address: <u>3867</u> Danbury Rd, Brewster, NY 10509	Email:info@wdesigne.com
Applicant's Name (if different):	Phone:
Applicant's Address:	_Email:
Agent's Name (if applicable): <u>Peder Scott, P.E., R.A.</u>	Phone:845-278-2110
Agent's Address: <u>3871 Danbury Rd, Brewster, NY 10509</u>	Email:pwscott@pwscott.com

TO BE COMPLETED BY OWNER/APPLICANT

The approval authority is? (see §189-5 of the Town Code)

□ Town Engineer and Stormwater Management Officer ≱ Planning Board

Is the project located within the NYCDEP Watershed? $at the Yes \square No$

Total area of proposed disturbance: 🖄 5,000 s.f. - < 1 acre 👘 □ ≥1 acre

Will the project require coverage under the NYSDEC General Permit for Stormwater Discharges from Construction Activity? \bowtie Yes \Box No \Box Requires post-construction stormwater practice

Does the proposed action require any other permits/approvals from other agencies/departments? (Wetland Inspector, Planning Board, Town Board, Zoning Board of Appeals, Building Department, Town Highway, ACARC, NYSDEC, NYCDEP, WCDOH, NYSDOT, etc): Identify all other permits/approvals required: NYCDEP IRSP Approved: 6/13/23; WCDOH Approved: #L2023 dated 6/26/23

Note: The applicant, owner and/or agent is responsible for reviewing and complying with Chapter 189, "Stormwater Management and Erosion and Sediment Control," of the Town Code. This application must be submitted with all applicable plans, reports and documentation specified under §189-8, "SWPPP requirements," of the Town Code; all SWPPP's shall be prepared in conformance with Chapter 189 and shall be prepared by a qualified professional, as defined therein. The provision for obtaining a Town Stormwater Permit is in addition to the requirement of obtaining overage under the SPDES General Permit for Stormwater Discharges from Construction Activity, if applicable.

Owner Signature:

Date: 6/26/23

TOWN OF LEWISBORO PLANNING BOARD

79 Bouton Road, South Salem, NY 10590 Email: <u>planning@lewisborogov.com</u> Tel: (914) 763-5592 Fax: (914) 875-9148

Affidavit of Ownership

State of :	New York			,		
County of:	Westchester			,		
Alex Bernabo	o (wDesigne, I	nc.)	_ being duly swo	rn, deposes	and says that he/sh	e
resides at2	Avery Dr, Maho	pac, NY 10541		•	· ,	-
in the County o	fPutnan	n		State of	NY	
and that he/she	e is (check one)	X the owner, or	the	15 MJ 18 40 M 19 M 1		
of	wDesigne, Inc.			Title		
Na	me of corporation	, partnership, or oth	er legal entity			N PER PARAMAN AND
which is the ow	mer, in fee of all th	hat certain log, piec	e or parcel of land	l situated, l	ying and being in the	9
Town of Lewisb	ooro, New York, af	foresaid and know a	and designated or	n the Tax M	ap in the Town of	
Lewisboro as:						
Block	10812, i	Lot 3		25		
ر ب		(Bli			
		Owner's	Signature			
Sworn to befor	e me this	<i>41</i>	and a second	and a second		
	May		023			
\wedge	\mathcal{O}_{A}	<i>,</i>				
feli.	las 1	FFLIX F BF		le la		
Notary Public -	affix stamp	Notary Public - S	tate of New York			
		Qualified in O My Commission Ex	range County pires Feb 7, 2026		Revise	ed 2-2019
		and the second		perilin.		

TOWN OF LEWISBORO PLANNING BOARD

79 Bouton Road, South Salem, NY 10590 Email: <u>planning@lewisborogov.com</u> Tel: (914) 763-5592 Fax: (914) 875-9148

Tax Payment Affidavit Requirement

This form must accompany all applications to the Planning Board.

Under regulations adopted by the Town of Lewisboro, the Planning Board may not accept any application unless an affidavit from the Town of Lewisboro Receiver of Taxes is on file in the Planning Board office. The affidavit must show that all amounts due to the Town of Lewisboro as real estate taxes and special assessments on the total area encompassed by the application, together with all penalties and interest thereon, kave been paid.

Under New York State law, the Westchester County Clerk may not accept any subdivision map for filing unless the same type of affidavit from the Town of Lewisboro Receiver of Taxes is submitted by the applicant at the time of filing.

This form must be completed by the applicant and must accompany all applications to the Planning Board. Upon receipt, the Planning Board Secretary will send the form to the Receiver of Taxes for signature and notarization. If preferred, the applicant may directly obtain the signature of the Receiver of Taxes and notarization prior to submission.

Alex Bernabo	To Be Completed by Applicant (Please type or print)		
w-Designe, Inc. 96 Post Office Rd			
Name of Applicant Project Name			
Property Description 10812	Property Assessed to:		
Tax Block(s): $-43.1, -1-2$	wDesigne, Inc		
Tax Lot(s):3	Name 3867 Danbury Rd		
Tax Sheet(s): 25	Address Brewster	NY	10509
•	City	State	Zip

The undersigned, being duly sworn deposes and says that a search of the tax records in the office of the Receiver of Taxes, Town of Lewisboro, reveals that all amounts due to the Town of Lewisboro as real estate taxes and special assessments, together with all penalties and interest thereon, affecting the premises described below, have been paid.

Signature Receiver of Taxes: Une Baust 515123 Date Sworn to before me this 2023 day of JANET L. DONOHUE NOTARY PUBLIC, STATE OF NEW YORK No. 01D06259627 Qualified in Westchester County Commission Expires April 16, 202 Signature - Notary Public (affix stamp)

96 Post Office Rd, Waccabuc, NY (T) Lewisboro

Area Wetland Impact Table

Residence & Garage & Deck

Sediment Trap: Well and water line Subtotal: 9.306 sf = 0.213 acres

Wetland Buffer Area -100 ft Subtotal: 13,471 sf = 0.309 acres

Total Site Disturbance: 0.52 acres

ŧ

Short Environmental Assessment Form Part 1 - Project Information

Instructions for Completing

Part 1 – Project Information. The applicant or project sponsor is responsible for the completion of Part 1. Responses become part of the application for approval or funding, are subject to public review, and may be subject to further verification. Complete Part 1 based on information currently available. If additional research or investigation would be needed to fully respond to any item, please answer as thoroughly as possible based on current information.

Complete all items in Part 1. You may also provide any additional information which you believe will be needed by or useful to the lead agency; attach additional pages as necessary to supplement any item.

Part 1 – Project and Sponsor Information		
Name of Action or Project:		
96 Post Office Rd		
Project Location (describe, and attach a location map):		
96 Post Office Rd		
Brief Description of Proposed Action:		
Construction of 2,600 sf single family 2-bedroom residence with a 600 sf garage with a gra sewage disposal system (OWTS) with 12' of fill, 1,000 gal. septic tank and 1,000 gal. pump	vel driveway and individual we tank.	II and individual subsurface
Name of Applicant or Sponsor:	Telephone: 845-278-211	0
Peder Scott, P.E., R.A.	E-Mail: pwscott@pwscot	it.com
Address:		
PW Scott Engineering & Architecture, PC		
City/PO:	State:	Zip Code:
Brewster	NY	10509
1. Does the proposed action only involve the legislative adoption of a plan, loc administrative rule, or regulation?	al law, ordinance,	NO YES
If Yes, attach a narrative description of the intent of the proposed action and the	environmental resources th	
may be affected in the municipality and proceed to Part 2. If no, continue to que	stion 2.	
2. Does the proposed action require a permit, approval or funding from any oth	er government Agency?	NO YES
If Yes, list agency(s) name and permit or approval: NYCDEP, WCDOH, Town Building Permit	of Lewisboro, Wetland Pe	rmit,
3. a. Total acreage of the site of the proposed action? 4.04 acres		
b. Total acreage to be physically disturbed?	0.45 acres	
c. Total acreage (project site and any contiguous properties) owned or controlled by the applicant or project sponsor?	4.04 acres	
4. Check all land uses that occur on, are adjoining or near the proposed action:		
Urban 🔲 Rural (non-agriculture) 🗌 Industrial 🔲 Commerci	al 🔲 Residential (subur	·ban)
Forest 🔲 Agriculture 🗌 Aquatic 🔽 Other(Spe	cify): Wetlands	
Parkland	- /	

5. Is the proposed action,	NO	YES	N/A
a. A permitted use under the zoning regulations?		\checkmark	
b. Consistent with the adopted comprehensive plan?		\checkmark	
C la the money and extign acceptent with the mode winest share star of the switting hould be set on the desce of		NO	YES
6. Is the proposed action consistent with the predominant character of the existing built or natural landscape?			
7. Is the site of the proposed action located in, or does it adjoin, a state listed Critical Environmental Area?		NO	YES
If Yes, identify:			

8. a. Will the proposed action result in a substantial increase in traffic above present levels?		NO	YES
b. Are public transportation services available at or near the site of the proposed action?			
A reary padestrian accommodations or biguals routes available on or near the site of the proposed			
action?			
9. Does the proposed action meet or exceed the state energy code requirements?		NO	YES
If the proposed action will exceed requirements, describe design features and technologies:			
			\checkmark
10. Will the proposed action connect to an existing public/private water supply?		NO	YES
If No, describe method for providing potable water:			
		\checkmark	
11. Will the proposed action connect to existing wastewater utilities?		NO	YES
If No, describe method for providing wastewater treatment:			
12. a. Does the project site contain, or is it substantially contiguous to, a building, archaeological site, or district	t	NO	YES
which is listed on the National or State Register of Historic Places, or that has been determined by the			
State Register of Historic Places?			
b. Is the project site, or any portion of it, located in or adjacent to an area designated as sensitive for archaeological sites on the NY State Historic Preservation Office (SHPO) archaeological site inventory?			
13. a. Does any portion of the site of the proposed action, or lands adjoining the proposed action, contain wetlands or other waterbodies regulated by a federal, state or local agency?		NO	YES
b. Would the proposed action physically alter, or encroach into, any existing wetland or waterbody?			
If Yes, identify the wetland or waterbody and extent of alterations in square feet or acres:			
Local wetland. Waterbody Tributary to NYSDEC River - 864-317 Class A (T)			

14. Identify the typical habitat types that occur on, or are likely to be found on the project site. Check all that apply:		
Shoreline 🔽 Forest 🗌 Agricultural/grasslands 🔲 Early mid-successional		
✓ Wetland □ Urban □ Suburban		
15. Does the site of the proposed action contain any species of animal, or associated habitats, listed by the State or	NO	YES
Federal government as threatened or endangered? Long Eared Bat		\checkmark
16. Is the project site located in the 100-year flood plan? Stream is beyond flood zone.	NO	YES
	\checkmark	
17. Will the proposed action create storm water discharge, either from point or non-point sources?	NO	YES
If Yes,		\checkmark
a. Will storm water discharges flow to adjacent properties?		\checkmark
b. Will storm water discharges be directed to established conveyance systems (runoff and storm drains)?		\checkmark
Discharges to wetland & stream which bisects the property.		
18 Does the proposed action include construction or other activities that would result in the impoundment of water	NO	VES
or other liquids (e.g., retention pond, waste lagoon, dam)?	NO	ILS
If Yes, explain the purpose and size of the impoundment:		
19. Has the site of the proposed action or an adjoining property been the location of an active or closed solid waste management facility?	NO	YES
If Yes, describe:		
		L
20.Has the site of the proposed action or an adjoining property been the subject of remediation (ongoing or	NO	YES
If Yes, describe:		
L CEDTIEV THAT THE INFORMATION DOWIDED ADOVE IS THE AND ACCURATE TO THE DE		
MY KNOWLEDGE	SI UF	
Applicant/sponsor/name: Peder/Scott, P.E., R.A. Date: April 5, 2023		
Signature:Ittle:Ittle:I		

PRINT FORM



Pursuant to the authority granted under:

Article 11 of the New York State Public Health Law.

Rules and Regulations for The Protection from Contamination, Degradation and Pollution of The New York City Water Supply and Its Sources, 15 RCNY Chapter 18, 10 NYCRR Part 128.

New York City Department of Environmental Protection (DEP) makes the following determinations with respect to the individual residential stormwater permit (IRSP) described below:

Name of Project: 96 Post Office Road

- Location: Tax Map # 43.1-1-2 96 Post Office Road Town of Lewisboro Westchester, New York
- **Owner:** Alex Bernabo
- Address: 3867 Danbury Road Brewster, New York 10509
- **Drainage Basin:** Cross River Reservoir Basin

General Description:

The project proposes the construction of a single family residence in the Town of Lewisboro, Westchester County. An Individual Residential Stormwater Permit (IRSP) is required for the project by Section §18-39 (e)(1)(i) of the "Rules and Regulations for the Protection from Contamination, Degradation and Pollution of the New York City Water Supply and Its Sources" (Watershed Regulations) as the proposed residence is within 100 feet of a watercourse. The total disturbance is approximately 0.45 acres with 3,200 square feet of impervious surfaces proposed. The proposed stormwater management practice, a 31' x 20' concrete planter, will capture and treat runoff from the proposed impervious surfaces.

The entire 4.04-acre site is situated in the Town of Lewisboro, Westchester County, New York. The project site is identified Tax Map # 43.1-1-2 on the Town of Lewisboro Tax Maps and is located in the Town's residential zoning district.

The Individual Residential Stormwater Permit (IRSP) shall be implemented in accordance with the Individual Residential Stormwater Report dated April 6, 2023, and set of drawings prepared

96 Post Office Road (T) Lewisboro

June 13, 2023 Page 2 of 5

for 96 Post Office Road, Town of Lewisboro, Westchester County, New York, revised March 30, 2023, prepared by Peder W. Scott, P.E.

Date(s) of site inspection:

October 2002

(XX) Approved

() Denied

Conditions of Approval:

This approval is granted with the following conditions:

- The regulated activity must be conducted in compliance with the plans as approved, listed in Appendix A, all applicable accepted standards, and all applicable laws, rules, and regulations.
- Any alteration or modification of the IRSP must be approved by DEP prior to implementation; DEP may opt to issue an amended IRSP Determination.
- The applicant must schedule a pre-construction conference prior to the start of construction. Present at the meeting should be the applicant, the design engineer, the general contractor, and DEP staff.
- The applicant must notify DEP at least forty-eight (48) hours prior to the commencement of construction activity so that compliance inspections may be scheduled by DEP.
- All erosion and sediment controls must be properly installed and maintained until the site has been stabilized and the risk of erosion eliminated. Final stabilization is defined in the General Permit as all soil disturbing activities at the site have been completed, and that a uniform perennial vegetative cover with a density of 80% cover for the area has been established or equivalent stabilization measures (such as the use of mulches or geotextiles) have been employed.
- At the completion of the project, the applicant is required to submit as-built drawings for all stormwater management, runoff reduction and water quality facilities.

96 Post Office Road (T) Lewisboro June 13, 2023 Page 3 of 5

- The stormwater management and water quality facilities must be maintained in accordance with the maintenance schedule included in the IRSP as approved by DEP.
- This approval shall expire and thereafter be null and void unless construction is completed within two (2) years of the date of issuance or within any extended period of time approved by DEP upon good cause shown.
- In the event that the material submitted is inaccurate or misleading, this approval is not valid, and construction of this project is in violation of DEP regulations.
- Failure to comply with any of the conditions of this approval is a violation of this approval and the *Rules and Regulations for The Protection from Contamination, Degradation and Pollution of The New York City Water Supply and Its Sources.*
- A copy of the approved plans and determination should be maintained for record, and a copy must be available for inspection at the construction site.
- DEP shall be provided access to the project site during the construction phase for monitoring and inspection purposes.
- This approval and all conditions of the approval are binding on the owner of the property where the facility is to be located. Any references to the "applicant" in this approval or in any conditions of this approval shall be deemed to refer to the owner of such property.
- If the applicant sells or otherwise transfers title of 96 Post Office Road before all construction planned for the property is completed and the site is stabilized, the applicant shall require the new owner ("Buyer") to comply with the IRSP approved by the New York City Department of Environmental Protection on December 15, 2021 including, but not limited to, conservation easements, negative covenants, all provisions relating to erosion and sediment control during construction and to all maintenance of the stormwater management facilities once construction is complete. In particular, the applicant shall provide the Buyer with a copy of the IRSP and shall cause the following real covenants and restrictions to be recorded with the deed for 96 Post Office Road with the following provisions:
 - (1) Buyer hereby acknowledges, covenants, warrants, and represents that he/she shall install and maintain any and all erosion controls and stormwater management facilities on the premises in accordance with the IRSP, such IRSP being attached hereto as Exhibit ___.

96 Post Office Road (T) Lewisboro

June 13, 2023 Page 4 of 5

- (2) Buyer's installation and maintenance of the erosion control and stormwater management facilities shall be for the benefit of the City of New York as well as for the owners of **96 Post Office Road, Town of Lewisboro, Westchester County, NY.**
- (3) Buyer's obligation to install and maintain any and all erosion controls and stormwater management facilities on the premises in accordance with the attached IRSP shall be perpetual, shall run with the land, and shall be binding on Buyer's heirs, successors, and assigns.
- (4) Buyer hereby covenants, warrants and represents that any lease, mortgage, subdivision, or other transfer of 96 Post Office Road, Town of Lewisboro, Westchester County, NY, IRSP, or any interest therein, shall be subject to the restrictive covenants contained herein pertaining to the installation and maintenance of erosion control and stormwater management facilities, and any deed, mortgage, or other instrument of conveyance shall specifically refer to the attached SWPPP and shall specifically state that the interest thereby conveyed is subject to covenants and restrictions contained herein.
- Prior to conveying title to 96 Post Office Road, Town of Lewisboro, Westchester County, NY, the applicant shall submit to the New York City Department of Environmental Protection a proposed deed containing the aforementioned real covenants and restrictions.

Date: June 13, 2023

Determination made by:

Danny Shedlo, P.E. Section Chief EOH Project Review Group Regulatory & Engineering Programs

96 Post Office Road (T) Lewisboro June 13, 2023 Page 5 of 5

APPENDIX A

The following documents were prepared by Peder W. Scott, P.E.:

- 1. Individual Residential Stormwater Report, prepared for 96 Post Office Road, Town of Lewisboro, Westchester County, New York, dated March 28, 2023.
- 2. Drawing SY-1 titled "IRSP Erosion Control Plan" prepared for 96 Post Office Road, Town of Lewisboro, Westchester County, New York, dated March 30, 2023.
- 3. Drawing SY-2 titled "Concrete Planter Details" prepared for 96 Post Office Road, Town of Lewisboro, Westchester County, New York, dated March 30, 2023.
- 4. Drawing D-1 titled "Pre-Post Drainage Overlay" prepared for 96 Post Office Road, Town of Lewisboro, Westchester County, New York, dated September 20, 2021.

Environmental Protection

Rohit T. Aggarwala Commissioner

Paul V. Rush, P.E. Deputy Commissioner

P.O. Box 358 Grahamsville, NY 12740

Tel. (845) 340-7800 Fax (845) 334-7175 prush@dep.nyc.gov Mr. Peder W. Scott, P.E., R.A. P. W. Scott Engineering & Architecture, PC 3871 Danbury Road Brewster, New York 10509

Re: 96 Post Office Road - IRSP Tax Map# 43.1-1-2 (T) Lewisboro; (C) Westchester East Branch Reservoir Drainage Basin DEP Log #1998-CR-0637-IR.2

Dear Mr. Scott:

This letter is to inform you that your application to engage in the above referenced regulated activity pursuant to the "Rules and Regulations for the Protection from Contamination, Degradation, and Pollution of the New York City Water Supply and its Sources" (Regulations) was *approved* on June 13, 2023.

The Department reserves the right to modify, suspend, or revoke this approval based on the grounds set forth in Section §18-26 of the Regulations.

The activity proposed in your application only applies to the terms of this approval and are subject to the Regulations cited above. Failure to comply with the conditions of the approval may be the cause for suspension of this approval and initiation of an enforcement action. Should modification, suspension or revocation of an approval be necessary, DEP will notify the regulated party, via mail or personal service, prior to modifying, suspending, or revoking the approval. The notice will state the alleged facts or conduct which appear to warrant the intended action and explain the procedures to be followed.

The Regulations provide that an applicant may appeal the imposition of a substantial condition in an approval by filing a petition, in writing, with NYC DEP and with the New York City Office of Administrative Trials and Hearings ("OATH") within thirty (30) days of the date if this determination was mailed.

If you have any questions, please contact the undersigned at (914)749-5266.

June 13, 2023

Sincerely,

Danny Shedlo, P.E. Section Chief EOH - Regulatory & Engineering Programs

c: Town of Lewisboro Planning Board – <u>planning@lewisborogov.com</u> Natalie S. Browne, NYS DEC – <u>natalie.browne@dec.nv.gov</u>

5	UE @ 140#/ACRE; . RYE @ 33#/ACRE; .1 SS BLEND @ 44#/ACRE; .1	3.3∦/1000 SF.)7∦/1000 SF.)0∦/1000 SF.	· .
	SPECIFICATIONS		MULCH SPECIFICATIONS
CITY OF NEW YORK DEPT. OF ENVIRONMENTAL PROTECTION BUREAU OF WATER SUPPLY REGULATORY AND ENGINEERING PROGRAMS APPROVED			
NECT TO SPECIFIED CONDITIONS IN		REFER TO SHEET SY2	FOR EROSION CONTROL NOTES
Cley H CH PE		TEMPORARY & P	ERMANENT
PROVED BY		THE REQUIRED PARTIES RES STORMWATER FACILITY INSP CONSISTS OF THE LAND OWN	PONSIBLE FOR FOR THE IMPLEMENTATION OF ECTION AND AND MAINTENANCE PROGRAM JER DURING & AFTER CONSTRUCTION:
		GWNEP:	ALEX REPNABD WDECIGNE, INC.
and a second sec	***	ADDREGS:	3867 DANEURY ROAD BREWSTER NY 10509
Maintenance and Sediment Removal			EMAIL: Info@wdesigne.con
Union material when a "bulge" develops, ensure tence	κ.		IELE #: (914)-906-1336
extends into soil and fence upright, staple fencing Fix fence up right and staple as required to ensure integrity. Remove material when a "bulge" develops, ensure fence		ALL SITE WORK THE DIRECT SUP	SHALL BE COMPLETED UNDER ERVISION OF A LICENSED STATE OF NEW YORK.
extends into soil and fence is upright, starte tenong Repair Top Dressing with additional aggregate and	Title IRSP EROSIC	N CONTROL PLAN	Seal Dwg. No.
Bi-weekly, remove sediment, set stones to correct profile, fix berm blow-outs	et Tille 96 POST OFFIC	E ROAD, LEWISBORO,N	MARINEOVA
Due to the downhill proximity of the well, it is recommended to remove the concrete off-site once curred	No. 21-110	Drawn by MA/PWS	
THESE DRAWINGS ARE THE SO NOT BE REPRODUCED BY ANY PERMISSION OF P.W. SCOTT EI	LF 3/30/23	Scale AS NOTED	

Ł



NYSDEC Mapper 96 Post Office Rd, Waccabuc



NYSDEC Mapper 96 Post Office Rd, Waccabuc





NRCS Soil Map 96 Post Office Rd, Waccabuc

Brev 387 Brev n of Lev puton R	wisboro	A Architecture, P.C. www.pwscott.com iry Rd (845) 278-2110 Y 10509 V Letter of Transmittal
Brev brof Lev bouton R n Salem	wisboro	<u>Y 10509</u> Letter of Transmittal
n of Lev outon R n Salerr	wisboro	Letter of Transmittal
n of Lev outon R n Salem	wisboro	Letter of Transmittal
n of Lev outon R n Salem	wisboro	
outon R 1 Salem	1	Planning Board Date: July 10, 2023
n Salem		
	1, NY 10	S90 Re: 96 Post Office Rd, Waccabuc
ding v	vou: ∎	Attached
ing(s)		\Box Letter(s) \Box Plans \Box Misc Documents
Date	Pages	Description
26/23	1	wDesigne Inc ck # 5024 - \$410 – Wetland Permit & Stormwater Permit Fees (\$255 & \$1
26/23	1	wDesigne Inc ck # 5025 - \$2,000– Escrow
20/23	1	Town Environmental Questionnaire
27/23	1	Wetland Permit Application
26/23	1	Stormwater Permit Application
15/23	1	Affidavit of Ownership (notarized)
15/23	1	Tax Payment Affidavit (notarized)
30/23	5	Ecological Solutions, LLC Wetland Assessment
27/23	1	PWS Area Wetland Impact Table
5/23	3	SFEAF
13/23	8	NYCDEP IRSP Permit Approval
27/23	1	NYSDEC Mapper (color)
27/23	1	Aerial Photo (color)
27/23	1	NRCS Soil Map (color)
25/23	3	CS, SY1, SY2 (24 x 36) (signed and stamped)
28/23	1	A-1.0 (11 x 17)
	ate 6/23 6/23 0/23 7/23 5/23 5/23 7/23	ate Pages $6/23$ 1 $6/23$ 1 $6/23$ 1 $6/23$ 1 $7/23$ 1 $7/23$ 1 $5/23$ 1 $5/23$ 1 $5/23$ 1 $7/23$ 1 $7/23$ 3 $3/23$ 8 $7/23$ 1 $7/23$ 1 $7/23$ 1 $7/23$ 1 $7/23$ 1 $7/23$ 1 $7/23$ 1 $7/23$ 1 $7/23$ 1 $7/23$ 1 $7/23$ 1 $7/23$ 1 $7/23$ 1 $7/23$ 1 $7/23$ 1

□ For Your Use/Records	Approved as N	loted 🗌	As Requeste
\Box Returned for Corrections	Return	Corrected Prints	For Review

	As Requested
nts	For Review & Comment

Remarks:	Fed Ex_	
Copy To		



Stream	n Buffer	Plants			
SYM	Quant.	Botanical Name	Common Name	Caliper/Cont.	Spacing
<u>Shrubs</u>					
AA	6	Amelanchier arborea	Common serviceberry	2 gal.	5'
CA	6	Clethra alnifolia	Sweet pepperbush	2 gal.	5'
CR	6	Cornus racemosa	Gray dogwood	2 gal.	6'
IG	6	llex glabra	Inkberry	2 gal.	8'
LB	6	Lindera benzoin	Spicebush	2 gal.	6'
RP	6	Rhododendron periclymenoides	Pinkster azalea	2 gal.	<mark>8</mark> '
VP	6	Vaccinium pallidum	Blue Ridge blueberry	2 gal.	8'
	42				

EE STRAW. FENCING FOR 3		P. W. SCOTT	 No.	Re Date	evisions Description	Dwg. Tit	le C	OVER SH	EET	Seal	D	wg. No.
	NOTE: DO NOT SCALE DRAWINGS	ENGINEERING & ARG	CHITECTURE, P.C.			Project	Title 96 POST LEWISE	OFFICE ROAD BORO, NY				$\cap \cap$
PERTY OF P.W. SCOTT ENGINEERING A	AND ARCHITECTS, P.C. AND WILL	3871 ROUTE 6				Proj. No	· 21—110	Drawn by	MA/PWS			60
AND BE GIVEN TO ANY OTHER TRADES/PERSONS WITHOUT THE EXPRESS NG AND ARCHITECTS, P.C.		BREWSTER, NY 10509 845-278-2110				Date 5/25/23 s		Scale	AS NOTED			





Zoning Tabluation Zone: RA4

	Required	Proposed
Min. Lot Area:	4.0	4.04
Lot Width (circle ft):	250.0	320.0
Min. Yards		
Front - Street Center Line	75.0	713.0*
Front - Front Lot Line	50.0	54.0
Side Setback:	50.0	53.51
Rear Setback:	50.0	439.14
Max. Building Steel		
Stories	2.5 Stories	1 Story
Feet	35 Feet	22 Feet
Max. Building Coverage:		
House & Planter Footprint:		
3,780 sf	6.0%	2.10%
Treatment Planter: 584 sf		
(included in coverage)		
Including Deck: 1500 sf		3.0%

Disturbances Proposed		
Wetland:	0.215 acre	house & planter
Upland areas:	0.53 acre	driveway & SSDS Area

DRAWING LIST

		Issue Date		
#	Drawing	5/30/2023		
CS	COVER SHEET	Х		
SY1	IRSP EROSION CONTROL PLAN	Х		
SY2	CONCRETE PLANTER DETAILS	Х		
SP1	SEPTIC PLAN - NEW CONSTRUCTION	X		

LEGEND JO QUANTITY JO SPECIES (+)PLANT SYMBOLS

------ DEER FENCING ADJACENT TO SPLIT RAIL FENCE

PROPERTY IDENTIFICATION

UWNER:	ALEX BERNABO wdesigne, inc.
ADDRESS:	3867 DANBURY ROAD Brewster ny 10509
E911 # :	96 POST OFFICE ROAD, LEWISBORD
LEWISBORD T.M.	SHEET 25 BLOCK 10812 LOT 3
PROPERTY ADDRESS	96 POST OFFICE ROAD Lewisbord, ny 10590
NYC DEP WATERSHE	D: CROSS RIVER BASIN
AREA OF HOUSE PROPOSED:: # BEDROOMS:	2600 SF+ 600SF GARAGE 2 BEDROOM



. .

DATE: 06/28/2023				
DRAWN BY: M. ORDONE				
ARCHITECT:				
ZONE: XXXX SEC: 00.0 BLK: 00 LOT: 00				
PROPOSED GROUND LEVEL FLOOR PLAN AND ELEVATIONS A-1.				
SD DESIGN WHITE PLAINS, NY 10606 (914) 879-5411				
NUNZIO PIETROSANTI CONSULTING ENGINEER 63 DOVER LANE YONKERS, NEW YORK 10710 (914) 760-0528				
BERNABO RESIDENCE POST OFFICE ROAD WACCABUC, NY				

۰.



EROSION CONTROL LEGEND						
NO.	SYMBOL	DESCRIPTION	STATUS			
1		SILT FENCE	TEMPORARY SEE DET. 1/SY1 PLACE PARALLEL TO GRADE-CONTOU			
2	-00	CONSTRUCTION FENCE	AROUND EDGE SEPTIC FILL: SEE DET.2/SY			
3	٢	TOPSOIL STOCKPILE AREA	<u>temporary see det. 3/sy1</u> Ring with silt fence			
4		CONSTRUCTION ENTRANCE	<u>TEMPORARY SEE DET. 4/SY1</u> PLACE @ EA. POINT OF ENTRY INTO SI			
5		STONE OUTLET SEDIMENT TRAP	<u>PERMANENT SEE DET. 5/SY1</u>			
6		CONCRETE PUMP OUT TRAP	TEMPORARY SEE DET. 6/SY1			
7		SEED & MULCH SPECIFICATIONS	<u>TEMPORARY SEE DET. 7/SY1</u>			
8		STORAGE AREA				
9	LD	LIMIT OF DISTURBANCE				

<u>Maintenance Schedule – During Construction – Temporary Structures</u>

_	<u>Component</u>	<u>MINIMUM</u> Inspection <u>Required</u>	<u>After</u> <u>Every</u> <u>Storm</u> <u>Event</u>	Item to Inspect	<u>Sediment</u> <u>Removal</u> <u>Req'd</u>	Special Inspection Items Inspect the following:	Maintenance and Sediment Removal
1	Silt Fence	Bi-Weekly	Х	Woven Wire Fence Alignment	Yes	Woven Wire & Fence Stability	Remove material when a "bulge" develops, ensure fence extends into soil and fence upright, staple fencing
2	Construction Fence	Bi-Weekly		Fence Woven Wire Conditions	None	Fence posts and grid	Fix fence up right and staple as required to ensure integrity.
3	Topsoil Stockpile Area	Bi-Weekly	Х	Soil Pile Condition	None	Silt Fence at Base of Pile to be inspected and seeding reviewed.	Remove material when a "bulge" develops, ensure fence extends into soil and fence is upright, staple fencing
4	Construction Entrance	Weekly	Х	Stone Placement	None	Stone Placement & soil deposit between stones	Repair Top Dressing with additional aggregate and correct stone placement.
5	Stone Outlet Sediment Trap	Bi-Weekly	Х	Stone Placement & Location	Yes	Stone & Sediment Accumulation	Bi-weekly, remove sediment, set stones to correct profile, fix berm blow-outs
6	Concrete Pump Out	Monthly	Х	Soil Stability	None	Once filled topsoil, seed & mulch	Due to the downhill proximity of the well, it is recommended to remove the concrete off-site once curred

THESE DRAWINGS ARE THE SOLE PRO NOT BE REPRODUCED BY ANY MEANS PERMISSION OF P.W. SCOTT ENGINEERING AND ARCHITECTS, P.C.



				A	5/8/23	REVISE
NOTE: DO NOT SCALE DRAWINGS			ENGINEERING & ARCHITECTURE, P.C.			1
DIMENSIONS SUPERCEDE SCALE						
OPERTY OF P.W. SCOTT ENGINEERING AND ARCHITECTS, P.C. AND WILLMULCH	SPE	S	3871 ROUTE 6			<u> </u>
S AND BE GIVEN TO ANY OTHER TRADES/PERSONS WITHOUT THE EXPRESS			DEWSTED NV 10500 945 278 2110			
						í



THESE DRAWINGS ARE THE SOLE PRO NOT BE REPRODUCED BY ANY MEAN PERMISSION OF P.W. SCOTT ENGINE

	P. W. SCOTT	No.	Revisions Date Description	Dwg. Title	CONCRETE P	PLANTER	r details	Seal	 Dwg. No.
NOTE: DO NOT SCALE DRAWINGS	ENGINEERING & ARCHITECTURE, P.C.		5/8/23 NO REVISIONS	Project Title96	Project Title96 POST OFFICE ROAD, LEWISBORO,N			$O \setminus O$	
OPERTY OF P.W. SCOTT ENGINEERING AND ARCHITECTS, P.C. AND WILLMULCH	SPE SPE SA STANDARY STATES SPE			Proj. No. 21	-110	Drawn by	MA/PWS		SY2
IS AND BE GIVEN TO ANY OTHER TRADES/PERSONS WITHOUT THE EXPRESS	BREWSTER, NY	10509 845-278-2110		Date3/3	30/23	Scale	AS NOTED		

96 Post Office RdWaccabuc, NY(T) Lewisboro

IRSP INDIVIDUAL RESIDENTIAL STORMWATER PERMIT

Prepared by:

Peder W. Scott, P.E., R.A. P W Scott Engineering & Architecture, PC 3871 Danbury Rd (Route 6) Brewster, NY 10509

March 28, 2023

96 Post Office Rd Waccabuc, NY

TABLE OF CONTENTS

1.0 OBJECTIVE	5
2.0 THE OBJECTIVES OF THIS IRSP	
2.1 Owner's Responsibilities	
2.2 Contractor's Responsibilities	
2.3 NOI Compliance Requirements	
3.0 PROPOSED ACTIVITY	6
4.0 LOCATION AND TOPOGRAPHY	
4.1 Location Description	6
4.2 Existing Soil Conditions	7
4.3 Existing Watercourses	7
4.4 Existing Wetlands	7
4.5 Watershed Determination	7
4.6 Enforcement Actions	
5.0 PROPOSED PROJECT	
5.1 Proposal Description	
5.2 Proposed Buffers	
5.3 Stormwater Management	
5.4 Anticipated Permits	
5.4.1 New York State Department of Environmental	Conservation8
5.4.2 Town of Lewisboro	9
5.4.3 NYCDEP	
5.5 NOI Application Outline	9
6.0 POST-CONSTRUCTION WATER OUALITY AND O	UANTITY CONTROLS 9
6.1 Regulations	
6.1.1 NYSDEC Sizing Criteria	9
6.1.2 NYCDEP Requirements	
6.2 Design Analysis	
6.2.1 Comparison at Analysis Point A	
6.3 Nonstructural Stormwater Management	
6.4 Summary	
7.0 FLOW THROUGH PLANTER	12
7.1 Analysis of Site Uses	12
7.1.2 Proposed Treatment – Flow Through Planter	12
7.1.2 Treatment Analysis	13
7.2 Frosion and Sediment Controls	
7.3 Frosion and Sediment Control Practices – Tempora	v 14
7.3.1 Stabilized Construction Entrance / Evit	14
7.3.2 Silt Fence	14
7.3.3 Stocknile Detail	14
7.3.4 Dust Control	
7.3.5 Temporary Seeding and Stabilization	14
7.3.6 Temporary Diversion Swale	
7.3.7 Snow Removal	

	7.3.8 Materials Handling/Soil Stabilization	.15
7.4	Erosion and Sediment Control Practices - Permanent	.15
	7.4.1 Stone Outlet Sediment Trap	.15
	7.4.2 Concrete Flow Through Planter	.15
	-	
8.0 SEC	QUENCE OF CONSTRUCTION	. 15
9.0 INS	PECTION AND MAINTENANCE	. 16
9.1	Inspections and Record Keeping During Construction	. 16
	9.1.1 Record Forms	. 16
	9.1.2 Inspections	.17
	9.1.3 Erosion and Sediment Control Maintenance Measures	. 18
9.2	Maintenance Practices – Temporary	. 19
	9.2.1 Stabilized Construction Entrance/Exit	. 19
	9.2.2 Silt Fence	. 19
	9.2.3 Clean Material Stockpile	. 19
	9.2.4 Dust Control	. 19
	9.2.5 Temporary Seeding and Stabilization	. 19
	9.2.6 Construction Fence.	. 20
	9.2.7 Material Handling/Soil Stabilization	. 20
9.3	Maintenance Practices – Permanent	. 20
	9.3.1 Sediment Trap Stone Outlet	. 20
	9.3.2 Concrete Planter	. 20
9.4	Maintenance Requirements	. 20
	9.4.1 Responsible Entity	.21
9.5	Long Term Operation and Maintenance	.21
	9.5.1 Site Maintenance	. 21

APPENDIX A

A: Certifications B: Construction Inspection Logs C: Maintenance Schedule Temporary D: NOI Application -NYSDEC E: MS-4 SW PPP Acceptance Form filed with Town of Lewisboro F: Short Form EAF

FIGURES

Figure 1.0: Lot Aerial Photo Figure 2.0: NYSDEC Mapper Printout Figure 3.0: Soils Map

DRAWINGS (attached)

IRSP DRAWINGS

DRAWING	SY1:	IRSP Erosion Control Plan
DRAWING	SY2:	Concrete Planter Details
DRAWING	D1:	Pre & Post Drainage Overlays
DRAWING	A1:	Floor Plan Single Story Residence

OWTS DRAWINGS

DRAWING	SP1:	Septic Plan – New Construction
DRAWING	SP1A:	Overall Septic Site Plan
DRAWING	SP2:	Septic Details
DRAWING	SP3:	Pump Sheet Single Family – OWTS

1.0 Objective

P.W. Scott Engineering & Architecture, P.C. (PWSE&A, PC) prepared this Individual Residential Stormwater Pollution Permit Plan (IRSP) in accordance with the following applicable rules, regulations, and guidance documents:

- New York State Stormwater Management Design Manual, latest version produced by NYSDEC;
- New York State Standards and Specifications for Erosion and Sediment Control, latest version produced by NYSDEC;
- City of New York, Rules and Regulations for the Protection from Contamination, Degradation and Pollution of the New York City Water Supply and its Sources;
- Town of Lewisboro, Stormwater Management and Erosion and Sediment Control, Chapter 189.

2.0 The Objectives of this IRSP

- 1. Outline Owner and Contractor responsibilities to maintain compliance with SPDES GP-0-20-001, including required inspections, maintenance, forms, and certifications.
- 2. Outline measures to install, inspect, and maintain erosion and sediment control measures for the proposed project. The objective of these measures is to eliminate or significantly minimize pollutant discharges to the adjacent surface water bodies during construction activities.
- 3. Post construction water quality practices required for disturbance within 100 ft of NYSDEC wetland & watercourse.

2.1 Owner's Responsibilities

Alex Bernabo/wDesigne, Inc., the "Owner," is responsible to ensure that the Contractor installs and maintains the erosion and sediment control measures in accordance with this IRSP. The Owner is also responsible to ensure that the appropriate forms and certifications contained herein are completed prior to and throughout the duration of demolition and construction activities. The Owner shall keep a copy of this document, associated attachments, and any inspection reports generated on-site for the duration of the project and for a minimum of 5 years from the date that the site achieves final stabilization. The Owner should ensure that the provisions of the IRSP are implemented from the commencement of construction activity until all areas of disturbance have achieved final stabilization and the Notice of Termination (NOT) has been submitted to the appropriate NYSDEC office. The Owner should maintain a copy of the SPDES GP-0-20-001, Notice of Intent (NOI), NOI acknowledgement letter, IRSP, and inspection reports at the construction site until all disturbed areas have achieved final stabilization and the Notice of Termination (NOT) has been submitted to NYSDEC. The documents must be maintained in a secure location, such as a job trailer, on site construction office, or mailbox with lock that is accessible during normal working hours to an individual performing a compliance inspection. The owner can retain the services of Qualified Stormwater Management Firm for supervision and compliance.

Refer to Appendix A for certification.

2.2 Contractor's Responsibilities

The Contractor is responsible for reading this entire IRSP and related project specifications and reviewing all forms, certifications, and contract drawings to become familiar with all aspects related to the SPDES GP-0-20-001. The Contractor shall retain a signed copy of this IRSP and all associated attachments onsite from the initiation of the dredging and proposed fill activities to the date of final stabilization. The Contractor is responsible for completing the certification contained herein prior to the commencement of demolition and proposed construction activities. The certification shall be signed by a president or any person who performs similar decision-making functions and by the on-site individual having responsibility for the firm. Each of the subcontractors involved in the implementation of erosion and sediment control measures must also complete a certification. The Contractor is responsible for each of the subcontractors
employed by the Contractor that are involved in the implementation of erosion and sediment controls.

It is the duty of the Contractor to properly install and maintain all erosion and sediment control measures on the site as per this IRSP. The Contractor shall also be responsible for the inspection of all erosion and sediment control measures for the proposed project site by a qualified inspector as per this SWPPP. Should the Owner, an owner's representative, or any local authority having jurisdiction deem that the IRSP or the Contractor's implementation of the IRSP proves to be ineffective in eliminating or significantly minimizing the pollutants or achieving the goals of the SPDES GP-0-20-001, the Contractor shall take any necessary action to conform to the objectives of the permit at no additional cost to the Owner.

The Contractor shall inspect and report the disturbed and stabilized areas for the duration of the project as indicated on the Record of Stabilization and Demolition and Construction Activities form contained herein. It is the duty of the Contractor to properly inspect and maintain all erosion and sediment control measures installed on the site as per this IRSP. Any revision to the IRSP in design, demolition and construction activities, inspection, or maintenance shall be reflected by the Contractor must designate a qualified inspector. The Contractor shall coordinate with the Engineer of Record to ensure that all of the inspection requirements are in conformance with this IRSP and the requirements of the SPDES GP-0-20-001. On a **bi-weekly basis**, copies of all inspection forms and maintenance records shall be organized and filed accordingly by the Contractor.

Refer to Appendix A for certifications.

2.3 NOI Compliance Requirements

The owner/operator shall coordinate NOI compliance requirements including inspections by a qualified Stormwater Inspector (CPESC) or licensed Professional Engineer or Architect twice per week and before & after any significant storm event over a 2-year – 24-hour storm event. Refer to Section 9.1.1 of the IRSP for additional inspection criteria.

3.0 Proposed Activity

Construction of 2,600 sf single family 2-bedroom residence with a 600 sf garage with a gravel driveway and individual well and individual subsurface sewage disposal system (OWTS) with 12' of fill, 1,000 gal. septic tank and pump tank.

4.0 Location and Topography

4.1 Location Description

The subject property is located at 96 Post Office Rd, 500' north of Benedict Rd on Post Rd in the Town of Lewisboro. The subject parcel is identified as Tax Map: 25, Block: 10812, Lot: 3 of 4.04 acres.

Existing Condition

The site is a wooded parcel extending from a stone wall at as slope between 18% and 20% to a wetland area extending along a non-regulated stream.

The 2' contours follow the alignment of the front property line for the length of the lot along Post Office Rd. Refer to Dwg SP1.

4.2 Existing Soil Conditions

The following soils are found on the property or adjacent sites based on the United States Department of Agriculture (USDA) Natural Resource Conservation Service Soil Survey of Putnam and Westchester Counties, New York. Refer to Dwg SP1A.

The soils within the site consist of:

Soil	Hydrogeological Classification
Paxton Silt Loam Soil (Pc) - 8 to 15 percent slopes	С
Sun Loan (Sh)	D
Woodbridge (WdC) - 8 to 15 percent slopes	D

Project Site Soils			
Symbol	Soil Series Name	Hydrologic Soil Group	Drainage Characteristics
РЬС	Paxton fine sandy loam, 8 to 15 percent slopes	С	This soil is strongly sloping, very deep, and well drained. It is on tile sides and tops of broad ridges and small hills. (K factor 0.24 to 0.32)
Sh	Sun Loam, 0 to 3 percent slopes	D	This soil consists of very deep, poorly drained soil formed in till derived primarily from limestone and sandstone with smaller amounts of schist, shale and granite in some areas.
WdC	Woodbridge, 8 to 15 percent slopes	С	This is a very deep, moderately well drained, gently sloping soil on tops of hills, on side slopes, and on toe slopes within uplands.

Tab	le 4-1
Project	Site Soils

5. Source: Soil Survey of Putnam and Westchester Counties, New York, USDA Soil Conservation Service.

NoIr: * indicates soil unit is within the proposed footprint of disturbance. "K" Factor given indicates the erosion potential of each soil type. This indicates the susceptibility of a soil to sheet and rill erosion by water. Values of "K" range from 0.05 to 0.69. The higher the value the more susceptible the soil lo erosion.

4.3 Existing Watercourses

There is a stream which extends through the lot approximately 145 ft from the property line. The NYSDEC Mapper does not denote this stream under jurisdiction of the NYDSDEC.

4.4 Existing Wetlands

The wetlands were flagged for BIBO Associates Approval in 2003. There has been no change in the character of the wetlands. The line is defined by a 'WL' symbol on the site plan. All septic disturbances are beyond the edge of the wetland line. The house site and the planter are within the wetland with top or first floor elevations 6.0 ft above the existing elevation.

4.5 Watershed Determination

The watershed for the lot drains to the subject watercourse and then drains to the south toward the NYSDEC wetland # L50- Class 1 of 23.4 acres. The stream continues to drain to the south through a Regulated #864-317 River – Class A(T) to the Cross River Reservoir and the Croton Reservoir Watershed.

4.6 Enforcement Actions

The property was subdivided prior to 1980. The project was issued a waiver from NYCDEP for slopes exceeding 15% in 1998 under the name Konetchy (Tax ID: 25-10812-3), DEP Log# 1998-CR-0637-IR.

The waiver requires a renewal with an application pending with this submission.

A Judicial Decision dated Sept. 8, 2003 provided conditions of approval including the filing of a General Release to WCDOH prior to issuance of an Certificate of Completion. No enforcement actions are pending at this time.

5.0 Proposed Project

- 5.1 **Proposal Description** (Reference Site Plan on SY I) Site plan improvements include:
 - Construction of residence.
 - Construction of OWTS
 - Installation of well
 - Installation of concrete planter
 - Installation of gravel driveway & parking area
 - Installation of erosion control

Limits of Disturbance

The plans outline the project disturbances on Dwg SP1 as 0.45 acres - Refer to "L/D" Limit of Disturbance Line of this area.

Net area of disturbance under 2.0 acres.

5.2 **Proposed Buffers**

The plan utilizes the trees as a buffer on the neighbor's property to the north. A review of properties along Post Office Rd reveals that the proposed encroachment on the wetland & stream is consistent along this roadway.

5.3 Stormwater Management

The site is pervious with regards to the driveway and the septic area. The house and garage of 3,200 sf shall have roof leaders drain to a centrally located concrete flow through planter for treatment of the stormwater in compliance with the NYSDEC Manual – 2022. The planter is more than 50.0' from any portion of the OWTS except for the sealed PVC waste pipe extending from the house to the septic tank.

A computer model is completed with the roof draining to the concrete planter with a 12" flood zone above the planting soil providing limited attenuation.

5.4 Anticipated Permits

The following is a list of anticipated permits for the construction activities associated with the proposed project.

5.4.1 New York State Department of Environmental Conservation

Coverage under the SPDES GP-0-20-001 will be required as part of the proposed development with development over 5,000 sf in phosphorus restricted watershed. The IRSP is being prepared in compliance with the requirements of the New York State Stormwater Management Design Manual. NYSDEC Protection of Waters Permit is required (Part 608.8) Joint Application for Permit Form to be filed.

5.4.2 Town of Lewisboro

- Stormwater, Soil Erosion and Sediment Control Permit (Town Code Chapter 119)
- The Town of Lewisboro, as a regulated land use MS4 agent, is responsible to review the IRSP and complete the MS4 acceptance form prior to filing the Notice of Intent with the NYSDEC.

5.4.3 NYCDEP

Due to the addition of impervious roof within 100' of a watercourse an IRSP is required.

5.5 NOI Application Outline

Attached in Appendix D is the NYSDEC Application Outline form prepared by PWSE&A PC, which shall be filed with the Town of Lewisboro and subsequent issuance of an MS-4 permit number (pending). This basic data was used to register the scope of the project within the NYSDEC database.

6.0 Post-Construction Water Quality and Quantity Controls

Post-construction water quality and quantity controls are required to meet pollutant removal goals, reduce channel erosion, prevent overbank flooding, and control extreme floods. These controls help mitigate the effects of development by controlling suspended solids content and peak flows of runoff from developed sites. The NYSDEC has developed unified sizing criteria to size stormwater management measures. However, the project is located within the NYCDEP watershed where the IRSP design must also address specific NYCDEP requirements. The proposed stormwater management system has been designed to address the criteria outlined in Chapter IO - Enhanced Phosphorous Removal Supplement of the New York State Stormwater Management Design Manual (NYSSMDM). The implementation of a stormwater management system is integral in the mitigation of the potential impacts associated with the proposed project. The NYCDEP requirements for the treatment volume, also referred to as water quality volume (WQv), is to capture and treat the runoff generated from a 1-year, 24-hour storm event. The WQv and channel protection volume criteria will follow the NYCDEP requirements, as they are more stringent. The NYSDEC criteria for water quality is evaluated based upon reduction of impervious surfaces. The NYSDEC requirements for overbank flood and extreme storm are the same as NYCDEP requirements for attenuating the larger storm events.

The stormwater treatment practices have been designed to meet the current WRR, including the requirement that the stormwater ponds be designed to capture and treat the runoff generated from the 1-year, 24-hour storm (0NRcc 2.83 inch) event from new impervious surfaces. The NYSDEC requirement for Water Quality Volume (WQv) for enhanced phosphorous removal is to capture the estimated runoff from the I -year, 24-hour design storm. The method for estimating the runoff volume is based on the USDA NRCS Technical Release 20 and Technical Release 55.

6.1 Regulations

6.1.1 NYSDEC Sizing Criteria

The following table is representative of the storm design criteria required within the New York State Storm water Management Design Manual.

e inform Sizing eriteria			
Water Quality Volume (WQv)*	WQv	Detention of 1-year storm event	
Channel Protection (Cpv)*	Срv	 24 hour extended detention of post- developed 1-year, 24-hour storm event. Control the peak discharge from the 10-year storm to 10-year predevelopment rates. Control the peak discharge from the 100-year storm to 100-year predevelopment rates. Safely pass the 100-year storm event. 	
Overbank Flood (Qp)			
Extreme Storm (Qr)			

Table 6-1 NYSDEC Uniform Sizing Criteria

Runoff reduction Volume

*NYCDEP requirements more stringent

As the project is within the NYCDEP East of Hudson Watershed, the requirements and guidelines within Chapters 9 and 10 of the New York State Stormwater Management Design Manual were used to design the stormwater management system. The major portion of development that will occur in the area of the existing driveway and will incorporate the enhanced phosphorous requirements outlined in Chapter 10.

New York City Department of Environmental Protection Requirements 6.1.2

The project is located within the Croton Reservoir watershed, which is part of New York City's surface water drinking water supply. NYCDEP is currently operating under a Memorandum of Agreement with the United States Environmental Protection Agency for filtration avoidance. Under this agreement certain provisions regarding impervious surface and stormwater runoff were incorporated within the City of New York, Rules and Regulations for the Protection from Contamination, Degradation and Pollution of the New York City Water Supply and its Sources (WRR) promulgated in 1997 and revised in 2010. The following sections of the WRR regarding impervious surfaces and stormwater are applicable to this project.

Section 18-39(c) requires NYCDEP's review and approval of an IRSP. Section 18-39(c)(2) states that proposed development within a phosphorous restricted basin requires the capture and treatment of storm water runoff generated from a 1-year, 24-hour storm event.

Design Analysis 6.2

In order to evaluate the pre- and post-development drainage conditions, the site has been delineated into one discharge analysis point based on pre-development hydrology: Design Point A. This point was analyzed to evaluate the effects of the proposed development on surface water runoff. The design point and their pre- and post-development contributing subcatchment areas are shown on Pre- and Post-Development Drainage Maps, Drawings D1 & D2. Analysis Point A is the discharge point from the concrete planter which drains across the brush hillside to the edge of the property into the wetland and the stream bisecting the parcel.

To analyze the peak flow in pre-and post-development conditions Haestad Methods Pond Pack, a computer TR-55 based system is used to evaluate and analyze the stormwater runoff from the site. The program also models the surface flow through the proposed stormwater practices determining the center-of-mass detention time within the ponds. A simultaneous routing process is used to evaluate the impacts associated with stormwater practices in series. Runoff volumes and rates are calculated by determining the curve numbers (CN) and calculating the time of concentration (Tc) for each sub catchment area depending on the given rainfall value. The CN values are based on the TR55 table and the hydrologic soil

group, cover type, hydrologic condition, and antecedent runoff condition. The Tc represents the time it takes for surface water to travel the hydraulically most distant point within the sub catchment area. Since the site includes an existing pond, the existing and proposed ponds are modeled to determine attenuation characteristics of the site.

The following rainfall values for the site as noted on the NRCC Interactive Website, shown in Table 6-2, were used in the analysis. For the purposes of the hydrologic analysis the runoff was based on Type II rainfall distribution for the northeast region. The following rainfall values represent the rainfall distribution for various 24-hour storm frequencies.

Rainfall Value (inches)	24-hour Storm Event (Year) NRCC
2.82	1
3.40	2
5.08	10
9.04	100

Table 6-2 Rainfall Values

Source: NYSDEC Manual

6.2.1 Comparison At Analysis Point A (To The South)

The Pre & Post Discharges are listed as follows: (Includes offsite components not impacted with this property).

Analysis Point	А			
	1 YR (cfs)	2 YR (cfs)	10 YR (cfs)	100 YR (cfs)
PRE	.48	.73	1.53	3.60
POST	.42	.64	1.33	3.40
NET	-0.6	09	-0.20	-0.20
%	-12%	-12%	-13%	-5.6%

NYSDEC Attenuation Requirements

- A) 1-Year Storm Event-Channel Protection
 Detain 1-Year Storm 24 Hours
 Reduce by 50% from pre-development levels.
- B) 2-Year Storm Event
 Peak Discharge approx. reduced to 1-Year Storm Event.
- C) 1-Year Storm Event Overbank Control Attenuate to Pre-Development Levels
- D) 100-Year Storm Event Extreme Flood Control Attenuate to Pre-Development Levels

Findings

The following is an overall review of the project relative to hydraulic requirements of NYSDEC Stormwater Management. The discharge is divided around the disturbed areas with the resulting reduced watershed area meeting the required discharge levels.

A.	1-Year Storm Event	Channel protection could not be reduced by 50% even
		though planter did not discharge any of the 1-year storm.
		Large area of pervious cover discharges off site - reduction
		by 12%
B.	2-Year Storm Event	Reduced is reduced by 12%. Could not meet the pre-
		development discharge rate even though planter did not
		discharge any of the 2-year storm event. Large area of site
		drained directly into the wetland and stream.
C.	10-Year Storm Event	Attenuation met to pre-development levels.

D. 100-Year Storm Event Attenuation met to pre-development levels.

6.3 Nonstructural Stormwater Management

Nonstructural stormwater management practices include the following:

- Providing site access through the use of gravel driveway at 14% grade.
- Long-term soil stabilization through landscaping and maintenance in the developed areas. Prevention of soil loss, through establishment of vegetation and a landscape plan that will increase the amount of tree canopy and healthy ground cover. The landscape plan will also maximize the travel time of stormwater runoff and minimize concentrated flows.
- The grounds maintenance program limits the potential for excessive nutrient loading, specifically controlling the application of phosphate-based fertilizers to the lawns.
- Limiting development of site to 100' from front property lines

6.4 Summary

The proposed stormwater management system has been designed to attenuate the larger storm events to predevelopment conditions. The project is designed based on Chapter 10 of the NYSSMDM. The proposed drainage systems will be sufficient to mitigate the potential impacts of the proposed project related to the quantity of storm water runoff. Refer to the Green Practice Summary for the extent of Quality Treatment.

7.0 Flow Through Planter

Total volume reduction; reduced to 45% for Class-C soils.

7.1 Analysis of Site Uses

Residence	Metal Roof	Impervious	3,200 sf
Driveway	Gravel	Not Impervious	1,930 sf
Septic Area	Grass Cover		5,800 sf

Remaining site uses is grass in disturbed area (8,680 sf) with the remainder of the woods or wetlands same CN number.

Overall WQv Analysis

Limited to area of site disturbance: 19,701 sf

WQv = PRv A/12 Where P = 1-year storm event = 2.82 inches I = 3,200 sf roof = 0.073 acres % I = 16.3 Rv = .05 + .009 (16.3) = .197 WQv = 2.82 (1.97) (.045) / 12 = .012 acre-ft = 907 cubic feet

7.1.2 Proposed Treatment – Flow Through Planter

Treatment limited to roof only (no pretreatment required)

WQv Roof = PRvA / 12 Where P = 2.82 1-year storm Area = 3,200 sf Roof + 569 planter = 3,880 sf = .086I = 3200 / 3,770 = .84Rv = .05 + .009 (84) = .80

WQv = (2.82) (0.80) (.086) / 12 = .016 acre-ft = 696 cu ft 1-Year Storm Event (extreme precipitation) Q @ CN = 83 Volume 1-Year = (2.40 in) (3.200 sf) = 640 cu ft

Flow Through Planter

Size Infiltration Planter (RR7)
12" ponding depth
18" larger storm overflow through weirs in concrete perimeter walls
18" to 30" soils – propose df = 30"

 $AF = \underbrace{WQv \, df}_{k(hf + df) tf} = \underbrace{(696) 2.5}_{(6.0) (.5 + 2.5) (0.17)} = 568 \text{ sf}$ k = 18" leaf compost with 12" soil top = [8.6 (1.5) + 2.0 (1)] / 2.5 = 6.0 hf = 1.0 ft. / 2 = 0.5 ft tf = 4 hrs = .17 days

Make Filter 19.2 ft wide x 29.66 ft long = 569 sf (planter outside dimensions: 20' x 31.0') This is routed with (2) 12" weirs as overflow.

Note: Planter is more than 50.0 ft from OWTS including tank.

7.1.3 Treatment Analysis

RRv min = P Rv (imp) S/12 Rv = .95 Amp = 3,200 sf = 0.073 P = 2.82 in. 1-year storm S Class C = 0.30 RRv = 2.82 (.95) (.073) (.3) / 12 = .005 acre-ft = 213 cf

Treatment of Roof WQv by Planter

Class C - 45% efficient RRv = (696 cf) (.45) = 313 cf = 0.007 acre-ft

7.2 Erosion and Sediment Controls

The proposed work will have minimal impact on the site. Grading generally follows existing grades. In this way, significant impacts to topography and slopes will be avoided. The slope is approximately between 18% to 20%. The existing and proposed grading plan is shown on Drawing SP1. An outline of Erosion Control Practices are as follows:

A construction entrance is proposed off the driveway for access to the site. Construction fence will surround the perimeter (approx. 390 linear feet) of the proposed septic area. *A* line of silt fencing (approx. 245 linear feet) will be downhill of the house construction worksite. Other lengths of site fence (approx. 200 linear feet) will be placed as shown on the SP1. Once all erosion control is in place, the work may proceed.

7.3 Erosion and Sediment Control Practices - Temporary

The following are specific erosion control measures as identified in the drawings prepared for this project.

7.3.1 Stabilized Construction Entrance (SCE) /Exit

All construction entrances and exits shall have a stabilized aggregate pad underlain with filter cloth to prevent construction vehicles from tracking sediment off-site. Stabilized construction entrances shall be located throughout the project site at specific transition areas between concrete/asphalt to exposed earth.

7.3.2 Silt Fence

Silt fence shall be installed on the down gradient edge of disturbed areas parallel to existing or proposed contours or along the property line as perimeter control. Silt fence are to be used where stakes can be properly driven into the ground as per the Silt Fence Barrier Detail in the New York State Standards and Specifications for Erosion and Sediment Control and as shown on the Drawings.

Silt fence controls sediment runoff where the soil has been disturbed by slowing the flow of water and encouraging the deposition of sediment before the water passes through the straw bale or silt fence. Built-up sediment shall be removed from silt fences when it has reached one-third the height of the bale/fence and properly disposed.

7.3.3 Stockpile Detail

Stockpiled soil is to be protected, stabilized, and sited in accordance with the Soil Stockpile Detail, as shown on the Detail Sheets. Soil stockpiles and exposed soil shall be stabilized by seed, mulch, or other appropriate measures, when activities temporarily cease during construction for 7 days or more in accordance with NYSDEC requirements.

7.3.4 Dust Control

During the demolition and construction process, debris and any disturbed earth shall be wet clown with water, if necessary to control dust. After demolition and construction activities, all disturbed areas shall be covered and/or vegetated to provide for dust control on the site.

7.3.5 Temporary Seeding and Stabilization

In areas where demolition and construction activities, clearing, and grubbing have ceased, temporary seeding or permanent landscaping shall be performed to control sediment-laden runoff and provide stabilization to control erosion during storm events. This temporary seeding/stabilization or permanent landscaping shall be in place no later than 14 days after demolition and construction activity has ceased.

7.3.6 Construction Fence

To protect the integrity of soils for the SSTS, at each lot, the perimeter as noted on the plans, must be enclosed with orange construction fence per the EC details (SP2.SY1 series).

7.3.7 Snow Removal

During winter operations, snow accumulations will be removed from active work sites and placed in a snow dump located on the project site. The snow dump will be located in an area that will prevent any potential for stormwater pollution and shall drain to the stone outlet sediment trap.

7.3.8 Materials Handling/Soil Stabilization

The Contractor must store construction and waste materials as far as practical from any environmentally sensitive areas. Where possible, materials shall be stored in a covered area to minimize any potential runoff. The Contractor shall incorporate storage practices to minimize exposure of the materials to stormwater, and spill prevention and response where practicable. Prior to commencing any construction activities the contractor shall obtain all necessary permits or verify that all permits have been obtained.

7.4 Erosion and Sediment Control Practices -Permanent

7.4.1 Stone Outlet Sediment Trap

At the base of the gravel driveway, it is proposed to install an outlet sediment trap to collect runoff from the gravel driveway before said flow discharges into the stream corridor.

7.4.2 Concrete Flow Through Planter

(While not an erosion control device, this requires maintenance as discussed in this IRSP).

The structure is an 8" thick reinforced concrete wall on footings with an open bottom. The walls extend 16" above the soil strata with overflow 12" above the soil surface. The soil material is leaf compost with topsoil above. Refer to Detail Sheet SY1.

8.0 Sequence of Construction for Erosion and Sediment Control

This narrative describes the erosion and sediment controls proposed for this project, discusses the construction sequence and states the requirements for inspection and maintenance of the erosion and sediment controls. The plan has been designed in accordance with the State of New York "2016 Standards and Specifications for Erosion and Sediment Control."

The sequences provided include anticipated start dates, which are predicated on municipal and state agency approvals.

INTRODUCTION

- 1. Pre-application meeting with Town of Lewisboro Town Engineer/MS4 Agent, Contractor & Engineer and NYCDEP for IRSP for project scheduling and final plan coordination. There are no NYSDEC wetlands, wetland approval on local basis.
- 2. File NYSDEC NOI Forms with start dates
- 3. E.O.R. to complete NYSDEC inspections twice/week per NOI permit.

GENERAL SPECIFICATIONS - Area Disturbance: 0.45 acres; Anticipated start date: October 2023

- 4. Surveyor to locate limits of house, planter, septic & driveway.
- 5. Cut trees and clear leave stumps in place.
- 6. Install erosion control devices including erosion control fence. Refer to Sheet SY2
- 7. Install construction fence around septic area as noted.
- 8. Remove topsoil and stockpile as noted.
- 9. Contractor to verify elevation at planter and limits of building (cut & fill) E.O.R. to verify with site visit.
- 10. Install stone outlet sediment trap on hillside below driveway to collect runoff from driveway construction.

- 11. Excavate driveway and stabilize with Item #4 due to slope.
- 12. Stump the lot with access established for trucks picking up stumps.
- 13. Install concrete pump out pit adjacent to driveway
- 14. Install footings for residence & planter
- 15. Extend power to house site
- 16. Pour house walls & planter walls, allow sleeves for water, sewer out, and electrical, and propane lines.
- 17. Install concrete wall, waterproof and backfill
- 18. Install well by creating concrete gravel pad, install silt fence and install pump out pit for water test.
- 19. Remove concrete collected in the pump out pit and remove off site.
- 20. Install septic tanks and pump chamber. Install fill for septic and mechanically compact. Cut in trenches – D-Boxes for primary only. Complete as-built inspections with E.O.R.
- 21. Spread 6" to 12" topsoil, seed and mulch
- 22. Clean out stone outlet sediment trap
- 23. Leave stone ring in place as permanent sediment collection point.
- 24. Complete final utility connection. Electrical overhead or underground per Contractor.
- 25. Construct wood deck with sono tube piers as footings, poured in cardboard forms.
- 26. Once deck is complete, complete soil filling of concrete planter per specs. Connect roof leaders to planter (residence has flat roof pitching to rear and common leaders). Ensure overflows are functional in wall perimeter. Install plants between March 15th and June 15th; September 15th to October 15th. Water weekly as required if rainstorms not imminent within one week.
- 27. When entire site is stabilized with grass cover, remove silt fence.
- 28. Schedule MS4 Inspection with Town of Lewsiboro.
- 29. File NOT with NYSDEC.

Project complete

9.0 Inspection and Maintenance

9.1 Inspections and Record Keeping During Construction

Once the contract has been let, the name, address, and phone number of responsible parties for maintenance will be provided to the NYSDEC. The following is a description of the maintenance and inspection practices that will be implemented as part of the project. Maintenance and inspection is important to ensure that the stabilization and structural practices that are part of the IRSP continue to be effective in preventing sediment and other pollutants from entering the storm water system. It is the responsibility of the owner or operator to ensure that inspections are completed in accordance with NYSDEC regulations.

9.1.1 Record Forms

Inspection and maintenance are important to ensure that the erosion and sediment control practices that are part of the IRSP continue to be effective in preventing sediment and other pollutants from entering the stormwater system. It is the responsibility of the owner to ensure that inspections are completed in accordance with SPDES GP-0-20-001.

As a part of the IRSP inspection and maintenance activities during construction, forms shall be updated and kept on-site, including:

- Erosion and Sediment Control Inspection Report
- Monthly Summary of Inspection Activities

Inspections would be conducted by the qualified inspector periodically according to the schedule required by the SPDES GP-0-20-001 **twice per week.** During each inspection, the qualified inspector would record the areas of disturbance, deficiencies in

erosion and sediment control practices, required maintenance, and areas of temporary or permanent stabilization. The need for modifications to the Erosion and Sediment Control Plan would be identified and implemented immediately.

The Erosion and Sediment Control Inspection Report will be completed by a qualified inspector to fully document each inspection. A qualified inspector is a person knowledgeable in the principles and practices of erosion and sediment control, such as a licensed Professional Engineer, Certified Professional in Erosion and Sediment Control (CPESC), licensed Landscape Architect, or other NYSDEC endorsed individual(s). It also means someone working under the direct supervision of the licensed Professional engineer or licensed Landscape Architect, provided the person has training in the principles and practices of erosion and sediment control. Training in the principles and practices of erosion and sediment control means that an individual performing the site inspection has received four hours of training, which has been endorsed by the NYSDEC, from a Soil and Water Conservation District, CPESC, Inc., or other NYSDEC endorsed entity, in proper erosion and sediment control principles no later than two years from the date SPDES GP-0-20-001 is issued. After receiving the initial training, an individual working under the direct supervision of the licensed Professional Engineer or licensed Landscape Architect shall receive four hours of training every three years.

9.1.2 Inspections

Inspections shall be conducted by the qualified inspector periodically according to the following schedule:

- 1. When construction activities are ongoing, the qualified inspector shall conduct a site inspection at least Twice Per Week per NYSDEC regulations.
- 2. If soil disturbance activities have been suspended (e.g., winter shutdown) and temporary stabilization measures have been applied to all disturbed areas, the qualified inspector shall conduct a site inspection at least once every thirty (30) calendar clays. The owner or operator shall notify the Regional Office stormwater contact person in writing prior to reducing the frequency of inspections.

3. If soil disturbance activities have been shut clown with partial project completion, the qualified inspector can stop conducting inspections if all areas disturbed as of the project shutdown elate have achieved final stabilization and all post- construction stormwater management practices required for the completed portion of the project have been constructed in conformance with the IRSP and are operational. The owner or operator shall notify the Regional Office stormwater contact person in writing prior to the shutdown. If soil disturbance activities have not resumed within 2 years from the date of shutdown, the owner or operator shall have the qualified inspector(s) perform a final inspection and certify that all disturbed areas have achieved final stabilization, and all temporary, structural erosion and sediment control measures have been removed, and that all post- construction stormwater management practices have been constructed in conformance with the IRSP by signing the "Final Stabilization" and "Post- Construction Stormwater Management Practice" certification statements on the Notice of Termination (NOT). The owner or operator shall then submit the completed NOT form in accordance with NYSDEC regulations.

During each inspection, the qualified inspector should fill out the Erosion and Sediment Control Inspection Report as directed below: On the Erosion and Sediment Control Inspection Report site map show the following:

- Disturbed site areas and drainage pathways.
- Site areas that are expected to undergo initial disturbance or significant site work within the next 14-day period.
- Site areas that have undergone temporary or permanent stabilization.
- In areas where soil disturbance activity has been temporarily or permanently ceased, temporary and/or permanent soil stabilization measures shall be installed and/or implemented within seven (7) days from the date the soil disturbance activity ceased. The soil stabilization measures selected shall be in conformance with the most current version of the technical standard, New York State Standards and Specifications for Erosion and Sediment Control.

Record the following information on the Erosion and Sediment Control Inspection Report:

- For each structural measure, circle YES, NO, or N/A (not applicable) to indicate if the pollutant control measure is in conformance with specifications.
- For each structural measure, circle YES, NO, or N/A to indicate whether the structural measure is performing effectively in minimizing stormwater pollution.
- Inspect all sediment control practices and record the approximate degree of sediment accumulation as a percentage of the sediment storage volume in the allocated location on the Inspection Form Chart (i.e., 10 percent, 20 percent, and 50 percent).
- A description of the condition of the runoff at all points of discharge from the construction site. This shall include identification of any discharges of sediment from the construction site. Include discharges from conveyance systems (i.e., pipes, culverts, ditches, etc.) and overland flow;
- A description of the condition of all natural surface water bodies located within, or immediately adjacent to, the property boundaries of the construction site, which receive runoff from, disturbed areas. This shall include identification of any discharges of sediment to the surface water body;

The qualified inspector will give a brief explanation for all locations where he/she has noted that the structural practice was either not in conformance with specifications or in need of repair. This should be noted in the Erosion and Sediment Control Inspection Report. The qualified inspector will then give a brief recommendation for soil erosion and sediment control practices that were not installed properly or are not functioning as designed and need to be reinstalled or replaced.

9.1.3 Erosion and Sediment Control Maintenance Measures

All maintenance described below shall be completed in accordance with the New York State Standards and Specifications for Erosion and Sediment Control. Any material removed from erosion and sediment control measure shall be properly disposed.

All measures will be maintained in good working order; if repairs are found to be necessary, the qualified inspector shall notify the owner or operator and appropriate contractor (and subcontractor) of any corrective actions needed within one business day. The contractor (or subcontractor) shall begin implementing the corrective actions within one business day of this notification and shall complete the corrective actions in a reasonable time frame. A maintenance inspection report, titled "Erosion and Sediment Control Inspection Report," will be made after each inspection conducted by a qualified inspector.

Disturbed areas and materials storage areas will be inspected for evidence of potential pollutants entering stormwater systems. Within one business day of the completion of the inspection, the qualified inspector shall notify the owner or operator and the appropriate contractor (or subcontractor) of any corrective actions that need to be taken.

The contractor (or subcontractor) shall begin implementing the corrective actions within one business day of this notification and shall complete the corrective actions in a reasonable time frame.

A Monthly Summary of Site Inspection Activities will be prepared and kept on file with completed Erosion and Sediment Control Inspection Report. A Record of Stabilization and Construction Activities will be prepared and kept on file with the completed Construction Duration Inspection Forms.

The following are the maintenance requirements for each practice that will be implemented at the site.

9.2 Maintenance Practices - Temporary

Refer to attached table - Appendix C

9.2.1 Stabilized Construction Entrance/Exit

The stabilized construction entrance/exit shall be maintained in a condition that will prevent the tracking or flow of sediment onto public rights-of-way. All sediment spilled, dropped, washed or tracked onto public rights-of-way must be removed immediately; streets shall be swept as needed. The gravel pad shall be replaced as necessary. Sediment tracked onto public streets should be removed or cleaned on a daily basis.

9.2.2 Silt Fence

Maintenance of all silt fences shall be performed as needed. If a silt fence is knocked down, it shall be replaced immediately. When a silt fence appears deteriorated or ineffective and/or built-up sediment reaches one-third the height of the fence, the silt fence shall be replaced and/or cleaned accordingly. When "bulges" of material develop on the fence, they shall be removed.

Silt fence controls sediment runoff where the soil has been disturbed by slowing the flow of water and encouraging the deposition of sediment before the water passes through the silt fence. Built-up sediment shall be removed from silt fences when it has reached one-third the height of the fence and properly disposed.

9.2.3 Clean Material Stockpile

The silt fence should be inspected for bulges and proper installation. The soil stockpile should be stabilized with grass or rolled erosion control blanket.

9.2.4 Dust Control

Dust control maintenance requires exposed areas to be covered or seeded and mulched. Maintain through dry periods.

9.2.5 Temporary Seeding and Stabilization

In areas where demolition and construction activities, clearing, and grubbing have ceased, temporary seeding or permanent landscaping shall be performed to control sediment-laden runoff and provide stabilization to control erosion during storm events. This temporary seeding/stabilization or permanent landscaping shall be in place no later than 14 days after demolition and construction activity has ceased.

9.2.6 Construction Fence

Maintenance consists of ensuring that the fence posts are upright and unbroken. The fence shall remain taut between posts and any debris trapped by the fence shall be removed and disposed of off-site. Supplemental posts may be required to support broken fence posts.

9.2.7 Material Handling/ Soil Stabilization

The ensure that the site is properly seeded and stabilized, the Contractor must initiate stabilization measures as soon as practicable in areas of the site where construction activities have <u>permanently</u> ceased and in no case more than 14 days after the construction activity in that portion of this site has temporarily or permanently ceased. The Contractor will be responsible for the maintenance of the vegetated cover for the duration of construction activities. The areas shall be monitored to ensure that vegetation achieves a good coverage over the entire disturbed section. Additional seeding shall be completed as needed. Watering shall be provided as needed.

In areas where soil disturbance activity has been <u>temporarily</u> ceased, temporary and/or permanent soil stabilization measures shall be installed and/or implemented within seven days from the date the soil disturbance activity ceased. The soil stabilization measures selected shall be in conformance with the most current version of the technical standard, New York State Standards and Specifications for Erosion and Sediment Control.

9.3 Maintenance Practices - Permanent

9.3.1 Sediment Trap Stone Outlet

Maintenance consists of weekly inspection during construction for stone placement, edge erosion and sediment build-up. Sediment should be removed every one year or when trap is $\frac{1}{2}$ full, 18" deep.

9.3.2 Concrete Planter

- 1. Debris and trash removal required on weekly basis initially and monthly if debris not evident. Ensure outlet weirs in wall are clean.
- 2. Inspect planter after each storm event greater than 0.5 inches and at least twice in the first six months. After six months, inspect seasonally and after storms greater than 1-year storm event.
- 3. Maintenance consists of:
 - Pruning and replacing dead or dying vegetation.
 - Plant thinning and erosion repair.
- 4. Inspect surface for sediment build up from roof and for surface ponding.
- 5. The first season requires special care to ensure plant survival and possible supplemental watering due to rainfall events.

9.4 Maintenance Requirements

The responsibility for the implementation of long-term operation and maintenance of a postconstruction storm water management practice shall be vested with the property owner: Alex Bernabo or his successors, by a legally binding and enforceable mechanism as prepared by the project attorney and approved by the NYCDEP legal department. The following items are provided in compliance with Section 3.5 of the NYSSMDM, 2010 Manual.

9.4.1 Responsible Entity

Identity of the entity responsible for long-term operation and maintenance of the storm water practices:

Alex Bernabo wDesigne, Inc 3867 Danbury Rd Brewster, NY 10509 (914) 906-1336 info@wdesigne.com

9.5 Long Term Operation and Maintenance

Following completion of construction, a long-term inspection and maintenance program will be implemented to ensure the proper function of the stormwater management system. The program will be carried out by the Owner of Record. Post construction includes maintenance of the permanent erosion control structures, swales, the accessway to the well and infiltration structures.

Following completion of construction, a long-term inspection and maintenance program will be implemented to ensure the proper function of the stormwater management system. This includes the maintenance of permanent Storm water Structures which are listed below.

9.5.1 Site Maintenance

- 1. Litter and debris will be removed from parking areas and driveway. Sand or silt from parking lot shall be removed if it exceeds 1 inch in the permanent sediment trap.
- 2. The storm water management system should be inspected after each major storm event (greater than 2-year, 24-hour storm) to ensure concrete planter outlet structure remains clear.
- 3. Any settlement within lawn areas shall be corrected with topsoil with seed and mulch across the OWTS area.
- 4. All planting shall be inspected each year and replaced as necessary for a period of 3 years to maintain 80% survival rate.
- 5. Concrete flow through planter shall follow the Maintenance Inspection Protocol of 9.3.2.
- 6. Site shall be maintained with lawn mowing, tree trimming, leaf clean-up as is necessary for an acceptable residential environment.
- 7. Review stability of the soils and vegetation under the dock due to rainfall discharge between the deck boards. Add gravel to stabilize eroded areas.

21

APPENDIX A

Certifications

Contractor's Certification

"I hereby certify that I understand and agree to comply with the terms and conditions of the SWPPP and agree to implement any corrective actions identified by the qualified inspector during a site inspection. I also understand that the owner or operator must comply with the terms and conditions of the most current version of the New York State Pollutant Discharge Elimination System ("SPDES") general permit for stormwater discharges from construction activities and that it is unlawful for any person to cause or contribute to a violation of water safety quality standards. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of the referenced permit and the laws of the state of New York and could be subject me to criminal, civil and/or administrative proceedings."

Signed	Date
Name	
Company	
Address	
Phone	
Site	
SWPPP Implementer's Name	
SWPPP Implementer's Title	
Contractor's Scope	
Trained Contractor's Name	
Trained Contractor's Title	

* The SWPPP Implementer must be a trainer contractor responsible for SPPP implementation, an employee of the firm who has received training in accordance with SPEDES GP-0-20-001.

S:\OPEN PROJECTS\Bernabo-Waccabue\IRSP Report\Contractor Certification.doc



Department of Environmental Conservation

Owner/Operator Certification Form

SPDES General Permit For Stormwater Discharges From Construction Activity (GP-0-20-001)

Project/Site Name:	96 Post Office Rd		
eNOI Submission Νι	ımber:		
eNOI Submitted by:	Owner/Operator	SWPPP Preparer	Other

Certification Statement - Owner/Operator

I have read or been advised of the permit conditions and believe that I understand them. I also understand that, under the terms of the permit, there may be reporting requirements. I hereby certify that this document and the corresponding documents were prepared under my direction or supervision. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations. I further understand that coverage under the general permit will be identified in the acknowledgment that I will receive as a result of submitting this NOI and can be as long as sixty (60) business days as provided for in the general permit. I also understand that, by submitting this NOI, I am acknowledging that the SWPPP has been developed and will be implemented as the first element of construction, and agreeing to comply with all the terms and conditions of the general permit for which this NOI is being submitted.

Alex		
Owner/Operator	First	Name

Bernabo M.I. Last Name

Signature _____

Date ______

APPENDIX B

記録観察祭

Construction Inspection Logs

APPENDIX F CONSTRUCTION SITE INSPECTION AND MAINTENANCE LOG BOOK

STATE POLLUTANT DISCHARGE ELIMINATION SYSTEM FOR CONSTRUCTION ACTIVITIES

SAMPLE CONSTRUCTION SITE LOG BOOK

Table of Contents

- I. Pre-Construction Meeting Documents
 - a. Preamble to Site Assessment and Inspections
 - b. Pre-Construction Site Assessment Checklist
- II. Construction Duration Inspections
 - a. Directions
 - b. Modification to the SWPPP

I. PRE-CONSTRUCTION MEETING	G DOCUMENTS
Project Name	
Permit No.	Date of Authorization
Name of Operator	
Prime Contractor	

a. Preamble to Site Assessment and Inspections

The Following Information To Be Read By All Person's Involved in The Construction of Stormwater Related Activities:

The Operator agrees to have a qualified inspector¹ conduct an assessment of the site prior to the commencement of construction² and certify in this inspection report that the appropriate erosion and sediment controls described in the SWPPP have been adequately installed or implemented to ensure overall preparedness of the site for the commencement of construction.

Prior to the commencement of construction, the Operator shall certify in this site logbook that the SWPPP has been prepared in accordance with the State's standards and meets all Federal, State and local erosion and sediment control requirements. A preconstruction meeting should be held to review all of the SWPPP requirements with construction personnel.

When construction starts, site inspections shall be conducted by the qualified inspector at least every 7 calendar days. The Operator shall maintain a record of all inspection reports in this site logbook. The site logbook shall be maintained on site and be made available to the permitting authorities upon request.

Prior to filing the Notice of Termination or the end of permit term, the Operator shall have a qualified inspector perform a final site inspection. The qualified inspector shall certify that the site has undergone final stabilization³ using either vegetative or structural stabilization methods and that all temporary erosion and sediment controls (such as silt fencing) not needed for long-term erosion control have been removed. In addition, the Operator must identify and certify that all permanent structures described in the SWPPP have been constructed and provide the owner(s) with an operation and maintenance plan that ensures the structure(s) continuously functions as designed.

1 Refer to "Qualified Inspector" inspection requirements in the current SPDES General Permit for Stormwater Discharges from Construction Activity for complete list of inspection requirements.

2 "Commencement of construction" means the initial removal of vegetation and disturbance of soils associated with clearing, grading or excavating activities or other construction activities.

3 "Final stabilization" means that all soil-disturbing activities at the site have been completed and a uniform, perennial vegetative cover with a density of eighty (30) percent has been established or equivalent stabilization measures (such as the use of mulches or geotextiles) have been employed on all unpaved areas and areas not covered by permanent structures.

b. Pre-construction Site Assessment Checklist (NOTE: Provide comments below as necessary)

1. Notice of Intent, SWPPP, and Contractors Certification:

Yes No NA

- [] [] Has a Notice of Intent been filed with the NYS Department of Conservation?
- [] [] Is the SWPPP on-site? Where?____
- [] [] Is the Plan current? What is the latest revision date?______
- [] [] [] Is a copy of the NOI (with brief description) onsite? Where?
- [] [] Have all contractors involved with stormwater related activities signed a contractor's certification?
- 2. Resource Protection

Yes No NA

- [] [] Are construction limits clearly flagged or fenced?
- [] [] Important trees and associated rooting zones, on-site septic system absorption fields, existing vegetated areas suitable for filter strips, especially in perimeter areas, have been flagged for protection.
- [] [] [] Creek crossings installed prior to land-disturbing activity, including clearing and blasting.
- 3. Surface Water Protection

Yes No NA

- [] [] Clean stormwater runoff has been diverted from areas to be disturbed.
- [] [] Bodies of water located either on site or in the vicinity of the site have been identified and protected.
- [] [] Appropriate practices to protect on-site or downstream surface water are installed.
- [] [] [] Are clearing and grading operations divided into areas <5 acres?

4. Stabilized Construction Access

Yes No NA

- [] [] A temporary construction entrance to capture mud and debris from construction vehicles before they enter the public highway has been installed.
- [] [] Other access areas (entrances, construction routes, equipment parking areas) are stabilized immediately as work takes place with gravel or other cover.
- [] [] Sediment tracked onto public streets is removed or cleaned on a regular basis.

5. Sediment Controls

Yes No NA

- [] [] Silt fence material and installation comply with the standard drawing and specifications.
- [] [] Silt fences are installed at appropriate spacing intervals
- [] [] [] Sediment/detention basin was installed as first land disturbing activity.
- [] [] Sediment traps and barriers are installed.

6. Pollution Prevention for Waste and Hazardous Materials

Yes No NA

- [] [] The Operator or designated representative has been assigned to implement the spill prevention avoidance and response plan.
- [] [] The plan is contained in the SWPPP on page
- [] [] Appropriate materials to control spills are onsite. Where?

a. Directions:

Inspection Forms will be filled out during the entire construction phase of the project.

Required Elements:

- 1) On a site map, indicate the extent of all disturbed site areas and drainage pathways. Indicate site areas that are expected to undergo initial disturbance or significant site work within the next 14-day period;
- 2) Indicate on a site map all areas of the site that have undergone temporary or permanent stabilization;
- 3) Indicate all disturbed site areas that have not undergone active site work during the previous 14-day period;
- 4) Inspect all sediment control practices and record the approximate degree of sediment accumulation as a percentage of sediment storage volume (for example, 10 percent, 20 percent, 50 percent);
- 5) Inspect all erosion and sediment control practices and record all maintenance requirements such as verifying the integrity of barrier or diversion systems (earthen berms or silt fencing) and containment systems (sediment basins and sediment traps). Identify any evidence of rill or gully
 - erosion occurring on slopes and any loss of stabilizing vegetation or seeding/mulching. Document any excessive deposition of sediment or ponding water along barrier or diversion systems. Record the depth of sediment within containment structures, any erosion near outlet and overflow structures, and verify the ability of rock filters around perforated riser pipes to pass water; and
- 6) Immediately report to the Operator any deficiencies that are identified with the implementation of the SWPPP.

Page 1 of _____

SITE PLAN/SKETCH

Inspector (print name)

Date of Inspection

Qualified Inspector (print name)

Qualified Inspector Signature

The above signed acknowledges that, to the best of his/her knowledge, all information provided on the forms is accurate and complete.

July 2016

Page 2 of _____

Maintaining Water Quality

Yes No NA

- [] [] Is there an increase in turbidity causing a substantial visible contrast to natural conditions at the outfalls?
- [] [] Is there residue from oil and floating substances, visible oil film, or globules or grease at the outfalls?
- [] [] All disturbance is within the limits of the approved plans.
- [] [] Have receiving lake/bay, stream, and/or wetland been impacted by silt from project?

Housekeeping

1. General Site Conditions

Yes No NA

- [] [] [] Is construction site litter, debris and spoils appropriately managed?
- [] [] Are facilities and equipment necessary for implementation of erosion and sediment control in working order and/or properly maintained?
- [] [] [] Is construction impacting the adjacent property?
- [] [] [] Is dust adequately controlled?
- 2. Temporary Stream Crossing

Yes No NA

- [] [] Maximum diameter pipes necessary to span creek without dredging are installed.
- [] [] Installed non-woven geotextile fabric beneath approaches.
- [] [] Is fill composed of aggregate (no earth or soil)?
- [] [] [] Rock on approaches is clean enough to remove mud from vehicles & prevent sediment from entering stream during high flow.
- 3. Stabilized Construction Access

Yes No NA

- [] [] [] Stone is clean enough to effectively remove mud from vehicles.
- [] [] Installed per standards and specifications?
- [] [] Does all traffic use the stabilized entrance to enter and leave site?
- [] [] [] Is adequate drainage provided to prevent ponding at entrance?

Runoff Control Practices

1. Excavation Dewatering

Yes No NA

- [] [] Upstream and downstream berms (sandbags, inflatable dams, etc.) are installed per plan.
- [] [] Clean water from upstream pool is being pumped to the downstream pool.
- [] [] Sediment laden water from work area is being discharged to a silt-trapping device.
- [] [] Constructed upstream berm with one-foot minimum freeboard.

Runoff Control Practices (continued)

2. Flow Spreader

Yes No NA

- [] [] [] Installed per plan.
- [] [] Constructed on undisturbed soil, not on fill, receiving only clear, non-sediment laden flow.
- [] [] Flow sheets out of level spreader without erosion on downstream edge.

3. Interceptor Dikes and Swales

Yes No NA

- [] [] Installed per plan with minimum side slopes 2H:1V or flatter.
- [] [] Stabilized by geotextile fabric, seed, or mulch with no erosion occurring.
- [] [] Sediment-laden runoff directed to sediment trapping structure

4. Stone Check Dam

Yes No NA

- [] [] [] Is channel stable? (flow is not eroding soil underneath or around the structure).
- [] [] Check is in good condition (rocks in place and no permanent pools behind the structure).
- [] [] [] Has accumulated sediment been removed?.

5. Rock Outlet Protection

Yes No NA

- [] [] [] Installed per plan.
- [] [] [] Installed concurrently with pipe installation.

Soil Stabilization

1. Topsoil and Spoil Stockpiles

Yes No NA

- [] [] [] Stockpiles are stabilized with vegetation and/or mulch.
- [] [] [] Sediment control is installed at the toe of the slope.

2. Revegetation

Yes No NA

- [] [] [] Temporary seedings and mulch have been applied to idle areas.
- [] [] 4 inches minimum of topsoil has been applied under permanent seedings

Sediment Control Practices

1. Silt Fence and Linear Barriers

Yes No NA

- [] [] Installed on Contour, 10 feet from toe of slope (not across conveyance channels).
- [] [] Joints constructed by wrapping the two ends together for continuous support.
- [] [] Fabric buried 6 inches minimum.
- [] [] Posts are stable, fabric is tight and without rips or frayed areas.

Sediment accumulation is ____% of design capacity.

Page 4 of _____

Sediment Control Practices (continued)

2. Storm Drain Inlet Protection (Use for Stone & Block; Filter Fabric; Curb; or, Excavated; Filter Sock or Manufactured practices)

Yes No NA

- [] [] Installed concrete blocks lengthwise so open ends face outward, not upward.
- [] [] Placed wire screen between No. 3 crushed stone and concrete blocks.
- [] [] Drainage area is 1acre or less.
- [] [] Excavated area is 900 cubic feet.
- [] [] [] Excavated side slopes should be 2:1.
- [] [] 2" x 4" frame is constructed and structurally sound.
- [] [] Posts 3-foot maximum spacing between posts.
- [] [] Fabric is embedded 1 to 1.5 feet below ground and secured to frame/posts with staples at max 8-inch spacing.
- [] [] Posts are stable, fabric is tight and without rips or frayed areas.
- [] [] Manufactured insert fabric is free of tears and punctures.
- [] [] Filter Sock is not torn or flattened and fill material is contained within the mesh sock.
- Sediment accumulation ____% of design capacity.
- 3. Temporary Sediment Trap

Yes No NA

- [] [] Outlet structure is constructed per the approved plan or drawing.
- [] [] Geotextile fabric has been placed beneath rock fill.
- [] [] [] Sediment trap slopes and disturbed areas are stabilized.

Sediment accumulation is ____% of design capacity.

4. Temporary Sediment Basin

Yes No NA

- [] [] Basin and outlet structure constructed per the approved plan.
- [] [] Basin side slopes are stabilized with seed/mulch.
- [] [] Drainage structure flushed and basin surface restored upon removal of sediment basin facility.
- [] [] [] Sediment basin dewatering pool is dewatering at appropriate rate.

Sediment accumulation is ___% of design capacity.

<u>Note</u>: Not all erosion and sediment control practices are included in this listing. Add additional pages to this list as required by site specific design. All practices shall be maintained in accordance with their respective standards.

Construction inspection checklists for post-development stormwater management practices can be found in Appendix F of the New York Stormwater Management Design Manual.

b. Modifications to the SWPPP (Tc be completed as described below)

The Operator shall amend the SWPPP whenever:

- 1. There is a significant change in design, construction, operation, or maintenance which may have a significant effect on the potential for the discharge of pollutants to the waters of the United States and which has not otherwise been addressed in the SWPPP; or
- 2. The SWPPP proves to be ineffective in:
 - a. Eliminating or significantly minimizing pollutants from sources identified in the SWPPP and as required by this permit; or
 - b. Achieving the general objectives of controlling pollutants in stormwater discharges from permitted construction activity; and
- 3. Additionally, the SWPPP shall be amended to identify any new contractor or subcontractor that will implement any measure of the SWPPP.

Modification & Reason:

APPENDIX C

Maintenance Schedule - Temporary

<u> Maintenance Schedule – During Construction – Temporary Structures</u>

	T	Т	<u> </u>	T	Ţ	
Maintenance and Sediment Removal	Remove material when a "bulge" develops, ensure fence	Eiv fence un vicht and fence upright, staple fencing	Remove material when a "bulge" develops, ensure fence	extends into soil and fence is upright, staple fencing Repair Top Dressing with additional aggregate and correct	stone placement. Bi-weekly, remove sediment, set stones to correct profile, fix	berm blow-outs Due to the downhill proximity of the well, it is recommended to remove the concrete off-site once curred
Special Inspection Items Inspect the following:	Woven Wire & Fence Stability	Fence posts and prid	Silt Fence at Base of Pile to be inspected and	Stone Placement & soil deposit between stones	Stone & Sediment Accumulation	Once filled topsoil, seed & mulch
<u>Sediment</u> <u>Removal</u> <u>Req'd</u>	Yes	None	None	None	Yes	None
Item to Inspect	Woven Wire Fence Alignment	Fence Woven Wire	Soil Pile Condition	Stone Placement	Stone Placement & Location	Soil Stability
<u>After</u> <u>Every</u> <u>Storm</u> Event	Х		Х	Х	×	х
<u>MINIMUM</u> <u>Inspection</u> <u>Required</u>	Bi-Weekly	Bi-Weekly	Bi-Weekly	Weekly	Bi-Weekly	Monthly
Component	Silt Fence	Construction Fence	Topsoil Stockpile Area	Construction Entrance	Stone Outlet Sediment Trap	Concrete Pump Out
I	1	2	3	4	5	9

APPENDIX D

NYSDEC NOI

NOTICE OF INTENT

New York State Department of Environmental Conservation

Division of Water

625 Broadway, 4th Floor Albany, New York 12233-3505



Stormwater Discharges Associated with <u>Construction Activity</u> Under State Pollutant Discharge Elimination System (SPDES) General Permit # GP-0-20-001 All sections must be completed unless otherwise noted. Failure to complete all items may result in this form being returned to you, thereby delaying your coverage under this General Permit. Applicants must read and understand the conditions of the permit and prepare a Stormwater Pollution Prevention Plan prior to submitting this NOI. Applicants are responsible for identifying and obtaining other DEC permits that may be required.

-IMPORTANT-RETURN THIS FORM TO THE ADDRESS ABOVE

OWNER/OPERATOR MUST SIGN FORM

														Ow	me	r/	Op	era	atc	or	Inf	ori	nat	ioi	r										
Owi	ner	:/C)pe	ral	or	• (Coi	npa	any	7 N	lam	e∕E	ri	.va	te	O	vne	er	Na	me,	/Mu	nic	rip	ali	ty	Na	me)	۱.							
W	D	е	s	i	g	n	е	,		I	n	С	•																						
Owr	ler	:/C	pe	rat	lor	С	on [.]	tad	<u>pt</u>	Pe	rs	on	La	ist	No	ame	3	(NC	T	COI	NSU	LTF	NT)											
В	е	r	n	a	b	0																													
Owr	ner	:/0	pe	rat	or	С	on	tad	st	Pe	rs	on	Fi	rs	t 1	Nar	ne																		
A	1	е	x																													Τ	T	T	
Owr	ier	:/0	pe	rat	or	М	ai	Lir	ıg	Ad	dro	ess																							-
5		J	0	h	n		W	а	1	s	h		В	1	v	d																			T
Cit	:у																, ,				·														
P	e	e	k	s	k	i	1	l																											
Sta	ite	•				Zi	p				_																								
N	Y					1	0	5	6	6	;] _																								
Pho	ne	: (Owi	ner	:/0	pe:	rat	or	;)						Fa	x	(O'	wne	er/	'Op	era	ito:	r)												
9	1	4	-	9	0	6	- [1	3	3	6						Ι]_				_													
Fma	÷ 1	()	() []	nor		<u></u>	rat	or	1									_																	
i	n	f	0	@	w	d	e	s	i	q	n	e		с	0	m		Γ		Γ		Ť	T		T		Τ	1		T	T	T	T		
										-										 	 					+					+	+	+	 	
		71.32																	L	L]					<u> </u>	<u> </u>	<u> </u>		
1	3	АХ [3	8	8	9	5	6	9	,																									
	-	l	-	-		-1	-	-		(1	ot	re	equ	ur	ed	İ	or	ln	di	VIC	dua	⊥s)													
Į.																																			

Project Site Informa	tion
Project/Site Name	
96 Post Office Rd	
Street Address (NOT P.O. BOX)	
Side of Street O North O South O East O West	
City/Town/Village (THAT ISSUES BUILDING PERMIT)	
Waccabuc	
State Zip County N Y 1 0 5 9 7 - Westches	DEC Region
Name of Nearest Cross Street	
Benedict Rd	
Distance to Nearest Cross Street (Feet)	Project In Relation to Cross Street • North O South O East O West
Tax Map Numbers Section-Block-Parcel	Tax Map Numbers

1. Provide the Geographic Coordinates for the project site. To do this, go to the NYSDEC Stormwater Interactive Map on the DEC website at:

https://gisservices.dec.ny.gov/gis/stormwater/

Zoom into your Project Location such that you can accurately click on the centroid of your site. Once you have located the centroid of your project site, go to the bottom right hand corner of the map for the X, Y coordinates. Enter the coordinates into the boxes below. For problems with the interactive map use the help function.

х	Coc	rdi	nate	es (Eas	ting	J)
-7	3	5	7	9	2	0	
	Ex.	-73	3.74	9			

ΥC	Coor	dina	ates	(N	orth	ing)	
4	1	2	8	8	0	2	
Ex.	42	. 652	2				

2. What is	the nature of this construction project?
	• New Construction
	O Redevelopment with increase in impervious area
	O Redevelopment with no increase in impervious area
 Contract (1) 	

3. Select the predominant land use for both p SELECT ONLY ONE CHOICE FOR EACH	pre and post development conditions.
Pre-Development Existing Land Use	Post-Development Future Land Use
FOREST	● SINGLE FAMILY HOME Number of Lots
\bigcirc PASTURE/OPEN LAND	O SINGLE FAMILY SUBDIVISION
○ CULTIVATED LAND	O TOWN HOME RESIDENTIAL
· O SINGLE FAMILY HOME	○ MULTIFAMILY RESIDENTIAL
\bigcirc SINGLE FAMILY SUBDIVISION	○ INSTITUTIONAL/SCHOOL
○ TOWN HOME RESIDENTIAL	○ INDUSTRIAL
\bigcirc MULTIFAMILY RESIDENTIAL	○ COMMERCIAL
\bigcirc INSTITUTIONAL/SCHOOL	⊖ MUNICIPAL
\bigcirc INDUSTRIAL	○ ROAD/HIGHWAY
○ COMMERCIAL	○ RECREATIONAL/SPORTS FIELD
○ ROAD/HIGHWAY	○ BIKE PATH/TRAIL
○ RECREATIONAL/SPORTS FIELD	○ LINEAR UTILITY (water, sewer, gas, etc.)
⊖ BIKE PATH/TRAIL	O PARKING LOT
\bigcirc linear utility	○ CLEARING/GRADING ONLY
○ PARKING LOT	\bigcirc DEMOLITION, NO REDEVELOPMENT
O OTHER	\bigcirc WELL DRILLING ACTIVITY *(Oil, Gas, etc.)
	O OTHER

*Note: for gas well drilling, non-high volume hydraulic fractured wells only

Total Site Area	Total Area To Be Disturbed	Existing Imperviou Area To Be Disturbe	Future Impervious Area Within d Disturbed Area
4.0	0.5	0.0	0.1
Por	-	J==	
A	B		
	A PLACE TRANSPORT A PLACE AND	A DESCRIPTION PROFILE AND A DESCRIPTION AND A DE	
00	00	7 5 8	2 5 8

Name N Y S D E C - L F i f t y Jaa. Type of waterbody identified in Question 9? O Wetland / State Jurisdiction On Site (Answer 9b) Wetland / State Jurisdiction Off Site O Wetland / Federal Jurisdiction On Site (Answer 9b) O Wetland / Federal Jurisdiction Off Site O Stream / Creek Off Site O Stream / Creek Off Site O River On Site O Lake Or Site O Lake Off Site O Other Type On Site O Other Type Off Site O Other (identify) II. Has the surface waterbody(ies) in question 9 been identified as a 303(d) segment in Appendix E of GP-0-20-001? II. II. II. Is the project located in one of the Watersheds identified in Appendix C of GP-0-20-001? II. Is the project located in one of the watershed areas associated with AA and AA-S classified	9.	Ide dis	nt ch	ify arc	yt ie.	:he	e nea	re.	st	su	rfa	ce	Wa	ite	rbo	dy ((i∈	es)	tc	W]	hic	ch	COI	nst	rı	ict	io	n :	sit	e 1	cuno	off	wi	11	
9a. Type of waterbody identified in Question 9? 9a. Type of waterbody identified in Question 9? • Wetland / State Jurisdiction On Site (Answer 9b) • Wetland / Federal Jurisdiction Off Site • Stream / Creek On Site • Stream / Creek Off Site • River Off Site • Lake Off Site • Lake Off Site • Other Type Off Site • Other (identify) <th>Name</th> <th>q</th> <th>ח</th> <th>F</th> <th><u>م</u></th> <th></th> <th></th> <th>Т.</th> <th>ਸ</th> <th>i</th> <th>F</th> <th>+</th> <th>v</th> <th></th> <th></th> <th>T</th> <th>Τ</th> <th>Τ</th> <th>Т</th> <th>1</th> <th>Τ</th> <th>Γ</th> <th></th> <th><u> </u></th> <th> </th> <th>T</th> <th>Γ</th> <th>T</th> <th></th> <th></th> <th></th> <th>T</th> <th></th> <th></th> <th></th>	Name	q	ח	F	<u>م</u>			Т.	ਸ	i	F	+	v			T	Τ	Τ	Т	1	Τ	Γ		<u> </u>		T	Γ	T				T			
9s. Type of waterbody identified in Question 9? 0 Wetland / State Jurisdiction On Site (Answer 9b) • Wetland / Federal Jurisdiction Off Site 0 Wetland / Federal Jurisdiction Off Site 0 Wetland / Federal Jurisdiction Off Site 0 Stream / Creek On Site 0 Stream / Creek Off Site 0 River Off Site 0 Lake Off Site 0 Other Type On Site 0 Other Type Off Site 0 Ither Type Off Site 0 Other (identify) 10. Has the surface waterbody(ies) in question 9 been identified as a 303(d) segment in Appendix E of GP-0-20-001? 11. Is this project located in one of the Watersheds identified in Appendix C of GP-0-20-001? 12. Is the project located in one of the watershed areas associated with AA and AA-S classified									-	 			Y						T					 	 	 		+			-				
9a. Type of waterbody identified in Question 9? 0 Wetland / State Jurisdiction On Site (Answer 9b) • Wetland / Federal Jurisdiction Off Site 0 Wetland / Federal Jurisdiction Off Site 0 Stream / Creek On Site 0 Stream / Creek Off Site 0 River On Site 0 Lake On Site 0 Other Type Of Site 0 Other Type Off Site 0 Signent in Appendix E of GP-0-20-001? 10. Has the surface waterbody(ies) in question 9 been identified as a 303(d) segment in Appendix E of GP-0-20-001? 11. Is this project located in one of the Watersheds identified in Appendix C of GP-0-20-001? 12. Is the project located in one of the watershed areas associa								25575																				1							
 O Wetland / State Jurisdiction On Site (Answer 9b) Wetland / State Jurisdiction Off Site O Wetland / Federal Jurisdiction On Site (Answer 9b) O Wetland / Federal Jurisdiction Of Site O Wetland / Federal Jurisdiction Off Site O Wetland / Federal Jurisdiction Off Site O Wetland / Federal Jurisdiction Off Site O Stream / Creek On Site O Stream / Creek Off Site O River On Site O River Off Site O Lake Off Site O Lake Off Site O O Delineated by Consultant O Other Type Off Site O Uther (identify) I I Is this project located in one of the Watersheds identified in Appendix C of GP-0-20-001? Is the project located in one of the watershed areas associated with AA and AA-5 classified O Yes No 	9a.		Τ 1/1	зe	of	w	aterl	boc	łv	ide	-nt	if	ied	ir	ı O	ues	ti	on	93																
 Wetland / State Jurisdiction On Site (Answer 9b) Wetland / State Jurisdiction Off Site Wetland / Federal Jurisdiction On Site (Answer 9b) Wetland / Federal Jurisdiction Of Site Stream / Creek On Site Stream / Creek Off Site Stream / Creek Off Site Stream / Creek Off Site Pb. How was the wetland identified? River Off Site O Regulatory Map O Lake Off Site O Other Type On Site O Other Type Off Site O Uther (identify) I Is this project located in one of the Watersheds identified in Appendix C of GP-0-20-001? Is the project located in one of the watershed areas associated with AA and AA-S classified 	24.		- 11		0-				~1																										
 Wetland / State Jurisdiction Off Site Wetland / Federal Jurisdiction On Site (Answer 9b) Wetland / Federal Jurisdiction Off Site Stream / Creek On Site Stream / Creek Off Site Stream / Creek Off Site River On Site Pb. How was the wetland identified? River Off Site Lake On Site Other Type On Site Other Type Off Site Other (identify) Intermediate Stream / Other (identified as a sociated in one of the Watersheds identified in Appendix C of GP-0-20-001? 12. Is the project located in one of the watershed areas associated with AA and AA-S classified 	0	Wet	:la	ınd	/	St	tate	Ju	ri.	sdi	.ct.	ioı	1 0	n S	it€	∋ (.	An	swe	r	9b)															
 ○ Wetland / Federal Jurisdiction On Site (Answer 9b) ○ Wetland / Federal Jurisdiction Off Site ○ Stream / Creek On Site ○ Stream / Creek Off Site ○ River On Site ○ River Off Site ○ Lake Or Site ○ Lake Off Site ○ Lake Off Site ○ Delineated by Consultant ○ Other Type Off Site ○ Other Type Off Site ○ Other Type Off Site ○ Other (identify) ○ Other (identify) ○ Has the surface waterbody(ies) in question 9 been identified as a 303(d) segment in Appendix E of GP-0-20-001? 11. Is this project located in one of the Watersheds identified in Appendix C of GP-0-20-001? 12. Is the project located in one of the watershed areas associated with AA and AA-S classified ○ Yes ● No 	U	Wet	:la	ınd	1	St	tate	Ju	ri.	sdi	.ct.	ioı	10	ff	Sit	ze																			
 O Wetland / Federal Jurisdiction Off Site O Stream / Creek On Site O Stream / Creek Off Site O River Off Site O Lake On Site O Lake Off Site O Lake Off Site O Delineated by Consultant O Other Type On Site O Other Type Off Site O Other Type Off Site O Other (identify) I Is this project located in one of the Watersheds identified in Appendix C of GP-0-20-001? I Is the project located in one of the watershed areas associated with AA and AA-S classified O Yes No 	0	Wet	:la	ınd	7	Εe	edera	al	Ju:	ris	di	st:	on	Or	S:	ite	()	Ans	we	r 9	b)														
 O Stream / Creek On Site O Stream / Creek Off Site O River On Site O River Off Site O Lake On Site O Lake Off Site O Lake Off Site O Cher Type On Site O Other Type Off Site O Other Type Off Site O Other (identify) I Is the surface waterbody(ies) in question 9 been identified as a 303(d) segment in Appendix E of GP-0-20-001? I Is the project located in one of the Watersheds identified in Appendix C of GP-0-20-001? I Is the project located in one of the watershed areas associated with AA and AA-S classified O Yes No 	0	Wet	:la	nd	1	Fe	edera	al	Ju:	cis	di	st:	.on	Of	f S	3it	e																		
 O Stream / Creek Off Site O River On Site O River Off Site O Lake Or Site O Lake Off Site O Lake Off Site O Delineated by Consultant O Other Type On Site O Other Type Off Site O Other (identify) I and I and	0	Sti	ea	m	/ (Cre	eek (Dn	Si	ze																									
 O River On Site O River Off Site O Lake Or Site O Lake Off Site O Regulatory Map O Lake Off Site O Delineated by Consultant O Other Type On Site O Other Type Off Site O Other (identify) I I I Is this project located in one of the Watersheds identified in Appendix C of GP-0-20-001? I Is the project located in one of the watershed areas associated with AA and AA-S classified O Yes 	0	Sti	ea	m	/ (Cre	eek ()ff	S	ite	2																								
9b. How was the wetland identified? 0 River Off Site 0 Regulatory Map 0 Lake Off Site 0 Delineated by Consultant 0 Other Type On Site 0 Other (identify) 0 Other Type Off Site 0 Other (identify) 10. Has the surface waterbody(ies) in question 9 been identified as a 303(d) segment in Appendix E of GP-0-20-001? O Yes 11. Is this project located in one of the Watersheds identified in Appendix C of GP-0-20-001? Yes No 12. Is the project located in one of the watershed areas associated with AA and AA-S classified O Yes No	0	Rit	rer	0:	n s	Sit	ce												~																
 O Lake Or Site O Lake Off Site O Delineated by Consultant O Delineated by Army Corps of Engineers O Other Type Off Site O Other (identify) I I Appendix E of GP-0-20-001? I Is this project located in one of the Watersheds identified in Appendix C of GP-0-20-001? I Is the project located in one of the watershed areas associated with AA and AA-S classified O Regulatory Map O Delineated by Consultant O Delineated by Army Corps of Engineers O Other (identify) I Is the project located in one of the watershed areas associated with AA and AA-S classified 	0	Riv	rer	0	££	Si	ite												90	•	Н	ow	wa	ıs	τn	ev	vet	:1a	.nd	ıd	ent	LII.	Led	?	
 O Lake Off Site O Delineated by Consultant O Delineated by Army Corps of Engineers O Other Type Off Site O Other (identify) I I Appendix E of GP-0-20-001? I Is this project located in one of the Watersheds identified in Appendix C of GP-0-20-001? I Is the project located in one of the watershed areas associated with AA and AA-S classified O Delineated by Consultant O Delineated by Army Corps of Engineers O Other (identify) I Is the project located in one of the watershed areas associated with AA and AA-S classified 	0	Lał	e	0n	S	lte	3													() f	leg	ula	atc	ry	M	ар								
O Other Type On Site O Delineated by Army Corps of Engineers O Other Type Off Site O Other (identify) Image: Corps of Engineers O Yes	0	Lak	e	Of	E S	Sit	ze													. () e	el	ine	eat	.ed	b	y (Cor	sul	lta	nt				
O Other Type Off Site O Other (identify) Image: Constraint of the surface waterbody(ies) in question 9 been identified as a 303(d) segment in Appendix E of GP-0-20-001? O Yes In. Is this project located in one of the Watersheds identified in Appendix C of GP-0-20-001? Yes In. Is the project located in one of the watershed areas associated with AA and AA-S classified O Yes	0	Oth	er	T	ype	e C	Dn Si	te												() e	el	ine	eat	ed	b	y i	Arn	ny C	lor	ps	of	En	gin€	eers
 Has the surface waterbody(ies) in question 9 been identified as a OYes No Is this project located in one of the Watersheds identified in Appendix C of GP-0-20-001? Is the project located in one of the watershed areas associated with AA and AA-S classified OYes No 	0	Otr	er	T	γpe	e (Dff S	Sit	e											(th	er	(i	de	nt.	if	<u>y)</u>				1			-
 Has the surface waterbody(ies) in question 9 been identified as a OYes No 303(d) segment in Appendix E of GP-0-20-001? Is this project located in one of the Watersheds identified in Appendix C of GP-0-20-001? Is the project located in one of the watershed areas associated with AA and AA-S classified OYes No 	<																																		,
 10. Has the surface waterbody(ies) in question 9 been identified as a 303(d) segment in Appendix E of GP-0-20-001? 11. Is this project located in one of the Watersheds identified in Appendix C of GP-0-20-001? 12. Is the project located in one of the watershed areas associated with AA and AA-S classified O Yes • No 				001100														0.0410																	/
 303(d) segment in Appendix E of GP-0-20-001? 11. Is this project located in one of the Watersheds identified in Appendix C of GP-0-20-001? 12. Is the project located in one of the watershed areas associated with AA and AA-S classified O Yes O No 	10.	H	las	s t	he	s۱	urfac	ce	wa	ter	bod	dy	(ie	s)	in	qu	es	tio	n	9 b	ee	n :	ide	ent	if	ied	d a	as	a		03	(es		No	
 11. Is this project located in one of the Watersheds identified in Appendix C of GP-0-20-001? 12. Is the project located in one of the watershed areas associated with AA and AA-S classified O Yes O No 			303	8(d) :	seg	gment	: i	n .	Abb	en	diz	κE	of	Gl	2-0	-2	0-0	01	?											<u> </u>		-		
Appendix C of GP-0-20-001? • Yes O No 12. Is the project located in one of the watershed areas associated with AA and AA-S classified • Yes • No	11.	-		th	is	n	roiea	~ †	10	at	ed	ir	0.0	ne	of	+h	e I	Nat	er	she	ds	ic	len	t i	fi	əd	ir	1							
12. Is the project located in one of the watershed areas associated with AA and AA-S classified ○ Yes ● No		7	/pr	en	di:	x (C of	GP	-0	-20)-0)1'	>													~~					• 3	(es	C) No	
12. Is the project located in one of the watershed areas associated with AA and AA-S classified ○ Yes ● No																															ennen er i trais dal				
	12.] 6	ls are	th as	e p as	pro ssc	oject ociat	z l zed	000 W	ate Lth	d : Al	in Aa	on ind	e c AA	ft -S	che cla	wa as:	ate sif	rsh ied	ned 1											0 3	les.		No	

If no, skip question 13.

13. Does this construction activity disturb land with no existing impervious cover and where the Soil Slope Phase is O Yes O No identified as an E or F on the USDA Soil Survey? If Yes, what is the acreage to be disturbed?

14. Will the project disturb soils within a State regulated wetland or the protected 100 foot adjacent ○ Yes ● No area?
| 15. | Does the site runoff enter a separate storm sewer
system (including roadside drains, swales, ditches, O Yes I
culverts, etc)? | No O Unknown |
|-------------|--|--------------|
| 16. | What is the name of the municipality/entity that owns the separate system? | storm sewer |
| | | |
| | | |
| 17. | Does any runoff from the site enter a sewer classified O Yes O I as a Combined Sewer? | No 🔿 Unknown |
| 18. | Will future use of this site be an agricultural property as defined by the NYS Agriculture and Markets Law? | OYes No |
| 19. | Is this property owned by a state authority, state agency, federal government or local government? | O Yes 🔍 No |
| 20. | Is this a remediation project being done under a Department
approved work plan? (i.e. CERCLA, RCRA, Voluntary Cleanup
Agreement, etc.) | 🔾 Yes 🌘 No |
| 21. | Has the required Erosion and Sediment Control component of the
SWPPP been developed in conformance with the current NYS
Standards and Specifications for Erosion and Sediment Control
(aka Blue Book)? | •Yes ONo |
| 22 . | Does this construction activity require the development of a SWPPP that includes the post-construction stormwater management practice component (i.e. Runoff Reduction, Water Quality and Quantity Control practices/techniques)?
If No, skip questions 23 and 27-39. | ○Yes ●No |
| 23. | Has the post-construction stormwater management practice component
of the SWPPP been developed in conformance with the current NYS
Stormwater Management Design Manual? | O Yes O No |

24. The Stormwater Pollution Prevention Plan (SWPPP) was prepared by:																																						
	. C	P	ro:	fes	ssi	on	al	Eı	ngi	ne	er	(F	.e	.)																								
	C	s	oi:	1 a	and	. W	ate	ər	Co	ns	er	rat	io	n l	Dis	str	ic	t I	SW	CD)																		
	С	R	eg:	ist	er	ed	La	anc	lsc	ap	e /	Arc	hi	te	ct	(R	.L	.A)																				
	O Certified Professional in Erosion and Sediment Control (CPESC) O Owner/Operator																																					
	O Owner/Operator																																					
SWE	PP	P P	re	pa:	rer						Γ.	, ,	1	<u> </u>	Γ.			r		Ť		,		1	1,	Τ.	Τ.	T	1	Γ.	T	T		T				
LP]	W		S	C	0				E	n	<u>a</u>	1	n	e	e	r	1	n	g		&	ŀ	$F \mid :$	r c	n	lı	t	<u> </u> e	C	t	u	r	e		P	C		
Cor	ta	ct	N	amo	э ([La	st	; ج	Spa	ice	, :	Fir	st)	1					<u> </u>			1	1	T	<u> </u>	1	1	1		1	<u> </u>	1	1				
5		0	L	L	L	Р	e	a	le	L L	L															<u> </u>	<u> </u>		<u> </u>			<u> </u>		<u> </u>				
Mai	1i 0	ng	A 1	dd:	res	s	5	h		~			Б	7	r					T	\neg			<u> </u>	Т	T	1	1	1		T		<u> </u>					
	<u> </u>					a	11	D	u	<u> </u>	<u>Y</u>		R	u	İ]		<u> </u>			<u> </u>	1	<u> </u>	1					
B	y r	P	w	s	+	e	r								l							Τ			Γ	Τ	1	Γ		 	Ι			\square				
Sta	- +e						-								I										<u> </u>				I]	<u> </u>					
N	Y		1	0	5	0	9	_	[
Pho	 ne	1			I					L	I									F	ax																	
8	4	5	-	2	7	8	_	2	1	1	0]-				-											
Ema	iļ	اــــــ	1			r	1		··		·1														I		,											
р	w	s	С	0	t	t	@	р	w	s	С	0	t	t	•	С	0	m																				
													ALCHAR																									
			1			1	1		LI		1		1		L	l		1	!.						I	I	1	I			1	I	1	<u> </u>	I.			-)

SWPPP Preparer Certification

I hereby certify that the Stormwater Pollution Prevention Plan (SWPPP) for this project has been prepared in accordance with the terms and conditions of the GP-0-20-001. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of this permit and the laws of the State of New York and could subject me to criminal, civil and/or administrative proceedings.

First Name	MI
P e d e r	
Last Name	
Scott	
Signature	
4	Date
	04/05/2023

25.	Has a construction sequence schedule for practices been prepared?	the planned management O Yes O No
26.	Select all of the erosion and sediment co employed on the project site:	ontrol practices that will be
	Temporary Structural	Vegetative Measures
	\bigcirc Check Dams	○ Brush Matting
	\bigcirc Construction Road Stabilization	\bigcirc Dune Stabilization
	Dust Control	\bigcirc Grassed Waterway
	\bigcirc Earth Dike	○ Mulching
	\bigcirc Level Spreader	\bigcirc Protecting Vegetation
	\bigcirc Perimeter Dike/Swale	\bigcirc Recreation Area Improvement
	○ Pipe Slope Drain	Seeding
	\bigcirc Portable Sediment Tank	\bigcirc Sodding
	\bigcirc Rock Dam	\bigcirc Straw/Hay Bale Dike
	\bigcirc Sediment Basin	\bigcirc Streambank Protection
	Sediment Traps	\bigcirc Temporary Swale
	Silt Fence	Topsoiling
	Stabilized Construction Entrance	\bigcirc Vegetating Waterways
	\bigcirc Storm Drain Inlet Protection	Permanent Structural
	\bigcirc Straw/Hay Bale Dike	
	\bigcirc Temporary Access Waterway Crossing	🔿 Debris Basin
	\bigcirc Temporary Stormdrain Diversion	○ Diversion
	\bigcirc Temporary Swale	\bigcirc Grade Stabilization Structure
	\bigcirc Turbidity Curtain	Land Grading
	\bigcirc Water bars	\bigcirc Lined Waterway (Rock)
		\bigcirc Paved Channel (Concrete)
	Biotechnical	\bigcirc Paved Flume
	○ Brush Matting	\bigcirc Retaining Wall
	\bigcirc Wattling	\bigcirc Riprap Slope Protection
		\bigcirc Rock Outlet Protection
		\bigcirc Streambank Protection

	Important: Completion of Questions 27-39 is not required if response to Question 22 is No.
•	Identify all site planning practices that were used to prepare the final site plan/layout for the project.
	• Preservation of Undisturbed Areas
	O Preservation of Buffers
	Reduction of Clearing and Grading
	Locating Development in Less Sensitive Areas
	O Roadway Reduction
	• Sidewalk Reduction
	O Driveway Reduction
	O Cul-de-sac Reduction
	O Building Footprint Reduction
	O Parking Reduction

- 27a. Indicate which of the following soil restoration criteria was used to address the requirements in Section 5.1.6("Soil Restoration") of the Design Manual (2010 version).
 - All disturbed areas will be restored in accordance with the Soil Restoration requirements in Table 5.3 of the Design Manual (see page 5-22).
 - O Compacted areas were considered as impervious cover when calculating the WQv Required, and the compacted areas were assigned a post-construction Hydrologic Soil Group (HSG) designation that is one level less permeable than existing conditions for the hydrology analysis.

final site plan/layout). Total WQv Required	28.	Prov:	ide	the	tota	l Water	Oualit	v Volume	(WOV)	required	for t	his r	project	(based	on
Total WQv Required		fina	l si	te p	lan/	ayout)		7	1.0.2.07					(Nabea	Q
		Tota]	. WQ1	v Re	quire	d									
					1 0	1									

29. Identify the RR techniques (Area Reduction), RR techniques(Volume Reduction) and Standard SMPs with RRv Capacity in Table 1 (See Page 9) that were used to <u>reduce</u> the Total WQv Required(#28).

Also, provide in Table 1 the total impervious area that contributes runoff to each technique/practice selected. For the Area Reduction Techniques, provide the total contributing area (include: pervious area) and, if applicable, the total impervious area that contributes runoff to the technique/practice.

Note: Redevelopment projects shall use Tables 1 and 2 to identify the SMPs used to treat and/or reduce the WQv required. If runoff reduction techniques will not be used to reduce the required WQv, skip to question 33a after identifying the SMPs.

Table 1 - Runoff Reduction (RR) Techniques and Standard Stormwater Management Practices (SMPs)

	Total C	Contributin	g	Тс	otal	Co	ntr	ibu	ting
RR Techniques (Area Reduction)	Area	(acres)		Impe	ervi	ous	Ar	ea (a	acres)
○ Conservation of Natural Areas (RR-1)			and/	or].[
O Sheetflow to Riparian Buffers/Filters Strips (RR-2)			and/	or].		
○ Tree Planting/Tree Pit (RR-3) ○ Disconnection of Rooftop Runoff (RR-4).	•		and/	or or			•		
RR Techniques (Volume Reduction)				ſ	1		ı r		
○ Vegetated Swale (RR-5) ·····	•••••			[•		
🔿 Rain Garden (RR-6)							•		
Stormwater Planter (RR-7)				•		0	. (7 0	3
○ Rain Barrel/Cistern (RR-8)				•			•		
○ Porous Pavement (RR-9)				. [•		
\bigcirc Green Roof (RR-10)	•••••			•			-		
Standard SMPs with RRv Capacity									
\bigcirc Infiltration Trench (I-1)							•		
\bigcirc Infiltration Basin (I-2)				•			•		
\bigcirc Dry Well (I-3)	•••••						•		
\bigcirc Underground Infiltration System (I-4) .		•••••		. L			•		
\bigcirc Bioretention (F-5)	•••••	•••••		• _			•		
\bigcirc Dry Swale (O-1) \cdots	•••••			•			•		

Standard SMPs

	- 1
O Micropool Extended Detention (P-1)	
○ Wet Pond (P-2)	-
O Wet Extended Detention (P-3)	
O Multiple Pond System (P-4)	
O Pocket Pond (P-5) · · · · · · · · · · · · · · · · · · ·	
O Surface Sand Filter (F-1)	
O Underground Sand Filter (F-2)	-
O Perimeter Sand Filter (F-3)	
○ Organic Filter (F-4)	
○ Shallow Wetland (W-1)	
○ Extended Detention Wetland (W-2)	
○ Pond/Wetland System (W-3)	
○ Pocket Wetland (W-4)	
○ Wet Swale (0-2)	

Table 2 - Alternative SMPs (DO NOT INCLUDE PRACTICES BEING USED FOR PRETREATMENT ONLY)
Alternative SMP Total Contributing Impervious Area(acres)
O Hydrodynamic
O Wet Vault
O Media Filter
Provide the name and manufacturer of the Alternative SMPs (i.e. proprietary practice(s)) being used for WQv treatment. Name Name
Manufacturer
Note: Redevelopment projects which do not use RR techniques, shall use questions 28, 29, 33 and 33a to provide SMPs used, total WQv required and total WQv provided for the project.
30. Indicate the Total RRv provided by the RR techniques (Area/Volume Reduction) and Standard SMPs with RRv capacity identified in question 29.
Total RRv provided
31. Is the Total RRv provided (#30) greater than or equal to the total WQv required (#28). If Yes, go to question 36. If No, go to question 32.
32. Provide the Minimum RRv required based on HSG. [Minimum RRv Required = (P)(0.95)(Ai)/12, Ai=(S)(Aic)]
Minimum RRv Required
0.005 _{acre-feet}
 32a. Is the Total RRv provided (#30) greater than or equal to the Minimum RRv Required (#32)? If Yes, go to question 33. <u>Note</u>: Use the space provided in question #39 to <u>summarize</u> the specific site limitations and justification for not reducing 100% of WQv required (#28). A <u>detailed</u> evaluation of the specific site limitations and justification for not reducing 100% of the WQv required (#28) must also be included in the SWPPP. If No, sizing criteria has not been met, so NOI can not be processed. SWPPP preparer must modify design to meet sizing criteria.

Page 10 of 14

33. Identify the Standard SMPs in Table 1 and, if applicable, the Alternative SMPs in Table 2 that were used to treat the remaining total WQv(=Total WQv Required in 28 - Total RRv Provided in 30).

Also, provide in Table 1 and 2 the total <u>impervious</u> area that contributes runoff to each practice selected.

Note: Use Tables 1 and 2 to identify the SMPs used on Redevelopment projects.

33a.	Indicate the Total WQv provided (i.e. WQv treated) by the SMPs identified in question #33 and Standard SMPs with RRv Capacity identified in question 29. WQv Provided
	<u> </u>
<u>Note</u> :	: For the standard SMPs with RRv capacity, the WQv provided by each practice = the WQv calculated using the contributing drainage area to the practice - RRv provided by the practice. (See Table 3.5 in Design Manual)
34.	Provide the sum of the Total RRv provided (#30) and the WQv provided (#33a).
35.	Is the sum of the RRv provided (#30) and the WQv provided (#33a) greater than or equal to the total WQv required (#28)? $\textcircled{\label{eq:stable} Yes}$ \bigcirc No
	If Yes, go to question 36. If No, sizing criteria has not been met, so NOI can not be processed. SWPPP preparer must modify design to meet sizing criteria.
36.	Provide the total Channel Protection Storage Volume (CPv) required and provided or select waiver (36a), if applicable.
	CPv Required CPv Provided
	CPv Required CPv Provided
36a. :	CPv Required CPv Provided CPv Required CPv Provided
36a. 5	CPv Required CPv Provided
36a. : 	CPv Required CPv Provided
36a. 5 37.	CPv Required CPv Provided
36a. : 37.	CPv Required CPv Provided
36a. : 37.	CPv Required CPv Provided
36a. : 37.	CPv Required CPv Provided
36a. : 	CPv Required CPv Provided

37a. The need to meet the Qp and Qf criteria has been waived because:O Site discharges directly to tidal waters or a fifth order or larger stream.O Downstream analysis reveals that the Qp and Qf controls are not required

38. Has a long term Operation and Maintenance Plan for the post-construction stormwater management practice(s) been developed?

•Yes O No

If Yes, Identify the entity responsible for the long term $\ensuremath{\mathsf{Operation}}$ and $\ensuremath{\mathsf{Maintenance}}$

V O T	w n	o f	L	e w	i	s b	0	r	0	М	S	4							
				~															

39. Use this space to summarize the specific site limitations and justification for not reducing 100% of WQv required(#28). (See question 32a) This space can also be used for other pertinent project information.

All impervious areas are treated - lawn areas & gravel driveway are not treated - flow across lawn buffer to wetland.

40. Identify other DEC permits, existing and new, that are required for this project/facility.

 $\bigcirc\, {\rm Air}$ Pollution Control

 \bigcirc Coastal Erosion

- ⊖ Hazardous Waste
- Long Island Wells

○ Mined Land Reclamation

🔿 Solid Waste

 \bigcirc Navigable Waters Protection / Article 15

- Water Quality Certificate
- Dam Safety

○ Water Supply

○ Freshwater Wetlands/Article 24

O Tidal Wetlands

○ Wild, Scenic and Recreational Rivers

 \bigcirc Stream Bed or Bank Protection / Article 15

○ Endangered or Threatened Species(Incidental Take Permit)

 \bigcirc Individual SPDES

0	SPDES	Mu.	lti	L-S	lec	toı	GI GI	2	1	Y	R									
۲	Other	Ν	Y	C	D	Е	Р		I	R	S	Ρ								

() None

41.	Does this project require a US Army Corps of Engineers Wetland Permit? If Yes, Indicate Size of Impact.	O Yes	• No
42.	Is this project subject to the requirements of a regulated, traditional land use control MS4? (If No, skip question 43)	• Yes	() No
43.	Has the "MS4 SWPPP Acceptance" form been signed by the principal executive officer or ranking elected official and submitted along with this NOI?	• Yes	O No
44.	If this NOI is being submitted for the purpose of continuing or transf coverage under a general permit for stormwater runoff from constructio activities, please indicate the former SPDES number assigned. NYR	erring n	

Owner/Operator Certification I have read or been advised of the permit conditions and believe that I understand them. I also Induct read of been advised of the permit constraints and believe that I understand them. I also understand that, under the terms of the permit, there may be reporting requirements. I hereby certify that this document and the corresponding documents were prepared under my direction or supervision. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations. I further understand that coverage under the general permit will be identified in the acknowledgment that I will receive as a result of submitting this NOI and can be as long as sixty (60) business days as provided for in the general permit. I also understand that, by submitting this NOI, I am acknowledging that the SWPPP has been developed and will be implemented as the first element of construction, and agreeing to comply with all the terms and conditions of the general permit for which this NOI is being submitted. Print First Name MI Allex Print Last Name Bernabo Owner/Operator Signature Date 0 0 2 0 2 3 4 1 5

APPENDIX E

NYSDEC MS4

NYS	NEW YORK STATE OF OPPORTUNITYDepartment of Environmental ConservationDepartment of Environmental Conservation Division of Water 625 Broadway, 4th Floor Albany, New York 12233-3505
MS4 Stormwate	r Pollution Prevention Plan (SWPPP) Acceptance Form
Construction Act *(NOTE: Attach Co	ivities Seeking Authorization Under SPDES General Permit mpleted Form to Notice Of Intent and Submit to Address Above)
I. Project Owner/Operato	or Information
1. Owner/Operator Name:	Alex Bernabo / WDesigne
2. Contact Person:	Alex Bernabo
3. Street Address:	3867 Danbury Rd
4. City/State/Zip:	Brewster, NY 10509
II. Project Site Information	on
5. Project/Site Name:	96 Post Office Rd
6. Street Address:	96 Post Office Rd
7. City/State/Zip:	Waccabuc, NY 10597
III. Stormwater Pollution	Prevention Plan (SWPPP) Review and Acceptance Information
8. SWPPP Reviewed by:	
9. Title/Position:	
10. Date Final SWPPP Revi	ewed and Accepted:
IV. Regulated MS4 Information	ation
11. Name of MS4:	
12. MS4 SPDES Permit Ider	ntification Number: NYR20A
13. Contact Person:	
14. Street Address:	
15. City/State/Zip:	
16. Telephone Number:	

MS4 SWPPP Acceptance Form - continued

V. Certification Statement - MS4 Official (principal executive officer or ranking elected official) or Duly Authorized Representative

I hereby certify that the final Stormwater Pollution Prevention Plan (SWPPP) for the construction project identified in question 5 has been reviewed and meets the substantive requirements in the SPDES General Permit For Stormwater Discharges from Municipal Separate Storm Sewer Systems (MS4s). Note: The MS4, through the acceptance of the SWPPP, assumes no responsibility for the accuracy and adequacy of the design included in the SWPPP. In addition, review and acceptance of the SWPPP by the MS4 does not relieve the owner/operator or their SWPPP preparer of responsibility or liability for errors or omissions in the plan.

Printed Name:

Title/Position:

Signature:

Date:

VI. Additional Information

(NYS DEC - MS4 SWPPP Acceptance Form - January 2015)

Page 2 of 2

APPENDIX F

Short Form EAF

Short Environmental Assessment Form Part 1 - Project Information

Instructions for Completing

Part 1 – Project Information. The applicant or project sponsor is responsible for the completion of Part 1. Responses become part of the application for approval or funding, are subject to public review, and may be subject to further verification. Complete Part 1 based on information currently available. If additional research or investigation would be needed to fully respond to any item, please answer as thoroughly as possible based on current information.

Complete all items in Part 1. You may also provide any additional information which you believe will be needed by or useful to the lead agency; attach additional pages as necessary to supplement any item.

Part 1 Project and Snansor Information		
rart 1 – rroject and Sponsor information		
Name of Action or Project:		
96 Post Office Rd		
Project Location (describe, and attach a location map):		
96 Post Office Rd		
Brief Description of Proposed Action:		
Construction of 2,600 sf single family 2-bedroom residence with a 600 sf garage with a grav sewage disposal system (OWTS) with 12' of fill, 1,000 gal. septic tank and 1,000 gal. pump ta	el driveway and individual we ink.	ll and individual subsurface
Name of Applicant or Sponsor:	Telephone: 845-278-211	0
Peder Scott, P.E., R.A.	E-Mail: pwscott@pwscot	t.com
Address:		
PW Scott Engineering & Architecture, PC		
City/PO:	State:	Zip Code:
Brewster	NY	10509
1. Does the proposed action only involve the legislative adoption of a plan, loca administrative rule, or regulation?	l law, ordinance,	NO YES
If Yes, attach a narrative description of the intent of the proposed action and the e may be affected in the municipality and proceed to Part 2. If no, continue to ques	nvironmental resources th tion 2.	at 🔽 🗖
2. Does the proposed action require a permit, approval or funding from any other	er government Agency?	NO YES
If Yes, list agency(s) name and permit or approval: NYCDEP, WCDOH, Town of Building Permit	of Lewisboro, Wetland Pe	rmit,
3. a. Total acreage of the site of the proposed action?	4.04 acres	
b. Total acreage to be physically disturbed?	0.45 acres	
or controlled by the applicant or project sponsor?	4.04 acres	
4. Check all land uses that occur on, are adjoining or near the proposed action:		
🗌 Urban 🔲 Rural (non-agriculture) 🗌 Industrial 🔲 Commercia	l 🗌 Residential (subur	ban)
Forest Agriculture Aquatic I Other(Spec	ify): Wetlands	
Parkland	•	
		1

5. Is the proposed action,	NO	YES	N/A
a. A permitted use under the zoning regulations?		\checkmark	
b. Consistent with the adopted comprehensive plan?		\checkmark	
6 Is the proposed action consistent with the predominant character of the existing built or natural landscape?		NO	YES
· · · · · · · · · · · · · · · · · · ·			\checkmark
7. Is the site of the proposed action located in, or does it adjoin, a state listed Critical Environmental Area?		NO	YES
If Yes, identify:		\checkmark	
8 a Will the proposed action result in a substantial increase in traffic above present levels?		NO	YES
a. with the proposed action result in a substantial increase in traine above present revers?		\checkmark	
b. Are public transportation services available at or near the site of the proposed action?		\checkmark	
c. Are any pedestrian accommodations or bicycle routes available on or near the site of the proposed action?		\checkmark	
9. Does the proposed action meet or exceed the state energy code requirements?		NO	YES
If the proposed action will exceed requirements, describe design features and technologies:			
10. Will the proposed action connect to an existing public/private water supply?		NO	YES
If No, describe method for providing potable water:			
		\checkmark	
11. Will the proposed action connect to existing wastewater utilities?		NO	YES
If No, describe method for providing wastewater treatment:			
12. a. Does the project site contain, or is it substantially contiguous to, a building, archaeological site, or district	i l	NO	YES
Commissioner of the NYS Office of Parks, Recreation and Historic Preservation to be eligible for listing on the State Register of Historic Places?	-		
b. Is the project site, or any portion of it, located in or adjacent to an area designated as sensitive for archaeological sites on the NY State Historic Preservation Office (SHPO) archaeological site inventory?			
13. a. Does any portion of the site of the proposed action, or lands adjoining the proposed action, contain wetlands or other waterbodies regulated by a federal, state or local agency?		NO	YES
b. Would the proposed action physically alter, or encroach into, any existing wetland or waterbody?	-		
If Yes, identify the wetland or waterbody and extent of alterations in square feet or acres:		<u> </u>	
Local wetland. Waterbody Tributary to NYSDEC River - 864-317 Class A (T)			

 14. Identify the typical habitat types that occur on, or are likely to be found on the project site. Check all that apply: □ Shoreline		
 ☐ Shoreline		
 Wetland Urban Suburban 15. Does the site of the proposed action contain any species of animal, or associated habitats, listed by the State or Federal government as threatened or endangered? Long Eared Bat 		
15. Does the site of the proposed action contain any species of animal, or associated habitats, listed by the State or Federal government as threatened or endangered? Long Eared Bat		
Federal government as threatened or endangered? Long Eared Bat	NO	YES
16. Is the project site located in the 100-year flood plan? Stream is beyond flood zone.	NO	YES
	\checkmark	
17. Will the proposed action create storm water discharge, either from point or non-point sources?	NO	YES
If Yes,		\checkmark
a. Will storm water discharges flow to adjacent properties?		\checkmark
b. Will storm water discharges be directed to established conveyance systems (runoff and storm drains)?		$\mathbf{\nabla}$
If Yes, briefly describe: Discharges to wetland & stream which bisects the property.	<u> </u>	
18 Does the proposed action include construction or other activities that would result in the impoundment of water 1		VEG
or other liquids (e.g., retention pond, waste lagoon, dam)?	NO	YES
If Yes, explain the purpose and size of the impoundment:		
19. Has the site of the proposed action or an adjoining property been the location of an active or closed solid waste	NO	YES
If Yes, describe:		
		\square
		LJ
20.Has the site of the proposed action or an adjoining property been the subject of remediation (ongoing or	NO	YES
completed) for hazardous waste?		
IT Yes, describe:	7	
	<u>×</u>	
LCEDTIEV THAT THE INFORMATION BROWDER ABOVE IS TRUE AND A OCUPATE TO THE REPORT		
MY KNOWLEDGE	l'OF	
Applicant/sponsor/name: /Peder Scott, P.E., R.A Date: April 5, 2023		
Signature:		

FIGURES

Figure 1.0: Lot Aerial Photo Figure 2.0: NYSDEC Mapper Printout Figure 3.0: Soils Map





Figure 2.0 NYCDEC Mapper

Post Office Rd 8 Pab CSD

Figure 3.0 Soils Map 96 Post Office Rd, Waccabuc, NY (T) Lewisboro

Area Wetland Impact Table

Residence & Garage & Deck

Sediment Trap: Well and water line Subtotal: 9.306 sf = 0.213 acres

Wetland Buffer Area -100 ft Subtotal: 13,471 sf = 0.309 acres

Total Site Disturbance: 0.52 acres





WdC- Woodbridge, 8 TO 15 PERCENT SLOPES- class C Sh- Sun Ioam- Class D PnC-Paxton silt Loam, 8 to 15 PERCENT SLOPES- Class C

SOILS LEGEND

96 Post Office Rd WACCABUC, NY (T) LEWISBORO COUNTY OF WESTCHESTER

DRAINAGE ANALYSIS SYNOPSIS

Prepared By:

Peder W. Scott, P.E., R.A.P. W. Scott Engineering & Architecture, P.C.3871 Danbury Rd. (Route 6)Brewster, NY 10509

April 6, 2023

96 Post Office Rd Waccabuc, NY (T) Lewisboro

TABLE OF CONTENTS

Existing Conditions and Proposed Conditions

Concrete Planter Routing Analysis

Routing of Planter

Stormwater Attenuation Synopsis

Findings

Conclusion

Attachments

Attachment A:

- A: Pre-Development Analysis Watershed Worksheet
 1. Pond Pack Model Schematic
 2. Watershed Worksheet EX1
 - 3. Pond Pack Computer Printout
 - a. Watershed Summary
 - b. Tc Analysis
 - c. Hydrographs

Attachment B:

- Post-Development Analysis Watershed Worksheet1. Pond Pack Model Schematic
 - 2. Wetersteil Weiter volgt 9. W
 - 2. Watershed Worksheet WS1 & WS2
 - 3. Pond Pack Computer Printout
 - a. Watershed Summary
 - b. Tc Analysis
 - c. Hydrographs

Attachment C:

- Concrete Flow through Planter 1. Planter Volume
- 2. Planter Outlet Structures
- 3. Planter Routing
- 4. Planter 1-Year Routing Time

2

Existing Condition (Refer to Sheet D1 & Attachment A)

Soil ConditionWdC (Class C)Along RoadSh (Class D)Sh (Class D)CoverWoodsTravel TimeFrom North Street frontage to Analysis Point A location on stream
as noted on Dwg D1

Area of Analysis consists of area disturbed on the lot – remainder is wooded and wetland areas undisturbed.

Input Data

EX1 - Existing Condition Area = 0.651 acres CN = 74.8 Tc = .167 hoursRefer to Drainage Worksheet

<u>Proposed Condition</u> (Refer to Sheet D1 & Attachment B) Soil Condition – Wdc & Sh as noted above.

Cover – Woods remain at north property line and behind house. Driveway - Gravel Septic Area – Lawn Deck – Assumes rainfall drains through deck to brush cover below House Roof of 3,200 drains to planter (brush cover) of 570 sf

Input Data

 $\frac{\text{WS1 Roof \& Planter}}{\text{Area} = 3,770 \text{ sf} = .087 \text{sf}}$

CN = 92.7Tc = 0.10 hrs. Tt to Point A (.02 hrs.) insignificant

WS2 – Remainder of lot drains directly to rear of lot – Wetlands.

 Area =
 .565 acres

 CN = 74.2

 Tc = .134 hrs.

Includes driveway and parking area, septic lawn area, brush at rear of house Refer to Drainage Worksheets.

Concrete Planter Routing Analysis

Storm events per Extreme Precipitation Tables.

1-year	2.82 inches
2-year	3.40 inches
10-year	5.08 inches
100-year	9.04 inches

Concrete Flow through planter modeled as follows.

<u>Planter Model</u> Filter @ 486.0 Wood Chips @ 486.25 (+3") (start of ponding) Outlets (2) Weirs @ 487.25 Rectangular – 6" Long Weir Coef: 2.8 avg. Infiltration assumed at 2.0 in/hour: Topsoil cover

Routing of Planter

The routing of the planter for the above storms is tabulated below:

Storm	In Flow (cfs)	Out Flow (cfs)	Elevation (ft)	Storm (ft)
100-Year	.65	.36	487.5	0.02
10-Year	.35	0.0	487.06	0.014
2-Year	.22	0.0	486.58	0.008
1-Year	.18	0.0	486.43	0.006

Stormwater Attenuation Synopsis

The following is an overall analysis of the quantitative discharge from the site due to the development proposed. Mitigation is in the form of the concrete flow through the planter providing the required attenuation.

The NYSDEC attenuation requirements are as follows:

- A) 1 Year Storm Event Channel Protection Reduce by 50% from pre-development levels Attenuation level met.
- B) 2 Year Storm Event
 Peak Discharge approx. reduced to 1 Year Storm Event
 Attenuation Level met
- C) 10 Year Storm Event Overbank Control Attenuate to below Pre-Development Levels
- D) 100 Year Storm Event Extreme Flood Control Attenuate to below Pre-Development Levels.

Analysis Point A				
	1 YR (cfs)	2 YR (cfs)	10 YR (cfs)	100 YR (cfs)
PRE	.48	.73	1.53	3.60
POST	.42	.64	1.33	3.40
NET	-0.6	09	-0.20	-0.20
%	-12%	-12%	-13%	-5.6%

Findings

A.	1-Year Storm Event	Channel protection could not be reduced by 50% even though planter did not discharge any of the 1-year storm. Large area of pervious cover discharges off site – reduction by 12%
B.	2-Year Storm Event	Reduced is reduced by 12%. Could not meet the pre-development discharge rate even though planter did not discharge any of the 2-year storm event. Large area of site drained directly into the wetland and stream.
C. D.	10-Year Storm Event 100-Year Storm Event	Attenuation met to pre-development levels. Attenuation met to pre-development levels.

Conclusion

Planters attenuate stormwater discharge to the maximum extent possible while providing treatment of impervious areas on the site.

Remainder of the site is treated by riparian buffers in the place along the edge of the wetland, brush strip minimum of 20' wide @ 1% slope.

ATTACHMENT A

Pre-Development Analysis Watershed Worksheets

- 1. Pond Pack Model Schematic
- 2. Watershed Worksheet EX1
- 3. Pond Pack Computer Printout
 - a. Watershed Summary
 - b. Tc Analysis
 - c. Hydrographs





Extreme Precipitation Tables

Northeast Regional Climate Center

Data represents point estimates calculated from partial duration series. All precipitation amounts are displayed in inches.

Metadata for Point	Yes			41.290 degrees North	73.579 degrees West	150 feet	Thu Mar 30 2023 14:46:55 GMT-0400 (Eastern Davlight	Time)
	Smoothing	State	Location	Latitude	Longitude	Elevation	Date/Time	

Extreme Precipitation Estimates

													E				
	5min	10min	15min	30min	60min	120min		1hr	2hr	3hr	6hr	12hr	(24hr	48hr		1day	2da
1yr	0.33	0.51	0.63	0.83	1.03	1.29	1yr	0.89	1.22	1.48	1.84	2.28	2.83	3.18	1yr	2.50	3.0(
2yr	0.39	0.61	0.75	66.0	1.25	1.57	2yr	1.08	1.46	1.80	2.23	2.76	3.40	3.82	2yr	3.01	3.6
5yr	0.46	0.72	06.0	1.21	1.54	1.95	Syr	1.33	1.80	2.26	2.81	3.47	4.27	4.82	Syr	3.78	4.62
10yr	0.52	0.81	1.03	1.39	1.81	2.31	10yr	1.56	2.11	2.68	3.34	4.13	5.08	5.76	10yr	4.50	5.54
25yr	0.60	0.96	1.22	1.69	2.24	2.90	25yr	1.94	2.61	3.38	4.22	5.22	6.38	7.29	25yr	5.65	7.0
50yr	0.68	1.09	1.40	1.97	2.64	3.44	50yr	2.28	3.06	4.02	5.03	6.21	7.59	8.71	50yr	6.72	8.3
100yr	0.77	1.25	1.61	2.29	3.12	4.08	100yr	2.69	3.60	4.79	6.00	7.41	9.04	10.41	100vr	8.00	10.0
200yr	0.88	1.43	1.86	2.66	3.68	4.85	200yr	3.18	4.23	5.70	7.16	8.83	10.76	12.46	200vr	9.52	11.9
500yr	1.05	1.73	2.26	3.28	4.60	6.10	500yr	3.97	5.24	7.18	9.03	11.14	13.55	15.80	500yr	11.99	15.1
•		,													•		

Lower Confidence Limits

÷

2da ⁻			2.6; •
ldav			2.23
		ķ	N.
48hr			7./0
24 hr		Cy C	70.7
12hr		000	7.07
6hr		1 20	1.70
3hr		1 20	1.4U
2hr		0 03	>
1 hr		0.65	
		TV 1	
120min		0 95	
60min		0.75	
30min		0.61	
15min		0.45	
10min		0.37	
5min		0.24	
	,	lyr	

Type.... Design Storms Name.... WESTCH BRITTON File.... C:\HAESTAD\PPKW\RAINFALL\STORMS.RNQ Title... JOB TITLE NOT SPECIFIED Click Project Summary on the File Menu to enter title DESIGN STORMS SUMMARY Design Storm File, ID = STORMS.RNQ WESTCH BRITTON Storm Tag Name = 1-YR Description: 1 YEAR FIRST FLUSH -----Data Type, File, ID = Synthetic Storm SCSTYPES.RNF TypeIII 24hr Storm Frequency = 1 yr Total Rainfall Depth= 2.6987 in Duration Multiplier = 1 Resulting Duration = 30.0000 hrs Resulting Start Time= .0000 hrs Step= .1000 hrs End= 30.0000 hrs Storm Tag Name = 2-YR Description: 2 YEAR Data Type, File, ID = Synthetic Storm SCSTYPES.RNF TypeIII 24hr Storm Frequency = 2 yr Total Rainfall Depth= 3.2538 in Duration Multiplier = 1 Resulting Duration = 30.0000 hrs Resulting Start Time= .0000 hrs Step= .1000 hrs End= 30.0000 hrs Storm Tag Name = 10-YR Description: 10 YEAR -----Data Type, File, ID = Synthetic Storm SCSTYPES.RNF TypeIII 24hr Storm Frequency = 10 yr Total Rainfall Depth= 4.8616 in Duration Multiplier = 1 Resulting Duration = 30.0000 hrs Resulting Start Time= .0000 hrs Step= .1000 hrs End= 30.0000 hrs Storm Tag Name = 100-yr Description: 100 yr Data Type, File, ID = Synthetic Storm SCSTYPES.RNF TypeIII 24hr Storm Frequency = 100 yr Total Rainfall Depth= 8.6513 in Duration Multiplier = 1 Resulting Duration = 30.0000 hrs

Resulting Start Time= .0000 hrs Step= .1000 hrs End= 30.0000 hrs

ATTACHMENT A

Pre-Development Analysis Watershed Worksheets

- 1. Pond Pack Model Schematic
- 2. Watershed Worksheet EX1
- 3. Pond Pack Computer Printout
 - a. Watershed Summary
 - b. Tc Analysis
 - c. Hydrographs

Drain	age Area #	EX 1						
Devel	opment	Pre	X					28,373
		Post				*****	*******	, <u>· · · -</u>
							TOTAL	0.651
	-						-	
Use		Soil Ty	pe	Soil Clas	SS	CN	Area	CN x Area
						-		
Woods-fair Wdc		С		73	0.351	25.623		
Wood	-wetland	Sh	Sh		D		0.300	23.100
Buildi	ng							
Grave	1							
Brush	-							
					***		-	
				TOTAL			0.651	48.723
	CN	V (Weight	ed) =sum(Cl	N x A) div	ided by Su	ım (A) =		74.8
]	Runoff:	Stor	rm Event Ty	pe N10D	24 Hour R	lainfall	2002 NYS	DEC MANUAL
			1 Year =		2.82 in		2.50	in
			2 Year =) in		3.50	in
			10 Year =		3 in		5.00	in
			100 Year	9.04	in		7.50	in
Annua	l Rainfall: 4	0.2 in						
Tc Ana	alysis Calcul	ations: Mo	Cuen & Spi	ess Calcu	lations			
A	Sheet			Тс	Tc Flow Ler		8	3.0
	Flow							
				0.146	Slope:		11.	50%
	l				Cover:		wo	ods
B	Shallow	Concentra	ted Flow		Paved:			no
				0.021	Unpave	d:		yes
					Hydrau	lic		211
			Velocity	2.8	Average	e Land		3.00%
~					L	T		
U	Channel	Flow			FlowArea:		Q	
				0.000	Descrip.	15" pipe	N=	0.013
					Length:	0	Width:	
		L			Depth		Slope:	
		T			V	8	Wp	
		<u> </u>		·····				
		Minimun	$\frac{11c = 0.10}{2}$	0 1 15	·			
Total T _c			0.167					

i

* * * * * * * * * * * * * * * * * *	****** MASTER SUMMARY ************************************	*****
Watershed	Master Network Summary	1.01
* * * * * * * * * * * * * * * * * * *	** DESIGN STORMS SUMMARY ***********	****
WESTCH BRITTON	Design Storms	2.01
* * * * * * * * * * * * * * * * * * *	**** RUNOFF HYDROGRAPHS ************	****
EX1 EXISTING	1-YR SCS Unit Hyd. Summary	3.01
EX1 EXISTING	2-YR SCS Unit Hyd. Summary	3.02
EX1 EXISTING	10-YR SCS Unit Hyd. Summary	3.03
EX1 EXISTING	100-yr SCS Unit Hyd. Summary	3.04
WS1-ROOF&PLAN	1-YR SCS Unit Hyd. Summary	3.05
WS1-ROOF&PLAN	2-YR SCS Unit Hyd. Summary	3.06
WS1-ROOF&PLAN	10-YR SCS Unit Hyd. Summary	3.07
WS1-ROOF&PLAN	100-yr SCS Unit Hyd. Summary	3.08
WS2- TO WETLAND	1-YR SCS Unit Hyd. Summary	3.09

S/N: B21A01606A8C PondPack Ver. 7.5 (786c) Table of Contents (continued)

WS	2- TO WET	LAND	2-YR SCS Unit Hvd. Summary	3 10
WS	2- TO WETI	LAND	10-YR	5.10
			SCS Unit Hyd. Summary	3.11
WS	2- TO WETI	LAND	100-yr SCS Unit Hyd. Summary	3.12
:	* * * * * * * * * *	* * * * * *	**** POND VOLUMES ************************************	*****
FΤ	PLANTER.	••••	Vol: Planimeter	4.01
* * *	* * * * * * * * *	* * * * *	**** OUTLET STRUCTURES **************	*****
PLA	NTER OUT.		Outlet Input Data	5.01
* * *	*****	* * * * *	***** POND ROUTING ****************	* * * * * *
FT	PLANTER	OUT	1 - YR	
			Pond Routing Summary	6.01 6.02
FT	PLANTER	Ουτ	2-YR Pond Routing Summary	6.03
FT	PLANTER	OUT	10-YR Pond Routing Summary	6.04
FT	PLANTER	OUT :	100-yr Pond Routing Summary	6.05

Type.... Master Network Summary Page 1.01 Name.... Watershed File.... Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\PRE AND POST ANALYSIS.PPW

MASTER DESIGN STORM SUMMARY

Default Network Design Storm File, ID STORMS.RNQ WESTCH BRITTON

Total Depth Rainfall Return Event in Туре RNF File RNF ID ----------_____ ----------Synthetic CurveSCSTYPESSynthetic CurveSCSTYPESSynthetic CurveSCSTYPES 1-YR 2.6987 TypeIII 24hr 2 - YR 3.2538 TypeIII 24hr 10-YR 4.8616 TypeIII 24hr 100-yr 8.6513 Synthetic Curve SCSTYPES TypeIII 24hr

> MASTER NETWORK SUMMARY SCS Unit Hydrograph Method

(*Node=Outfall; +Node=Diversion;) (Trun= HYG Truncation: Blank=None; L=Left; R=Rt; LR=Left&Rt)

Stor	age			Return	HYG Vol		Qpeak	Qpeak	Max WSEL	Max Pond
No 	de ID		Туре	Event	ac-ft	Trun	hrs	cfs	ft	ac-ft
-										
*AN/	ALYSIS-PO	ST	JCT	1	.034		12.1500	47		
*AN/	ALYSIS-PO	ST	JCT	2	.051		12.1500	64		
*AN/	ALYSIS-PO	ST	JCT	10	.107		12.1000	1.33		
*AN/	ALYSIS-PO:	ST	JCT	100	.277		12.1500	3.40		
*AN/	ALYSIS-PRI	E	JCT	1	.041		12.1500	18		
*ANA	\LYSIS-PRE	E	JCT	2	.061		12.1500	.40		
*ANA	VLYSIS-PRE	-	JCT	10	.126		12.1500	1 5 3		
*ANA	LYSIS-PRE	-	JCT	100	.304		12.1500	3.60		
EX1	EXISTING	Ĵ	AREA	1	041		12 1500	40		
EX1	EXISTING		AREA	2	061		12.1500	.48		
EX1	EXISTING	5	AREA	10	126		12.1500	./3		
EX1	EXISTING	j	AREA	100	. 304		12.1500	3.60		
гт										
гі	PLANTER	1 N 7 N	POND	1	.014		12.1000	.18		
			PUND	2	.018		12.1000	. 22		
		1 N	POND	10	.029		12.1000	.35		
ΓI	FLANIER	1 N	POND	100	.056		12.1000	.64		
FT	PLANTER	ОИТ	POND	1	.000		7.0000	00	186 13	0.05
FT	PLANTER	OUT	POND	2	.000		6.2500	.00	400.43	.006
FT	PLANTER	OUT	POND	10	.000		4.3500	.00	487.06	.008 .014

S/N: B21A01606A8C PondPack Ver. 7.5 (786c)

P.W. Scott Engineering & Arch Compute Time: 14:09:00 Date: 04/06/2023
Type.... SCS Unit Hyd. Summary Page 3.01 Name.... EX1 EXISTING Tag: 1-YR Event: 1 yr File.... Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\PRE AND POST ANALYSIS.PPW Storm... TypeIII 24hr Tag: 1-YR SCS UNIT HYDROGRAPH METHOD STORM EVENT: 1 year storm Duration = 30.0000 hrs Rain Depth = 2.6987 in Rain Dir = C:\HAESTAD\PPKW\RAINFALL\ Rain File - ID = SCSTYPES.RNF - TypeIII 24hr Unit Hyd Type = Default Curvilinear = Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\ HYG Dir HYG File - ID = - EX1 EXISTING 1-YR

Drainage Area = .651 acres Runoff CN= 75

= .1670 hrs

Τc

Computational Time Increment= .02227 hrsComputed Peak Time= 12.1576 hrsComputed Peak Flow= .49 cfs

Time Increment for HYG File = .0500 hrs Peak Time, Interpolated Output = 12.1500 hrs Peak Flow, Interpolated Output = .48 cfs

DRAINAGE AREA

ID:None Selected CN = 75 Area = .651 acres S = 3.3690 in 0.2S = .6738 in

Cumulative Runoff -----. .7602 in

.041 ac-ft

HYG Volume... .041 ac-ft (area under HYG curve)

***** UNIT HYDROGRAPH PARAMETERS *****

Time Concentration, Tc = .16700 hrs (ID: None Selected) Computational Incr, Tm = .02227 hrs = 0.20000 Tp Unit Hyd. Shape Factor = 483.432 (37.46% under rising limb)K = 483.43/645.333, K = 7491 (also, K = 2/(1+(Tr/Tp)))Receding/Rising, Tr/Tp = 1.6698 (solved from K = .7491)Unit peak, qp = 4.42 cfsUnit peak time Tp = .11133 hrsUnit receding limb, Tr = .44533 hrs Total unit time, Tb = .55667 hrs

Type.... SCS Unit Hyd. Summary Name.... EX1 EXISTING File.... Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\PRE AND POST ANALYSIS.PPW Storm... TypeIII 24hr Tag: 2-YR

SCS UNIT HYDROGRAPH METHOD

STORM EVENT: 2 year storm Duration = 30.0000 hrs Rain Dept Rain Dir = C:\HAESTAD\PPKW\RAINFALL\ Rain Depth = 3.2538 in Rain File - ID = SCSTYPES.RNF - TypeIII 24hr Unit Hyd Type = Default Curvilinear = Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\ HYG Dir HYG File - ID = - EX1 EXISTING 2-YR Τc = .1670 hrs Drainage Area = .651 acres Runoff CN= 75 ________________________________ Computational Time Increment = .02227 hrs Computed Peak Time = 12.1576 hrs Computed Peak Flow = .73 cfs Time Increment for HYG File = .0500 hrs Peak Time, Interpolated Output = 12.1500 hrs Peak Flow, Interpolated Output = .73 cfs DRAINAGE AREA ID:None Selected CN = 75 Area = .651 acres S = 3.3690 in 0.25 = .6738 in Cumulative Runoff 1.1189 in .061 ac-ft HYG Volume... .061 ac-ft (area under HYG curve) ***** UNIT HYDROGRAPH PARAMETERS ***** Time Concentration, Tc = .16700 hrs (ID: None Selected) Computational Incr, Tm = .02227 hrs = 0.20000 Tp Unit Hyd. Shape Factor = 483.432 (37.46% under rising limb) K = 483.43/645.333, K = .7491 (also, K = 2/(1+(Tr/Tp))Receding/Rising, Tr/Tp = 1.6698 (solved from K = .7491) Unit peak, qp = 4.42 cfs Unit peak time Tp = .11133 hrsUnit receding limb, Tr = .44533 hrs Total unit time, Tb = .55667 hrs

Type....SCS Unit Hyd. SummaryPage 3.03Name....EX1 EXISTINGTag: 10-YREvent: 10 yrFile....Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\PRE AND POST ANALYSIS.PPWStorm...TypeIII 24hrTag:10-YR

SCS UNIT HYDROGRAPH METHOD

STORM EVENT: 10 year storm Duration = 30.0000 hrs Rain Dept Rain Dir = C:\HAESTAD\PPKW\RAINFALL\ Rain Depth = 4.8616 in Rain File -ID = SCSTYPES.RNF - TypeIII 24hr Unit Hyd Type = Default Curvilinear HYG Dir = Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\ HYG File - ID = - EX1 EXISTING 10-YR Τc = .1670 hrs Drainage Area = .651 acres Runoff CN= 75 Computational Time Increment = .02227 hrs Computed Peak Time = 12.1353 hrs Computed Peak Flow ----1.54 cfs Time Increment for HYG File = .0500 hrs Peak Time, Interpolated Output = 12.1500 hrs Peak Flow, Interpolated Output = 1.53 cfs DRAINAGE AREA ------ID:None Selected CN = 75 Area = .651 acres S = 3.3690 in 0.25 = .6738 in Cumulative Runoff ------2.3208 in .126 ac-ft HYG Volume... .126 ac-ft (area under HYG curve) ***** UNIT HYDROGRAPH PARAMETERS ***** Time Concentration, Tc = .16700 hrs (ID: None Selected) Computational Incr, Tm = .02227 hrs = 0.20000 Tp Unit Hyd. Shape Factor = 483.432 (37.46% under rising limb) K = 483.43/645.333, K = .7491 (also, K = 2/(1+(Tr/Tp))Receding/Rising, Tr/Tp = 1.6698 (solved from K = .7491) Unit peak, ab = 4.42 cfs Unit peak, qp = 4.42 crs Unit peak time Tp = .11133 hrs Unit receding limb, Tr = .44533 hrs Total unit time, Tb = .55667 hrs

Type....SCS Unit Hyd. SummaryPage 3.04Name....EX1 EXISTINGTag: 100-yrEvent: 100 yrFile....Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\PRE AND POST ANALYSIS.PPWStorm...TypeIII 24hrTag:100-yr

SCS UNIT HYDROGRAPH METHOD

STORM EVENT: 100 year storm Duration = 30.0000 hrs Rain Dept Rain Dir = C:\HAESTAD\PPKW\RAINFALL\ Rain Depth = 8.6513 in Rain File -ID = SCSTYPES.RNF - TypeIII 24hr Unit Hyd Type = Default Curvilinear HYG Dir = Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\ HYG File - ID = - EX1 EXISTING 100-yr = .1670 hrs Τc Drainage Area = .651 acres Runoff CN= 75 _____ Computational Time Increment = .02227 hrs Computed Peak Time=12.1353 hrsComputed Peak Flow=3.64 cfs Time Increment for HYG File = .0500 hrs Peak Time, Interpolated Output = 12.1500 hrs Peak Flow, Interpolated Output = 3.60 cfs ______ DRAINAGE AREA ID:None Selected CN = 75 Area = .651 acres S = 3.3690 in0.25 = .6738 in Cumulative Runoff 5.6088 in .304 ac-ft HYG Volume... .304 ac-ft (area under HYG curve) ***** UNIT HYDROGRAPH PARAMETERS ***** Time Concentration, Tc = .16700 hrs (ID: None Selected) Computational Incr, Tm = .02227 hrs = 0.20000 Tp Unit Hyd. Shape Factor = 483.432 (37.46% under rising limb) K = 483.43/645.333, K = .7491 (also, K = 2/(1+(Tr/Tp))Receding/Rising, Tr/Tp = 1.6698 (solved from K = .7491) Unit peak, Unit peak, qp = 4.42 cts Unit peak time Tp = .11133 hrs qp = 4.42 cfs Unit receding limb, Tr = .44533 hrs Total unit time, Tb = .55667 hrs







ATTACHMENT B

Post-Development Watersheds

- 1. Pond Pack Model Schematic
 - 2. Watershed Worksheet WS1 & WS2
 - 3. Pond Pack Computer Printout
 - a. Watershed Summary
 - b. Tc Analysis
 - c. Hydrographs

Drair	age Area #	WS #1		*****				
Deve	lopment	Pre		ſ				3,77
		Post	Х					
							TOTAL	0.08
Use		Soil Ty	pe	Soil Clas	s	CN	Area	CN x Area
Nood	5	WdC		C		73	0.000	0.00
Wood	s-wetlands	Sh		D		77	0.000	0.00
Buildi	ing	WdC		С		98	0.073	7.15
Grave	1	Wdc		С		89	0.000	0.00
Brush	- planter	Wdc		С		65	0.014	0.91
Brush	_	Sh		D		73	0.000	0.00
Lawn		Wdc		C.		61	0.000	0.00
				TOTAL		1	0.087	8.06
	CN	V (Weight	ed) =sum(C	N x A) div	rided by Su	im(A) =		92.
								L
	Runoff:	Stor	rm Event Ty	pe N10D	24 Hour F	Rainfall	2002 NYS	DEC MANUAI
			1 Year =	2.82	2 in	T	2.50	in
			2 Year =	3.40) in		3.50	in
			10 Year =	5.08	3 in		5.00	in
			100 Year	9.04	lin		7.50	in
					1		1.00	
Annua	1 Rainfall: 40).2 in						
c An	alysis Calcul	ations: Mc	Cuen & Sni	ess Calcul	ations			
<u>, , , , , , , , , , , , , , , , , , , </u>	Sheet			Te	Flow I	ength	5	
•	Flow					engui.	3	0.0
				0.006	Slope:		8 (0%
				0.000	Cover:			yo 70
	I			1		11 - 14 - 14 - 14 - 14 - 14 - 14 - 14 -	100	пор
	Shallow	Concentra	ted Flow	I	Paved			nc
-		T		0.000	Linnave	٠d٠		
		1		0.000	Hydrau	lic Length:		ye
		+	Velocity	10		e Land		
	1	1	velocity	1.7		C Lanu		170
1	Channel	Flow			FlowArea			****
		T		0.000	Descrip	15" nino		0.013
		1		0.000	Length		IN- W/:4+h.	0.013
				 	Donth		vv laun:	
		J				0	Siope:	
		1	T				wp	
	l	 Minimum	$T_0 = 0.10$			┼───┤		
	<u></u>	17 1 (11111111111111111111111111111111111	110-0.10	0.004				
			Total T	0.000		use Ton 1 h		
			i otal I c			1 c=.1 nr		

TRAVEL TIME TO point A

_{*} 0.21 HR.

Drain	age Area # \	WS #2 d	irect offsite						
Devel	opment	Pre						24,602	
L		Post	X						
							-		
							TOTAL	0.565	
•						-			
Use		Soil Ty	ре	Soil Clas	SS	CN	Area	CN x Area	
L				-					
Woods		WdC		С		73	0.140	10.220	
Woods	s-wetlands	Sh		D		77	0.103	7.931	
Buildi	ng	WdC		С		98	0.000	0.000	
Gravel	[Wdc		С		89	0.053	4.717	
Brush-		Wdc		C		65	0.090	5.850	
Brush-		Sh		D		73	0.170	12.410	
Lawn		Wdc		С	w	74	0.149	11.026	
				TOTAL :			0.565	41.934	
	CN	(Weight	ed) =sum(Cl	N x A) div	ided by Su	ım (A) =		74.2	
I	Runoff:	Sto	rm Event Ty	pe N10D	24 Hour F	Rainfall	2002 NYS	DEC MANUAL	
			1 Year =	2.82	2 in		2.50	in	
		2 Year =		3.40) in		3.50	in	
		10 Year =		5.08 in			5.00	in	
			100 Year	9.04	in		7.50	in	
		1				1			
Annual	Rainfall: 40	.2 in			4				
Tc Ana	lysis Calcula	tions: Mo	Cuen & Spi	ess Calcul	ations				
A	Sheet			Тс	Flow L	ength:	10	0.0	
	Flow					engui.	10	0.0	
				0.113	Slone [.]		11 4	50%	
		I		0.110	Cover:		11 hr	.50%	
								<u>usn</u>	
B	Shallow C	Concentra	ted Flow		Paved.		T	n	
				0.021	Unpave	٠d٠			
				0.021	Hydrau	u. lic Lenoth·		<u> </u>	
			Velocity	2.5	Average	e Land		20/	
	J							3 70	
C	Channel F	low	Ī		FlowArea:				
		/		0.000	Descrip	15" nine		0.012	
		******		0.000	Lenoth:	15 pipe	Width	0.015	
			+		Denth		Slope:		
					V	Q	Siope		
•••••••••••••••••••••••••••••••••••••••			ł		v	0	vv p		
	<u>I</u> /	Ainimun	$T_c = 0.10$						
	1			0 134					
			i utal i c	0.134					

TRAVEL TIME TO point A

0.00 HR.

21

Type.... Master Network Summary Page 1.01 Name.... Watershed File.... Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\PRE AND POST ANALYSIS.PPW

MASTER DESIGN STORM SUMMARY

Default Network Design Storm File, ID STORMS.RNQ WESTCH BRITTON

Return Event	Total Depth in	Rainfall Type	RNF File	RNF ID
1-YR 2-YR 10-YR 100-yr	2.6987 3.2538 4.8616 8.6513	Synthetic Curve Synthetic Curve Synthetic Curve Synthetic Curve	SCSTYPES SCSTYPES SCSTYPES SCSTYPES	TypeIII 24hr TypeIII 24hr TypeIII 24hr TypeIII 24hr TypeIII 24hr

MASTER NETWORK SUMMARY SCS Unit Hydrograph Method

(*Node=Outfall; +Node=Diversion;) (Trun= HYG Truncation: Blank=None; L=Left; R=Rt; LR=Left&Rt)

Storage			Return	HYG Vol		Qpeak	Qpeak	Max WSEL	Max Pond
Node ID		Туре	Event	ac-ft	Trun	hrs	cfs	ft	ac-ft
- * 4 N 4 I VS TS - PO	ст	ют	1	0.2.4		12 1500			
*ANAL VSTS_PO	от СТ		1	.034		12.1500	. 42		
	от ст	JCT	2	.051		12.1500	.64		
*ANALVETE DO) I ст	JUT	10	.107		12.1000	1.33		
ANALISIS-PU	21	JUL	100	. 277		12.1500	3.40		
*ANALYSIS-PR	E	ЛСТ	1	041		12 1500	10		
*ANALYSIS-PR	E	JCT	2	061		12.1500	.40		
*ANALYSIS-PR	E	JCT	10	126		12.1500	./3		
*ANALYSIS-PR	E	JCT	100	304		12.1500	3 60		
						12.1500	5.00		
EX1 EXISTIN	G	AREA	1	.041		12.1500	. 48		
EX1 EXISTIN	G	AREA	2	.061		12.1500	.73		
EX1 EXISTIN	G	AREA	10	.126		12.1500	1.53		
EX1 EXISTIN	3	AREA	100	. 304		12,1500	3.60		
ET PLANTED	TN	POND	1	014		12 1000			
ET PLANTED			1	.014		12.1000	.18		
			10	.018		12.1000	. 2 2		
		POND	10	.029		12.1000	.35		
FI FLANIEK	TN	POND	100	.056		12.1000	. 64		
FT PLANTER	OUT	POND	1	.000		7 0000	00	196 13	000
FT PLANTER	OUT	POND	2	000		6 2500	.00	400.43 10c co	.006
FT PLANTER	OUT	POND	10	000		4 3500	.00	400.00	.008
	001		10	.000		4.3300	.00	487.06	.014

S/N: B21A01606A8C PondPack Ver. 7.5 (786c)

P.W. Scott Engineering & Arch Compute Time: 14:09:00 Date: 04/06/2023

Type.... Master Network Summary Page 1.02 Name.... Watershed File.... Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\PRE AND POST ANALYSIS.PPW

MASTER NETWORK SUMMARY SCS Unit Hydrograph Method

(*Node=Outfall; +Node=Diversion;) (Trun= HYG Truncation: Blank=None; L=Left; R=Rt; LR=Left&Rt)

Storage		Return	HYG Vol		Qpeak	Qpeak	Max WSEL	Max Pond
Node ID	Туре	Event	ac-ft	Trun	hrs	cfs	ft	ac-ft
- FT PLANTER OUT	POND	100	.016		12.2000	. 36	487.50	. 020
WS1-ROOF&PLAN WS1-RÕOF&PLAN WS1-ROOF&PLAN WS1-ROOF&PLAN	AREA AREA AREA AREA	1 2 10 100	.014 .018 .029 .056		12.1000 12.1000 12.1000 12.1000	.18 .22 .35 .64		
WS2- TO WETLAND WS2- TO WETLAND WS2- TO WETLAND WS2- TO WETLAND	AREA AREA AREA AREA	1 2 10 100	.034 .051 .107 .261		12.1500 12.1500 12.1000 12.1000	.42 .64 1.33 3.21		

Type.... SCS Unit Hyd. Summary Page 3.05 Name.... WS1-ROOF&PLAN Tag: 1-YR Event: 1 yr File.... Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\PRE AND POST ANALYSIS.PPW Title... WS1 ROOF AND PLANTER Storm... TypeIII 24hr Tag: 1-YR SCS UNIT HYDROGRAPH METHOD STORM EVENT: 1 year storm Duration = 30.0000 hrs Rain Depth = 2.6987 in Rain Dir = C:\HAESTAD\PPKW\RAINFALL\ Rain File - ID = SCSTYPES.RNF - TypeIII 24hr Unit Hyd Type = Default Curvilinear HYG Dir = Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\ HYG File - ID = - WS1-ROOF&PLAN 1-YR Tc = .1000 hrs Drainage Area = .087 acres Runoff CN= 93 Computational Time Increment = .01333 hrs Computed Peak Time = 12.1067 hrs Computed Peak Flow = .18 cfs Time Increment for HYG File = .0500 hrs Peak Time, Interpolated Output = 12.1000 hrs Peak Flow, Interpolated Output = .18 cfs DRAINAGE AREA ------ID:None Selected CN = 93Area = .087 acres S = .7875 in 0.2S = .1575 in Cumulative Runoff 1.9401 in .014 ac-ft HYG Volume... .014 ac-ft (area under HYG curve) ***** UNIT HYDROGRAPH PARAMETERS ***** Time Concentration, Tc = .10000 hrs (ID: None Selected) Computational Incr, Tm = .01333 hrs = 0.20000 Tp Unit Hyd. Shape Factor = 483.432 (37.46% under rising limb) K = 483.43/645.333, K = .7491 (also, K = 2/(1+(Tr/Tp))Receding/Rising, Tr/Tp = 1.6698 (solved from K = .7491) qp = Unit peak, .99 cfs Unit peak time Tp = .06667 hrsUnit receding limb, Tr = .26667 hrs Total unit time, Tb = .33333 hrs

Type....SCS Unit Hyd. SummaryPage 3.06Name....WS1-ROOF&PLANTag: 2-YREvent: 2 yrFile....Z:\PROGRAMS\PONDPACK\96POST OFFICE ROAD\PRE AND POST ANALYSIS.PPWStorm...TypeIII24hrTag: 2-YR

SCS UNIT HYDROGRAPH METHOD

STORM EVENT: 2 year storm Duration = 30.0000 hrs Rain Dept Rain Dir = C:\HAESTAD\PPKW\RAINFALL\ Rain Depth = 3.2538 in Rain File - ID = SCSTYPES.RNF - TypeIII 24hr Unit Hyd Type = Default Curvilinear HYG Dir = Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\ HYG File - ID = - WS1-ROOF&PLAN 2-YR Tc = .1000 hrs Drainage Area = .087 acres Runoff CN= 93 ______ Computational Time Increment = .01333 hrs Computed Peak Time = 12.1067 hrs Computed Peak Flow = .22 cfs Time Increment for HYG File = .0500 hrs Peak Time, Interpolated Output = 12.1000 hrs Peak Flow, Interpolated Output = .22 cfs DRAINAGE AREA ------ID:None Selected CN = 93Area = .087 acres .00/ = .7875 in 0.25 = 1575 Cumulative Runoff ------2.4685 in .018 ac-ft HYG Volume... .018 ac-ft (area under HYG curve) ***** UNIT HYDROGRAPH PARAMETERS ***** Time Concentration, Tc = .10000 hrs (ID: None Selected) Computational Incr, Tm = .01333 hrs = 0.20000 Tp Unit Hyd. Shape Factor = 483.432 (37.46% under rising limb) K = 483.43/645.333, K = .7491 (also, K = 2/(1+(Tr/Tp))Receding/Rising, Tr/Tp = 1.6698 (solved from K = .7491) Unit peak, qp = .99 cfs Unit peak time Tp = .06667 hrs Unit receding limb, Tr = .26667 hrs Total unit time, Tb = .33333 hrs

Type.... SCS Unit Hyd. Summary Name.... WS1-ROOF&PLAN Tag: 10-YR Event: 10 yr File.... Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\PRE AND POST ANALYSIS.PPW Storm... TypeIII 24hr Tag: 10-YR

SCS UNIT HYDROGRAPH METHOD

STORM EVENT: 10 year storm Duration = 30.0000 hrs Rain Depth = 4.8616 in Rain Dir = C:\HAESTAD\PPKW\RAINFALL\ Rain File -ID = SCSTYPES.RNF - TypeIII 24hr Unit Hyd Type = Default Curvilinear HYG Dir = Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\ HYG File - ID = - WS1-ROOF&PLAN 10-YR Τc = .1000 hrs Drainage Area = .087 acres Runoff CN= 93 ______ Computational Time Increment = .01333 hrs Computed Peak Time = 12.1067 hrs Computed Peak Flow = .35 cfs Time Increment for HYG File = .0500 hrs Peak Time, Interpolated Output = 12.1000 hrs Peak Flow, Interpolated Output = .35 cfs _____ DRAINAGE AREA -----ID:None Selected CN = 93 Area = .087 acres S = .7875 in 0.2S = .1575 in Cumulative Runoff ------4.0295 in .029 ac-ft HYG Volume... .029 ac-ft (area under HYG curve) ***** UNIT HYDROGRAPH PARAMETERS ***** Time Concentration, Tc = .10000 hrs (ID: None Selected) Computational Incr, Tm = .01333 hrs = 0.20000 Tp Unit Hyd. Shape Factor = 483.432 (37.46% under rising limb) K = 483.43/645.333, K = .7491 (also, K = 2/(1+(Tr/Tp))Receding/Rising, Tr/Tp = 1.6698 (solved from K = .7491) Unit peak, qp = .99 cfs Unit peak time Unit peak time Tp = .06667 hrs Unit receding limb, Tr = .26667 hrs Total unit time, Tb = .33333 hrs

S/N: B21A01606A8C PondPack Ver. 7.5 (786c)

P.W. Scott Engineering & Arch Compute Time: 14:09:00 Date: 04/06/2023

Dee

Type.... SCS Unit Hyd. Summary Name.... WS1-ROOF&PLAN Tag: 100-yr Event: 100 yr File.... Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\PRE AND POST ANALYSIS.PPW Storm... TypeIII 24hr Tag: 100-yr

SCS UNIT HYDROGRAPH METHOD

STORM EVENT: 100 year storm Duration = 30.0000 hrs Rain Dept Rain Dir = C:\HAESTAD\PPKW\RAINFALL\ Rain Depth = 8.6513 in Rain Dir Rain File - ID = SCSTYPES.RNF - TypeIII 24hr Unit Hyd Type = Default Curvilinear HYG Dir = Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\ HYG File - ID = - WS1-ROOF&PLAN 100-yr = .1000 hrs Τc Drainage Area = .087 acres Runoff CN= 93 Computational Time Increment = .01333 hrs Computed Peak Time = 12.1067 hrs Computed Peak Flow = .64 cfs Time Increment for HYG File = .0500 hrs Peak Time, Interpolated Output = 12.1000 hrs Peak Flow, Interpolated Output = .64 cfs _____ DRAINAGE AREA ------ID:None Selected CN = 93 Area = .087 acres S = .7875 in 0.2S = .1575 in .1575 in Cumulative Runoff ------7.7731 in .056 ac-ft HYG Volume... .056 ac-ft (area under HYG curve) ***** UNIT HYDROGRAPH PARAMETERS ***** Time Concentration, Tc = .10000 hrs (ID: None Selected) Computational Incr, Tm = .01333 hrs = 0.20000 Tp Unit Hyd. Shape Factor = 483.432 (37.46% under rising limb) K = 483.43/645.333, K = .7491 (also, K = 2/(1+(Tr/Tp))Receding/Rising, Tr/Tp = 1.6698 (solved from K = .7491) Unit peak, qp = .99 cfs Unit peak time Tp = .06667 hrsUnit receding limb, Tr = .26667 hrs Total unit time, Tb = .33333 hrs

Type.... SCS Unit Hyd. Summary Page 3.09 Name.... WS2- TO WETLAND Tag: 1-YR Event: 1 yr File.... Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\PRE AND POST ANALYSIS.PPW Title... WS2 - DIRECT TO WETLAND AND POINT A Storm... TypeIII 24hr Tag: 1-YR SCS UNIT HYDROGRAPH METHOD STORM EVENT: 1 year storm Duration = 30.0000 hrs Rain Depth = 2.6987 in Rain Dir = C:\HAESTAD\PPKW\RAINFALL\ Rain File -ID = SCSTYPES.RNF - TypeIII 24hr Unit Hyd Type = Default Curvilinear HYG Dir = Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\ HYG File - ID = - WS2- TO WETLAND 1-YR Tc = .1340 hrs Drainage Area = .565 acres Runoff CN= 74 ______ Computational Time Increment = .01787 hrs Computed Peak Time = 12.1315 hrs Computed Peak Flow = .43 cfs Time Increment for HYG File = .0500 hrs Peak Time, Interpolated Output = 12.1500 hrs Peak Flow, Interpolated Output = .42 cfs _____ DRAINAGE AREA ------ID:None Selected CN = 74 .565 acres Area = S = 3.4771 in 0.25 = .6954 in Cumulative Runoff ------.7323 in .034 ac-ft HYG Volume... .034 ac-ft (area under HYG curve) ***** UNIT HYDROGRAPH PARAMETERS ***** Time Concentration, Tc = .13400 hrs (ID: None Selected) Computational Incr, Tm = .01787 hrs = 0.20000 Tp Unit Hyd. Shape Factor = 483.432 (37.46% under rising limb) K = 483.43/645.333, K = .7491 (also, K = 2/(1+(Tr/Tp)) Receding/Rising, Tr/Tp = 1.6698 (solved from K = .7491) Unit peak,

Type....SCS Unit Hyd. SummaryPage 3.10Name....WS2- TO WETLANDTag: 2-YREvent: 2 yrFile....Z:\PROGRAMS\PONDPACK\96POST OFFICE ROAD\PREAND POST ANALYSIS.PPWStorm...TypeIII24hrTag: 2-YR

SCS UNIT HYDROGRAPH METHOD

STORM EVENT: 2 year storm Duration = 30.0000 hrs Rain Dept Rain Dir = C:\HAESTAD\PPKW\RAINFALL\ Rain Depth = 3.2538 in Rain File -ID = SCSTYPES.RNF - TypeIII 24hr Unit Hyd Type = Default Curvilinear HYG Dir = Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\ HYG File - ID = - WS2- TO WETLAND 2-YR Tc = .1340 hrs Drainage Area = .565 acres Runoff CN= 74 ______ Computational Time Increment = .01787 hrs Computed Peak Time = 12.1315 hrs Computed Peak Flow = .65 cfs Time Increment for HYG File = .0500 hrs Peak Time, Interpolated Output = 12.1500 hrs Peak Flow, Interpolated Output = .64 cfs WARNING: The difference between calculated peak flow and interpolated peak flow is greater than 1.50% DRAINAGE AREA ------ID:None Selected CN = 74Area = .565 acres S = 3.4771 in 0.25 = .6954 in Cumulative Runoff -----1.0845 in .051 ac-ft HYG Volume... .051 ac-ft (area under HYG curve) ***** UNIT HYDROGRAPH PARAMETERS ***** Time Concentration, Tc = .13400 hrs (ID: None Selected) Computational Incr, Tm = .01787 hrs = 0.20000 Tp Unit Hyd. Shape Factor = 483.432 (37.46% under rising limb) K = 483.43/645.333, K = .7491 (also, K = 2/(1+(Tr/Tp)) Receding/Rising, Tr/Tp = 1.6698 (solved from K = .7491) Unit peak, qp = 4.78 cfs Unit peak time Tp = .08933 hrs Unit receding limb, Tr = .35733 hrs Total unit time, Tb = .44667 hrs

Type....SCS Unit Hyd. SummaryPage 3.11Name....WS2- TO WETLANDTag: 10-YREvent: 10 yrFile....Z:\PROGRAMS\PONDPACK\96POST OFFICE ROAD\PRE AND POST ANALYSIS.PPWStorm...TypeIII 24hrTag: 10-YR

SCS UNIT HYDROGRAPH METHOD

STORM EVENT: 10 year storm Duration = 30.0000 hrs Rain Dept Rain Dir = C:\HAESTAD\PPKW\RAINFALL\ Rain Depth = 4.8616 in Rain File - ID = SCSTYPES.RNF - TypeIII 24hr Unit Hyd Type = Default Curvilinear = Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\ HYG Dir HYG File - ID = - WS2- TO WETLAND 10-YR = .1340 hrs Tc Drainage Area = .565 acres Runoff CN= 74 Computational Time Increment = .01787 hrs Computed Peak Time = 12.1315 hrs Computed Peak Flow = 1.37 cfs Time Increment for HYG File = .0500 hrs Peak Time, Interpolated Output = 12.1000 hrs Peak Flow, Interpolated Output = 1.33 cfs WARNING: The difference between calculated peak flow and interpolated peak flow is greater than 1.50% DRAINAGE AREA ------ID:None Selected CN = 74 .565 acres Area = S = 3.4771 in 0.25 = .6954 in Cumulative Runoff ------2.2709 in .107 ac-ft HYG Volume... .107 ac-ft (area under HYG curve) ***** UNIT HYDROGRAPH PARAMETERS ***** Time Concentration, Tc = .13400 hrs (ID: None Selected) Computational Incr, Tm = .01787 hrs = 0.20000 Tp Unit Hyd. Shape Factor = 483.432 (37.46% under rising limb) K = 483.43/645.333, K = .7491 (also, K = 2/(1+(Tr/Tp))Receding/Rising, Tr/Tp = 1.6698 (solved from K = .7491) Unit peak, qp = 4.78 cfs Unit peak time Tp = .08933 hrsUnit receding limb, Tr = .35733 hrs Total unit time, Tb = .44667 hrs

Type....SCS Unit Hyd. SummaryPage 3.12Name....WS2- TO WETLANDTag: 100-yrEvent: 100 yrFile....Z:\PROGRAMS\PONDPACK\96POST OFFICE ROAD\PREAND POST ANALYSIS.PPWStorm...TypeIII24hrTag: 100-yr

SCS UNIT HYDROGRAPH METHOD

STORM EVENT: 100 year storm Duration = 30.0000 hrs Rain Depth = 8.6513 in = C:\HAESTAD\PPKW\RAINFALL\ Rain Dir Rain File - ID = SCSTYPES.RNF - TypeIII 24hr Unit Hyd Type = Default Curvilinear = Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\ HYG Dir HYG File - ID = - WS2- TO WETLAND 100-yr = .1340 hrs Τc Drainage Area = .565 acres Runoff CN= 74 Computational Time Increment = .01787 hrs Computed Peak Time = 12.1136 hrs Computed Peak Flow ----3.24 cfs Time Increment for HYG File = .0500 hrs Peak Time, Interpolated Output = 12.1000 hrs Peak Flow, Interpolated Output = 3.21 cfs DRAINAGE AREA ------ID:None Selected CN = 74.565 acres Area = S = 3.4771 in 0.25 = .6954 in Cumulative Runoff -----------------5.5363 in .261 ac-ft HYG Volume... .261 ac-ft (area under HYG curve) ***** UNIT HYDROGRAPH PARAMETERS ***** Time Concentration, Tc = .13400 hrs (ID: None Selected) Computational Incr, Tm = .01787 hrs = 0.20000 Tp Unit Hyd. Shape Factor = 483.432 (37.46% under rising limb) K = 483.43/645.333, K = .7491 (also, K = 2/(1+(Tr/Tp)) Receding/Rising, Tr/Tp = 1.6698 (solved from K = .7491) Unit peak, ap = 4.78 cfs Unit peak time Unit peak time Tp = .08933 hrs Unit receding limb, Tr = .35733 hrs Total unit time, Tb = .44667 hrs

Hydrograph WS1-ROOF&PLAN 1-YR



Hydrograph WS2- TO WETLAND 1-YR



ATTACHMENT C

Concrete Flow through Planter

- 1. Planter Volume
- 2. Planter Outlet Structures
- 3. Planter Routing
- 4. Planter 1-Year Routing Time

Type.... Vol: Planimeter Name.... FT PLANTER

File.... Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\PRE AND POST ANALYSIS.PPW
Title... PLANTER

POND VOLUME CALCULATIONS

Planimeter scale: 1.00 ft/in

Elevation	Planimeter	Area	A1+A2+sqr(A1*A2)	Volume	Volume Sum
(ft)	(sq.in)	(acres)	(acres)	(ac-ft)	(ac-ft)
486.00	570.000	.0131	.0000	.000	. 000
488.00	570.000	.0131	.0393	.026	. 026

POND VOLUME EQUATIONS

* Incremental volume computed by the Conic Method for Reservoir Volumes.

Volume = (1/3) * (EL2-EL1) * (Area1 + Area2 + sq.rt.(Area1*Area2))

where: EL1, EL2 = Lower and upper elevations of the increment Area1,Area2 = Areas computed for EL1, EL2, respectively Volume = Incremental volume between EL1 and EL2

Type.... Outlet Input Data Name.... PLANTER OUT

File.... Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\PRE AND POST ANALYSIS.PPW Title... CONCRETE WIERS

REQUESTED POND WS ELEVATIONS:

Min. Elev.=	486.00	ft
Increment =	.10	ft
Max. Elev.=	488.00	ft

---> Forward Flow Only (UpStream to DnStream) <--- Reverse Flow Only (DnStream to UpStream) <---> Forward and Reverse Both Allowed

Structure	No.		Outfall	E1, ft	E2, ft
Weir-Rectangular Weir-Rectangular TW SETUP, DS Channel	A B	> >	TW TW	487.250 487.250	488.000 488.000

J'all

File.... Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\PRE AND POST ANALYSIS.PPW Title... CONCRETE WIERS

OUTLET STRUCTURE INPUT DATA

Structure ID = A Structure Type = Weir-Rectangular -----# of Openings = 1
Crest Elev. = 487.25 ft
Weir Length = .50 ft
Weir Coeff. = 2.800000 Weir TW effects (Use adjustment equation) Structure ID = B Structure Type = Weir-Rectangular -----# of Openings = 1
Crest Elev. = 487.25 ft
Weir Length = .50 ft
Weir Coeff. = 2.800000 Weir TW effects (Use adjustment equation) Structure ID = TW Structure Type = TW SETUP, DS Channel FREE OUTFALL CONDITIONS SPECIFIED CONVERGENCE TOLERANCES... Maximum Iterations= 30 Min. TW tolerance =.01 ftMax. TW tolerance =.01 ftMin. HW tolerance =.01 ftMax. HW tolerance =.01 ftMin. Q tolerance =.10 cfsMax. Q tolerance =.10 cfs

Туре	Pond Routing	Summary						Page 6.01	
Name	FT PLANTER	OUT Tag:	1-YR				E١	/ent: 1 yr	
File	Z:\PROGRAMS\F	PONDPACK\96	POST	OFFICE	ROAD\PRE	AND	POST	ANALYSIS.PP	w
Storm	TypeIII 24hr	Tag: 1-YF	2						

LEVEL POOL ROUTING SUMMARY

HYG Dir = Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\ Inflow HYG file = NONE STORED - FT PLANTER IN 1-YR Outflow HYG file = NONE STORED - FT PLANTER OUT 1-YR Pond Node Data = FT PLANTER Pond Volume Data = FT PLANTER Pond Outlet Data = PLANTER OUT Infiltration = 2.0000 in/hr INITIAL CONDITIONS Starting WS Elev = 486.33 ft Starting Volume = .004 ac-ft Starting Outflow = .00 cfs Starting Outflow=.00 cfsStarting Infiltr.=.03 cfsStarting Total Qout=.03 cfsTime Increment=.0500 hrs INFLOW/OUTFLOW HYDROGRAPH SUMMARY Peak Inflow=.18 cfsat12.1000 hrsPeak Outflow=.00 cfsat7.0000 hrsPeak Infiltration=.03 cfsat6.9500 hrs Peak Elevation = 486.43 ft Peak Storage = .006 ac-ft MASS BALANCE (ac-ft) + Initial Vol = .004 + HYG Vol IN = .014 - Infiltration = .018 - HYG Vol OUT = .000 - Retained Vol = .000 _ _ _ _ _ _ _ _ _ _ _ _ Unrouted Vol = -.000 ac-ft (.391% of Inflow Volume)

S/N: B21A01606A8C PondPack Ver. 7.5 (786c)

38

Type.... Detention Time Page 6.02 Name.... FT PLANTER OUT Tag: 1-YR Event: 1 yr File.... Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\PRE AND POST ANALYSIS.PPW Storm... TypeIII 24hr Tag: 1-YR

DETENTION TIMES SUMMARY

HYG Dir = Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\ Inflow HYG file = NONE STORED - FT PLANTER IN 1-YR Outflow HYG file = NONE STORED - FT PLANTER OUT 1-YR Pond Node Data = FT PLANTER Pond Volume Data = FT PLANTER Pond Outlet Data = PLANTER OUT Infiltration = 2.0000 in/hr APPROXIMATE DETENTION TIME -----Qout+Infilt. Centroid = 12.6828 hrs Inflow Centroid = 12.8175 hrs Centroid to Centroid = -.1347 hrs -----

Type....Pond Routing SummaryPage 6.03Name....FTPLANTEROUTTag: 2-YREvent: 2 yrFile....Z:\PROGRAMS\PONDPACK\96POSTOFFICEROAD\PREANDPOSTANALYSIS.PPWStorm...TypeIII24hrTag: 2-YRTag: 2-YRTag: 2-YR

LEVEL POOL ROUTING SUMMARY

HYG Dir = Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\ Inflow HYG file = NONE STORED - FT PLANTER IN 2-YR Outflow HYG file = NONE STORED - FT PLANTER OUT 2-YR Pond Node Data = FT PLANTER Pond Volume Data = FT PLANTER Pond Outlet Data = PLANTER OUT Infiltration = 2.0000 in/hr INITIAL CONDITIONS Starting WS Elev = 486.33 ft Starting Volume=.004 ac-ftStarting Outflow=.00 cfsStarting Infiltr.=.03 cfsStarting Total Qout=.03 cfsTime Increment=.0500 hrs INFLOW/OUTFLOW HYDROGRAPH SUMMARY Peak Inflow=.22 cfsat12.1000 hrsPeak Outflow=.00 cfsat6.2500 hrsPeak Infiltration=.03 cfsat6.2000 hrs Peak Elevation = 486.58 ft Peak Storage = .008 ac-ft _____ MASS BALANCE (ac-ft) + Initial Vol = .004 + HYG Vol IN = .018 - Infiltration = .022 - HYG Vol OUT = .000 - Retained Vol = .000 - - - - - . - - - - -Unrouted Vol = -.000 ac-ft (.305% of Inflow Volume)

Type.... Pond Routing Summary Page 6.04 Name.... FT PLANTER OUT Tag: 10-YR Event: 10 yr File.... Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\PRE AND POST ANALYSIS.PPW Storm... TypeIII 24hr Tag: 10-YR

LEVEL POOL ROUTING SUMMARY

HYG Dir = Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\ Inflow HYG file = NONE STORED - FT PLANTER IN 10-YR Outflow HYG file = NONE STORED - FT PLANTER OUT 10-YR Pond Node Data = FT PLANTER Pond Volume Data = FT PLANTER Pond Outlet Data = PLANTER OUT Infiltration = 2.0000 in/hr INITIAL CONDITIONS Starting WS Elev = 486.33 ft Starting Volume=.004 ac-ftStarting Outflow=.00 cfsStarting Infiltr.=.03 cfsStarting Total Qout=.03 cfsTime Increment=.0500 hrs INFLOW/OUTFLOW HYDROGRAPH SUMMARY ______ Peak Inflow=.35 cfsat12.1000 hrsPeak Outflow=.00 cfsat4.3500 hrsPeak Infiltration=.03 cfsat4.3000 hrs -----Peak Elevation = 487.06 ft Peak Storage = .014 ac-ft ______ MASS BALANCE (ac-ft) ------+ Initial Vol = .004 + HYG Vol IN = .029 - Infiltration = .033 - HYG Vol OUT = .000 - Retained Vol = .000 -----Unrouted Vol = -.000 ac-ft (.187% of Inflow Volume)

Type.... Pond Routing Summary Page 6.05 Name.... FT PLANTER OUT Tag: 100-yr Event: 100 yr File.... Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\PRE AND POST ANALYSIS.PPW Storm... TypeIII 24hr Tag: 100-yr

LEVEL POOL ROUTING SUMMARY

HYG Dir = Z:\PROGRAMS\PONDPACK\96 POST OFFICE ROAD\ Inflow HYG file = NONE STORED - FT PLANTER IN 100-yr Outflow HYG file = NONE STORED - FT PLANTER OUT 100-yr Pond Node Data = FT PLANTER Pond Volume Data = FT PLANTER Pond Outlet Data = PLANTER OUT Infiltration = 2.0000 in/hr INITIAL CONDITIONS Starting WS Elev = 486.33 ft Starting Volume=.004 ac-ftStarting Outflow=.00 cfsStarting Infiltr.=.03 cfsStarting Total Qout=.03 cfsTime Increment=.0500 hrs INFLOW/OUTFLOW HYDROGRAPH SUMMARY ______ Peak Inflow=.64 cfsat12.1000 hrsPeak Outflow=.36 cfsat12.2000 hrsPeak Infiltration=.03 cfsat2.3500 hrs -----Peak Elevation = 487.50 ft Peak Storage = .020 ac-ft _____ MASS BALANCE (ac-ft) -------+ Initial Vol = .004 - Infiltration = .044 - HYG Vol OUT = .016 - Retained Vol = .000 + HYG Vol IN = Unrouted Vol = -.000 ac-ft (.097% of Inflow Volume)

Hydrograph FT PLANTER IN 2-YR



Hydrograph PLANTER OUT 1-YR



44

	P.W. Scott	pwscott@pwscott.com
	Engineering & Architecture, P.C.	www.pwscott.com
	3871 Danbury Rd (Route 6)	(845) 278-2110
	Brewster, NY 10509	

Nover	mber 4, 2021
Rev.:	3.30.23

Engineering Report

- Project Location: 96 Post Office Rd, Waccabuc, NY
- Project Description: Renewal of Septic System approved in 2003 (WCDOH # L2003-33) with NYCDEP slope waiver granted.
- Soil Type: (Wb) Woodbridge soils
- Deep Tests completed on July 7, 2021 witnessed by WCDOH.

DII	
0 - 6"	Topsoil
6"- 42"	Medium Compact Sandy Loam
42"-7"	"O" Moderate to Tight Sandy Loam
70"	Medium Fine Sand
72"	No Water
	NoLedge
DT 2	110 20080
0-6"	Topsoil
6"-84"	Medium Compact Sandy Loam
42"-6"	2-0" Moderate Compact Sandy Loam
6'-0"	Ledge
0 0	No Water
DT 3	
0 - 6"	Topsoil
6"- 44"	Medium Compact Sandy Loam
44" – 72	2" Tighter Compact Sandy Loam
6'-0"	Ledge
	No Water
DT 4	
0-6"	Topsoil
6"- 36"	Medium Compact Silt
36" – 78	8" Medium Fine Sand w/Silt
78"	Sand with Silt
	No Ledge
	No Water
DT 5	
0-6"	Topsoil
6"- 36"	Medium Compact Sandy Loam
36"-72	2" Tighter Compact Sandy Loam
6'-0"	Ledge
	No Water
DT 6	
0-6"	Topsoil
6"- 24"	Medium Compact Sandy Loam
24" - 7	"O" Medium Fine Sand Trace Silt
,	No Ledge
	No Water

Percolation Tests: Pre-soaked on July 15, 2021; Recorded July 16, 2021 PT 1 1" drop in 6.0 minutes PT 2 1" drop in 5.0 minutes PT 3 1" drop in 18 minutes (Governs)

Design Parameters – Table 1

System: Primary Residence: (2) (110 gpd) = 220 gpd

No garbage grinder is permitted.

SSDS on slopes 18% to 20%, a variance is required. Wetlands are within 100 feet of the proposed SSTS – NOT REGISTERED No reservoirs, reservoir stems and controlled lakes within 500 feet of the proposed SSTS. No wells except for existing lot well, are within 200 feet of the reserved areas for the OWTS. Separation required to bottom of trench: 5.0' above ledge

5.0' above high water table

Existing soil required to be a min of 24 inches Septic Fill to be installed and compacted in 6" lifts Soil percolation rates in fill shall be less than 15 min/inch stabilized rate Fill pad to extend 3' past the end of fields + 7 feet per Fill section detail. 100% percent expansion area is required. All trenches are proposed at a spacing of 6.0' on center.

Refer to the septic site plan for location

I. <u>System - Main Residence</u> – Refer to 2022 WCDOH Code Design Flow Rate: 220 gpd

Septic Tank Design The flow analysis is as follows: Min size: Table 3: Precast Unit – 27 sf Liquid Level surface area:

<u>2 Bedroom Residence</u> 1,000 gal tank Refer to detail

II. <u>Subsurface Sewage Design</u>

Percolation Rate SYSTEM #2: P3:

18 Min/InchDesign Category:16-20 min/inchApplication Rate:0.53 gpd/sfTable 4 Required Fields:220 lf of 2' wide trenches

III. Septic Field Design

Based upon the percolation rates on the attached test forms, the following is the design of the septic fields using the percolation rates.

Propose: Pump System: Primary: 3 rows of 74 lf @ 6.0 ft o.c. with 74 ft spread Reserve: 3 rows of 74 lf Total Length Provided: 222 lf

Proposed Roof Treatment is: Filtration Planter. Separation required per NYSDEC Manual = 50 ft

IV. <u>Fill Required</u>

Depth to Ledge: 6.0 Ft Fill Required: -6.0 + 5.0 ft Separation + 1.0' deep Field + 1.0' Topsoil = 1.0' Topsoil

Fill is les than 24". Setbacks are measured from trenches.

V. <u>Curtain Drain</u>

Not applicable to this site, ledge is the issue.

VI. Septic Pump Station design

A pump tank is proposed to provide a dose of 0.5 gal/lf of trenches within the primary fields (171 lf) equals a 111 gallon dose plus the volume in the 2" dia force main: alt pumps. and to provide storage of the daily flow* (220 gallons)

Distance to the fields:40 lf to PrimaryThe pump dose is:118 gallons including the volume in the force main.Pump chamber proposed:1000 gallons Refer to SP3B for the head and storage calculations.

An audio & visual alarm is provided for high flow and low flow to be located within an outdoor control box. Power is from the house site. The pump chamber contains dual activated pumps and controls for redundant capacity. Pumps are: Goulds 3885 Series, WE0311L- 1/3 hp pumps.

VII. Distribution System

Propose 4 way distribution box with a baffle for equal distribution to the 3 primary trenchs. The reserve requires additional 4-way distribution with a baffle for the 3 reserve lines.

VIII. <u>Water Supply</u>

Water supply is from a private drilled well as noted on the plans. Adjacent lot wells are located beyond the septic constraints to SSDS and any neighboring SSDS. The septic systems across the street are located in the rear yard of the existing residences, more than 200 feet from the well.

IX. Garbage Grinders

Not Permitted

Refer to drawings SP1, SP1A, SP2 and SP3 for all specifications and designs. Please accept this report for the file.

Respectfully submitted,

Peder Scott

Peder W. Scott, PE, RA. President



-22LF-4" PVC SCH40 @ 1/4"/FT ASTM D-2665.

-1000 GAL PUMP CHAMBER -1000 GAL SEPTIC TANK

45 DEG BEND AS REQ'D ADD TRACER WIRE - DB#1(4)WAY DBOX WITH BAFFLE

- 4"SDR35@½'/FTW/45DEG BENDS

—4" SDR 35 @ ½"/FT MIN

-2.0" DIA SCH 40 FORCE MAIN

. All pipes connecting to tank and boxes shall be cut flush with the inside wall of box. 2. The proposed OWTS shall be installed by a Westchester County licensed septic contractor.

Westchester County Department of Health.

There shall be no trees within 10 feet of the OWTS

open works inspection on the appropriate form to WCDH.

drainage of the area.

mulched.

and approved by WCDH.

There are no wells within 200' of OWTS unless otherwise shown on plan.

There are no OWTS within 200' of well unless otherwise shown on plan.

The proposed OWTS area shall be isolated and protected against damage by erosion, storage of earth or materials, displacement, compaction or other adverse physical change in the characteristics of the soil or in the

If for any reason the approved construction plan cannot be followed, a revised plan must be prepared, submitted,

The design professional shall supervise the construction of the OWTS and make an open works inspection.

That no backfilling of a completed OWTS can occur until after it has been inspected and accepted by the

. The installation of the OWTS shall be in accordance with the Rules and Regulations for the Design and

Within 24-hours of the completion of the OWTS, the design professional must notify the Westchester County

Department of Health (WCDH) that the OWTS is ready for inspection by submitting a completed request for an

After backfilling the OWTS, the area shall be covered with a minimum of 4 inches of clean topsoil, seeded and

Construction of Residential Subsurface Sewage Treatment Systems and Drilled Wells in Westchester County,

- 13. Prior to any excavation all underground utilities must be located. Call 1-800-962-7962.
- 4. The Westchester County Health Department approval expires one year from the date on the approval stamp and is required to be renewed on or before the expiration date. The approval is revocable for cause or may be amended or modified when considered necessary by the department.

INVERT CHARTS

INVERT CHART

FF	488.50	
Garage	487.00	
Crawl space with footi	ng drains	
Septic Line Out	486.60	
Septic Tank In	486.25	
Septic Tank Out	486.00	
Septic Tank FG	488.00	(< 12" over)
Pump Tank In	485.90	
Pump Tank Out	485.80	
Bottom Pump	481.90	
Pump Chamber FG	488.00	

				Proposed
DBOX #	Exist Grade	Inv In	Inv Out	Grade
1(PRIMARY)	492.3	492.2	492	493.5
2 (RESERVE)	491.0	490.9	490.7	493.2
			Final Grade	Trench
FIELDS	Exist Grade	Top of Fill	6" Topsoil	Inv In
Primary				
P1	491.2	492.2	492.7	491.7
P2	489.6	490.6	491.1	490.1
Р3	488.2	489.2	489.7	488.7
	· · ·			
			Final Grade	Trench
RESERVE	Exist Grade	Top of Fill	6" Topsoil	Inv In
R1	490.0	491.0	491.5	490.5
R2	488.3	489.3	489.8	488.8

487.3

PROPOSED FILL NOTES:

1. SITE MODIFICATION ACTIVITIES INVOLVING PLACEMENT OF FILL ARE TO BE CONDUCTED DURING RELATIVELY DRY PERIODS TO MINIMIZE SOIL SMEARING AND EXCESSIVE SOIL COMPACTION. NO MACHINERY TO PASS WITHIN 5' OF SEPTIC AREA BEFORE OR AFTER FILL PLACEMENT, ERDSIDN CONTROLS TO BE IN PLACE BEFORE PLACEMENT OF FILL. TRESS SHOULD BE CUT LEAVING ROOTS IN PLACE, SITE SHOULD BE PLOWED PEREPENDICULAR. TO THE SLOPE TO A DEPTH OF 8-12 INCHES TO PENETRATE THE TOPSDIL LAYER.

488.3

488.8 487.8

2. THE REQUIRED DEPTH OF FILL WITHIN THE SEWAGE TREATMENT SYSTEM AREA IS 12" MIN WHICH APPROXIMATES TO 140 CUBIC YARD PRIMARY; 120 CUBIC YARDS FOR RESERVE. FILL TO BE SUITABLE FOR SEWAGE ABSORPTION, BE FREE OF FINES OR OTHER UNSUITABLE MATERIAL AND SHALL HAVE AN IN-PLACE PERCOLATION RATE UNDER 10MIN/INCH THE DESIGN PROFESSIONAL SHALL PERFORM A MINIMUM OF TWO (2) PERCOLATION TESTS IN THE FILL AFTER STABILIZATION IS ACHIEVED.

3. FILL SUITABLE FOR SEWAGE ABSORPTION SHOULD CONTAIN THE FOLLOWING BY WEIGHT. THE FILL SHALL HAVE LESS THAN 5% FINES(#200) BY WEIGHT, PREFERABLY UNDER 2%. FILL SHALL BE RUN OF BANK SAND & GRAVEL, INSTALLED WITH NO TAMPING, ROLLING OR PUDDLE. SIEVE SIZE PERCENT PASSING

#4	100 PERCENT
#10	70-100 PERCENT
#40	10 -50 PERCENT
#100	0 - 10 PERCENT
#200	0 - 5 PERCENT
MOISTURE CONTENT OF 8" DEPTH	H TO BE CHECKED BEFORE CONSTRUCTION.
FILL CANNOT BE PLACED ON FR	ROZEN GROUND.

4. THE IMPERVIOUS FILL, SHALL BE A DENSE CLAY TYPE SOIL WITH LITTLE OR NO SEWAGE ABSORPTION CAPACITY

	EROSION CONTROL LEGEND						
NO.	SYMBOL	DESCRIPTION	STATUS				
1	SF	SILT FENCE	TEMPORARY SEE DET. SP2 PLACE PARALLEL TO GRADE-CONTOURS				
2	-00	CONSTRUCTION FENCE	AROUND EDGE SEPTIC FILL: SEE DET.SP2				
3	٢	TOPSOIL STOCKPILE AREA	TEMPORARY SEE DET. SP2 RING WITH SILT FENCE				
4		CONSTRUCTION ENTRANCE	TEMPORARY SEE DET. SP2 PLACE @ EA. POINT OF ENTRY INTO SITE				

REFER TO SY1 FOR IRSP DETAILS

o the garage slab conduit.	al dose tank Septic fill of 12" deep refer to septic fill. amber to D-Box as noted on details. cycles - Engineer of Record to field- estchester County Department of Hea s in place remove silt fence.	c fill notes. -test for compliance lth	 <u>SUKVEY</u> <u>NUTES</u>; 1. INFORMATION TAKEN FROM CHICAGO TITLE COMPANY AND PLANS PREPARED BY BIBBO ASSOCIATES, DATED 2002 2. AREA OF LOT: 4.04 ACRES 3. ZONING R2A ZONE: : FYSB: 50', RYSB& SYSB: 40' 4. REFER TO SURVEY FOR OVERALL PROPERTY DESCRIPTION: DWG SP1A 			
	o the garage slab conduit.		D W SCOTT			Revisions
				A	11/4/21	REVISED PER WCDC
A 11/4/21 REVISED PER WCDC		NOTE: DO NOT SCALE DRAWINGS	ENGINEERING & ARCHITECTURE, P.C.	В	12/2/21	REVISED PER NYCDI
NOTE: DO NOT SCALE DRAWINGS DIMENSIONS SUPERCEDE SCALE	DIMENSIONS SUPERCEDE SCALE		3871 ROUTE 6 BREWSTER, NY 10509 845-278-2110		3/30/23	REVISED 2022 COD
NOTE: DO NOT SCALE DRAWINGS DIMENSIONS SUPERCEDE SCALE ENGINEERING & ARCHITECTURE, P.C. A 11/4/21 REVISED PER WCDC B 12/2/21 REVISED PER NYCDE C 3/30/23 REVISED 2022 COD	OPERTY OF P.W. SCOTT ENGINEERING AND ARCHITECTS, P.C. AND WILL S AND BE GIVEN TO ANY OTHER TRADES/PERSONS WITHOUT THE EXPRESS				5/8/23	REVISE PER WCDOH
NOTE: DO NOT SCALE DRAWINGS DIMENSIONS SUPERCEDE SCALE ENGINEERING & ARCHITECTURE, P.C. A 11/4/21 REVISED PER WCDD 0 11/4/21 REVISED PER WCDD B 12/2/21 REVISED PER NYCDD 0 3/30/23 REVISED 2022 COD C 3/30/23 REVISED 2022 COD 0 5/8/23 REVISE PER WCDD D 5/8/23 REVISE PER WCDD						

WESTCHESTER COUNTY HEALTH DEPT. NOTES

- 15. For properties located in NYC Watershed, the following information is needed
- A. There are no reservoirs, reservoir stems or controlled lake within 500 feet of the proposed OWTS unless otherwise shown on plan.
- 3. There are no NYSDEC wetlands or watercourses within 200 feet of the proposed OWTS unless otherwise shown on plan.
- NYCDEP must be contacted at least two days prior to start of construction of the OWTS so that the NYCDEP may inspect and monitor the installation.
- Well Installation Notes A. Well to be installed by a NYS Department of Environmental Conservation registered well driller.

B. The minimum well yield is 5 gpm, yields less than 5 gpm must be immediatley reported to this department

C. Drilled well to be sampled and tested in accordance with WCDH private Well testing Law.(only for new wells).

Additional Notes

- All erosion control measures shall be installed prior to the start of any construction. Cut or fill is not permitted in the SSTS area except if so specified on this plan
- The SSTS design shown hereon does not provide for installation of a garbage grinder. Such installation requires additional design and approval of the Westchester County Department of Health.
- Occupancy of this structure will not be permitted until the Construction Compliance Application has been received and approved by the Westchester County Department of Health and forwarded to the Building Inspector of the respective municipality as part of the Certificate of Occupancy application. A copy of the house plans submitted to the Building Inspector of the local municipality, when filing for a Building Permit, must be submitted to the Westchester County Department of Health to verify
- the bedroom count All stone walls in and within 10 feet of the SSTS area shall be removed to their entire depth and the resulting void replaced with similar on-site soil.

PERCOLATION TESTS

Percolation Tests: Pre-soaked on July 15, 2021;

- PT 1
- 1" drop in 5.0 minutes
- PT 2 1" drop in 5.0 minutes
- PT 3 1" drop in 18 minutes (Governs)

DESIGN DATA

2 BEDROOM (PROPOSED)

TOTAL FLOW: (2) 110 = 220 GPD Design Application Rate: 16min/inch-20 min/inch: 0.53GPD/SF

12" FILL REQUIRED

SLOPE ACROSS OWTS: 15-20%

Refer to table 4 for 2 bedrooms: 220 If req'd

Primary: 3 rows of 74 lf @ 6.0' oc with74' spread Reserve: 3 rows of 74 lf @ 6.0' oc with 74' spread

SP3

GENERAL RELEASE

Refer to judicial Decision dated September 18, 2003, a general release is required to be submitted by the owner to the Department for review and approval and filed in the Westchester County Land Records Office and proof of which will be required to be submitted prior to the issuance of the Certificate of Construction Compliance by the Department.

CALL BEFORE YOU DIG

CONSTRUCTION NOTES

- THE CONTRACTOR SHALL REMOVE AND STOCKPILE AVAILABLE TOPSOIL AT THE SITE; NOT TO BE PLACED IN AREA OF FUTURE SEPTIC SYSTEM.
- 2. THE CONTRACTOR SHALL FURNISH AND INSTALL ALL MATERIALS NECESSARY FOR COMPLETE INSTALLATION AS PER THESE PLANS.
- 3. THE CONTRACTOR SHALL EXCAVATE ALL ORGANIC MATERIAL FROM EXISTING TRENCH AREA.
- 4. SEPTIC SYSTEM SHALL BE INSTALLED INTO EXISTING GRADE
- . SEPTIC SYSTEM NOT TO BE DRIVEN OVER PRIOR TO AND AFTER CONSTRUCTION
- CONTRACTOR MUST VERIFY ALL LOCATIONS IN THE FIELD. IT IS THE CONTRACTOR'S RESPONSIBILITY TO NOTIFY P. W. SCOTT ENGINEERING & ARCHITECTURE, P. C. IF ANY DEVIATION OR ALTERATION IS REQUIRED FOR COMPLETION OF THIS PROJECT.

Recorded July 16, 2021



BASED UPON 2022 WCDOH REGULATIONS FLOW PER BEDROOM: 110 GPD

SYSTEM DESIGN: 220 GPD

A WAIVER IS REQUIRED: SECTION 4.0.1 SLOPES, 1.A.ii. REFER TO NYCDEP LOG #1998-CR-0637-1 SEPTIC TANK: 1000 Gallons

Pump-up system required, refer to drawing

11/1/12	XX	CIT	EN			
			50	The		-
			Post Office	4	A	N
1		17	Rd	-		
1 miles	M		2	X	4	X
21771			7	-	500 1	Benedict
1 72	1					



DEEP TEST PIT DATA

Deep tests completed on July 7, 2021 witnessed by WCDOH DT 1

	0 - 6" 6"- 42" 42" - 7'0" 70" 72"	Topsoil Medium Com Moderate to T Medium Fine No Water No Ledge	pact Sandy Loam ïght Sandy Loam Sand
DT	2 0-6" 6"-84" 42" - 6'-0" 6'-0"	Topsoil Medium Com Moderate Con Ledge No Water	pact Sandy Loam npact Sandy Loam
DT	3 0 - 6" 6"- 44" 44" - 72" 6'-0"	Topsoil Medium Com Tighter Comp Ledge No Water	pact Sandy Loam act Snady Loam
DT	4 0-6" 6"- 36" 36" – 78" 78"	Topsoil Medium Com Medium Fine Sand with Silt No Ledge No Water	pact Silt Sand w/Silt
DT	5 0-6" 6"- 36" 36" - 72" 6'-0"	Topsoil Medium Com Tighter Comp Ledge No Water	pact Sandy Loam act Sandy Loam
DT	6 0-6" 6"- 24" 24" – 7'0"	Topsoil Medium Com Medium Fine No Ledge	pact Sandy Loam Sand Trace Silt
	<u>PROPE</u>	IRTY II)ENTIFICATION
	DWNER:		ALEX BERNABO wdesigne, inc.
	ADDRESS:		3867 DANBURY ROAD Brewster ny 10509
	E911 # :		96 POST OFFICE ROAD, LEWISBORD
	LEWISBOR	RD T.M.	SHEET 25 BLOCK 10812 LOT 3
	PROPERTY	ADDRESS:	96 POST OFFICE ROAD Lewisbord, ny 10590
	NYC DEP	WATERSHE	D: CROSS RIVER BASIN
	AREA OF PROF # Be	HOUSE POSED:: EDROOMS:	2600 SF+ 600SF GARAGE 2 Bedroom

CALL 1-800-922-4455 PRIOR TO ANY EXCAVATIONS THAT TAKE PLACE ON THE SITE. THE LOCATION OF ALL UTILITIES ON THE PROPERTY, SERVICE LINES AND PUBLIC UTILITIES ON THE STREET MUST BE DEFINED. IT IS A VIOLATION OF ARTICLE VII OF THE STATE EDUCATION LAW FOR ANY PERSON TO ALTER ANY ITEM ON THIS DOCUMENT IN ANY WAY UNLESS SAID PERSON IS ACTING UNDER THE DIRECTION OF A LICENSED ARCHITECT OR PROFESSIONAL ENGINEER. IF ANY ITEM IS ALTERED THE ALTERING ARCHITECT OR ENGINEER SHALL AFFIX TO THE ITEM ALTERED HIS/HER SEAL AND SIGNATURE AND THE DATE OF SUCH ALTERATION, AND A SPECIFIC DESCRIPTION WESTCHESTER COUNTY APPROVAL STAMP OF THE ALTERATION.

	Dwg. Title SFP () PI AN-	-NEW CONSTRUCTIONT	Seal	Dwg. No.
ption				
DH10/8/21 MEMO	Proiect Title96 POST OFFIC	F ROAD LEWISBORO NY		
EP 11/8/21MEMO	, 50 1 001 01110			
DE & IRSP	Proj. No. $21 - 110$	Drawn by MA/PW/S		
H 5/8/23 MEMO	21 110	, ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	\backslash /	
	Date 9/20/21	Scale AS NOTED		