

**AGENDA PACKET**

**DECEMBER 19, 2023 MEETING**

	<b><u>CAL#</u></b>	<b><u>PAGE</u></b>
<b><u>AGENDA</u></b>		<b>3</b>
<b><u>MCARTHUR AND SALAZAR RESIDENCE, 40 OLD POND ROAD, SOUTH SALEM</u></b>	<b>Cal #91-19WP</b>	<b>Cal #10-19SW</b>
No new materials		-
<b><u>RINGS END OF LEWISBORO SOLAR, 382 SMITH RIDGE ROAD, SOUTH SALEM</u></b>	<b>Cal #07-23PB</b>	
Planning Board application, dated November 18, 2023		<b>4</b>
<b><u>WOLF CONSERVATION CENTER, BUCK RUN, SOUTH SALEM</u></b>	<b>Cal #06-17PB</b>	<b>Cal #43-23WP</b>
KSCJ comment memo, dated December 15, 2023	<b>Cal #18-23SW</b>	<b>20</b>
Applicant response letter, dated November 27, 2023		<b>23</b>
Business plan, Wolf Conservation Center, dated March 1, 2023		<b>29</b>
Revised site plan, Bibbo Associates, dated November 28, 2023		<b>43</b>
72 Hour Well Pump Test Work Plan and Well Testing Plan, Bibbo Associates, dated November 28, 2023		<b>62</b>
Revised SWPPP, Bibbo Associates, dated October 20, 2023		<b>67</b>
Revised Notice of Intent, undated		<b>298</b>
<b><u>BERNABO VACANT LAND, 96 POST OFFICE ROAD, WACCABUC</u></b>	<b>Cal #29-23WP</b>	<b>Cal #09-23SW</b>
Correspondence from applicant, dated November 28, 2023		<b>312</b>
Site plan and erosion control plan, P.W. Scott Engineering & Architecture, dated November 27, 2023		<b>313</b>
Building Inspector comment drawing, dated December 5, 2023		<b>315</b>
Applicant response letter, dated December 6, 2023		<b>316</b>
Correspondence from applicant, dated December 12, 2023		<b>317</b>
Revised site plan, P.W. Scott Engineering & Architecture, dated December 12, 2023		<b>318</b>
Architectural renderings, undated		<b>319</b>
Comment email with photographs, Peter Aupperle, dated November 22, 2023		<b>324</b>

<b><u>SUPERVISOR'S RESPONSE TO PLANNING BOARD'S INQUIRY ABOUT CAPACITY AND ADDITIONAL CONNECTIONS AT THE OAKRIDGE WATER DISTRICT AND OAKRIDGE SEWER DISTRICT FACILITIES RELATING TO THIS PROPOSAL: Villas at Vista, 920 Oakridge Common, South Salem</u></b>	<b>Cal #12-22PB</b>	<b>Cal #36-22WP</b>
Oakridge Water Connection Inquiry letter, Planning Board to Town Board, dated November 18, 2022		<b>329</b>
Response letter, Town Board to Planning Board, dated December 1, 2023		<b>331</b>
<b><u>RIDGEFIELD, CT PLANNING AND ZONING COMMISSION TO AMEND ITS TOWN CODE §2.2 and §3.3</u></b> - family day care and child daycare.	-	
Cover letter, Alice Dew, dated December 6, 2023		<b>332</b>
Proposed Amendment to The Zoning Regulations, undated		<b>333</b>



**TOWN OF LEWISBORO**  
**Westchester County, New York**



**Planning Board**  
**79 Bouton Road**  
**South Salem, New York 10590**

**Tel: (914) 763-5592**  
**Fax: (914) 875-9148**  
**Email: [planning@lewisborogov.com](mailto:planning@lewisborogov.com)**

**AGENDA**

**Tuesday, December 19, 2023**

**The Commons / Courtroom at 79 Bouton Road**

Meeting will start at 7:30 p.m. and end at or before 11:00 p.m.

**I. DECISION**

**Cal #91-19WP, Cal #10-19SW**

**McArthur and Salazar Residence, 40 Old Pond Road, South Salem, NY 10590, Sheet 33C, Block 11155, Lots 16, 17 & 44 (William McArthur, owner of record) - Amendment of the Wetland Permit Approval and Stormwater Permit Approval in connection with the reconstruction of a lakeside residence and cottage.**

**Cal #07-23PB**

**Rings End of Lewisboro solar, 382 Smith Ridge Road, South Salem, NY 10590; Sheet 49B, Block 9827, Lots 23 & 79 (Lewisboro Supply Co Inc, owner of record) - Application for roof-mounted solar panels.**

**II. CONTINUATION OF PUBLIC HEARING**

**Cal #06-17PB, Cal #43-23WP, Cal #18-23SW**

**Wolf Conservation Center, Buck Run, South Salem, NY 10590; Sheet 21, Block 10803, Lots 3, 65, 67, 81, 82, 83, 86 & 88 (Wolf Conservation Center, owner of record) - Application for a Site Development Plan Approval, Special Use Permit Approval, Wetland Activity Permit Approval and Stormwater Permit Approval for a private nature preserve.**

**III. WETLAND PERMIT REVIEW**

**Cal #29-23WP, Cal #09-23SW**

**Bernabo Residence, 96 Post Office Road, Waccabuc, NY 10597; Sheet 25, Block 10812, Lot 3 (Alex Bernabo, owner of record) – Application for a new well, septic and house.**

**IV. DISCUSSION**

**Supervisor's response to Planning Board's inquiry about capacity and additional connections at the Oakridge Water District and Oakridge Sewer District facilities relating to this proposal:**

**Cal #12-22PB, Cal #36-22WP**

**Villas at Vista, 920 Oakridge Common, South Salem, NY 10590 Sheet 49D, Block 9829, Lot 10 (Smith Ridge Associates, owner of record) - Application for construction of 18 additional housing units.**

**V. CORRESPONDENCE**

**Ridgefield, CT Planning and Zoning Commission to amend its Town Code §2.2 and §3.3 - family day care and child daycare.**

**VI. MINUTES OF November 21, 2023.**

**VII. NEXT MEETING DATE: January 16, 2024.**

**VIII. ADJOURN MEETING.**

# TOWN OF LEWISBORO PLANNING BOARD

79 Bouton Road, South Salem, NY 10590 Tel: (914) 763-5592 Email: [planning@lewisborogov.com](mailto:planning@lewisborogov.com)

# 07-23 PB

app fee ☒  
escrow est'd

## Site Development Plan/Subdivision Plat Application - Check all that apply:

Waiver of Site Development Plan Procedures ☒  
Site Development Plan Approval ☐  
Special Use Permit Approval ☐  
Subdivision Plat Approval ☐

Step I ☐

Step I ☐

Step I ☐

Step I ☐

Step II ☐

Step II ☐

Step II ☐

Step III ☐

## Project Information

Project Name: Rings End

Project Address: 382 Smith Ridge South Salem N.Y 10590

Lot 23 = 2.3 ac Gross Parcel Area: 2.3 ac Zoning District: GB Sheet(s): 49B Block(s): 9827 Lot(s): 23 & 79

Project Description: Roof mounted Solar are merged

Is the site located within 500 feet of any Town boundary?

YES ☐

NO ☒

Is the site located within the New York City Watershed?

YES ☐

NO ☒

Is the site located on a State or County Highway?

YES ☐

NO ☒

Does the proposed action require any other permits/approvals from other agencies/departments?

Town Board ☐

ZBA ☐

Building Dept. ☒

Town Highway ☐

ACARC ☐

NYSDEC ☐

NYCDEP ☐

WCDH ☐

NYSDOT ☐

Town Wetland ☐

Town Stormwater ☐

Other ☐

## Owner's Information

Name: \_\_\_\_\_

Email: \_\_\_\_\_

Address: \_\_\_\_\_

Phone: \_\_\_\_\_

## Applicant's Information (if different)

Name: Helio Solar

Email: Installs@helio.solar

Address: 4 Research Dr Suite 402 Shelton CT 06484

Phone: 888-868-4562

## Authorized Agent's Information

Name: \_\_\_\_\_

Email: \_\_\_\_\_

Address: \_\_\_\_\_

Phone: \_\_\_\_\_

THE APPLICANT understands that any application is considered complete only when all information and documents required have been submitted and received by the Planning Board. The applicant further understands that the applicant is responsible for the payment of all application and review fees incurred by the Planning Board.

THE UNDERSIGNED WARRANTS the truth of all statements contained herein and in all supporting documents according to the best of his/her knowledge and belief, and authorizes visitation and inspection of the subject property by the Town of Lewisboro and its agents.

APPLICANT'S SIGNATURE [Signature]

DATE 11/15/2023

OWNER'S SIGNATURE \_\_\_\_\_

DATE \_\_\_\_\_

## TOWN OF LEWISBORO PLANNING BOARD

79 Bouton Road, South Salem, NY 10590  
Email: [planning@lewisborogov.com](mailto:planning@lewisborogov.com)  
Tel: (914) 763-5592 Fax: (914) 875-9148

### Tax Payment Affidavit Requirement

*This form must accompany all applications to the Planning Board.*

*Under regulations adopted by the Town of Lewisboro, the Planning Board may not accept any application unless an affidavit from the Town of Lewisboro Receiver of Taxes is on file in the Planning Board office. The affidavit must show that all amounts due to the Town of Lewisboro as real estate taxes and special assessments on the total area encompassed by the application, together with all penalties and interest thereon, have been paid.*

*Under New York State law, the Westchester County Clerk may not accept any subdivision map for filing unless the same type of affidavit from the Town of Lewisboro Receiver of Taxes is submitted by the applicant at the time of filing.*

This form must be completed by the applicant and must accompany all applications to the Planning Board. Upon receipt, the Planning Board Secretary will send the form to the Receiver of Taxes for signature and notarization. If preferred, the applicant may directly obtain the signature of the Receiver of Taxes and notarization prior to submission.

#### To Be Completed by Applicant (Please type or print)

Rings End Inc  
Name of Applicant

382  
386 Smith Ridge Rd - Rings End  
Project Name

#### Property Description

Tax Block(s): 9827

Tax Lot(s): 23 & 79

Tax Sheet(s): 488 49 B

#### Property Assessed to:

Lewisboro Supply Co. Inc  
Name

382  
386 Smith Ridge Rd  
Address

South Salem  
City

New York 10590  
State Zip

Fyi:  
Mailing Address  
Rings End  
160 Avon St  
Lewisboro Stratford, CT 066

The undersigned, being duly sworn deposes and says that a search of the tax records in the office of the Receiver of Taxes, Town of Lewisboro, reveals that all amounts due to the Town of Lewisboro as real estate taxes and special assessments, together with all penalties and interest thereon, affecting the premises described below, have been paid.

Signature - Receiver of Taxes: Deirdre W. Casper

Date

11/28/2023

Sworn to before me this

28<sup>th</sup> day of

November

2023

Janet L. Donohue  
Signature - Notary Public (affix stamp)

JANET L. DONOHUE  
NOTARY PUBLIC, STATE OF NEW YORK  
No. 01D06259627  
Qualified in Westchester County  
Commission Expires April 16, 2024

# TOWN OF LEWISBORO PLANNING BOARD

79 Bouton Road, South Salem, NY 10590

Email: [planning@lewisborogov.com](mailto:planning@lewisborogov.com)

Tel: (914) 763-5592

Fax: (914) 875-9148

## Affidavit of Ownership

State of: New York

County of: Westchester

Matthew D. Dewing, being duly sworn, deposes and says that he/she

resides at 386 Smith Ridge Rd

in the County of Westchester, State of New York

and that he/she is (check one) ☐ the owner, or ☒ the Facilities manager  
Title

of Ring End Inc.  
Name of corporation, partnership, or other legal entity

which is the owner, in fee of all that certain log, piece or parcel of land situated, lying and being in the  
Town of Lewisboro, New York, aforesaid and know and designated on the Tax Map in the Town of  
Lewisboro as:

Block 9827, Lot 23 & 19, on Sheet 488

Matthew D. Dewing  
Owner's Signature

Sworn to before me this

20<sup>th</sup> day of November, 2023

JOHN G. GIARDINO  
Notary Public - Connecticut  
My Commission Expires  
March 31, 2025

[Signature]  
Notary Public - affix stamp

# Site Layout 386 Smith Ridge Rd, South Salem, NY 10590, USA 142.59 kW DC (100 kW AC) Roof Mounted Solar PV System



Satellite View  
(41 2125/4, -73.516/498)

## Project Details


Site Address	386 Smith Ridge Rd, South Salem, NY 10590, USA
Codes	NY Building Code CMR 780, 2021 IRC, 2020 NEC
Electric Utility	New York State Electric & Gas
PV Modules	(291) CS3Y-490MS
PV Inverters	(2) Solar Edge SE50k-US
System Size DC	142.59 kW
System Size AC	100 kW
PV Output Voltage	208V, 3-phase
PV Output Current	279 A

### Exterior:

- Proposed Location of:
- AC Disconnect
  - Solar Inverter
  - Point of Interconnection
- Existing:
- Generator Transfer Switch
  - Utility Meter

### Interior:

- Location of Existing component:
- Utility CT Cabinet
  - Main Disconnect
  - Main Distribution Panel



386 Smith Ridge Rd,  
South Salem, NY 10590,  
USA

142.59 kW DC;  
(100 kW AC)

## Client Information

MATT DEWING

(203)656-7585  
matthew.dewing@bringsend.com  
386 Smith Ridge Rd,  
South Salem, NY 10590,  
USA

Engineer's Seal

Designed by  
Sync Renewables, LLC  
64 Marlborough St,  
Portland, CT 06480

Account:  
1001-2645-194

Meters:  
64-8'9-261

Date: 11/10/2023  
Revision: 3.0

## REVISION HISTORY




**PARCEL AERIAL VIEW**  
**382-386 SMITH RIDGE ROAD**  
**RINGS END SOLAR PV SYSTEM**



386 Smith Ridge Rd,  
 South Salem, NY 10590,  
 USA

142.59 kW DC  
 (100 kW AC)

**Client Information**

**MATT DEWING**

(203)656-7585  
 matthew.dewing@ringsend.com  
 386 Smith Ridge Rd,  
 South Salem, NY 10590,  
 USA

Designed by  
 Sync Renewables, LLC  
 64 Marlborough St,  
 Portland, CT 06480



**Account:**  
 1001-2645-494

**Meter:**  
 64-819-261

**Date:** 11/10/2023  
**Revision:** 3.0

**REVISION HISTORY**

---	---
---	---
---	---
---	---

Module Specifications	
Canadian Solar CS2P-490W	
V <sub>oc</sub> (V <sub>mp</sub> )	17.0V
V <sub>mp</sub>	14.6V
I <sub>mp</sub>	11A
V <sub>oc</sub>	55.2V
I <sub>sc</sub>	11.67A
Quantity	291

Inverter Specifications	
SolarEdge SE50K-US [208V]	
Max AC Power Rating	50000W
Max Input Voltage	600V
Min AC Power Rating	0 W
Max Input Voltage	570 V
Max Continuous Current	1.915A @ 208 Vac
Quantity	2

**AC Solar Output**  
 kW DC: 142.59kW  
 kW-AC: 100kW  
 Max Current 690.8(A): 2/9A  
 Max Current 690.8(B): 348.7A  
 Volts: 208V, 3-Phase

386 Smith Ridge Rd,  
 South Salem, NY 10590,  
 USA

142.59 kW DC  
 (100 kW AC)

#### Client Information

MATT DEWING

(203)656-7585  
 matt@dwingbringsend.com  
 386 Smith Ridge Rd,  
 South Salem, NY 10590,  
 USA

Engineer's Seal

Designed by

Sync Renewables, LLC  
 64 Marlborough St,  
 Portland, CT 06460

Account:  
 1001-2645-494

Writer:  
 64-819-261


Date: 7/5/2023  
 Revision: 2.0

#### REVISION HISTORY

- Notes:
1. Photovoltaic system grounding will be installed per the requirements of section 800.41 through 800.47 of the NEC.
  2. The system shall comply with the anti-islanding protective IEEE function numbers applying to the inverter system.
  3. The photovoltaic system shall comply with the "Photovoltaic power systems and the 2011 NEC" suggested standards and practices."
  4. The system shall comply with NEC 2017 690.12 Rapid Shutdown.
  5. The inverters shall be certified to UL 1741SA Ride Through.

Optimizer Count: 144  
 Module Count: 144  
 1-2 Modules per  
 Optimizer

#10 PV Wire Cu  
 Positive: Red  
 Negative: Black




Module: CS2P-490WS  
 Optimizer: SolarEdge S1201  
 (Proposed Equipment)

SolarEdge SE50K-US  
 [208V] Inverter  
 (Proposed Equipment)  
 (Exterior of building)

Optimizer Count: 144  
 Module Count: 144  
 1-2 Modules per  
 Optimizer

#10 PV Wire Cu  
 Positive: Red  
 Negative: Black



Module: CS2P-490WS  
 Optimizer: SolarEdge S1201  
 (Proposed Equipment)

SolarEdge SE50K-US  
 [208V] Inverter  
 (Proposed Equipment)  
 (Exterior of building)

#1/0 THWN-2 Copper  
 #4 AWG THWN EGC  
 2-1/2" EMT Conduit

Point of interconnection is to be made on the line side of the ATS via lugs; proposed lugs to be 1/2-gang

AC Solar Disconnect  
 400A/208V 3p  
 Fusible NEMA3R  
 (Proposed Equipment)

(3) #500kcmil THWN Copper  
 (1) #1/0 AWG THWN EGC Ground  
 3" EMT Conduit

Main Distribution Panel  
 208V 3-Phase  
 (Existing Equipment)



400A Equipment  
 i.e. CUBB Suppression

CT coupler

INTELG  
 Utility Meter  
 #54800-01  
 Meter is  
 instrument type  
 with integral CT  
 cabinet and 400A  
 4's connect



INVERTER SETTINGS TABLE											
Inverter Voltage and Settings				Inverter Frequency and Settings				Grid Support (VFD) Interactive Inverter Function Status			
Grid Type	Required Settings	Factory Default	Factory Default	Grid Type	Required Settings	Factory Default	Factory Default	Grid Support	Default	Default	Default
High	100	0.15	0.15	High	0.15	0.15	0.15	Grid Support	Default	Default	Default
Low	100	0.15	0.15	Low	0.15	0.15	0.15	Grid Support	Default	Default	Default
High	100	0.15	0.15	High	0.15	0.15	0.15	Grid Support	Default	Default	Default
Low	100	0.15	0.15	Low	0.15	0.15	0.15	Grid Support	Default	Default	Default
High	100	0.15	0.15	High	0.15	0.15	0.15	Grid Support	Default	Default	Default
Low	100	0.15	0.15	Low	0.15	0.15	0.15	Grid Support	Default	Default	Default

## String Plan

386 Smith Ridge Rd, South Salem, NY 10590, USA  
142.59 kW DC (100 kW AC) Roof Mounted Solar PV System






Figure 9: Inverter Interfaces

### STRINGING NOTES:

1. Panels to be connected in series
2. MC4 connector heads to be used for all panel and jumper cables.
3. Wires to be managed on rail system using UV rated zip ties
4. Home run wires should be:  
Red Wire: POSITIVE (+ve)  
Black Wire: NEGATIVE (-ve)



386 Smith Ridge Rd,  
South Salem, NY 10590,  
USA

142.59 kW DC  
(100 kW AC)

### Client Information

MATTHEW COWING

(203)656-7585  
matthew.cowing@ringsend.com  
386 Smith Ridge Rd,  
South Salem, NY 10590,  
USA

### Engineer's Seal

Designed by  
Sync Renewables, LLC  
64 Marlborough St,  
Portland, CT 06480

Account:  
1001 2645 494

Master:  
64-819-261

Date: 6/26/2023  
Revision: 0.0

### REVISION HISTORY





# Structural Member Plan 386 Smith Ridge Rd, South Salem, NY 10590, USA 142.59 kW DC (100 kW AC) Roof Mounted Solar PV System


386 Smith Ridge Rd,  
 South Salem, NY 10590,  
 USA

142.59 kW DC  
 (100 kW AC)



Smith Ridge Rd.



I-Beam



Z-Purlin



## Client Information

MATT DEWING

(203)656-7535  
 matthew.dewing@ringsend.com  
 386 Smith Ridge Rd,  
 South Salem, NY 10590,  
 USA

## Engineer's Seal

Designed by  
 Sync Renewables, LLC  
 64 Marlborough St.  
 Portland, CT 06460

Account:  
 1001-2645-494

Metes:  
 64 8'9 261

Date: 6/26/2023  
 Revision: 0.0

## REVISION HISTORY


Racking Plan  
 386 Smith Ridge Rd, South Salem, NY 10590, USA  
 142.59 kW DC (100 kW AC) Roof Mounted Solar PV System

386 Smith Ridge Rd,  
 South Salem, NY 10590,  
 USA

142.59 kW DC  
 (100 kW AC)

Client Information

MATT DEWING

(203)656-7585  
 matthew.dewing@ringsend.com  
 386 Smith Ridge Rd,  
 South Salem, NY 10590,  
 USA

Engineer's Seal





Designed by  
 Sync Renewables, LLC  
 64 Marlborough St,  
 Portland, CT 06480

Account:  
 1001-2645-494

Notes:  
 64-819-261

Date: 7/6/2023  
Revision: 2.0

REVISION HISTORY

NEW

CanadianSolar

## HiKu5 Mono PERC

475 W ~ 500 W

CS3Y-475 | 480 | 485 | 490 | 495 | 500MS

### MORE POWER

- Module power up to 500 W  
Module efficiency up to 21.2 %
- Up to 4.0 % lower LCOE  
Up to 4.2 % lower system cost
- Comprehensive LID / LeTID mitigation technology, up to 50% lower degradation
- Compatible with mainstream trackers, cost effective product for utility power plant
- Better shading tolerance

### MORE RELIABLE

- Minimizes micro-crack impacts
- Heavy snow load up to 5400 Pa, enhanced wind load up to 2400 Pa\*

**12 Years** Enhanced Product Warranty on Materials and Workmanship\*

**25 Years** Linear Power Performance Warranty\*

1" year power degradation no more than 2%  
Subsequent annual power degradation no more than 0.55%

\*According to the applicable Canadian Solar Limited Warranty Statement.

### MANAGEMENT SYSTEM CERTIFICATES\*

ISO 9001: 2015 / Quality management system  
ISO 14001: 2015 / Standards for environmental management system  
ISO 45001: 2018 / International standards for occupational health & safety

### PRODUCT CERTIFICATES\*

IEC 61215 / IEC 61730 / CE / MCS / INMETRO  
CEC listed (US California) / FSEC (US Florida)  
UL 61730 / IEC 61701 / IEC 62716 / IEC 60068-2-68  
UN1 9177 Reaction to Fire: Class 1 / Take-e-way




\* The specific certificates applicable to different module types and markets will vary, and therefore not all of the certifications listed herein will simultaneously apply to the products you order or use. Please contact your local Canadian Solar sales representative to confirm the specific certificates available for your Product and applicable in the regions in which the products will be used.

CSI Solar Co., Ltd. is committed to providing high quality solar products, solar system solutions and services to customers around the world. Canadian Solar was recognized as the No. 1 module supplier for quality and performance/price ratio in the IHS Module Customer Insight Survey, and is a leading PV project developer and manufacturer of solar modules, with over 50 GW deployed around the world since 2001.


\* For detailed information, please refer to the Installation Manual.

CSI Solar Co., Ltd.  
199 Lushan Road, SND, Suzhou, Jiangsu, China, 215129, www.csisolar.com, support@csisolar.com

### ENGINEERING DRAWING (mm)



### CS3Y-490MS / I-V CURVES



### ELECTRICAL DATA | STC\*

CS3Y	475MS	480MS	485MS	490MS	495MS	500MS
Nominal Max. Power (Pmax)	475 W	480 W	485 W	490 W	495 W	500 W
Opt. Operating Voltage (Vmp)	44.0 V	44.2 V	44.4 V	44.6 V	44.8 V	45.0 V
Opt. Operating Current (Imp)	10.81 A	10.87 A	10.94 A	11.00 A	11.06 A	11.12 A
Open Circuit Voltage (Voc)	52.7 V	52.9 V	53.1 V	53.3 V	53.5 V	53.7 V
Short Circuit Current (Isc)	11.52 A	11.57 A	11.62 A	11.67 A	11.72 A	11.77 A
Module Efficiency	20.1%	20.3%	20.6%	20.8%	21.0%	21.2%
Operating Temperature	-40°C ~ +85°C					
Max. System Voltage	1500V (IEC/UL) or 1000V (IEC/UL)					
Module Fire Performance	TYPE 1 (UL 61730 1500V) or TYPE 2 (UL 61730 1000V) or CLASS C (IEC 61730)					
Max. Series Fuse Rating	20 A					
Application Classification	Class A					
Power Tolerance	0 ~ +10 W					

\* Under Standard Test Conditions (STC) of irradiance of 1000 W/m², spectrum AM 1.5 and cell temperature of 25°C.

### ELECTRICAL DATA | NMOT\*

CS3Y	475MS	480MS	485MS	490MS	495MS	500MS
Nominal Max. Power (Pmax)	355 W	359 W	362 W	366 W	370 W	374 W
Opt. Operating Voltage (Vmp)	41.1 V	41.3 V	41.5 V	41.7 V	41.8 V	42.0 V
Opt. Operating Current (Imp)	8.64 A	8.70 A	8.74 A	8.78 A	8.86 A	8.91 A
Open Circuit Voltage (Voc)	49.7 V	49.9 V	50.1 V	50.2 V	50.4 V	50.6 V
Short Circuit Current (Isc)	9.29 A	9.33 A	9.38 A	9.42 A	9.46 A	9.50 A

\* Under Nominal Module Operating Temperature (NMOT), irradiance of 800 W/m², spectrum AM 1.5, ambient temperature 55°C, wind speed 1 m/s.

### MECHANICAL DATA

Specification	Data
Cell Type	Mono-crystalline
Cell Arrangement	156 [2 X (13 X 6)]
Dimensions	2252 X 1048 X 35 mm (88.7 X 41.3 X 1.38 in)
Weight	25.7 kg (56.7 lbs)
Front Cover	3.2 mm tempered glass
Frame	Anodized aluminium alloy
J-Box	IP68, 3 bypass diodes
Cable	4 mm² (IEC), 12 AWG (UL)
Cable Length (Including Connector)	410 mm (16.1 in) (+) / 290 mm (11.4 in) (-) or customized length*
Connector	T4 series or H4 UTX or MC4-EVO2
Per Pallet	30 pieces
Per Container (40' HQ)	600 pieces

\* For detailed information, please contact your local Canadian Solar sales and technical representatives.

### TEMPERATURE CHARACTERISTICS

Specification	Data
Temperature Coefficient (Pmax)	-0.34 % / °C
Temperature Coefficient (Voc)	-0.26 % / °C
Temperature Coefficient (Isc)	0.05 % / °C
Nominal Module Operating Temperature	42 ± 3°C

### PARTNER SECTION



\* The specifications and key features contained in this datasheet may deviate slightly from our actual products due to the on-going innovation and product enhancement. CSI Solar Co., Ltd. reserves the right to make necessary adjustment to the information described herein at any time without further notice.

Please be kindly advised that PV modules should be handled and installed by qualified people who have professional skills and please carefully read the safety and installation instructions before using our PV modules.

### CSI Solar Co., Ltd.

199 Lushan Road, SND, Suzhou, Jiangsu, China, 215129, www.csisolar.com, support@csisolar.com

# Three Phase Inverter with Synergy Technology

## For the 208V Grid for North America

### SE50KUS



INVERTERS

#### Powered by unique pre-commissioning process for rapid system installation

- Pre-commissioning feature for automated validation of system components and wiring during the site installation process and prior to grid connection
- Easy 2-person installation with lightweight, modular design (each inverter consists of 3 Synergy units and 1 Synergy Manager)
- Independent operation of each Synergy unit enables higher uptime and easy serviceability
- Built-in thermal sensors detect faulty wiring ensuring enhanced protection and safety
- Built-in arc fault protection and rapid shutdown
- Built-in PID mitigation for maximized system performance
- Monitored\* and field-replaceable surge protection devices, to better withstand surges caused by lightning or other events
- Built-in module-level monitoring with Ethernet or cellular communication for full system visibility

\*Applies only for VDC and AC SPDs

## Three Phase Inverter with Synergy Technology

### For the 208V Grid for North America

#### SE50KUS

MODEL NUMBER	SE50KUS	UNITS
APPLICABLE TO INVERTERS WITH PART NUMBER	SE50KUS	
<b>OUTPUT</b>		
Rated AC Active Output Power	50000	W
Maximum AC Apparent Output Power	50000	VA
AC Output Line Connections	3W + PE, 4W + PE	
Supported Grids	WYE TN-C, TN-S, TN-C-S, TT, IT, Delta, IT	
AC Output Voltage Minimum-Nominal-Maximum <sup>(1)</sup> (L-L)	105 – 120 – 132.5	Vac
AC Output Voltage Minimum-Nominal-Maximum <sup>(1)</sup> (L-N)	183 – 208 – 229	Vac
AC Frequency Min-Nom-Max <sup>(2)</sup>	59.5 – 60 – 60.5	Hz
Maximum Continuous Output Current (per Phase, P1 – I)	139.5	Aac
GI DI Threshold	1	A
Utility Monitoring, Islanding Protection, Configurable Power Factor, Country Configurable Thresholds	Yes	
Total Harmonic Distortion	≤ 3	%
Power Factor Range	+/-0.2 to 1	
<b>INPUT</b>		
Maximum DC Power (Module STC) Inverter / Synergy Unit	87500 / 29165	W
Transformer-less, Ungrounded	Yes	
Maximum Input Voltage DC+ to DC-	600	Vdc
Operating Voltage Range	370 – 600	Vdc
Maximum Input Current	3 x 46.5	Adc
Reverse Polarity Protection	Yes	
Ground-Fault Isolation Detection	167kΩ sensitivity per Synergy Unit <sup>(3)</sup>	
CFC Weighted Efficiency	97	%
Nighttime Power Consumption	≤ 12	W
<b>ADDITIONAL FEATURES</b>		
Supported Communication Interfaces <sup>(1)</sup>	2 x RS485, Ethernet, Wi-Fi (optional), Cellular (optional)	
Smart Energy Management	Export Limitation	
Inverter Commissioning	With the SerApp mobile application using built-in Wi-Fi access point for local connection	
Arc Fault Protection	Built-in, User Configurable (According to UL1699A)	
Photovoltaic Rapid Shutdown System	NEC 2014, 2017 and 2020, Built-in	
PID Rectifier	Nighttime, built-in	
RS/BS Surge Protection (ports 1-2)	Type II, field replaceable, integrated	
AC, DC Surge Protection	Type II, field replaceable, integrated	
DC Fuses (Single Pole)	25A, integrated	
Pre-Commissioning	Built-in <sup>(4)</sup>	
<b>DC SAFETY SWITCH</b>		
DC Disconnect	Built-in	
<b>STANDARD COMPLIANCE</b>		
Safety	UL1699B, UL1741, UL1741 SA, UL1741 SB, UL1998, CSA C22.2 #107.1	
Grid Connection Standards	Canadian AFCEI according to T.I.L. M-07	
Emissions	IEEE 1547-2018, Rule 21, Rule 14 (1) (1)	
	FCC part 15 class A	

<sup>(1)</sup> For other regional listings please contact SolarEdge support.

<sup>(2)</sup> Where permitted by local regulations.

<sup>(3)</sup> For specifications of the optional communication options, visit the [www.solaredge.com/products](https://www.solaredge.com/products) page or the [Downloads Library](https://www.solaredge.com/downloads) to download the relevant product datasheet.

<sup>(4)</sup> Not available for E/US/SE/TH/BR/JP.



# Power Optimizer

## For North America

S1201



POWER OPTIMIZER

SolarEdge's most advanced, cost-effective Power Optimizer for commercial and large field installations

### Greater Energy Yields

- High efficiency (99.5%) with module-level MPPT, for maximized system energy production and revenue, and fast project ROI
- Supports high power and bifacial PV modules, and high string current for more power per string.

### Maximum Protection with Built-In Safety

- Designed to automatically reduce high DC voltage to touch-safe levels, upon grid/inverter shutdown, with SafeDC™
- Includes SolarEdge Sense Connect, allowing continuous monitoring to detect overheating due to installation issues or connector-level wear and tear

### Lower BoS Costs

- Flexible system design enables maximum space utilization and up to 2x longer string lengths, 50% less cables, fuses and combiner boxes
- Supports connection of two PV modules in series with easy cable management and fast installation times

### Simpler O&M

- Module-level system monitoring enabling pinpointed fault detection and remote, time-saving troubleshooting

## Power Optimizer

### For North America

#### S1201

	S1201	Units
<b>INPUT</b>		
Rated Input, DC Power <sup>(1)</sup>	1200	W
Absolute Maximum Input Voltage (Voc)	150	Voc
MPPT Operating Range	12.5 – 105	Voc
Maximum Short Circuit Current (Isc) of Connected PV Module	15	Adc
Maximum Efficiency	99.5	%
Weighted Efficiency	98.8	%
Oven Voltage Category	II	
<b>OUTPUT DURING OPERATION</b>		
Maximum Output Current	16	Adc
Maximum Output Voltage	80	Voc
<b>OUTPUT DURING STANDBY (POWER OPTIMIZER DISCONNECTED FROM INVERTER OR INVERTER OFF)</b>		
Safety Output Voltage per Power Optimizer	1	Voc
<b>STANDARD COMPLIANCE</b>		
Photovoltaic Rapid Shutdown System	Compliant with NEC 2014, 2017, 2020	
FMC	FCC Part 15, IEC 61000-6-2, and IEC 61000-6-3	
Safety	IEC 62109-1 (class II safety), UL 1741, UL 3741, CSA C22.2 #107.1	
Material	UL 94 V-0, 1V Resistant	
RoHS	Yes	
Fire Safety	VDT-AI-F 7100-710-2013-05	
<b>INSTALLATION SPECIFICATIONS</b>		
Maximum Allowed System Voltage	1000	Voc
Dimensions (W x L x H)	129 x 155 x 59 / 5.08 x 6.10 x 2.32	mm / in
Weight	1105 / 2.4	g / lb
Input Connector	MC4 <sup>(2)</sup>	
Input Wire Length	1.6 / 5.25 <sup>(3)</sup>	m / ft
Output Connector	MC4	
Output Wire Length	(-) 5.3 (-) 17.38, (+) 0.32	m / ft
Operating Temperature Range <sup>(4)</sup>	-40 to +85 / -40 to +185	°C / °F
Protection Rating	IP68 / NEMA6P	
Relative Humidity	0 – 100	%

<sup>(1)</sup> Rated power of the module at STC will not exceed the power optimizer rated input DC Power. Modules with up to +5% power tolerance are allowed.

<sup>(2)</sup> For other connector types please contact SolarEdge.

<sup>(3)</sup> The Sense Connect Solution is only considered if it is output cable connectors.

<sup>(4)</sup> For ambient temperatures above +55°C / +132°F power derating is applied.

PV System Design Using a SolarEdge Inverter <sup>(1)(2)(3)</sup>	208V Grid SE10K	208V Grid SE17.3K*	277/480V Grid SE20K, SE30K	277/480V Grid SE40K*
Compatible Power Optimizers				
	S1201			
Minimum String Length	Power Optimizers 8 PV Modules 15	10 19	15 29	15 29
Maximum String Length	Power Optimizers 30 PV Modules 60	30 60	30 60	30 60
Maximum Continuous Power per String	7200	8820	15300	15300
Maximum Allowed Connected Power per String <sup>(7)</sup>	1 string – 8400	1 string – 10020	1 string – 17550	2 strings or less – 17550
	2 strings or more – 16800	2 strings or more – 20040	2 strings or more – 23000	3 strings or more – 23000
Parallel Strings of Different Lengths or Orientations	Yes			
Maximum Difference in Number of Power Optimizers Allowed Between the Shortest and Longest String Connected to the Same Inverter Unit	5 Power Optimizers			

\*The same rules apply to Synergy units of equivalent power ratings that are part of the modular Synergy Technology Inverter.

<sup>(1)</sup> S1201 cannot be mixed with any other Power Optimizers models in the same string.

<sup>(2)</sup> For each string, a Power Optimizer may be connected to a single PV module (if it is the only Power Optimizer connected to a single PV module in the string).

<sup>(3)</sup> To connect more STC power per string, using Synergy project using SolarEdge Design.

solaredge.com



**solar**edge

© SolarEdge Technologies, Ltd. All rights reserved. SOLAREGE, the SolarEdge logo, OPTIMIZED BY SOLAREGE are trademarks or registered trademarks of SolarEdge Technologies, Inc. All other trademarks mentioned herein are trademarks of their respective owners. Date: February 1, 2023 US-000131-NA-NA. Subject to change without notice.

RoHS  
InnoTek



## XR100® Rail









Rail Section Properties	
Property	Value
Total Cross-Sectional Area	0.582 in <sup>2</sup>
Section Modulus (X-axis)	0.297 in <sup>3</sup>
Moment of Inertia (X-axis)	0.390 in <sup>4</sup>
Moment of Inertia (Y-axis)	0.085 in <sup>4</sup>
Torsional Constant	0.214 in <sup>4</sup>
Polar Moment of Inertia	0.126 in <sup>4</sup>

APPROVED MATERIALS:  
6005-T6, 6005A-T61, 6105-T5, 6N01-T6  
(34,000 PSI YIELD STRENGTH MINIMUM)

Clear Part Number	Black Part Number	Description / Length	Material	Weight
XR-100-132A	XR-100-132B	XR100, Rail 132" (11 Feet)	6000-Series Aluminum	7.50 lbs.
XR-100-168A	XR-100-168B	XR100, Rail 168" (14 Feet)		9.55 lbs.
XR-100-204A	XR-100-204B	XR100, Rail 204" (17 Feet)		11.60 lbs.


S-5-U Clamp  
 386 Smith Ridge Rd, South Salem, NY 10590, USA  
 142.59 kW DC (100 kW AC) Roof Mounted Solar PV System

**S-5-U**



**General Notes:**

1. S-5-U
2. 0.9" 3/8-24 T30 Drive SetScrew
3. M8-1.25 16 mm Bolt
4. Example roof



386 Smith Ridge Rd,  
 South Salem, NY 10590,  
 USA

142.59 kW DC  
 (100 kW AC)

Client Information

MATT DEWING

(203)656-7583  
 matthew.dewing@ringsend.com  
 386 Smith Ridge Rd,  
 South Salem, NY 10590,  
 USA

Engineer's Seal

Designed by

Sync Renewables, LLC  
 84 Marlborough St.,  
 Portland, CT 06460

Account:

1001-2645-494

Material:

84-819-261

Date: 7/9/2023

Revision: 1.0

REVISION HISTORY


## PV Labeling

386 Smith Ridge Rd, South Salem, NY 10590, USA  
142.59 kW DC (100 kW AC) Roof Mounted Solar PV System  
System Labeling shall comply with the 2020 NEC Labeling Requirements

### 2020 NEC Labeling Requirements

NEC Section	Location of Label	Label Text and Appearance	NEC Section	Location of Label	Label Text and Appearance
690.54	All interactive system(s) points of interconnection with other sources shall be marked at an accessible location at the disconnecting means as a power source and with the rated ac output current and the nominal operating ac voltage.		705.12 (B)(5)(i)	A permanent warning label shall be applied to the distribution equipment adjacent to the back-fed breaker from the inverter.	
690.13(B) 690.15 705.10	Each PV system disconnecting means shall plainly indicate whether in the open (OFF) or closed (ON) position and be permanently marked. "PV SYSTEM DISCONNECT" Or equivalent.	 MAIN PHOTOVOLTAIC SYSTEM DISCONNECT PHOTOVOLTAIC DC DISCONNECT PHOTOVOLTAIC AC DISCONNECT MAXIMUM VOLTAGE OF PV SYSTEM	705.12 (B)(5)(ii)	Permanent warning labels shall be applied to distribution equipment.	
690.53	A permanent readily visible label indicating the highest maximum dc voltage to a PV system, calculated in accordance with 690.7, shall be provided by the installer at one of the three locations:		690.56 (C)	Buildings with PV systems shall have a permanent label located at each service equipment location to which the PV systems are connected or at an approved readily visible location and shall indicate the location of rapid shutdown initiation devices. The label shall include a simple diagram of a building with a roof and shall include the following words: The following PV SYSTEM IS EQUIPPED WITH RAPID SHUTDOWN. SAFETY: SHUT DOWN TO THE "OFF" POSITION TO SHUTDOWN PV SYSTEM AND REDUCE SHOCK HAZARD IN ARRAY. (2) A rapid shutdown switch shall have a label located on or no more than 2 ft from the switch that indicates the wording. The label shall be reflective, with all letters capitalized and having a minimum height of 3/8 in., in white on red background.	
690.52 (D)(4)	Unless the purpose is evident, the following wiring methods and enclosures that contain PV system dc circuit conductors shall be marked: (1) Exposed raceways, cable trays, and other wiring methods. (2) Covers or enclosures of pull boxes and junction boxes. (3) Conduit bodies in which any of the available conduit openings are unused.	 SOLAR PV DC CIRCUIT PHOTOVOLTAIC POWER SOURCE	(3) Buildings with More Than One Rapid Shutdown Type. For buildings that have PV systems with both rapid shutdown types or a PV system with a rapid shutdown type and a PV system with no rapid shutdown, a detailed plan view diagram of the roof shall be provided showing each different PV system and a dotted line around areas that remain energized after the rapid shutdown switch is operated.		
690.13(B) 690.15(C)	Where all terminals of the disconnecting means may be energized in the open position, a warning sign shall be mounted on or adjacent to the disconnecting means.				


### NEC Section

### Location of Label

### Label Text and Appearance


690.56(B)  
690.4(D)  
705.10

A permanent plaque or directory shall be installed at each service equipment location, or at an approved readily visible location. The plaque or directory shall denote the location of each power source disconnecting means for the building or structure and be grouped with other plaques or directories for other on-site sources. The plaque or directory shall be marked with the wording  
"CAUTION: MULTIPLE SOURCES OF POWER."  
Any posted diagrams shall be correctly oriented with respect to the diagram's location. The marking shall comply with 110.21(B).



5" x 6"







**MEMORANDUM**

TO: Chairperson Janet Andersen and  
Members of Lewisboro Planning Board

CC: Ciorsdan Conran  
Judson Siebert, Esq.  
Kevin Kelly, Building Inspector

FROM: Jan K. Johannessen, AICP   
Joseph M. Cermele, P.E., CFM   
Town Consulting Professionals

DATE: December 15, 2023

RE: Wolf Conservation Center  
Mead Street and Buck Run  
Sheet 21, Block 10803, Lots 3, 77, 65, 81, 82, 83, 86, and 88

---

**PROJECT DESCRIPTION**

The subject property consists of ±32.3 acres of land and is located off Buck Run, a private road, within the R-2A and R-4A Zoning Districts. The applicant has submitted an application for a Special Use Permit, under Section 220-43.2, Private Nature Preserves, of the Zoning Code, and is proposing several improvements in the furtherance of its goals and objectives.

**REQUIRED APPROVALS/REFERRALS**

1. Subdivision, a Special Use Permit, a Wetland Activity Permit and a Town Stormwater Permit are required from the Planning Board; a public hearing is required to be held.
2. Area variance(s) may be required from the Zoning Board of Appeals (ZBA).
3. The application must be referred to the Architecture and Community Appearance Review Council (ACARC) for review and recommendations.
4. Westchester County Department of Health (WCDH) Approval is required for Realty Subdivision, reconstruction of an existing sanitary sewage disposal systems and new potable water well(s). A public water system will likely be required by the WCDH.

5. The proposed action requires Stormwater Pollution Prevention Plan (SWPPP) Approval from the New York City Department of Environmental Protection (NYCDEP).
6. Land disturbance will exceed one (1) acre located within the NYCDEP East of Hudson Watershed; coverage under the New York State Department of Environmental Conservation (NYSDEC) SPDES General Permit for Stormwater Discharge from Construction Activity (GP-0-20-001) is required.
7. An Article 24 Freshwater Wetland Permit may be required from the NYSDEC.
8. Improvements and modifications within the State right-of-way will require approval from the New York State Department of Transportation (NYSDOT).
9. The proposed action must be referred to the Westchester County Planning Board in accordance with Section 239-m of the General Municipal Law; the Planning Board administrator will coordinate this referral.

#### **COMMENTS**

1. The applicant has updated and resubmitted its previously submitted business plan and written description demonstrating compliance with the Special Use Permit provisions for Private Nature Preserves, for the Board's review.
2. As previously noted, the applicant acknowledges that the SWPPP Report will need to include pipe flow calculations; please provide with future submissions. The calculations shall demonstrate that the proposed pipe network along the Buck Run driveway will have sufficient capacity.
3. We defer further comments regarding the SWPPP until the application has received comments back from the NYCDEP.
4. The applicant has submitted the 72-Hour Well Pump Test Work Plan, which is being forwarded to our Hydrogeologist Consultant for review and comment.

In order to expedite the review of subsequent submissions, the applicant should provide annotated responses to each of the comments outlined herein.

#### **PLANS REVIEWED, PREPARED BY BIBBO ASSOCIATES, LLP, DATED NOVEMBER 28, 2023:**

- Cover (CS-1)
- Preliminary Subdivision Plan (PP-1)
- Existing Conditions Plan (EX-1)

Chairperson Janet Andersen  
Wolf Conservation Center – Mead Street and Buck Run  
December 15, 2023  
Page 3 of 3

- Existing Conditions & Removals Plan (EX-2)
- Layout Plan – South (LP-1)
- Layout Plan – North (LP-2)
- Construction Plan – South (CP-1)
- Construction Plan – North (CP-2)
- Erosion Control Plan (EC-1)
- Erosion Control Notes & Details (EC-2)
- Road Profiles (P-1)
- Drainage Profiles (P-2)
- Turning Maneuvers (T-1)
- Sight Distance & Profiles (SD-1)
- Mitigation Plan (M-1)
- Lighting Plan (LP-1)
- Details (D-1, D-2, D-3)
- Well Testing Plan (WT-1)

**DOCUMENTS REVIEWED:**

- Letter, prepared by Janet J. Giris, dated November 27, 2023
- Stormwater Pollution Prevention Plan Report, dated October 20, 2023
- Operational Plan and Special Use Permit Compliance, dated March 1, 2023
- Notice of Intent
- 72-Hour Well Pump Test Work Plan

JKJ/dc

**DELBELLO DONNELLAN WEINGARTEN  
WISE & WIEDERKEHR, LLP**

**Janet J. Giris**  
**Partner**  
jjg@ddw-law.com

COUNSELLORS AT LAW  
THE GATEWAY BUILDING  
ONE NORTH LEXINGTON AVENUE  
WHITE PLAINS, NEW YORK 10601  
(914) 681-0200  
FACSIMILE (914) 684-0288

Connecticut Office  
1111 SUMMER STREET  
STAMFORD, CT 06905  
(203) 298-0000

November 27, 2023

**By Hand Delivery**

Honorable Janet Anderson, Chair  
and Members of the Planning Board  
Town of Lewisboro  
79 Bouton Road  
South Salem, New York 10590

**Re: Application of The Wolf Conservation Center, Inc., for Subdivision, Site Plan, Special Permit Approval, Wetland Permit and Stormwater Permit in Connection with a Private Nature Preserve on Property Located on Buck Run, South Salem.**

Dear Chairwoman Anderson and Members of the Board:

As you know, this firm represents the Wolf Conservation Center, Inc. (the "Applicant"), in connection with the above-referenced applications. On behalf of the Applicant and in support of our applications, we respectfully submit the enclosed revised plans and materials for the Board's review and consideration at its meeting on December 19, 2023.

Over the course of the last several meetings with the Board, the Applicant has focused on the subdivision which was approved by the Board on November 21, 2023. In addition, the Applicant and its consultants have been working to address the outstanding comments regarding the remainder of its applications for special permit, site plan, wetland permit and stormwater permit approvals received from the Town's consulting professionals, KSCJ Consulting, in its memorandum to the Board dated May 12, 2023 (the "KSCJ Memo"). Accordingly, on behalf of the Applicant and in support of our applications, we respectfully submit the enclosed set of site plan drawings and materials which have been revised to address the comments contained in the KSCJ Memo. Each set of revised plans consists of the following sheets:

Drawing No.	Title	Prepared By	Dated or Last Revised
CS-1	Cover Sheet	Bibbo Associates, LLP ("Bibbo")	11-28-23
PP-1	Preliminary Plot Plan	Bibbo	11-28-23

EX-1	Existing Conditions Plan	Bibbo	11-28-23
EX-2	Removals Plan	Bibbo	11-28-23
LP-1	Layout Plan - South	Bibbo	11-28-23
LP-2	Layout Plan – North	Bibbo	11-28-23
CP-1	Construction Plan - South	Bibbo	11-28-23
CP-2	Construction Plan – North	Bibbo	11-28-23
EC-1	Erosion Control Plan	Bibbo	11-28-23
EC-2	Erosion Control Notes & Detail	Bibbo	11-28-23
P-1	Road Profiles	Bibbo	11-28-23
P-2	Drainage Profiles	Bibbo	11-28-23
T-1	Turning Maneuvers	Bibbo	11-28-23
SD-1	Sight Distance & Profiles	Bibbo	11-28-23
M-1	Mitigation Plan	Bibbo	11-28-23
LP-1	Lighting Plan	Bibbo	11-28-23
D-1	Details	Bibbo	11-28-23
D-2	Details	Bibbo	11-28-23
D-3	Details	Bibbo	11-28-23
D-4	Details	Bibbo	11-28-23

In addition to the revised plans referenced above, we also respectfully submit the following materials for your review and consideration:

1. A “72 Hour Well Pump Test Work Plan,” together with Drawing WT-1, entitled “Well Testing Plan” prepared by Bibbo and dated November 28, 2023;
2. A revised “Stormwater Pollution Prevention Plan”, prepared by Bibbo and last revised October 20, 2023 (NYCDEP Completeness); and
3. A revised Notice of Intent (“NOI”).

In response to the comments contained in the KSCJ Memo, we respectfully offer the following responses. As requested in the KSCJ Memo, each of the comments is repeated below with the response following:

- 1. Comment: The applicant acknowledges the request to submit an updated Existing Conditions Survey (boundary and 2-foot contours), signed and sealed by a NYS Licensed Land Surveyor.**

Response: A signed and sealed existing conditions survey entitled “Topographic Map Prepared for the Wolf Conservation Center, Inc.”, prepared by Insite Engineering, Surveying & Landscape Architecture, P.C. , dated 11/21/2018 (consisting of two (2) sheets) was included in our previous submission to the Board on June 26, 2023.

- 2. Comment: The applicant has acknowledged the need to update and resubmit its previously submitted business plan and written description demonstrating**

**compliance with the Special Use Permit provisions for Private Nature Preserves. The business plan shall include a title and date for reference purposes.**

Response: A revised business plan, entitled “Operational Plan and Special Use Permit Compliance Created for Review by the Town of Lewisboro”, dated March 1, 2023 is enclosed with this submission. As previously stated to the Board, the proposed Private Nature Preserve complies with the specific site standards contained in Section 220-43.2 (B) of the Zoning Code as follows:

- a. The Property, which consists of approximately 33.1 acres, exceeds the ten (10) acre minimum required for qualification as a Private Nature Preserve;
- b. The Property is located on a private road (Buck Run) which has direct access to a state highway (Route 35);
- c. The accessory uses and structures existing and proposed on the Property are customarily incidental to a private nature preserve, and include animal enclosures, employee offices, a learning center; a storage and maintenance building, camping pods, a refrigeration and kitchen building for animal food preparation, composting toilets and an amphitheater.
- d. The Applicant respectfully submits that the Property is appropriately fenced and screened so that impacts from any activity on the Property are properly mitigated.
- e. In order to ensure that animal waste will not adversely impact the Property or any wetlands or waterbodies on the Property or adjacent properties, animal waste is handled in two ways; The two enclosures housing the WCC ambassador packs are cleaned approximately 2 to 4 times a week. All debris including scat and remnant bones from feedings is removed and disposed of in the trash that is picked up weekly. The enclosures for the federally protected endangered species are cleaned only intermittently, consistent with the “hands off” management of these critically endangered wolves. Regular human presence can adversely impact preparation for potential release into the wild. Clean ups are therefore done at opportune times such as during health checks and enclosure and fence maintenance. This protocol ensures that they are disturbed as minimally as possible. When in large quantities, collected bones and scat are double bagged and disposed of at the Town of Somers transfer station.

In addition to the specific site standards contained in Section 220-43.2(B) of the Zoning Code, the proposed Private Nature Preserve complies with the general special permit standards contained in Section 220-32(E) as follows:

- a. The location and size of the use, the nature and intensity of the operations involved in the Private Nature Preserve or conducted in connection with it, the size of the site in relation to it and the location of the site with respect to streets giving access

to it, are such that it will be in harmony with the appropriate and orderly development of the district in which it is located and that it complies with all special requirements for such use established in the Zoning Code. As we have discussed with the Board, site size of the site now consists of more than thirty-three (33) acres and is appropriately sized for the approximately twenty-six (26) wolves currently living at the Property<sup>1</sup> and related educational and conservation activities. The Applicant intends to preserve the wooded and natural environment of the Property, and its improvement plan has been thoughtfully designed to minimize disturbance to the Property. The Wolf Conservation Center has harmoniously existed in its current location since 1999; the additional land acquired by the Applicant and the proposed improvements will further enhance its harmonious existence within the community. As stated above, the Wolf Center complies with the site standards contained in Section 220-43.2 (B) of the Zoning Code.

- b. The location, nature and height of buildings, walls and fences and the nature and extent of existing or proposed plantings on the site are such that the use will not hinder or discourage the appropriate development and use of adjacent land and buildings. The proposed improvements have been designed in accordance with the bulk and dimensional regulations of the Zoning Code, and as previously stated have been designed to minimize site disturbance. The Applicant is adaptively repurposing a number of existing structures on the Property. Accordingly, the Applicant respectfully submits that the proposed improvements and use of the Property as a Private Nature Preserve will not affect the development or use of adjacent land or buildings.
- c. Operations in connection with the Private Nature Preserve will not be more objectionable to nearby properties by reason of noise, fumes, vibration or other characteristics than would be the operations of any permitted use not requiring a special permit. As previously stated, the Wolf Center has existed harmoniously on the Property since 1999. The Private Nature Preserve will operate in a manner which is harmonious with the surrounding land uses, and will not generate noise, fumes, vibrations or other characteristics which are more objectionable to nearby properties than other uses permitted in the R-4A and R-2A Districts which include schools and municipal uses.
- d. Parking areas will be of adequate size for the particular use, properly located and suitably screened from adjoining residential uses, and the entrance and exit drives shall be laid out so as to achieve maximum and adequate safety. As part of its application, the Applicant has proposed: a) improvements to and widening of Buck Run; and b) construction of a new off-street parking area containing a total of 26 parking spaces, including two (2) handicap spaces of parking spaces. The Applicant respectfully submits that the parking areas are of adequate size for the proposed use, and access to the Property has been adequately and safely designed.

---

<sup>1</sup> This number varies depending on births, deaths and relocation of wolves.



- 3. Comment: The proposed tree plantings have not been accounted for in the Area Reduction RR Techniques (Question #29 of the NOI). Please add.**

Response: The enclosed NOI has been revised to account for the proposed Tree Planting Area Reduction Practices contained in Question #29.

- 4. Comment: Please provide a detail for Proposed Outlet Structure #1.1.**

Response: A detail for the proposed Infiltration Basin 1.1P outlet structure is included on Sheet D-2 of the enclosed drawings.

- 5. Comment: The applicant acknowledges that the SWPPP Report will need to include pipe flow calculations; please provide with future submissions. The calculations shall demonstrate that the proposed pipe network along the Buck Run driveway will have sufficient capacity.**

Response: Comment noted. Pipe sizing calculations will be included in the final SWPPP for the project.

- 6. Comment: We defer further comments regarding the SWPPP until the application has received comments back from the NYCDEP.**

Response: Comment noted. The Applicant received a notice of complete application from the NYCDEP on November 15, 2023; we anticipate receipt of NYCDEP's technical comments to the SWPPP by December 30, 2023.

- 7. Comment: As previously noted, we continue to recommend the need for diversion swales and water bars to be utilized during construction. The practices as shown and described in the SWPPP will only function once the conveyances have been installed. It is recommended that temporary sediment traps be constructed during construction. A second temporary sediment trap may be required at the upper portion of the development. Provide adequate sizing calculations in accordance with the NYSDEC Stormwater Management Design Manual (SMDM). A lot of the disturbance will be located on steep slopes, which will affect the downgraded portions of the project. Furthermore, a phasing plan should be implemented which outlines the phases of construction noted in the construction sequencing notes.**

Response: The erosion control plans have been revised to include additional erosion and sediment control measures in the form of water bars, temporary stone check dams and a double row of silt fence which has been added immediately downgradient of critical areas. As the Applicant's consultants continue to coordinate with NYCDEP on the SWPPP, they will explore the possibility of utilizing an infiltration basin as a temporary sediment basin during construction.

- 8. Comment: A “No Parking Anytime” sign should be shown for the ADA loading space on the plan and detail.**

Response: As requested, the plans have been revised to include a “No Parking Anytime” sign at the ADA loading space. Details for signage are included on Sheet D-3 of the enclosed plans.

- 9. Comment: Since all curbs will be concrete, please remove the asphalt pavement label located on sheet CD-1.**

Response: Comment noted. The plans have been revised accordingly.

- 10. Comment: The applicant acknowledges that the WCDH will require that a 72-hour pump test be performed for the public water system. The applicant shall coordinate with this office regarding the pump test, including preparation and approval of a work plan.**

Response: The proposed “72 Hour Pump Test Work Plan” is enclosed. Upon review and approval by KSCJ, the Applicant will conduct the test in accordance with the work plan.

We respectfully request that this matter be placed on the Board’s December 19, 2023 agenda for continued review. Thank you for your consideration, and we look forward to meeting with the Board on December 19.

Very truly yours,



JANET J. GIRIS

Enclosures

cc: Judson Siebert, Esq.  
Jan Johannessen, AICP, KSCJ  
Spencer Wilhelm, The Wolf Conservation Center  
Bill Cordiano, The Wolf Conservation Center  
Dean Travalino, The Wolf Conservation Center  
Matthew Gironda, P.E., Bibbo Associates



**Operational Plan and Special Use Permit Compliance**  
**Created for Review by the Town of Lewisboro**  
**March 1, 2023**

**MISSION:** *Advance the survival of wolves by inspiring a global community through education, advocacy, research, and recovery.*

- WCC mailing address: Wolf Conservation Center, PO Box 421, South Salem, NY 10590
- WCC physical address: 7 Buck Run, South Salem, NY 10590
- Phone: 914-763-2373
- Email: [info@nywolf.org](mailto:info@nywolf.org)

Founded by **Hélène Grimaud** in 1999, the Wolf Conservation Center (WCC) is a 501(c)(3) not-for-profit environmental education organization working to protect and preserve wolves in North America through science-based education, advocacy, and participation in the federal recovery and release programs for two critically endangered wolf species - the Mexican gray wolf and red wolf. The WCC's two 'ambassador wolves' reside on exhibit where they help teach the public about wolves and their vital role in the environment. Through wolves, the WCC teaches the broader message of conservation, ecological balance, and personal responsibility for improved human stewardship of our World.

The Wolf Conservation Center (WCC) participates in the federal Species Survival Plan (SSP) recovery programs for the Mexican gray wolf and the red wolf, two of the rarest mammals in North America. Both species at one time were completely extinct in the wild. Since 2003 the WCC has played a critical role in preserving and protecting these imperiled species through carefully managed breeding and reintroduction. To date, the WCC remains one of the three largest holding facilities for these rare species, and six wolves from the Center have been given the extraordinary opportunity to resume their rightful place in the wild landscape.

#### **What is a Species Survival Plan?**

A Species Survival Plan (SSP) is a breeding and management program designed to ensure the long-term sustainability of captive-based animal populations. It's a coordinated effort among zoos, organizations like the Wolf Conservation Center, U.S. Fish and Wildlife Service, Mexico's Fish & Wildlife Agencies and managed under the Association of Zoos and Aquariums (AZA).

To best prepare the critically endangered wolves who are candidates for wild-release, the center's approximately 20 Mexican gray wolves and 10 red wolves reside off exhibit within the WCC's Endangered Species Facility.

**The WCC is governed by a 16-member Board of Directors, a full-time staff, an advisory board of veterinarians, educators, scientists and other naturalists. AKA - Wolf Conservation Center Team**

**Current Staff:**

Caleb Alexander, Media & Communications Manager  
Rebecca Bose, Curator  
Jeff Dow, Partnership Manager  
Regan Downey, Director of Education  
Dana Goin, Wildlife Outreach Specialist  
Jared Gorman, Education Assistant  
Joseph W. Hinton, PhD, Senior Research Scientist  
Alice O'Rourke, Executive Director, interim  
Chris Lovell, IT Operations Specialist  
Sunny Murphy, Research Associate  
Deputy Director  
Hannah Power, Program Educator  
Sean Seary, Program Educator and Volunteer Coordinator  
Alex Spitzer, Facilities Manager  
Spencer Wilhelm, Director of Operations

**Board of Directors**

Errol Antzis	Scott Kantro
Jeffrey Blockinger	Tracy Kraft
Cristina Civetta	Tripp Killin
Bill Cordiano	Claudia Neary
Susie Freund	Shari Wolf Ruckh
Helene Grimaud, Founder	Rob Shultz
Martha Handler, President	Dean Travalino
Maryanne Hartley	Patrick Valentino

**Advisory Board**

Diane Bentivegna	Cathy Kangas
Erica Cornwall	Randolf Perry
Nina Fascione	

**Scientific Advisory Board**

Charlie Duffy, VMD (Veterinary Medical Doctor)  
Cristina Eisenberg, Ph.D., Earthwatch Lead Scientist, Author  
Dr. Don Moore, Smithsonian Zoo/ Polar Bear international  
Rolf Peterson, Wolf Biologist

\*Individuals and their titles and/or the number of WCC team members listed above are subject to change without notice.

**Hours of Operation:** The WCC is staffed seven days per week. General office operating hours are 9:00am-5:00pm, although staff and guests may be on-site during extended evening/overnight/early morning hours while participating in one of the WCC's scheduled public events.

## **GUIDELINES AND RULES**

The Wolf Conservation Center (WCC) is a smoke-free facility (this includes no juuls, e-cigarettes, vaping, drugs, or tobacco products of any kind).

- Visitors aged 16 and under must be accompanied by a chaperone. Sleeping with Wolves registrants under age 18 must be accompanied by a chaperone.
- Touching or feeding the wolves is prohibited.
- Deposit trash in designated receptacles.
- Shirts and shoes are required at all times.
- We reserve the right to escort from WCC grounds any individuals or groups who are acting in ways deemed harmful to our animals, or that impinge upon the enjoyment of the facility by other guests.
- Weapons of any kind are not allowed at the WCC.
- Alcohol is not permitted, unless provided by the WCC during specified adult programming.

We don't allow visitors to have physical contact with our wolves, as they are wild animals and here to assist with education programs. A majority of our wolves are critically endangered red wolves and Mexican gray wolves, and they reside at our center as part of federal recovery programs. As such, it is critical we safeguard their wild, elusive behavior and natural wariness of humans. Visitors are able to see our ambassador wolves quite closely and clearly through a fence and photos/videos are allowed.

**Weather Policy & Guests:** The WCC programming usually runs rain or shine, but the WCC staff monitors weather conditions closely, and if potentially severe storms are predicted, the staff will contact registered visitors to inform of cancellations and to reschedule. If conditions become severe or if lightning occurs during a visit, then visitors will be directed to the safety of the WCC classroom. In the event of a tornado warning all visitors will be led to the lower level of the WCC administration.

## **Behind the Public Scene of the WCC**

### **Current On-Site Structures & Use:**

**1 Buck Run** – Ranch style residential building. Used by the WCC as staff/intern/special guest sleeping quarters.

**3 Buck Run** – Cape style residential building to be demolished. Site to become Education Pavilion.

**4 Buck Run** – Ranch style residential building used by the WCC as offices for operations and facilities. There is a small shed in rear that remains.

**7 Buck Run** – (1) Contemporary residential building that is used by the WCC as its' administrative, education, and animal care headquarters. (2) There is a shed to the south of admin which houses freezers. This building will be removed during renovations. (3) The current classroom site will have a newly constructed building that will become cold storage and animal food prep.

**Enclosures** – There are two enclosures for WCC's ambassador wolves and eight enclosures for wolves under the SSP program. Each enclosure ranges from 0.75-1.5 acres in size.

**Medical:** All WCC onsite staff members and all volunteer educators are CPR/first aid certified. The WCC has an AED and emergency first aid kits available if needed. Staff communicates on-site via handheld radios and cellphones.

**Storms:** When a severe storm is expected a WCC staff member(s) will stay on-site to monitor conditions. Much of the site can also be monitored 24/7 with the existing network camera system. The WCC is served by a stand-by 38KW generator which provides site power to #7 Buck Run and wolf enclosures.

**Enclosure Breach:** If a wolf enclosure is breached during a storm or by any other cause, then the on-site staff member will assess the situation, stay at the breached area, and contact the WCC emergency response team members. If the breach results in a wolf out of its enclosure, then the previous protocol remains, but includes participation from a wildlife management company to assist if trapping is necessary. If an animal makes a full breach of the WCC property's two fence system, then local authorities will also be contacted. If guests are on property, then they will be escorted to an area away from the breach or asked to leave the facility.

**Property Walks:** Every day, the areas of the property containing the wolf enclosures are walked and surveyed to look for enclosure breaches, maintenance needs to enclosures, needed tree work, or other.

**Property Tree Maintenance:** Each year the WCC meets with a certified arborist to conduct a property tree assessment to identify trees that are diseased, dead, have broken limbs, or pose a potential hazard to people or structures. The same tree company also gives priority to the WCC to assist with emergencies involving trees.

**Fencing Maintenance:** The WCC works with a local fence company for as needed repairs or improvements. The fencing company also prioritizes the WCC to aid in any fencing emergency.

**Waste Management:** Trash, including cardboard and other recyclables, is collected weekly by a waste management company. Large items are trucked to the Town of Somers transfer station or to a recycling facility.

Animal waste is handled in two ways: (1) The two enclosures housing the WCC ambassador packs are cleaned approximately 2 to 4 times a week. Scat and remnant bones from feedings are removed, bagged, and disposed of in the trash that is picked up weekly. (2) The enclosures for the federally protected endangered species are cleaned only intermittently, consistent with the "hands off" management of these critically endangered wolves. Regular human presence can adversely impact preparation for potential release into the wild. Clean ups are therefore done at opportune times such as during health checks, the weekly feeding, or during enclosure and fence maintenance. This protocol ensures that they are disturbed as minimally as possible. All collected bones and scat are double bagged, and depending on quantity, put into WCC refuse or dumped at the transfer station in Somers.

**Buck Run Maintenance:** Buck Run is a private road with six adjoining parcels, five of which are now owned by the WCC. The one remaining parcel contains a 2-acre lot of NYCDEP wetlands. Historic deeds suggested that the owner of each parcel is responsible for 1/6 of the cost of road maintenance. However, since its founding in 1999, the WCC has maintained Buck Run at its own effort and expense.

**Financials:** To view the yearly audited financials, 990's, or annual reports please visit and download from the WCC website @ [www.nywolf.org/financials](http://www.nywolf.org/financials).

## **VOLUNTEERING AT THE WCC – 16 YEARS AND OLDER – MUST COMPLETE THE ONLINE APPLICATION**

### **Onsite Help**

There's always work to be done at the Center. The jobs aren't always glamorous, but they do all come with the benefit of getting to observe the wolves.

- **Ground Maintenance:** We could always use help cleaning, cutting grass, clearing brush, assisting with the various construction tasks and projects that arise.
- **Guides:** We are always looking for dynamic and engaging people to run visits and give educational presentations.
- **Assistant Guides:** Assist with programs, set up and clean up while participating in the educational program as a center representative.
- **Veterinary Care:** We are extremely indebted to the vets that already help us out, but we always have the need to add more to our roster.

### **Offsite Help**

We know that many people want to help out the wolves but cannot make it to the WCC very often or at all. Here are a few examples of things people can do for us from the comfort of their own homes:

- **Grant writing**
- **Creating crafts to be sold onsite**
- **Publicity**

### **Fundraising**

We are sustained by donations from individuals, so another huge way people of all ages can help us is by conducting their own fund-raising events for the Wolf Conservation Center. It doesn't have to be difficult or even involve too much preparation or planning – we want you to enjoy whatever you do with us or on our behalf!

## **INTERN AT THE WOLF CONSERVATION CENTER**

The Wolf Conservation Center is pleased to offer the opportunity for high school and college interns to gain experience in wildlife conservation and education.

### **HIGH SCHOOL INTERNSHIP**

High school interns will learn about animal husbandry and enrichment; environmental education; enclosure and grounds maintenance; and non-profit fundraising by participating in daily activities alongside WCC staff. Daily activities that interns will assist with include food preparation, helping with on-site education programs, and enclosure construction.

The high school internship runs throughout the spring season and is unpaid. **The application deadline for this internship is March 1st.**

### **QUALIFICATIONS:**

- Must be at least 16 years of age (driver's license is encouraged).
- Must enjoy working outdoors.
- Must be in good physical condition and able to lift 50 pounds.
- Preference is given to students pursuing a career in a related field.

### **COLLEGE INTERNSHIP**

The WCC offers year-round environmental education and conservation internship opportunities for college students, those who have recently graduated, or others looking to explore a new career path. The internships are designed to

expose interns to the field of conservation education and wildlife biology. Interns conduct a variety of educational programs and assist with the daily operations of the WCC, which may vary depending on the internship season.

Throughout the course of the internship, interns will primarily deal with the general public but will also have opportunities to interact with camps, scouts, and school groups. Interns will contribute to the success of the WCC through development of special projects, support work, and general maintenance.

**The WCC does not offer housing for interns. All interns are responsible for securing their own transportation to and from the WCC.**

The internship seasons and descriptions are as follows:

**Winter/Spring (February-May):** This season at the Wolf Conservation Center is very busy with programming, winter weather preparations and spring clean-ups. As an intern during this season, you are able to observe the wolves in their full winter coats as they illustrate how animals are able to adapt to their ever-changing landscape. This internship is very flexible to accommodate school, work, and possible weather schedules.

**The application deadline for this internship is December 1.**

**Summer (June – August):** This internship will focus on environmental education, as interns will take part in our summer camp as counselors and educators. There will also be opportunities to assist with general operations such as enclosure upkeep, grounds work, overnight and weekend programming, as well as potential fundraising opportunities. This internship period is very structured and full-time availability is required. Due to the demand of this full-time internship, there is a stipend for this season. **The application deadline for this internship is March 8th.**

**Fall (September– December):** As the summer subsides the need for interns does not. Our fall season consists of school programming and winter preparation projects. Interns are able to have a flexible schedule to work around school, life, and other obligations. **The application deadline for this internship is July 1<sup>st</sup>.**

## **Planned Campus Renovation – Overview**

### **Special Use Permit & Compliance**

The following information is to provide reference on the efforts of the Wolf Conservation Center to be compliant with the Local Law, Private Nature Preserve Law, §220-43.2. Presented first are brief answers to section A: Site Standards and Section B: Traffic Controls. More descriptive explanations follow as well as summaries of the planned site improvements, trailed by copies of the required approvals and permits applicable to Part C of the local law. Next, listed are the public opportunities provided by the WCC offering passive, yet organized recreational experiences consistent with the special permit's pursuits.

#### **Site Standards**

1. Minimum lot size needed (10) acres: The WCC provides 33+ acres.
2. Access to a state highway or major street: The WCC's private entrance is located off of State Route 35 providing easy access for all vehicular traffic.
3. Permitted accessory uses: The current and planned accessory uses are supportive buildings for administration, storage, animal enclosures, freezers, public education and event space, and staff housing as needed.



4. Fencing is comprised of 11 gauge, 8' galvanized chain link for the secondary perimeter fencing. The primary enclosure fencing is composed of 9 gauge, 11' galvanized or brown vinyl coated chain link. Fencing specifications are consistent with USDA requirements.
5. Wetland delineation: Wetlands have been delineated.
  - a. Animal waste is handled in one of two ways.
    - i. The two enclosures housing the WCC ambassador packs are cleaned approximately 2 to 4 times a week. Scat and remnant bones from feedings are removed, bagged, and disposed of in the trash that is picked up weekly.
    - ii. The enclosures for the federally protected endangered species are cleaned intermittently, consistent with the "hands off" management of these critically endangered wolves. Regular human presence can adversely impact preparation for potential release into the wild. Clean ups are therefore done at opportune times such as during health checks, the weekly feeding, or during enclosure and fence maintenance. This protocol ensures that they are disturbed as minimally as possible. When in large quantities, collected bones and scat are double bagged, disposed of at the transfer station in Somers.

#### B. Wolf Menu and frequency

- i. The animals at the WCC eat better than most human carnivores. The wolf menu is made up of organic meat consisting of local wild game (deer, beaver, turkey, fish) primarily from road kill, seasonal hunts & state beaver trapping, NYS poaching confiscations. Domesticated food, typically poultry and seafood, is donated from various grocery stores such as Whole Foods and Mom's Organic Market.
- ii. Wolves are gorging creatures meaning they eat large meals when possible and are forced to fast when food is not plentiful.
  1. The majority of each wolf group, are fed typically one large meal once per week. Consuming their fill and returning over time until fully consumed. Wolves will eat a deer from the head to the hoof. Local scavengers, such as ravens and vultures, help to fully eliminate the given food source.

#### Traffic Controls

1. Staff Traffic Control: All guests must pre-register to visit the WCC which controls attendance and the number of vehicles. Because events are prescheduled and staggered throughout the day, guest traffic commonly all arrive/depart within a 30-minute window of the event. Staff and/or volunteers currently check in guests as they park.
2. Bus and Van Transport: The WCC intends to provide a large vehicle traffic loop to help accommodate all sized buses, vans, & delivery vehicles.
3. ON street parking: The WCC doesn't encourage on-street parking; adequate parking will be provided in the parking area to be constructed.
4. OFF street parking: Guest parking for 26- vehicles (including two (2) handicap accessible spaces) and/or two busses is to be provided. Staff parking is provided at each accessory building. From time to time, the Center may conduct planned larger events for which the WCC cannot accommodate the number of expected

vehicles. In that instance, one option will be for the WCC to rent the Lewisboro Town Park parking lot, hire a charter bus service, and shuttle guests to the WCC. Foreseeable large events requiring the town park (or other parking venue) could consist of Galas and fundraisers, Halloween or Holiday lights evenings, or larger private parties.

## **New Buildings and Their Planned Use**

The WCC campus is comprised of approximately 33+ acres located on the north side of Route 35 with access from WCC's private drive, Buck Run (to be renamed "Atka's Way" in connection with other approvals from the Town of Lewisboro) in South Salem, New York. The site is heavily wooded with steep slopes. Visitors' opportunities and administrative activities are clustered to the southeastern portion of the site with the northern and western parts of the site used for additional wolf enclosures that are not accessible to visitors. There are several buildings on the site today including the original home that functions as an administrative building and veterinary facility, a small cabin for educational gatherings, and storage buildings.

The WCC's campus planned renovation is ambitious. The scope of work includes a variety of new elements: A 4,700 sq. ft. educational pavilion consisting of a classroom, gift shop, extended learning hall/gallery, conference room with kitchenette, full unfinished basement for mechanicals and storage, and an amphitheater. An animal care facility containing freezers, butchering area, sink space, and storage will replace the current classroom cabin. The WCC will install 12 prefabricated camping huts for the popular "Sleeping with Wolves" event. Adjacent to the huts will be a composting toilet(s) comfort station for campers and also support for day visitors. Other renovations include the widening and repaving of Buck Run, construction of a guest parking area for cars and buses, pathways, installation of site lighting, construction of infrastructure improvements including storm water management measures, and underground utilities for the entire site.

### **Arrival/Parking/Accessibility**

The site plan which will be implemented as designed by Bibbo Engineering includes a bus turn around, drop off area and a 26-car visitor parking lot on the lowest portion of the property on the east side of Buck Run. This layout will allow multiple buses to make their way up a portion of the hill, park, and safely leave students and visitors with a paved walkway that leads up to the planned Educational Pavilion. Large delivery vehicles will also benefit from the new turn around access. Two ADA Handicapped parking spaces will be provided adjacent to the Educational Pavilion, and another ADA space closer to the wolf enclosures. The WCC will also provide guests who have limited abilities with a staff driven, ADA handicapped/wheelchair accessible golf cart for transfers around the property.

### **Green/Low Impact Design**

Sustainability is defined as the consumption of natural resources in a manner that ensures that the resource will not be permanently depleted or damaged. The WCC is committed to building facilities that employ 'green low-impact' solutions which will lengthen the useful life of individual buildings and lessen the campus' impact on the surrounding environment for future generations to enjoy. The concept of sustainable architecture is the design, construction and maintenance of buildings and sites in a way that maintains the regional natural resources and the quality of our surrounding environment.

The WCC's "green" approach will: Feature water efficiency through both selection of landscape design/material and low flow plumbing fixtures, utilize energy efficient mechanical and electrical systems, select materials that are produced

regionally, contain high recycled material content, and no VOCs, and utilize natural light and natural ventilation to minimizing fossil fuel energy needs. Site Design is the first step to a sustainable project. The landscape design will take into consideration limiting water consumption on campus by utilizing indigenous landscape materials that will require no or minimal irrigation once established over the first year. All building products will be designed with regional building materials wherever possible, a high level of recyclable building materials and no volatile organic compounds (VOC's). More specifically, the WCC is committed to use building techniques such as a 38kw photovoltaic (solar panel) system, ground source heat pumps (geothermal), direct on-demand hot water, touchless and low flow sinks and toilets, touchless air hand dryers, long lasting LED light fixtures, a green vegetative roof, a super insulated exterior wall envelope, and extensive use of materials with high recycled content and no VOC (volatile organic compounds). The Education Center has been positioned to face north on the southern sloped hill to limit the sun's impact on thermal gain which minimizes the demand of the mechanical cooling system. Facing north also provides for a use of soft natural daylight throughout the day.

**Education Pavilion:** The pavilion is the first stop for WCC Guests. The Pavilion consists of five main components:

- (1) Gift Shop/Reception – Used as described.
- (2) Extended Learning Hall/Gallery – This is a multifunctional space used for displaying exhibits, group gatherings, and more.
- (3) Classroom – This is the main space for educational presentations. Intended occupancy is consistent with our current programming at an attendance of 40-43 for general, 1.5-hour events.
- (4) Conference Hall – This building is separated from the three spaces listed above. It consists of a dedicated space for web conferencing and board/staff meetings. Other events to use the space would be birthday parties, small corporate retreats, or rented for other private parties. The building also has a small kitchenette that will provide support for events that require light snacks, pizza, ice cream, and drinks or for catering companies to use as staging and to reheat/keep warm prepared food during less frequent events such as a fundraising gala.
- (5) Amphitheater – Other than simply retaining the hillside it provides an outdoor learning area, staging area for larger school groups, and large event space.

**Trail System:** From the education pavilion, switch backing uphill through the forest, will be a new pathway for guests to safely walk to the wolf enclosures. The path will be constructed out of crushed rock “fines” providing a permeable, yet sure footed surface. As needed, precut stone steps will also be placed along the pathway. Steps are to remain as limited as possible. Along the entire pathway, cedar bollards with LED downlights to illuminate the pathway during evening events will be placed at roughly 20' intervals.

**Composting Toilet:** The WCC will construct a Clivus Multrum, two stall, composting toilet comfort station. The Comfort Station, designed by Centerbrook Architects, will support guests participating in “Sleeping with Wolves” events. Regular guests will also be encouraged to use the facility if they need a restroom while they are in the vicinity of the wolf enclosures. The building consists of two levels. At ground level (approaching from the downhill side) is a walkout basement that will contain the composting equipment, electrical service, water heater, and small water holding tank. Approaching from the north (or uphill), guests will be able to directly walk into one of two identical units. Each stall will have a foam flush toilet, sink, hand dryer, and a supply cabinet with countertop which may able be used as a baby changing table. The M35 system is the largest that is made by Clivus Multrum. The manufacturer suggests that the system be pumped by a septic company every two years if the composted material is not removed to be used as compost. The WCC's intent will be to pump the system every two years and/or if we are experiencing higher guest usage than expected.

**Camping Dens:** The most popular event offered to guests is the nocturnal overnight adventure, “Sleeping with Wolves.” For many seasons, the WCC has provided guests the opportunity to spend the night in a private party tent sleeping up to four people. As part of the proposed improvements, the WCC intends to install twelve (12) prefabricated units (10’x16’) manufactured by the Glamping Pods of America in southern Missouri. The pods (DENS) will provide sleeping quarters for up to four, electricity, lights, and heat & AC. The dens are configured into a horseshoe pattern where the rear of each unit faces a wolf enclosure. Construction is simple with the dens being prefabricated off-site. The dens will sit on concrete supports elevated off the ground. An underground electric supply will connect to each unit fed from the Comfort Station’s basement electrical supply.

**Animal Care/Cold Storage:** Constructed in the location of the WCC current 15’ x 30’ classroom will be a 16’x45’ rectangular building which will include a large walk-in freezer, small cooler, and a heated meat thawing room. There will also be a wash station with sinks and hoses to spray down the entire building. The floor offers a number of floor drains with material strainers to filter out any solid waste from making its way to the septic system. There is also an interior parking area for the food delivery vehicle. Although rectangular in footprint, the design of the building has been artistically created by Centerbrook Architects to somewhat mimic the shape of a wolf in a “lying down with head up” position. At the rear of the building is a covered set of stairs that leads to a second floor, unfinished storage area. The stairway also provides cover for the freezer mechanical systems.

**Buck Run: To Become ATKA’S WAY.** As part of the approvals process with the Town of Lewisboro, the WCC intends to rename the private roadway “Atka’s Way” after the fallen ambassador wolf, “Atka.” The entire private drive will be repaved with new asphalt and widened to accommodate two-way traffic. Storm water drainage has been engineered to accompany installation of the new roadway.

**Guest Parking:** The new guest parking lot will be constructed with a gravel substrate. There will be a total of 26 passenger car parking spaces. The parking area will also have a one-way bus loop into the main lot to drop off visitors to the Center. The one-way loop is intended primarily for daytime bus activity but can be utilized for material deliveries and special events as needed, or those that expect a larger audience where guests may be shuttled to the site from an offsite location. The parking and bus loop will have a number of LED downlights on 14’ wood poles to help guide guests during evening hours. The parking/road lighting will be controllable through various switches to turn on/off as needed. Evening programming (with the exception of campouts) typically concludes around 9pm during the summer months; the WCC will do its best to limit the use of these fixtures. The parking lot lights will also be fitted with light shields to keep light from extending into neighboring property.

**Site Electrical:** The WCC has determined that it is necessary to install the current and future electrical supply from Route 35 underground vs above using telephone poles. Today’s environmental climate, damaging storms, fire safety, and public safety were all factors in this decision.

**Current Structures/Features:** All other existing structures will retain their use as described on page #4.

## Wolf Conservation Center Public Events

Year	Number of Onsite Programs	Number of Guests
2018	542	15,749
2019	567	16,401
2020	129	2,766
2021	258	4,074
2022	515	14,192

### Onsite Programs:

Visit the Wolf Conservation Center (WCC) for a unique and educational experience! All of our education programs offer guests of all ages opportunities to not only learn about wolves but to see wolves too! Program lengths vary, but most generally run approximately 1.5 hours. All public visits are guided by a staff member and/or an approved volunteer. In addition to general public visits, the WCC hosts school children, special guest lectures, overnight adventures, birthday parties, summer camps, and private group visits.

The WCC's two 'ambassador wolves' reside on exhibit where they help teach the public about the importance and plight of wolves. To best prepare the critically endangered wolves who are candidates for wild-release, the center's approximately 20 Mexican gray wolves and 10 red wolves reside off exhibit within the WCC's Endangered Species Facility.

All visitors are required to pre-register for a program via the WCC website at [www.nywolf.org](http://www.nywolf.org) - simply click on the event of your choice on the **Program Calendar** for additional information and registration! Space is limited for all events. The WCC reserves the right to cancel and refund any program due to a lack of registrants. The WCC discourages walk in visitors.

**Visit limitations:** The WCC must self-regulate its visit schedule closely. Other events do need to occur on a daily to weekly schedule that do not include the public. The WCC attempts to perform any activity that can be described as “a distraction to a guest visit experience,” to be completed when the facility is closed to the public. Such events could include the feeding of the wolves or performing any property maintenance task. Most importantly, wolves need time to be wolves while not in the presence of people.

Looking beyond 2023, the WCC intends to provide the public with visit opportunities in the same manner as before. All visits will continue to require preregistration to a scheduled public event or to arrange a variety of private group experiences. The new and improved campus will provide more opportunities to increase visits to the Center. It is expected that the largest likely increase will come from weekday school groups due to the improved bus access and other facilities, as well as the WCC's increased exposure within the global community. The weekdays, however, are not just for public school groups. We also welcome senior citizens and people with disabilities, universities, West Point cadets, home schooled students, corporate retreats, service groups, “Sleeping with Wolves” participants, and more.

Historically, weekend visit opportunities have been extremely well attended by families, couples & individuals. Typically, during peak spring – fall seasons, each weekend provides six to eight public or private events scheduled throughout morning into the overnight. While there is not much room for additional weekend events during this time of the year to be scheduled, we expect that events will continue to meet maximum registration capacity.

Winter season is a great time to visit too. During winter, the typical weekend will provide four to six visit opportunities due to the shortened days and colder weather. School visits are less frequent than in spring and fall, but we welcome their registration. With the addition of the camping pods, winter time “Sleeping with Wolves” events will now be offered during colder months. The frequency of winter time SWW events is yet to be determined.

**WCC Sample of Events Offered: Unless otherwise noted, each event can be held any day of the week.**

**Wolves of North America** - Learn about the mythology, biology and ecology of wolf families and discover why it’s a special time for packs in North America. Whether the wolves are living on the Arctic tundra or the woodlands of the southwest, wolf families are out searching for prey as their pups grow bigger and bolder! Guests will visit Ambassador Wolves Silas & Nikai, and possibly the WCC’s endangered red wolves and Mexican gray wolves as well.

1.5-hour event. Target audience size: 40 people

**Pack Chat for Kids** - This is the best introduction to wolves for families with young children. Kids will learn about the mythology surrounding wolves and the important role of wolves in the natural world. This is an exciting time for wolves; they are out searching for prey as their pups grow bigger and bolder! Guests will visit Ambassador Wolves Nikai, and Silas, and possibly the WCC’s endangered red wolves and Mexican gray wolves as well. 1.5-hour event. Target audience size: 40 people

**Sleeping with Wolves** – This popular nocturnal adventure experience gives guests a chance to camp out overnight with the 40+ wolves that call the WCC home! With all the howls, circling vultures, and nature’s nighttime chatter, you’ll feel like you’re camping under the stars with wild wolves. Fun highlights include an education program, dinner, outdoor movie, campfires, and continental breakfast in the morning. 5pm-8:30am Maximum audience size: 48 people

**Summer Wolf Camp for Kids** - Give the young animal lover in your family a chance to thrive among wolves all week long! The five-day program will include opportunities for your child to learn about nature and wildlife through woodland exploration, scavenger hunts, wilderness games, live animals, etc. Children will learn about various habitats, animal communication and behavior, food chains, and local wildlife.

8:30am-3pm Monday-Friday Target audience size: 36 children

**Coffee with Wolves** - Enjoy your morning coffee with our wolves! Visitors are encouraged to bring their newspapers and spend a relaxing morning with our Ambassador and red wolves. We’ll provide the coffee... and the wolves! The wolves can be very active in the early morning, so we ask that visitors remain quiet and subdued, as this is a peaceful, private moment for all involved.

1-hour event. Target audience size: 12 people

**Full Moon Wolf Walk** - While enjoying nature’s chatter by the WCC’s outdoor fire pit, guests will enjoy seasonal treats and the symphony of howls from the wolves that call the WCC home. Guests will learn about the history of wolves in the United States, the importance of wolves in a healthy ecosystem, and the efforts to save these magnificent creatures for future generations. Guests will also take a short moonlit walk to visit Ambassador Wolves Silas and Nikai! Please bring flashlights.

1.5-hour event. Target audience size: 35.

**Photo Session** - Join us for this special opportunity to photograph the WCC's Ambassador Wolves: Nikai and Silas! Guests will also be given access to photograph the WCC's endangered Mexican wolves and red wolves from vantage points not generally available during regular visits.

2-hour event. Target audience size: 12 people

**Evening Howl for Adults Only** - Join us for a special Evening Howl and enjoy visiting the wolves during their favorite hour - dusk. Learn about the mythology, biology and ecology of wolves in North America while enjoying a lovely spread of wine and cheese. Guests will take a short sunset hike to howl with Ambassador wolves Nikai and Silas and potentially behold the WCC's critically endangered red wolves and Mexican wolves too. This program is for adults 21 years old and over.

1.5-hour event. Target audience size: 40 people

**Evening Howl for Pups of All Ages** - Enjoy visiting the wolves during their favorite hour - dusk. Learn about the mythology, biology and ecology of wolf families and discover why May is a magical time for packs in North America. Guests will take a short sunset hike to howl with Ambassador wolves Nikai and Silas and potentially behold the WCC's endangered red wolves and Mexican wolves. All guests will be served weather appropriate treats.

1.5-hour event. Target audience size: 40 people

**Coyotes: Behavior, Ecology, and Coexistence** - Join the Wolf Conservation Center (WCC) for a special program about our local cousin to the wolf – the Eastern Coyote. Learn more about their biology and behavior and ways to reduce or prevent problems from occurring between people, pets and coyotes. After the talk, guests will visit Ambassador wolves Nikai and Silas and will potentially behold the WCC's critically endangered red wolves.

1.5-hour event. Target audience size: 40 people

**Wildlife Explorers: After School Program** - Take a walk on the wild side and join us at the Wolf Conservation Center (WCC) as we explore the natural world and give the young animal lover in your family a chance to thrive among wolves and other woodland critters! The WCC's educational and interactive afterschool program encourages your child to embrace Nature's wild treasures and helps foster an understanding of the importance of healthy and balanced ecosystems. 1-hour event.

Target audience size: 12 students

**Birthday Parties** - After our informative introduction to wolves, we begin a wolf-related activity. Currently we offer the group an opportunity to give gifts to the ambassador wolves! Prior to visiting the wolves, the kids will assemble "enrichment boxes." We will supply all kinds of goodies (spices, old toys, feathers, fur etc.) for the kids to choose from and they can create custom made gifts for the wolves to enjoy! Once the boxes are completed, the birthday group will help throw the gifts into the wolves' enclosures. The group then returns to the classroom area for food, etc.

2-hour event. Target audience size: 15 children

**Private Group Visit** - These programs are one (1) hour in length, but they provide visitors with the opportunity to see the WCC's two ambassador wolves while learning about the history, biology, and ecology of wolves in North America. An emphasis is placed on recovery efforts for endangered red wolves and Mexican gray wolves; visitors even have the chance to potentially see some of these elusive wolves that reside at the WCC.

1-hour event. Typical Target audience size: up to 15 people

**School Field Trips** - Learn about North America's wildest residents - wolves - during an education session with a WCC wolf expert. Students will be exposed to the history, ecology, and biology of wolves, and will learn about the current challenges

facing wolf recovery across the United States. An emphasis will be placed on endangered species recovery programs for critically endangered red wolves and Mexican gray wolves. This program is suitable for students in elementary, middle, and high school and college, and can be tailored to meet specific course requirements.

1.5 hours. Target audience size: 45 students in one session/90 students in two sessions.

### **Offsite Programs**

The Wolf Conservation Center's offsite education programs are intended to supplement classroom-based lesson plans or serve as a stand-alone presentation, and offer an in-depth look at wolves and their ecological importance. Each program is 45 minutes in length (but can be adjusted if needed) and includes supplemental materials for students to complete both before and after the program (if desired), as a way to further their learning. The WCC offers four offsite education modules: Wolves of North America, Saving a Species, Animal Adaptations, Coyote Behavior, Ecology, and Coexistence. Program length varies. Target audience size: No limit

**Virtual Webinars** - Choose from a variety of program topics, ranging from animal adaptations to critically endangered wolf recovery efforts, and enjoy a 45-minute immersion into the wild world of wolves! Each program is intended to supplement classroom-based lesson plans and offer an in-depth look at wolves and their ecological importance. Programs are suitable for elementary – college aged students and align with various Next Generation Science Standards (NGSS).

Program length varies. Target audience size: 500 people

**Virtual Field Trips** - Our virtual field trips allow viewers to learn about the history and biology of wolves in North America and see the WCC's ambassador wolves. There's even a chance to potentially see endangered red wolves and Mexican gray wolves!

Program length varies. Target audience size: 500 people

**Virtual Birthday Parties** - These parties are approximately 45 minutes in length and attendees will see the WCC's ambassador wolves in live time; there's also the possibility of seeing two red wolves and two Mexican gray wolves! A WCC educator will also be on screen teaching the attendees about the wolves, guiding the children through creating presents for the wolves, and answering any questions they ask.

Program length varies. Target audience size: 100 people


**Virtual Corporate Retreats** - Learn about the importance of teamwork and adapting to constantly-changing environments using wolves as examples! Attendees will enjoy a live session featuring the WCC's ambassador wolves and a WCC educator; a potential sighting of some of the WCC's endangered red wolves and Mexican gray wolves is also possible.

Program length varies. Target audience size: 100 people



# WOLF CONSERVATION CENTER

## BUCK RUN, SOUTH SALEM, NY WESTCHESTER COUNTY, NY



LOCATION MAP  
1" = 200'

### PLAN SET (LIST OF DRAWINGS) PLANS PROVIDED BY BIBBO ASSOCIATES, LLP.

#### DRAWING INDEX:

SHT #	DWG I.D.	TITLE
1	CS-1	COVER SHEET
2	PP-1	PRELIMINARY PLOT PLAN
3	EX-1	EXISTING CONDITIONS PLAN
4	EX-2	REMOVALS PLAN
5	LP-1	LAYOUT PLAN - SOUTH
6	LP-2	LAYOUT PLAN - NORTH
7	CP-1	CONSTRUCTION PLAN - SOUTH
8	CP-2	CONSTRUCTION PLAN - NORTH
9	EC-1	EROSION CONTROL PLAN
10	EC-2	EROSION CONTROL NOTES AND DETAIL
11	P-1	ROAD PROFILES
12	P-2	DRAINAGE PROFILES
13	T-1	TURNING MANEUVERS
14	SD-1	SIGHT DISTANCE & PROFILES
15	M-1	MITIGATION PLAN
16	LP-1	LIGHTING PLAN
17	D-1	DETAILS
18	D-2	DETAILS
19	D-3	DETAILS
20	D-4	DETAILS

#### SITE DATA

- TOTAL AREA OF PARCELS: 118.907 AC±
- OWNER AND APPLICANT:  
WOLF CONSERVATION CENTER  
7 BUCK RUN  
SOUTH SALEM, NY 10590
- ZONING DISTRICT(S): R-4A and R-2A
- SURVEY BY:  
INSITE ENGINEERING, SURVEYING  
& LANDSCAPE ARCHITECTURE, P.C.  
3 GARRETT PLACE  
CARMEL, NY 10512
- TAX ID #:  
SHEET 21  
BLOCK 10803  
LOT 3, 65, 67, 81, 82, 83, 84, 86 & 88

11-28-23	PLANNING BOARD SUBMISSION	RH/MG	01-16-23	BUILDING DEPARTMENT COMMENTS	RH/MG
10-20-23	NYCDEP COMPLETENESS COMMENTS	RH/MG	02-07-22	WCHD NYCDEP COMMENTS	ZF/ED
04-25-23	PLANNING BOARD SUBMISSION	RH/MG	06-04-21	NYCDEP APPLICATION	RH/MG
02-07-23	PLANNING BOARD SUBMISSION	RH/MG	04-27-21	PLANNING BOARD SUBMISSION	RH/MG
DATE:	DESCRIPTION	BY/CK	DATE:	DESCRIPTION	BY/CK



#### COVER SHEET

**WOLF CONSERVATION CENTER**  
7 BUCK RUN, SOUTH SALEM, NY 10590  
TOWN OF LEWISBORO, WESTCHESTER COUNTY, NY

**BIBBO ASSOCIATES, LLP**  
293 ROUTE 100 SUITE 203  
SOMERS, NEW YORK 10589  
TEL. 914 277 5805

DATE: 12-29-2020  
SCALE: 1" = 100'  
FILE: L5  
DSGN / CHK: MG/RH  
DRN. BY: RH  
SHT NO. 1 OF 20  
DWG NO. **CS-1**

#### PROJECT TEAM:

**OWNER/APPLICANT**  
WOLF CONSERVATION CENTER  
7 BUCK RUN  
SOUTH SALEM, NY 10590  
(914) 763-2373  
CONTACT: SPENCER WILHELM


**CIVIL ENGINEERING**  
BIBBO ASSOCIATES, LLP  
293 ROUTE 100, SUITE 203  
SOMERS, NY 10589  
(914) 277-5805  
CONTACT: MATTHEW J. GIRONDA, P.E.

**ENVIRONMENTAL/WETLAND**  
EVANS ASSOCIATES ENVIRONMENTAL  
CONSULTING, INC.  
205 AMITY ROAD  
BETHANY, CT 06524  
(203) 393-0690  
CONTACT: BETH EVANS, PWS

**SURVEYOR**  
INSITE ENGINEERING, SURVEYING, &  
LANDSCAPE ARCHITECTURE, P.C.  
3 GARRETT PLACE  
CARMEL, NY 10512  
(845) 225-9690  
CONTACT: JEFFREY DEROSA, LS

**ARCHITECT**  
**(FOR EDUCATION PAVILION)**  
KG+D ARCHITECTS  
285 MAIN STREET  
MT. KISCO, NY 10549  
(914) 666-5900  
CONTACT: ERIK KAEYER, AIA

**(FOR COMPOST RESTROOM & FREEZER FACILITIES)**  
CENTERBROOK  
ARCHITECTS AND PLANNERS, LLP.  
67 MAIN STREET  
CENTERBROOK, CT 06409  
(860) 767-0175



**PLAN**  
GRAPHIC SCALE



1 inch = 100 ft

UNAUTHORIZED ALTERATIONS AND ADDITIONS  
TO THIS DRAWING IS A VIOLATION OF  
SECTION 2209 (2) OF THE NEW YORK STATE  
EDUCATION LAW.  
COPYRIGHT © 2023 BIBBO ASSOCIATES, LLP  
ALL RIGHTS RESERVED. UNAUTHORIZED  
DUPLICATION IS A VIOLATION OF  
APPLICABLE LAW.



CALL BEFORE YOU DIG 1-800-962-7962

- UNDER THE NY STATE LAW PROTECTING UNDERGROUND FACILITIES,  
THE FOLLOWING RULES AND REGULATIONS ARE IN EFFECT FOR ALL  
EXCAVATORS:
- THEY MUST CALL FOR A UTILITY STAKE-OUT (2) TWO FULL WORKING DAYS  
PRIOR TO AN EXCAVATION.
  - THEY MUST CONFIRM PRECISE LOCATIONS OF UNDERGROUND FACILITIES.
  - THEY MUST PRESERVE STAKES AND MARKINGS UNTIL NO LONGER NEEDED AT SITE.
  - THEY MUST CONTACT NON-UPFO MEMBER UTILITY OWNERS FOR STAKE-OUTS.



GENERAL NOTES:

- EXISTING PROPERTY BOUNDARIES AND SITE FEATURES SHOWN HEREON FOR ARE BASED ON THE FOLLOWING:  
  
"SURVEY OF PROPERTY", DATED JUNE 12, 2017, PREPARED BY INSITE ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C.  
  
"SUBDIVISION MAP", DATED JULY 21, 2015, PREPARED BY INSITE ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C.  
  
"SURVEY OF PROPERTY" PREPARED FOR 1 BUCK RUN, DATED SEPTEMBER 25, 2018, PREPARED BY INSITE ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C.
- EXISTING SUBSURFACE SEWAGE TREATMENT SYSTEM LOCATIONS SHOWN HEREON OBTAINED FROM SSTS AS-BUILT PLANS ON FILE WITH THE WESTCHESTER COUNTY HEALTH DEPARTMENT.
- EXISTING TOPOGRAPHY SHOWN HEREON IS BASED ON TOPOGRAPHIC MAP PREPARED BY INSITE ENGINEERING, SURVEYING & LANDSCAPE ARCHITECTURE, P.C., DATED NOVEMBER 21, 2018. ELEVATIONS CONFORM TO NORTH AMERICAN VERTICAL DATUM 1929 (N.A.V.D. 29).
- PRIOR TO EXCAVATION THE CONTRACTOR SHALL BE RESPONSIBLE TO TO OBTAIN A MARKOUT OF ALL SUBSURFACE UTILITIES WITHIN THE WORK ZONE. THE CONTRACTOR SHALL CONTACT THE DESIGN ENGINEER UPON VERIFICATION OF EXISTING UTILITY LOCATIONS TO DETERMINE IF FIELD CHANGES ARE REQUIRED.



CALL BEFORE YOU DIG 1-800-962-7962

- UNDER THE NY STATE LAW PROTECTING UNDERGROUND FACILITIES, THE FOLLOWING RULES AND REGULATIONS ARE IN EFFECT FOR ALL EXCAVATORS:
- THEY MUST CALL FOR A UTILITY STAKE-OUT (2) TWO FULL WORKING DAYS PRIOR TO AN EXCAVATION.
  - THEY MUST CONFIRM PRECISE LOCATIONS OF UNDERGROUND FACILITIES.
  - THEY MUST PRESERVE STAKES AND MARKINGS UNTIL NO LONGER NEEDED AT SITE.
  - THEY MUST CONTACT NON-UPCO MEMBER UTILITY OWNERS FOR STAKE-OUTS.

LEGEND

- EXISTING PROPERTY LINE  
WETLAND BUFFER LINE  
WETLAND BOUNDARY LINE  
EXISTING WOLF ENCLOSURE FENCE  
EXISTING EASEMENT LINE  
EXISTING ZONING BOUNDARY

UNAUTHORIZED ALTERATIONS AND ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 2209 (2) OF THE NEW YORK STATE EDUCATION LAW.  
COPYRIGHT © 2023 BIBBO ASSOCIATES, LLP  
ALL RIGHTS RESERVED. UNAUTHORIZED REPRODUCTION IS A VIOLATION OF APPLICABLE LAW.



PRELIMINARY SUBDIVISION PLAN

**WOLF CONSERVATION CENTER**  
7 BUCK RUN, SOUTH SALEM, NY 10690  
TOWN OF LEWISBORO, WESTCHESTER COUNTY, NY

**BIBBO ASSOCIATES, LLP**  
293 ROUTE 100 SUITE 203  
SONNERS, NEW YORK 10589  
TEL. 914.277.5805

DATE: 12-29-2020  
SCALE: 1" = 100'  
FILE: L5  
DSGN / CHK: MG/RH  
DRN. BY: RH  
SHT NO. 2 OF 20  
DWG NO. **PP-1**

11-28-23	PLANNING BOARD SUBMISSION	RH/MG	01-16-23	BUILDING DEPARTMENT COMMENTS	RH/MG
10-20-23	NYCDEP COMPLETENESS COMMENTS	RH/MG	02-07-22	WCHD NYCDEP COMMENTS	ZF/ED
04-25-23	PLANNING BOARD SUBMISSION	RH/MG	06-04-21	NYCDEP APPLICATION	RH/MG
02-07-23	PLANNING BOARD SUBMISSION	RH/MG	04-27-21	PLANNING BOARD SUBMISSION	RH/MG
DATE:	DESCRIPTION	BY/CK	DATE:	DESCRIPTION	BY/CK



EXISTING CONDITIONS PLAN 1/22/2023 12:46:07 PM

#### LEGEND

EXISTING PROPERTY LINE	—————
WETLAND BUFFER LINE	- - - - -
WETLAND BOUNDARY LINE	- - - - -
EXISTING WOLF ENCLOSURE FENCE	- x - x - x - x -
EXISTING EASEMENT LINE	- - - - -
EXISTING 2' CONTOUR	————— 2
EXISTING 10' CONTOUR	————— 10



TREE CHART			
TREE #	DIAMETER	SPECIES	STATUS
1	10"	SPRUCE	
2	12"	PINE	
3	14" & 16"	BURCH	
4	12" & 16"	HEMLOCK	
5	8"	TULIP	
6	22"	SPRUCE	
7	12", 14" & 16"	HEMLOCK	
8	10"	ELM	
9	8"	MAPLE	
10	6"	MAPLE	
11	12" & 18"	MAPLE	
12	6"	MAPLE	
13	6"	LOCUST	
14	28"	MAPLE	TBR
15	28"	LOCUST	TBR
16	12"	MAPLE	TBR
17	14"	CHERRY	TBR
18	8"	MAPLE	TBR
19	10"	MAPLE	TBR
20	6"	MAPLE	TBR
21	6" TW, 5" & 3"	MAPLE	TBR
22	10"	MAPLE	TBR
23	36"	MAPLE	TBR
24	38"	MAPLE	TBR
25	14" & 5"	MAPLE	TBR
26	8"	MAPLE	TBR
27	14"	MAPLE	TBR
28	16"	LOCUST	TBR
29	6"	MAPLE	TBR
30	14" & 8"	MAPLE	TBR
31	12"	MAPLE	TBR
32	8"	MAPLE	TBR
33	30"	MAPLE	TBR
34	12"	CHERRY	TBR
35	6"	MAPLE	TBR
36	10"	MAPLE	TBR
37	10"	MAPLE	TBR
38	30"	MAPLE	TBR
39	38"	MAPLE	TBR
40	6"	MAPLE	TBR
41	36"	MAPLE	TBR
42	30"	MAPLE	TBR
43	28"	MAPLE	TBR
44	18"	MAPLE	TBR
45	12"	MAPLE	TBR
46	36"	MAPLE	TBR
47	12"	MAPLE	
48	36"	MAPLE	
49	12"	LOCUST	TBR
50	6"	LOCUST	
51	12"	LOCUST	TBR
52	4"	MAPLE	
53	6"	MAPLE	TBR
54	6" & 10"	MAPLE	TBR
55	6"	MAPLE	TBR
56	16"	MAPLE	TBR
57	12"	MAPLE	TBR
58	12"	MAPLE	TBR
59	12"	MAPLE	TBR
60	24"	MAPLE	TBR
61	10"	MAPLE	TBR
62	24"	MAPLE	TBR
63	26"	MAPLE	TBR
64	16"	MAPLE	TBR
65	12"	MAPLE	TBR
66	10"	MAPLE	TBR
67	14"	MAPLE	TBR
68	6"	MAPLE	TBR
69	18"	MAPLE	TBR
70	14"	MAPLE	TBR
71	16"	MAPLE	TBR
72	6"	MAPLE	TBR
73	16"	MAPLE	TBR
74	12"	MAPLE	TBR
75	14"	MAPLE	TBR
76	22"	MAPLE	TBR
77	12", 24" & 28"	MAPLE	TBR
78	14"	MAPLE	TBR
79	16"	MAPLE	TBR
80	8"	MAPLE	TBR
81	16"	MAPLE	TBR
82	22"	MAPLE	TBR
83	UNIDENTIFIED	UNKNOWN	TBR
84	22"	MAPLE	TBR
85	22"	MAPLE	TBR
86	224"	ASH	TBR
87	18"	MAPLE	TBR
88	8"	ELM	TBR
89	10"	ELM	TBR
90	6"	ELM	TBR
91	18"	ASH	TBR
92	16"	ASH	TBR
93	16"	MAPLE	TBR
94	26"	ASH	TBR
95	16"	MAPLE	TBR
96	26"	ASH	TBR


TREE CHART			
TREE #	DIAMETER	SPECIES	STATUS
97	10"	ELM	TBR
98	6"	LOCUST	TBR
99	6"	ELM	TBR
100	24"	MAPLE	TBR
101	26"	MAPLE	TBR
102	6"	LOCUST	TBR
103	14"	MAPLE	TBR
104	6"	ELM	TBR
105	26"	MAPLE	TBR
106	10"	MAPLE	TBR
107	6"	ELM	TBR
108	8"	ELM	TBR
109	6"	MAPLE	
110	6"	MAPLE	
111	18"	MAPLE	
112	28"	MAPLE	
113	14"	MAPLE	TBR
114	10"	ELM	TBR
115	16"	MAPLE	
116	14"	MAPLE	
117	6" & 4"	MAPLE	
118	24"	ASH	
119	22"	OAK	TBR
120	22"	MAPLE	
121	24"	LOCUST	
122	12"	MAPLE	
123	16"	MAPLE	
124	10"	MAPLE	TBR
125	6"	MAPLE	TBR
126	16"	MAPLE	TBR
127	14"	MAPLE	TBR
128	14"	MAPLE	
129	24" & 12"	MAPLE	
130	8"	HICKORY	
131	26"	MAPLE	
132	6"	MAPLE	
133	14"	HICKORY	
134	10" & 10"	HICKORY	
135	20"	OAK	
136	14"	MAPLE	
137	N/A	UNKNOWN	
138	12"	OAK	
139	12"	OAK	
140	6"	MAPLE	
141	14"	ASH	
142	14"	MAPLE	
143	6" & 4"	MAPLE	
144	6"	MAPLE	
145	6"	MAPLE	
146	12"	WALNUT	
147	28"	WALNUT	
148	8"	SPRUCE	
149	24"	MAPLE	
150	24"	HICKORY	
151	6"	MAPLE	
152	16"	ELM	
153	6"	MAPLE	
154	14" & 16"	HICKORY	
155	14" & 16"	HICKORY	
156	34"	OAK	
157	12"	MAPLE	
158	12"	MAPLE	
159	8"	MAPLE	
160	22"	MAPLE	
161	12"	MAPLE	
162	10"	MAPLE	
163	14"	OAK	
164	6"	OAK	
165	14"	OAK	
166	12"	OAK	
167	22"	MAPLE	
168	20"	MAPLE	
169	32"	HICKORY	
170	24"	OAK	
171	26"	OAK	
172	16"	MAPLE	
173	14"	LOCUST	
174	24"	MAPLE	
175	14"	MAPLE	TBR
176	20"	MAPLE	
177	12"	LOCUST	
178	14"	MAPLE	
179	16"	MAPLE	
180	26"	MAPLE	
181	24"	LOCUST	
182	6"	CHERRY	
183	12"	LOCUST	
184	14"	MAPLE	TBR
185	14"	MAPLE	
186	24"	MAPLE	
187	14"	HICKORY	TBR
188	24"	OAK	TBR
189	12"	CHERRY	
190	6"	CHERRY	
191	6"	CHERRY	
192	12"	CHERRY	TBR

TREE CHART			
TREE #	DIAMETER	SPECIES	STATUS
193	10"	MAPLE	TBR
194	16"	MAPLE	
195	14"	LOCUST	TBR
196	16"	LOCUST	TBR
197	14"	LOCUST	TBR
198	22"	MAPLE	
199	18"	LOCUST	TBR
200	22"	CHERRY	TBR
201	16"	LOCUST	
202	6"	HICKORY	
203	18"	LOCUST	
204	24"	MAPLE	TBR
205	22"	OAK	
206	10"	LOCUST	
207	26"	OAK	
208	16"	OAK	
209	28"	WALNUT	
210	26"	OAK	
211	20"	CHERRY	
212	26"	OAK	
213	16"	OAK	
214	16"	MAPLE	
215	8"	MAPLE	
216	24"	MAPLE	
217	14"	MAPLE	TBR
218	12"	MAPLE	TBR
219	12"	MAPLE	TBR
220	12"	MAPLE	
221	6"	MAPLE	
222	12"	MAPLE	TBR
223	38"	OAK	TBR
224	14"	MAPLE	TBR
225	18"	MAPLE	TBR
226	14"	MAPLE	TBR
227	14"	MAPLE	TBR
228	28"	OAK	TBR
229	16"	MAPLE	TBR
230	22"	MAPLE	TBR
231	10"	MAPLE	TBR
232	18"	MAPLE	TBR
233	14"	MAPLE	
234	28"	MAPLE	TBR
235	12"	ASH	TBR
236	16"	OAK	
237	16"	OAK	TBR
238	12"	MAPLE	TBR
239	16"	MAPLE	TBR
240	14"	MAPLE	TBR
241	24"	ASH	TBR
242	14"	MAPLE	
243	20"	MAPLE	TBR
244	26"	MAPLE	TBR
245	8"	MAPLE	TBR
246	18"	ASH	TBR
247	12"	MAPLE	TBR
248	16"	MAPLE	TBR
249	28"	MAPLE	TBR
250	10"	DOGWOOD	TBR
251	14"	SPRUCE	
252	24"	MAPLE	
253	6"	MAPLE	
254	4"	SPRUCE	TBR
255	16"	SPRUCE	TBR
256	4"	SPRUCE	TBR
257	16"	MAPLE	TBR
258	12"	SPRUCE	
259	8"	SPRUCE	
260	8"	SPRUCE	
261	10"	SPRUCE	
262	16"	SPRUCE	TBR
263	24"	OAK	
264	N/A	HOLLY	
265	8"	LOCUST	TBR

#### CALL BEFORE YOU DIG 1-800-962-7962

UNDER THE NY STATE LAW PROTECTING UNDERGROUND FACILITIES, THE FOLLOWING RULES AND REGULATIONS ARE IN EFFECT FOR ALL EXCAVATORS:

- THEY MUST CALL FOR A UTILITY STAKE-OUT (2) TWO FULL WORKING DAYS PRIOR TO AN EXCAVATION.
- THEY MUST CONFIRM PRECISE LOCATIONS OF UNDERGROUND FACILITIES.
- THEY MUST PRESERVE STAKES AND MARKINGS UNTIL NO LONGER NEEDED AT SITE.
- THEY MUST CONTACT NON-UPFO MEMBER UTILITY OWNERS FOR STAKE-OUTS.



#### EXISTING CONDITIONS PLAN

**WOLF CONSERVATION CENTER**  
7 BUCK RUN, SOUTH SALEM, NY 10589  
TOWN OF LEWISBORO, WESTCHESTER COUNTY, NY

**BIBBO ASSOCIATES, LLP**  
293 ROUTE 100 SUITE 203  
SONEN, NEW YORK 10589  
TEL. 914 277 5805

DATE: 12-29-2020

SCALE: 1" = 60'

FILE: L5

DSGN / CHK: MG/RH

DRN. BY: RH

SHT NO. 3 OF 20

DWG NO.

**EX-1**

11-28-23	PLANNING BOARD SUBMISSION	RH/MG	01-16-23	BUILDING DEPARTMENT COMMENTS	RH/MG
10-20-23	NYCDEP COMPLETENESS COMMENTS	RH/MG	02-07-22	WCHD NYCDEP COMMENTS	ZFED
04-25-23	PLANNING BOARD SUBMISSION	RH/MG	06-04-21	NYCDEP APPLICATION	RH/MG
02-07-23	PLANNING BOARD SUBMISSION	RH/MG	04-27-21	PLANNING BOARD SUBMISSION	RH/MG
DATE:	DESCRIPTION	BY/CK	DATE:	DESCRIPTION	BY/CK



**LEGEND**


EXISTING PROPERTY LINE

WETLAND BUFFER LINE

WETLAND BOUNDARY LINE


EXISTING WOLF ENCLOSURE FENCE




EXISTING EASEMENT LINE



UNDER THE NY STATE LAW PROTECTING UNDERGROUND FACILITIES,  
THE FOLLOWING RULES AND REGULATIONS ARE IN EFFECT FOR ALL  
EXCAVATORS:

- \* THEY MUST CALL FOR A UTILITY STAKE-OUT (2) TWO FULL WORKING DAYS PRIOR TO AN EXCAVATION.
- \* THEY MUST CONFIRM PRECISE LOCATIONS OF UNDERGROUND FACILITIES.
- \* THEY MUST PRESERVE STAKES AND MARKINGS UNTIL NO LONGER NEEDED AT SITE
- \* THEY MUST CONTACT NON-UFPO MEMBER UTILITY OWNERS FOR STAKE-OUTS.

 MATTHEW J. GRONDA P.E.	<b>EXISTING CONDITIONS &amp; REMOVALS PLAN</b>		DATE: 12-29-2020 SCALE: 1" = 60'
	<b>WOLF CONSERVATION CENTER</b> 7 BUCK RUN, SOUTH SALEM, NY 10590 TOWN OF LEWISBORO, WESTCHESTER COUNTY, NY		FILE: L5 DSGN / CHK: MKR/RH DRN. BY: RH
	 <b>BIBBO ASSOCIATES, LLP</b> 293 ROUTE 100 SUITE 203 SOMERS, NEW YORK 10589 TEL. 914-277 5805	SHT NO. 4 OF 20 DWG. NO. <b>EX-2</b>	




LEGEND			
EXISTING PROPERTY LINE	---		
WETLAND BUFFER LINE	- - - - -		
WETLAND BOUNDARY LINE	----		
EXISTING WOLF ENCLOSURE FENCE	- x - x - x -		
EXISTING EASEMENT LINE	- - - - -		
PROPOSED RETAINING WALL	=====		
PROPOSED ELECTRIC METER	[M]		
PROPOSED TRANSFORMER	[T]		
PROPOSED T-TAP	[TT]		
PROPOSED OVERHEAD ELECTRIC SERVICE	--- OHW --- OHW ---		
PROPOSED UNDERGROUND ELECTRIC SERVICE	- E - E - E - E -		
PROPOSED ROOF LEADER CONNECTION PIPE	- RD - RD - RD - RD -		
PROPOSED PVC DR-18 WATERMAIN	- W - W - W - W -		
PROPOSED CU WATER SERVICE	- WS - WS - WS - WS -		

CALL BEFORE YOU DIG 1-800-962-7962


UNDER THE NY STATE LAW PROTECTING UNDERGROUND FACILITIES, THE FOLLOWING RULES AND REGULATIONS ARE IN EFFECT FOR ALL EXCAVATORS:

- THEY MUST CALL FOR A UTILITY STAKE-OUT (2) TWO FULL WORKING DAYS PRIOR TO AN EXCAVATION.
- THEY MUST CONFIRM PRECISE LOCATIONS OF UNDERGROUND FACILITIES.
- THEY MUST PRESERVE STAKES AND MARKINGS UNTIL NO LONGER NEEDED AT SITE.
- THEY MUST CONTACT NON-UPPO MEMBER UTILITY OWNERS FOR STAKE-OUTS.



UNAUTHORIZED ALTERATIONS AND ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 2209 (2) OF THE NEW YORK STATE EDUCATION LAW.

COPYRIGHT © 2023 BIBBO ASSOCIATES, LLP ALL RIGHTS RESERVED. UNAUTHORIZED REPRODUCTION IS A VIOLATION OF APPLICABLE LAW.



**LAYOUT PLAN - SOUTH**

**WOLF CONSERVATION CENTER**

7 BUCK RUN, SOUTH SALEM, NY 10580  
TOWN OF LEVISTOWN, WESTCHESTER COUNTY, NY

**BIBBO ASSOCIATES, LLP**

293 ROUTE 100 SUITE 203  
SOMERS, NEW YORK 10589  
TEL. 914 277 5805

DATE: 12-29-2020  
SCALE: 1" = 30'  
FILE: L5  
DSGN / CHK: MGRH  
DRN. BY: RH  
SHT NO. 5 OF 20  
DWG NO. **LP-1**



EXISTING PROPERTY LINE

WETLAND BUFFER LINE

WETLAND BOUNDARY LINE

EXISTING WOLF ENCLOSURE FENCE

EXISTING EASEMENT LINE

PROPOSED RETAINING WALL

PROPOSED ELECTRIC METER

PROPOSED TRANSFORMER

PROPOSED T-TAP




OVERHEAD ELECTRIC SERVICE

UNDERGROUND ELECTRIC SERVICE


ROOF LEADER CONNECTION PIPE

PROPOSED PVC DR-18 WATERMAIN

PROPOSED CU WATER SERVICE



GRAPHIC SCALE




UNDER THE NY STATE LAW PROTECTING UNDERGROUND FACILITIES,  
THE FOLLOWING RULES AND REGULATIONS ARE IN EFFECT FOR ALL  
EXCAVATORS:

- \* THEY MUST CALL FOR A UTILITY STAKE-OUT (2) TWO FULL WORKING DAYS  
PRIOR TO AN EXCAVATION.
- \* THEY MUST CONFIRM PRECISE LOCATIONS OF UNDERGROUND FACILITIES.
- \* THEY MUST PRESERVE STAKES AND MARKINGS UNTIL NO LONGER NEEDED AT SITE.
- \* THEY MUST CONTACT NON-UFO MEMBER UTILITY OWNERS FOR STAKE-OUTS.

REVISIONS:	11-29-23	PLANNING BOARD SUBMISSION	RH/MG	01-16-23	BUILDING DEPARTMENT COMMENTS	RH/MG
	10-20-23	NYCDEP COMPLETENESS COMMENTS	RH/MG	02-07-22	WCHD NYCDEP COMMENTS	ZF/ED
	04-25-23	PLANNING BOARD SUBMISSION	RH/MG	06-04-21	NYCDEP APPLICATION	RH/MG
	02-07-23	PLANNING BOARD SUBMISSION	RH/MG	04-27-21	PLANNING BOARD SUBMISSION	RH/MG
	DATE:	DESCRIPTION	BY/CK	DATE:	DESCRIPTION	BY/CK



**WOLF CONSERVATION CENTER**  
7 BUCK RUN, SOUTH SALEM, NY 10590  
TOWN OF LEWISBORO, WESTCHESTER COUNTY, NY



**BIBBO ASSOCIATES, LLP**  
293 ROUTE 100 SUITE 203  
SOMERS, NEW YORK 10589  
TEL. 914 277 5805


DWG  
117

**LP-2**

UNAUTHORIZED ALTERATIONS AND ADDITIONS  
TO THIS DRAWING IS A VIOLATION OF  
SECTION 7209 (2) OF THE NEW YORK STATE  
EDUCATION LAW.

COPYRIGHT © 2023 BIRRO ASSOCIATES, LLP






BIBBO ASSOCIATES, LLP			
Consulting Engineers			
Project: Wolf Conservation Center			
Feature: Deep Test Results			
Sheet: 1 of 2		Revised By: Matthew Gronda	
		Date: May 25, 2021	
Test ID	TP #1	Test ID	TP #3
Depth:	Description:	Depth:	Description:
0-24"	Top Soil	0-18"	Top Soil
24"-96"	Light Brown Fine Sandy Loam	18"-30"	Red/Brown Fine Sandy Loam
96"-96"	Dark Brown Fine Sandy Loam	30"-104"	Brown Medium/Fine Sand
	No Rock		w/ Silt and Cobble
	No Rock		No Rock
	or Water at Full Depth		or Water at Full Depth
Test ID	TP #2	Test ID	TP #4
Depth:	Description:	Depth:	Description:
0-24"	Top Soil	0-18"	Top Soil
24"-96"	Red/Brown Fine Sandy Loam	18"-30"	Red/Brown Fine Sandy Loam
96"-96"	Brown Fine/Medium Sand	30"-104"	Brown Medium/Fine Sand w/ Silt and Cobble
	No Rock		traces of Silt and some cobble
	or Water at Full Depth		or Water at Full Depth

- SOS LEGEND**
- PROPOSED 1500 GAL. PVC CONCRETE SEPTIC TANK (SEE DETAIL)
  - PROPOSED 1000 GAL. PVC CONCRETE PUMP CHAMBER (SEE DETAIL)
  - PROPOSED 2" POLY FORCEMAIN (SEE DETAIL)
  - PROPOSED CONCRETE DISTRIBUTION BOX (SEE DETAIL)
  - REPLACE JUNCTION BOX #1-3 (SEE DETAIL)
  - REBUILD ENTIRE TRENCH #1 (SEE DETAIL)

BIBBO ASSOCIATES, LLP			
Consulting Engineers			
Project: Wolf Conservation Center			
Feature: Infiltration Test Results			
Sheet: 2 of 2		Revised By: Matthew Gronda	
		Date: May 25, 2021	
Test ID	Time Start	Time Stop	Depth to Water
ET 1	1:30:00 AM	11:30:00 AM	48.00
	1:30:00 AM	11:30:00 AM	48.00
	1:30:00 AM	11:30:00 AM	48.00
	1:30:00 AM	11:30:00 AM	48.00
ET 2	1:30:00 PM	1:42:00 PM	48.00
	1:30:00 PM	1:42:00 PM	48.00
	1:30:00 PM	1:42:00 PM	48.00
	1:30:00 PM	1:42:00 PM	48.00
ET 3	1:30:00 PM	1:42:00 PM	48.00
	1:30:00 PM	1:42:00 PM	48.00
	1:30:00 PM	1:42:00 PM	48.00
	1:30:00 PM	1:42:00 PM	48.00
ET 4	1:30:00 PM	1:42:00 PM	48.00
	1:30:00 PM	1:42:00 PM	48.00
	1:30:00 PM	1:42:00 PM	48.00
	1:30:00 PM	1:42:00 PM	48.00

- LEGEND**
- EXISTING PROPERTY LINE
  - PROPOSED PROPERTY LINE
  - WETLAND BUFFER LINE
  - WETLAND BOUNDARY LINE
  - EXISTING WOLF ENCLOSURE FENCE
  - EXISTING EASEMENT LINE
  - EXISTING 2' CONTOUR
  - EXISTING 10' CONTOUR
  - PROPOSED 2' CONTOUR
  - PROPOSED 10' CONTOUR
  - PROPOSED RETAINING WALL
  - PROPOSED ELECTRIC METER
  - PROPOSED TRANSFORMER
  - PROPOSED T-TAP
  - PROPOSED OVERHEAD ELECTRIC SERVICE
  - PROPOSED UNDERGROUND ELECTRIC SERVICE
  - PROPOSED ROOF LEADER CONNECTION PIPE
  - PROPOSED PVC DR-18 WATERMAIN
  - PROPOSED CU WATER SERVICE




DRAINAGE SCHEDULE			
NAME	RIM	PIPES IN:	PIPES OUT:
CB 1	552.37		15" HDPE INV. OUT =549.35 (TO CB 2) L = 9.9', S = 0.81%
CB 2	552.49	15" HDPE INV. IN =549.25 (FROM CB 1) L = 9.9', S = 0.81%	15" HDPE INV. OUT =548.02 (TO DMH 1) L = 95.0', S = 20.00%
CB 3	521.39		15" HDPE INV. OUT =516.46 (TO CB 4) L = 9.9', S = 0.98%
CB 4	521.02	15" HDPE INV. IN =516.18 (FROM DMH 1) L = 99.6', S = 10.00% 15" HDPE INV. IN =516.34 (FROM CB 3) L = 9.9', S = 0.98%	15" HDPE INV. OUT =516.18 (TO CB 19) L = 73.1', S = 15.00%
CB 5	494.25		15" HDPE INV. OUT =490.50 (TO CB 6) L = 16.1', S = 7.67%
CB 6	493.96	15" HDPE INV. IN =489.05 (FROM CB 5) L = 16.1', S = 7.67% 15" HDPE INV. IN =489.09 (FROM CB 19) L = 123.2', S = 12.80%	15" HDPE INV. OUT =487.80 (TO DMH 7) L = 102.4', S = 14.00%
CB 7	472.11	15" HDPE INV. IN =467.00 (FROM DMH 7) L = 41.9', S = 14.00% 15" HDPE INV. IN =466.93 (FROM CB 8) L = 19.1', S = 1.01%	15" HDPE INV. OUT =466.94 (TO DIV MH 1.2) L = 81.1', S = 1.00%
CB 8	470.34		15" HDPE INV. OUT =467.16 (TO CB 7) L = 19.1', S = 1.01%
CB 9	467.50		15" HDPE INV. OUT =463.50 (TO DMH 2) L = 75.8', S = 9.43%
CB 10	465.99		15" HDPE INV. OUT =461.00 (TO CB 12) L = 68.9', S = 10.80%
CB 11	456.48		15" HDPE INV. OUT =453.82 (TO CB 12) L = 21.4', S = 0.90%
CB 12	456.28	15" HDPE INV. IN =453.40 (FROM CB 10) L = 68.9', S = 10.80% 15" HDPE INV. IN =453.40 (FROM CB 11) L = 21.4', S = 0.90%	15" HDPE INV. OUT =453.40 (TO HDS 1.1) L = 1.8', S = 1.33%
CB 13	519.99		8" HDPE INV. OUT =517.00 (TO CB 14) L = 71.9', S = 1.30%
CB 14	519.44	8" HDPE INV. IN =516.02 (FROM CB 13) L = 71.9', S = 1.30% 6" HDPE INV. IN =516.00 (FROM 1) L = 524.5', S = -994.28%	15" HDPE INV. OUT =514.27 (TO CB 15) L = 37.5', S = 1.00%
CB 15	518.63	15" HDPE INV. IN =513.74 (FROM CB 14) L = 37.5', S = 1.30%	15" HDPE INV. OUT =513.74 (TO DMH 4) L = 40.0', S = -5.50%
CB 16	512.87	15" HDPE INV. IN =509.30 (FROM DMH 4) L = 51.9', S = 4.00%	15" HDPE INV. OUT =508.28 (TO CB 19) L = 51.9', S = 8.00%
CB 17	511.50		15" HDPE INV. OUT =505.39 (TO DMH 6) L = 51.9', S = 8.00%
CB 18	528.00		8" HDPE INV. OUT =524.50 (TO CB 22) L = 22.2', S = 1.15%
CB 19	512.00	15" HDPE INV. IN =507.10 (FROM CB 16) L = 51.4', S = 4.00% 15" HDPE INV. IN =504.88 (FROM CB 4) L = 73.1', S = 15.00%	15" HDPE INV. OUT =504.88 (TO CB 6) L = 123.2', S = 12.80%
CB 20	531.52		6" HDPE INV. OUT =524.75 (TO CB 22) L = 49.3', S = 1.02%
CB 21	435.94	15" HDPE INV. IN =432.77 (FROM CB 24) L = 104.1', S = 1.00% 15" HDPE INV. IN =432.77 (FROM CB 23) L = 29.2', S = 0.00%	15" HDPE INV. OUT =432.77 (TO ES 2) L = 47.7', S = 1.14%
CB 22	527.50	8" HDPE INV. IN =524.20 (FROM CB 18) L = 22.2', S = 1.15% 6" HDPE INV. IN =524.20 (FROM CB 20) L = 49.3', S = 1.02%	12" HDPE INV. OUT =519.80 (TO DMH 5) L = 42.4', S = 9.23%
CB 23	435.82		15" HDPE INV. OUT =432.80 (TO CB 21) L = 29.2', S = 0.00%
CB 24	440.31	15" HDPE INV. IN =433.85 (FROM DMH 5) L = 97.5', S = 12.30%	15" HDPE INV. OUT =433.85 (TO CB 21) L = 104.1', S = 1.00%
CB 25	509.56		8" HDPE INV. OUT =506.00 (TO DMH 7) L = 104.1', S = 31.02%
DIV MH 1.2	471.53	15" HDPE INV. IN =466.09 (FROM CB 7) L = 81.1', S = 1.00%	8" HDPE INV. OUT =466.09 (TO HDS 1.2) L = 3.0', S = 1.00% 8" HDPE INV. OUT =462.28 (TO DMH 2) L = 15.9', S = 4.50%
DMH 1	533.75	15" HDPE INV. IN =528.74 (FROM CB 2) L = 46.6', S = 20.00%	15" HDPE INV. OUT =528.45 (TO CB 4) L = 99.6', S = 10.00%
DMH 2	465.00	8" HDPE INV. IN =460.99 (FROM DIV MH 1.2) L = 15.9', S = 6.50% 15" HDPE INV. IN =460.00 (FROM CB 9) L = 75.8', S = 9.43%	15" HDPE INV. OUT =466.00 (TO DMH 3) L = 80.0', S = 11.73%
DMH 3	453.97	15" HDPE INV. IN =446.23 (FROM DMH 2) L = 80.0', S = 11.73% 12" HDPE INV. IN =446.45 (FROM O.C.S. 1) L = 17.9', S = 17.83%	15" HDPE INV. OUT =446.23 (TO CB 24) L = 97.5', S = 12.30%
DMH 4	517.30	15" HDPE INV. IN =511.34 (FROM CB 15) L = 40.0', S = 5.50%	15" HDPE INV. OUT =511.53 (TO CB 16) L = 51.9', S = 4.00%
DMH 5	519.89	12" HDPE INV. IN =515.54 (FROM CB 22) L = 46.4', S = 9.23%	12" HDPE INV. OUT =512.80 (TO DMH 6) L = 110.6', S = 10.00%
DMH 6	505.78	15" HDPE INV. IN =500.05 (FROM CB 17) L = 51.2', S = 8.00% 12" HDPE INV. IN =501.20 (FROM DMH 5) L = 110.6', S = 10.00%	15" HDPE INV. OUT =497.96 (TO ES 4) L = 125.6', S = 11.00%
DMH 7	478.50	15" HDPE INV. IN =473.15 (FROM CB 6) L = 102.4', S = 14.00% 8" HDPE INV. IN =473.50 (FROM DMH 5) L = 104.5', S = 31.02%	15" HDPE INV. OUT =473.15 (TO CB 7) L = 41.5', S = 14.00%
ES 1		15" HDPE INV. IN =453.00 (FROM HDS 1.1) L = 26.6', S = 1.17%	
ES 2		15" HDPE INV. IN =432.20 (FROM CB 21) L = 47.7', S = 1.14%	
ES 3		8" HDPE INV. IN =430.00 (FROM UNDER DRAIN) L = 41.1', S = 1.00%	
ES 4		15" HDPE INV. IN =484.06 (FROM DMH 6) L = 125.6', S = 11.00%	
HDS 1.1	457.52	15" HDPE INV. IN =453.33 (FROM CB 12) L = 1.8', S = 1.33%	15" HDPE INV. OUT =453.33 (TO ES 1) L = 26.6', S = 1.17%
HDS 1.2	471.96	8" HDPE INV. IN =466.60 (FROM DIV MH 1.2) L = 3.0', S = 1.00%	8" HDPE INV. OUT =466.60 (TO INF 1.2) L = 7.4', S = 1.00%
INF 1.2		8" HDPE INV. IN =466.51 (FROM HDS 1.2) L = 7.4', S = 1.00%	
O.C.S. 1	455.50		12" HDPE INV. OUT =450.30 (TO DMH 3) L = 17.9', S = 17.83%
UNDER DRAIN			8" HDPE INV. OUT =530.55 (TO ES 3) L = 51.1', S = 1.00%

DRAINAGE SCHEDULE			
NAME	RIM	PIPES IN:	PIPES OUT:
CB 26	580.50		6" HDPE INV. OUT =575.00 (TO ES 5) L = 105.4', S = 1.40%
DIV MH 1.3	600.87		4" HDPE INV. OUT =593.10 (TO HDS 1.3) L = 2.9', S = 0.87% 8" HDPE INV. OUT =595.00 (TO ES 6) L = 42.0', S = 1.15%
ES 5		6" HDPE INV. IN =573.50 (FROM CB 26) L = 105.4', S = 1.40%	
ES 6		8" HDPE INV. IN =594.50 (FROM DIV MH 1.3) L = 42.0', S = 1.15%	
HDS 1.3	600.11	4" HDPE INV. IN =593.04 (FROM DIV MH 1.3) L = 2.9', S = 0.87%	4" HDPE INV. OUT =593.04 (TO INF 1.3) L = 2.4', S = 0.88%
INF 1.3		4" HDPE INV. IN =593.00 (FROM HDS 1.3) L = 2.4', S = 0.88%	

**NOTES:**

- PIPE ANCHORS TO BE INSTALLED WHERE PROPOSED DRAINAGE PIPE SLOPE EXCEEDS 15%.
- ANCHORS SHALL BE PLACED EVERY JOINT.
- PIPE TO BE INSTALLED PER MANUFACTURERS RECOMMENDATIONS.
- CONTRACTOR SHALL CONSULT WITH ADVANCED DRAINAGE SYSTEMS, INC. (ADS) FOR SPECIFIC DESIGN AND INSTALLATION REQUIREMENTS.

11-28-23 PLANNING BOARD SUBMISSION	RHMG	01-16-23 BUILDING DEPARTMENT COMMENTS	RHMG
10-20-23 NYCDEP COMPLETENESS COMMENTS	RHMG	02-07-22 WCHD NYCDEP COMMENTS	ZF/ED
04-25-23 PLANNING BOARD SUBMISSION	RHMG	06-04-21 NYCDEP APPLICATION	RHMG
02-07-23 PLANNING BOARD SUBMISSION	RHMG	04-27-21 PLANNING BOARD SUBMISSION	RHMG
DATE:	DESCRIPTION	DATE:	DESCRIPTION




MATTHEW J. GRONDA P.E.

**CONSTRUCTION PLAN - SOUTH**

**WOLF CONSERVATION CENTER**

7 BUCK RUN, SOUTH SALEM, NY 10580  
TOWN OF LEVISOBO, WESTCHESTER COUNTY, NY



**BIBBO ASSOCIATES, LLP**  
293 ROUTE 100 SUITE 203  
SOMERS, NEW YORK 10589  
TEL. 914.277.5805

DATE:	12-29-2020
SCALE:	1" = 30'
FILE:	L5
DSGN / CHK:	MGR/RH
DRN. BY:	RH
SHT NO.	7 OF 20
DWG NO.	<b>CP-1</b>

**CALL BEFORE YOU DIG 1-800-962-7962**

UNDER THE NY STATE LAW PROTECTING UNDERGROUND FACILITIES, THE FOLLOWING RULES AND REGULATIONS ARE IN EFFECT FOR ALL EXCAVATORS:

- THEY MUST CALL FOR A UTILITY STAKE-OUT (2) TWO FULL WORKING DAYS PRIOR TO AN EXCAVATION.
- THEY MUST CONFIRM PRECISE LOCATIONS OF UNDERGROUND FACILITIES.
- THEY MUST PRESERVE STAKES AND MARKINGS UNTIL NO LONGER NEEDED AT SITE.
- THEY MUST CONTACT NON-UPPO MEMBER UTILITY OWNERS FOR STAKE-OUTS.






DRAINAGE SCHEDULE			
NAME	RIM:	PIPES IN:	PIPES OUT:
CB 1	552.37		15" HDPE INV. OUT =549.35 (TO CB 2) L = 9.9', S = 0.81%
CB 2	552.49	15" HDPE INV. IN =549.25 (FROM CB 1) L =9.9', S = 0.81%	15" HDPE INV. OUT =548.02 (TO DMH 1) L = 50.0', S = 20.00%
CB 3	521.39		15" HDPE INV. OUT =516.40 (TO CB 4) L = 9.9', S = 0.89%
CB 4	521.02	15" HDPE INV. IN =516.18 (FROM DMH 1) L =99.6', S = 10.00% 15" HDPE INV. IN =516.34 (FROM CB 3) L =9.9', S = 0.98%	15" HDPE INV. OUT =516.18 (TO CB 19) L = 73.1', S = 15.00%
CB 5	494.25		15" HDPE INV. OUT =489.50 (TO CB 6) L = 16.1', S = 7.67%
CB 6	493.96	15" HDPE INV. IN =489.05 (FROM CB 5) L =16.1', S = 7.67% 15" HDPE INV. IN =489.06 (FROM CB 19) L =123.2', S = 12.60%	15" HDPE INV. OUT =487.80 (TO DMH 7) L = 102.4', S = 14.00%
CB 7	472.11	15" HDPE INV. IN =467.00 (FROM DMH 7) L =41.5', S = 14.00% 15" HDPE INV. IN =466.93 (FROM CB 8) L =18.1', S = 1.01%	15" HDPE INV. OUT =466.94 (TO DIV MH 1.2) L = 81.1', S = 1.00%
CB 8	470.34		15" HDPE INV. OUT =467.16 (TO CB 7) L = 75.8', S = 9.43%
CB 9	467.50		15" HDPE INV. OUT =463.50 (TO DMH 2) L = 75.8', S = 9.43%
CB 10	465.99		15" HDPE INV. OUT =461.00 (TO CB 12) L = 68.9', S = 10.60%
CB 11	456.48		15" HDPE INV. OUT =453.62 (TO CB 12) L = 21.4', S = 0.96%
CB 12	456.26	15" HDPE INV. IN =453.40 (FROM CB 10) L =18.1', S = 1.01% 15" HDPE INV. IN =453.40 (FROM CB 11) L =21.4', S = 0.96%	15" HDPE INV. OUT =453.40 (TO HDS 1.1) L = 1.8', S = 1.33%
CB 13	519.99		8" HDPE INV. OUT =511.00 (TO CB 14) L = 71.9', S = 1.30%
CB 14	519.44	8" HDPE INV. IN =516.02 (FROM CB 13) L =71.9', S = 1.30% 8" HDPE INV. IN =516.00 (FROM ) L =524.5', S = 994.29%	15" HDPE INV. OUT =514.27 (TO CB 15) L = 37.5', S = 1.30%
CB 15	518.63	15" HDPE INV. IN =513.74 (FROM CB 14) L =37.5', S = 1.30%	15" HDPE INV. OUT =510.29 (TO DMH 4) L = 40.0', S = 5.50%
CB 16	512.87	15" HDPE INV. IN =509.30 (FROM DMH 4) L =51.9', S = 4.00%	15" HDPE INV. OUT =509.29 (TO CB 19) L = 51.4', S = 4.00%
CB 17	511.50		15" HDPE INV. OUT =505.39 (TO DMH 6) L = 51.5', S = 8.00%
CB 18	528.00		8" HDPE INV. OUT =524.50 (TO CB 22) L = 22.2', S = 1.15%
CB 19	512.00	15" HDPE INV. IN =507.10 (FROM CB 16) L =51.4', S = 4.00% 15" HDPE INV. IN =504.86 (FROM CB 4) L = 73.1', S = 15.00%	15" HDPE INV. OUT =504.86 (TO CB 6) L = 123.2', S = 12.60%
CB 20	531.52		8" HDPE INV. OUT =524.75 (TO CB 22) L = 49.3', S = 1.02%
CB 21	435.94	15" HDPE INV. IN =432.77 (FROM CB 24) L =101.1', S = 1.15% 15" HDPE INV. IN =432.77 (FROM CB 23) L =28.2', S = 0.09%	15" HDPE INV. OUT =432.77 (TO ES 2) L = 47.7', S = 1.14%
CB 22	527.50	8" HDPE INV. IN =524.20 (FROM CB 18) L =27.2', S = 1.15% 6" HDPE INV. IN =524.20 (FROM CB 20) L =48.3', S = 1.02%	12" HDPE INV. OUT =519.80 (TO DMH 5) L = 42.4', S = 9.23%
CB 23	435.82		15" HDPE INV. OUT =432.80 (TO CB 21) L = 29.2', S = 0.09%
CB 24	440.31	15" HDPE INV. IN =433.85 (FROM DMH 3) L =97.5', S = 12.30%	15" HDPE INV. OUT =433.85 (TO CB 21) L = 104.1', S = 1.00%
CB 25	509.56		8" HDPE INV. OUT =506.00 (TO DMH 7) L = 104.5', S = 31.02%
DIV MH 1.2	471.53	15" HDPE INV. IN =466.09 (FROM CB 7) L =81.1', S = 1.00%	8" HDPE INV. OUT =466.67 (TO HDS 1.2) L = 3.6', S = 1.00% 8" HDPE INV. OUT =462.28 (TO DMH 2) L = 15.9', S = 6.50%
DMH 1	533.75	15" HDPE INV. IN =528.74 (FROM CB 2) L =85.0', S = 20.00%	15" HDPE INV. OUT =526.45 (TO CB 4) L = 98.9', S = 10.00%
DMH 2	465.00	8" HDPE INV. IN =460.99 (FROM DIV MH 1.2) L =15.9', S = 6.50% 15" HDPE INV. IN =466.00 (FROM CB 9) L =75.8', S = 9.43%	15" HDPE INV. OUT =466.00 (TO DMH 3) L = 80.0', S = 11.73%
DMH 3	453.97	15" HDPE INV. IN =446.23 (FROM DMH 2) L =80.0', S = 11.73% 12" HDPE INV. IN =446.48 (FROM O.C.S. 1) L =17.9', S = 17.83%	15" HDPE INV. OUT =446.23 (TO CB 24) L = 67.5', S = 12.30%
DMH 4	517.30	15" HDPE INV. IN =511.34 (FROM CB 15) L =40.0', S = 5.50%	15" HDPE INV. OUT =511.53 (TO CB 16) L = 51.9', S = 4.00%
DMH 5	519.89	12" HDPE INV. IN =515.54 (FROM CB 22) L =42.4', S = 9.23%	12" HDPE INV. OUT =512.60 (TO DMH 6) L = 110.6', S = 10.00%
DMH 6	505.78	15" HDPE INV. IN =500.95 (FROM CB 17) L =51.3', S = 8.00% 12" HDPE INV. IN =501.20 (FROM DMH 5) L =110.6', S = 10.00%	15" HDPE INV. OUT =497.96 (TO ES 4) L = 125.6', S = 11.00%
DMH 7	478.50	15" HDPE INV. IN =473.15 (FROM CB 6) L =102.4', S = 14.00% 8" HDPE INV. IN =473.90 (FROM CB 25) L =104.5', S = 31.02%	15" HDPE INV. OUT =473.15 (TO CB 7) L = 41.5', S = 14.00%
ES 1		15" HDPE INV. IN =453.00 (FROM HDS 1.1) L =26.6', S = 1.17%	
ES 2		15" HDPE INV. IN =432.20 (FROM CB 21) L =47.7', S = 1.14%	
ES 3		8" HDPE INV. IN =530.00 (FROM UNDER DRAIN) L =51.1', S = 1.05%	
ES 4		15" HDPE INV. IN =484.00 (FROM DMH 6) L =125.6', S = 11.00%	
HDS 1.1	457.52	15" HDPE INV. IN =443.33 (FROM CB 12) L =1.8', S = 1.33%	15" HDPE INV. OUT =453.33 (TO ES 1) L = 26.6', S = 1.17%
HDS 1.2	471.96	8" HDPE INV. IN =466.60 (FROM DIV MH 1.2) L =3.6', S = 1.00%	8" HDPE INV. OUT =466.60 (TO INF 1.2) L = 7.4', S = 1.00%
INF 1.2		8" HDPE INV. IN =466.51 (FROM HDS 1.2) L =7.4', S = 1.00%	
O.C.S. 1	455.50		12" HDPE INV. OUT =456.30 (TO DMH 3) L = 17.9', S = 17.83%
UNDER DRAIN			8" HDPE INV. OUT =530.55 (TO ES 3) L = 51.1', S = 1.05%

DRAINAGE SCHEDULE			
NAME	RIM:	PIPES IN:	PIPES OUT:
CB 26	580.50		6" HDPE INV. OUT =575.00 (TO ES 5) L = 105.4', S = 1.40%
DIV MH 1.3	600.87		4" HDPE INV. OUT =593.10 (TO HDS 1.3) L = 2.8', S = 0.87% 8" HDPE INV. OUT =595.00 (TO ES 6) L = 42.9', S = 1.15%
ES 5		8" HDPE INV. IN =573.50 (FROM CB 26) L =105.4', S = 1.40%	
ES 6		8" HDPE INV. IN =584.50 (FROM DIV MH 1.3) L =42.0', S = 1.15%	
HDS 1.3	600.11	4" HDPE INV. IN =593.04 (FROM DIV MH 1.3) L =2.9', S = 0.87%	4" HDPE INV. OUT =593.04 (TO INF 1.3) L = 2.4', S = 0.88%
INF 1.3		4" HDPE INV. IN =593.00 (FROM HDS 1.3) L =2.4', S = 0.88%	

NOTES:  
1. PIPE ANCHORS TO BE INSTALLED WHERE PROPOSED DRAINAGE PIPE SLOPE EXCEEDS 15%  
2. ANCHORS SHALL BE PLACED EVERY JOINT.  
3. PIPE TO BE INSTALLED PER MANUFACTURERS RECOMMENDATIONS.  
4. CONTRACTOR SHALL CONSULT WITH ADVANCED DRAINAGE SYSTEMS, INC. (ADS) FOR SPECIFIC DESIGN AND INSTALLATION REQUIREMENTS.

REVISIONS	DATE	DESCRIPTION	BY/CHK	DATE	DESCRIPTION	BY/CHK
11-28-23	PLANNING BOARD SUBMISSION	RH/MG	01-16-23	BUILDING DEPARTMENT COMMENTS	RH/MG	
10-20-23	NYCDEP COMPLETENESS COMMENTS	RH/MG	02-07-22	WCHD NYCDEP COMMENTS	ZF/ED	
04-25-23	PLANNING BOARD SUBMISSION	RH/MG	06-04-21	NYCDEP APPLICATION	RH/MG	
02-07-23	PLANNING BOARD SUBMISSION	RH/MG	04-27-21	PLANNING BOARD SUBMISSION	RH/MG	
DATE:	DESCRIPTION	BY/CHK	DATE:	DESCRIPTION	BY/CHK	




**CONSTRUCTION PLAN - NORTH**  
**WOLF CONSERVATION CENTER**  
7 BUCK RUN, SOUTH SALEM, NY 10586  
TOWN OF LEVISOBORO, WESTCHESTER COUNTY, NY

**BIBBO ASSOCIATES, LLP**  
293 ROUTE 100 SUITE 203  
SONNERS, NEW YORK 10589  
TEL. 914 277 5805

DATE: 12-29-2020  
SCALE: 1" = 30'  
FILE: L5  
DSGN / CHK: MG/RH  
DRN. BY: RH  
SHT NO. 8 OF 20  
DWG NO. **CP-2**

UNAUTHORIZED ALTERATIONS AND ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 2209 (3) OF THE NEW YORK STATE EDUCATION LAW.  
COPYRIGHT © 2023 BIBBO ASSOCIATES, LLP ALL RIGHTS RESERVED. NO REPRODUCTION OR APPLICABLE LAW.






ESTIMATED QUANTITY OF EARTHWORK		
CUT (CY)	FILL (CY)	NET (CY)
7,018*	2,940	4,078 (CUT)

\* INCLUDES QUANTITY OF MATERIAL REMOVED FOR STORMWATER INFILTRATION SYSTEMS  
NOTE: QUANTITIES NOT TO BE USED FOR BIDDING PURPOSES.



#### EROSION CONTROL LEGEND:

- DRAIN INLET PROTECTION (TYP.)  
\* TO BE INSTALLED ON ALL CATCH BASINS
- PROPOSED SILT FENCE
- PROPOSED TEMPORARY CONSTRUCTION FENCING (ORANGE FENCING)
- PROPOSED TREE PROTECTION
- CONSTRUCTION ENTRANCE
- TEMPORARY STOCKPILE AREA
- LIMIT OF DISTURBANCE
- WATER BAR
- PROPOSED CHECK DAM (TYP.)



- #### LEGEND
- EXISTING PROPERTY LINE
  - WETLAND BUFFER LINE
  - WETLAND BOUNDARY LINE
  - EXISTING WOLF ENCLOSURE FENCE
  - EXISTING EASEMENT LINE
  - EXISTING 2' CONTOUR
  - EXISTING 10' CONTOUR
  - PROPOSED 2' CONTOUR
  - PROPOSED 10' CONTOUR
  - PROPOSED RETAINING WALL
  - PROPOSED ELECTRIC METER
  - PROPOSED TRANSFORMER
  - PROPOSED T-TAP
  - PROPOSED OVERHEAD ELECTRIC SERVICE
  - PROPOSED UNDERGROUND ELECTRIC SERVICE


#### CALL BEFORE YOU DIG 1-800-962-7962

UNDER THE NY STATE LAW PROTECTING UNDERGROUND FACILITIES, THE FOLLOWING RULES AND REGULATIONS ARE IN EFFECT FOR ALL EXCAVATORS:

- \* THEY MUST CALL FOR A UTILITY STAKE-OUT (2) TWO FULL WORKING DAYS PRIOR TO AN EXCAVATION.
- \* THEY MUST CONFIRM PRECISE LOCATIONS OF UNDERGROUND FACILITIES.
- \* THEY MUST PRESERVE STAKES AND MARKINGS UNTIL NO LONGER NEEDED AT SITE.
- \* THEY MUST CONTACT NON-UPPO MEMBER UTILITY OWNERS FOR STAKE-OUTS.

UNAUTHORIZED ALTERATIONS AND ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 2209 (2) OF THE NEW YORK STATE EDUCATION LAW.  
COPYRIGHT © 2011 BIBBO ASSOCIATES, LLP  
ALL RIGHTS RESERVED. UNAUTHORIZED REPRODUCTION OR TRANSMISSION OF ANY PART OF THIS DRAWING IS PROHIBITED.  
APPLICABLE LAWS

11-28-23	PLANNING BOARD SUBMISSION	RHMG	01-16-23	BUILDING DEPARTMENT COMMENTS	RHMG
10-20-23	NYCDEP COMPLETENESS COMMENTS	RHMG	02-07-22	WCHD NYCDEP COMMENTS	ZF/ED
04-25-23	PLANNING BOARD SUBMISSION	RHMG	06-04-21	NYCDEP APPLICATION	RHMG
02-07-23	PLANNING BOARD SUBMISSION	RHMG	04-27-21	PLANNING BOARD SUBMISSION	RHMG
DATE:	DESCRIPTION	BY/CHK	DATE:	DESCRIPTION	BY/CHK



**EROSION CONTROL PLAN**  
**WOLF CONSERVATION CENTER**  
7 BUCK RUN, SOUTH SALEM, NY 10589  
TOWN OF LEWISBORO, WESTCHESTER COUNTY, NY

**BIBBO ASSOCIATES, LLP**  
293 ROUTE 100 SUITE 203  
SOMERS, NEW YORK 10589  
TEL. 914 277 5805

MATTHEW J. GRONDA P.E.


DATE:	12-29-2020
SCALE:	1" = 30'
FILE:	L5
DSGN / CHK:	MG/RH
DRN. BY:	RH
SHT NO.	9 OF 20
DWG NO.	EC-1



CONSTRUCTION SEQUENCING:

1. SURVEY LOCATE THE CENTERLINE OF THE PROPOSED BUCK RUN DRIVEWAY EXTENSION, CENTERLINE OF THE PROPOSED DRIVEWAY TO PROPOSED BUILDING 1 AND 2 AND CENTERLINE OF THE PROPOSED GRAVEL PARKING AREA.
2. SURVEY LOCATE AND STAKE THE PROPOSED LIMITS OF DISTURBANCE, BERM OF THE INFILTRATION BASIN AND LOWER PROPOSED INFILTRATION SYSTEMS.
3. CORDON OFF LOWER INFILTRATION SYSTEMS AND EXISTING SSTS' ADJACENT TO PROPOSED BUILDING 1 WITH CONSTRUCTION FENCING.
4. IDENTIFY TREES TO REMAIN AND PROVIDE PROTECTIVE FENCING. CLEAR TREES WITHIN THE LIMITS OF DISTURBANCE (NOTE: MAINTAIN EXISTING VEGETATIVE GROUND COVER FOR AS LONG AS POSSIBLE ON AREAS NOT REQUIRING GRADING).
5. INSTALL STABILIZED CONSTRUCTION ENTRANCE FROM OLD POST ROAD (ROUTE 35).
6. INSTALL ALL SILT FENCE AS SHOWN.
7. DEMOLISH EXISTING STRUCTURES AS NEEDED AS CONSTRUCTION PROGRESSES FROM OLD POST ROAD NORTH INTO THE SITE.
8. STRIP TOPSOIL FROM THE DRIVEWAY SHOULDERS AND GRAVEL PARKING AREA AND STOCKPILE.
9. STRIP DRIVEWAY SURFACE OF BUCK RUN TO STA. 4+00, EXCAVATE AND FILL TO FORM EMBANKMENTS AND ROUGH GRADE GRAVEL PARKING AREA AND INFILTRATION BASIN.
10. CONSTRUCT PORTION OF DRIVEWAY TO STA. 4+00 AND GRAVEL PARKING AREA TO SUBGRADE. INSTALL CATCH BASIN(S), DRAIN MANHOLE(S), AND DRAINAGE PIPE, FROM STA. 0+00 TO 4+00. INSTALL INFILTRATION SYSTEM INCLUDING DIVERSION STRUCTURES AND HDS UNITS. PROVIDE INLET PROTECTION FOR CATCH BASINS.
11. REINSTALL CONSTRUCTION FENCING TO PROTECT INFILTRATION SYSTEM AREA.
12. ESTABLISH CONSTRUCTION STAGING AREA IN AREA OF GRAVEL PARKING AREA.
13. CONSTRUCT INFILTRATION BASIN.
14. INSTALL CURB AND BINDER COURSE OF PAVEMENT ON PORTION OF COMPLETED DRIVEWAY. BACK-UP CURBS WITH TOPSOIL AND APPLY SEED AND MULCH.
15. DEMOLISH EXISTING STRUCTURES IN AREA OF BUILDINGS 1 AND 2.
16. STRIP DRIVEWAY SURFACE OF BUCK RUN FROM STA. 4+00 TO 7+00, EXCAVATE AND FILL TO FORM EMBANKMENTS AND ROUGH GRADE AS NEEDED. CONSTRUCTION RETAINING WALL AND INSTALL SIDEWALK.
17. CONSTRUCT DRIVEWAY TO SUBGRADE AND RETAINING WALLS ASSOCIATED WITH ACCESS TO BUILDING'S 1 AND 2.
18. CONSTRUCT BUILDING 1 AND 2 AND ASSOCIATED IMPROVEMENTS AND INSTALL ELECTRICAL, TELEPHONE, AND CABLE UTILITIES.
19. INSTALL CATCH BASIN(S), DRAIN MANHOLE(S), AND DRAINAGE PIPE, FROM STA. 4+00 TO 7+00 AND PROPOSED DRIVEWAY TO NEW BUILDINGS. PROVIDE INLET PROTECTION FOR CATCH BASINS.
20. INSTALL CURB AND BINDER COURSE OF PAVEMENT ON PORTION OF COMPLETED DRIVEWAY. BACK-UP CURBS WITH TOPSOIL AND APPLY SEED AND MULCH.
21. STRIP DRIVEWAY SURFACE OF THE REMAINDER OF BUCK RUN, EXCAVATE AND FILL TO FORM EMBANKMENTS AND ROUGH GRADE AS NEEDED. CONSTRUCTION RETAINING WALLS AND PARKING AREA.
22. DEMOLISH EXISTING STRUCTURES AND CONSTRUCT PROPOSED FREEZER FACILITY.
23. INSTALL REMAINING CATCH BASIN(S), DRAIN MANHOLE(S), AND DRAINAGE PIPE ASSOCIATED WITH THE DRIVEWAY IMPROVEMENTS. PROVIDE INLET PROTECTION FOR CATCH BASINS.
24. INSTALL REMAINING ELECTRICAL, TELEPHONE, AND CABLE UTILITIES.
25. INSTALL CURB AND BINDER COURSE OF PAVEMENT ON PORTION OF COMPLETED DRIVEWAY. BACK-UP CURBS WITH TOPSOIL AND APPLY SEED AND MULCH.
26. CONSTRUCT UPPER SITE IMPROVEMENTS (CAMPING PODS AND RESTROOM FACILITIES) AND GRAVEL PATH RESURFACING AND REALIGNMENT.
27. FINE GRADE DRIVEWAY SHOULDERS, LAWN AREA, AND ALL OTHER DISTURBED AREAS TO BE RESTORED TO VEGETATIVE COVER AND COMPLETE RESTORATION OF THESE AREAS WITH SEED AND MULCH. INSTALL LANDSCAPE PLANTINGS AND MULCH BEDS. INDIVIDUAL INFILTRATION SYSTEMS SHALL BE PLACED INTO OPERATION ONLY AFTER FINAL STABILIZATION OF DISTURBED AREA FROM CONTRIBUTING AREA. REMOVE THE SEALS FROM THE PIPE OUTLETS IN DIVERSION STRUCTURES.
28. INSTALL GRAVEL COURSE OF GRAVEL PARKING AREA.
29. CLEANOUT CATCH BASINS AND REMOVE EROSION CONTROLS.
30. INSTALL TOP COURSE OF PAVEMENT.
31. INSTALL PAVEMENT MARKINGS AS NEEDED.
32. RE-VEGETATE ROAD SHOULDERS AND YARD AREAS AS NEEDED.

NOTE: SITE STABILIZATION (80% UNIFORM DENSITY OF PERMANENT VEGETATION OR PERMANENT MULCH/STONE) MUST BE ACHIEVED PRIOR TO REMOVING TEMPORARY EROSION CONTROL MEASURES.



CALL BEFORE YOU DIG 1-800-962-7962

UNDER THE NY STATE LAW PROTECTING UNDERGROUND FACILITIES, THE FOLLOWING RULES AND REGULATIONS ARE IN EFFECT FOR ALL EXCAVATIONS:

- \* THEY MUST CALL FOR A UTILITY STAKE-OUT (2) TWO FULL WORKING DAYS PRIOR TO AN EXCAVATION.
- \* THEY MUST CONFIRM PRECISE LOCATIONS OF UNDERGROUND FACILITIES.
- \* THEY MUST PRESERVE STAKES AND MARKINGS UNTIL NO LONGER NEEDED AT SITE.
- \* THEY MUST CONTACT NON-UPPO MEMBER UTILITY OWNERS FOR STAKE-OUTS.

CRITICAL AREA SEEDING SPECIFICATION

This practice applies to all disturbed areas void of vegetation except where specific seeding/planting recommendations exist in other standards and specifications for specific uses such as recreation.

**SEEDING**  
Site preparation-scarify soil surface for: seedbed preparation if compacted. Remove debris and obstacles such as rocks and stumps.

**Soil Amendments**  
1. Lime to PH 6.0  
2. Fertilize with 600lbs. of 5-10-10 or equivalent per acre (14lbs./ 1000 sq.ft.).

**Seed Mixtures**  
1. Temporary Seeding's  
a. Ryegrass (annual or perennial) @ 30lbs. per acre(0.7 lbs/ 100sq ft.).  
b. Certified "arostock" winter rye (cereal rye) @ 100 lbs. per acre(2.5lbs /1000 sq.ft.).

Use winter rye if seeding in October/November.

2) Permanent Seeding's  
a. Rough or occasionally mowed areas:  
Empire birdfoot trefoil 8 0.20  
OR  
Common white clover(1) 8 0.20  
PLUS  
Tall fescue 20 0.45  
PLUS  
Redtop 2 .05  
OR  
Ryegrass 5 0.10 (perennial)

(1) add inoculant immediately prior to seeding.

**Time of seeding**  
The optimum time for permanent seeding's with legumes (birdfoot trefoil or clover) is early spring.

Permanent seeding's may be any time of the year if properly mulched and adequate moisture is provided. Mid summer is not a good time to seed, but these seeding's if construction is complete, will facilitate covering the land. Portions may fail and may need reseeding the following year.

Temporary seeding's should be made within 24 hours of construction or disturbance. If not, the soil must be scarified prior to seeding.

**Method of seeding**  
Broadcasting, drilling with cultipack type seeder or hydroseeding are acceptable. Good soil to seed contact is the key to successful seeding's.

**Mulching and Mulch Anchoring**  
See specifications below.

**Irrigation**  
Watering may be essential to establish a new seeding. Weather conditions and the intended use of the area will dictate when to water. Irrigation is specialized practice and care needs to be taken not to exceed the application rate/infiltration rate of a given soil.

Each application must be uniformly applied and 1 to 2 inches of water should be applied per application set up.

**Mulching**  
The mulching specifications provided hereon apply to any disturbed areas or exposed slopes 20' vertical or greater that are exposed outside of the spring and fall grass growing season.

**Mulch Material:** Air-dried hay or straw: free of undesirable seeds and coarse materials.

**Application Rate:** 90-100 lbs per 1000 s.f. or 2 tons per acre.

**Recommended Surface Coverage:** Approximately 90%

**Mulch Anchoring Material:** Biodegradable Mulch netting; light-weight paper, jute wood fiber, or plastic netting

**Method of Anchoring Application:** Staple mulch netting to soil surface in accordance with netting manufacturers recommendations.

Each application must be uniformly applied and 1 to 2 inches of water should be applied per application set up.

**Mulching**  
The mulching specifications provided hereon apply to any disturbed areas or exposed slopes 20' vertical or greater that are exposed outside of the spring and fall grass growing season.



**Mulch Material:** Air-dried hay or straw: free of undesirable seeds and coarse materials.

**Application Rate:** 90-100 lbs per 1000 s.f. or 2 tons per acre.

**Recommended Surface Coverage:** Approximately 90%

**Mulch Anchoring Material:** Biodegradable Mulch netting; light-weight paper, jute wood fiber, or plastic netting

**Method of Anchoring Application:** Staple mulch netting to soil surface in accordance with netting manufacturers recommendations.




**CONSTRUCTION SPECIFICATION**  
1. STONE SIZE: USE 2" STONE, OR RECYCLED CONCRETE EQUIVALENT.  
2. LENGTH: NOT LESS THAN 50' EXCEPT ON A SINGLE RESIDENCE LOT WHERE A 30 FOOT MINIMUM LENGTH WOULD APPLY.  
3. THICKNESS: NOT LESS THAN SIX (6) INCHES.  
4. WIDTH: TWELVE (12) FOOT MINIMUM, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INDECS OR EGRESS OCCURS. TWENTYFOUR (24) FOOT IF SINGLE ENTRANCE TO SITE.  
5. FILTER CLOTH: WILL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING OF STONE.  
6. SURFACE WATER: ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CONSTRUCTION ENTRANCES SHALL BE PIPED ACROSS THE ENTRANCE. IF PIPING IS IMPRACTICAL, A MOUNTABLE BERM WITH 5' SLOPES WILL BE PERMITTED.  
7. MAINTENANCE: THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACTED ONTO PUBLIC RIGHTS-OF-WAY MUST BE REMOVED IMMEDIATELY.  
8. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE & WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.  
9. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN.

STABILIZED CONSTRUCTION ENTRANCE DETAIL

SEDIMENTATION & EROSION CONTROL NOTES

- A. **General Notes**  
1. Prior to commencement of any clearing, grading, or excavation in connection with any proposed construction activity, the Owner of Record shall file a notice of Intent (NOI) with the New York State Department of Environmental Conservation (NYSDEC) and the Town of Lewisboro. When all construction has been completed and the site has reached final stabilization, the Owner shall submit a Notice of Termination (NOT) to the NYSDEC and the Town of Lewisboro.  
2. A copy of all Notice of Intents and all Contractor's Certifications, required pursuant to the NYS DEC's "SPOES General Permit for Stormwater Discharges from Construction Activity" (Permit No. GP-02-01) for all land disturbances, development or redevelopment located within the Town of Lewisboro, shall also be filed with the Lewisboro Planning Department.  
3. All construction activities involving the removal or deposition of soil are to be provided with appropriate protective measures to minimize erosion and contain sediment deposition within the site. Minimum soil erosion and sediment control measures shall be implemented as shown on the plans approved by the Town of Lewisboro. All erosion and sediment control measures employed during construction shall comply with the NYS DEC's "New York Standards and Specifications for Erosion and Sediment Control," latest edition.  
4. The Owner's Field Representative (O.F.R.) will be responsible for the implementation and maintenance of sediment and erosion control measures on the site prior to and during construction. All erosion control measures are to be maintained in proper functioning order and are to be repaired or replaced as necessary, or as required by the Town Planner, Building Inspector, Town ECI, or Town Engineer.  
5. Sedimentation and erosion control measures shall be inspected and maintained on a daily basis by the O.F.R. to ensure that channels, temporary and permanent ditches and pipes are clear of debris, that embankments and berms have not been breached and that all straw bales and silt fences are intact. Any failure of sediment and erosion control measures shall be immediately repaired by the Contractor and inspected for approval by the O.F.R. and/or Site Engineer.  
6. The O.F.R. shall inspect downstream conditions for evidence of sedimentation on a weekly basis and after rainstorms of 0.5 inches or greater.  
7. All erosion control measures are to be inspected and maintained on a regular basis throughout the construction period and until all disturbed land has been stabilized by vegetation or paving. Responsibility for the erosion and sediment control plan rests with the landowner of record. This responsibility includes installation and maintenance of all control measures, informing all parties involved in site construction of the plan's objectives and requirements, notifying the Town of Lewisboro of any transfer of its responsibility and transferring a copy of the certified erosion and sediment control plan should the title of all or part of the land be transferred.  
8. Site inspections shall be conducted by a qualified soil erosion control professional (retained by the Owner) at least twice every seven (7) calendar days and within 24 hours of the end of a storm event of 0.5 inches or greater.  
9. Wherever feasible, natural vegetation should be retained and protected. Only the smallest practical area of land should be exposed at any one time during development, and the exposure shall be kept to the shortest practical period of time. Disturbance shall be limited to the areas required to perform construction.  
10. Stabilized construction entrances, silt fences and other erosion and sediment controls shall be installed as shown on plans approved by the Town of Lewisboro prior to beginning any clearing and grubbing or earthwork.  
11. The exposure of an area by site preparation shall be kept to the shortest practical period of time. Erosion and sediment control requirements shall include surface stabilization measures applied as soon as practical in portions of the site where construction activities have temporarily or permanently ceased, but in no case more than seven (7) days after the construction activity in that portion of the site has temporarily or permanently ceased. From November 1 through March 31 any disturbed area must be stabilized using a heavy mulch layer, a rolled erosion control product or another method that does not require seed germination to control erosion. Any graded areas not subject to further disturbance or construction traffic shall be immediately brought to final grade and receive permanent vegetation cover in combination with a suitable mulch.  
12. The permanent final vegetation and structures shall be installed as soon as practical and as may be directed by the Town Planner, Town ECI, or Town Engineer.  
13. All topsoil to be stripped from the area being developed shall be stockpiled not less than two hundred (200) feet from any body of surface water and shall be immediately seeded with a rye grass mixture having a quick germination time.  
14. Grass seed mix may be applied by either mechanical or hydroseeding methods. All seeding and turf establishment shall be performed in accordance with the current edition of the NYS DOT's "Standard Specifications- Construction and Materials," Section 610-3.02, Method No. 1. If seeding is performed between May 15th and August 15th irrigation may be required to ensure proper lawn establishment, and shall be performed if so directed by the project engineer or the Town's representatives.  
15. All cut slopes and embankment fills are to be immediately laid back and stabilized using appropriate techniques which meet the design standards found in the "New York Standards and Specifications for Erosion and Sediment Control," latest edition. At a minimum, slopes and embankments shall be stabilized as follows:  
a. Grade to finished slopes.  
b. Scarified.  
c. Topsoiled with not less than four (4) inches of suitable topsoil material.  
d. Seeded with perennial rye grass. Seed shall be applied at the rate of not less than five (5) pounds per one thousand (1,000) square feet.  
e. Mulched with not less than one (1) inch and not more than three (3) inches of straw (two tons per acre) and anchored in a suitable manner.  
f. All graded slopes greater than a 2h:1v shall use a rolled erosion control product or other means necessary to provide permanent stabilization, and shall be approved by the Town of Lewisboro prior to installation.  
16. On all embankment fill slopes, topsoil shall be stripped at least five (5) feet wider than required for the embankment toe of slope. A protective berm of topsoil shall be left in this area, running parallel to the contours for the purpose of restricting drainage runoff. The topsoil berm shall be seeded as required for stockpiles.  
17. Paved roadways shall be kept clean at all times.  
18. The site shall at all times be graded and maintained such that all stormwater runoff is diverted to soil erosion and sediment control facilities.  
19. All storm drainage outlets shall be stabilized, as required, before the discharge points become operational.  
20. Stormwater from disturbed areas must be passed through sediment control devices before discharge beyond disturbed areas or discharged into other drainage systems.  
21. Dust shall be controlled by sprinkling or other approved methods as necessary, or as directed by the O.F.R.  
22. Cut and fills shall not endanger adjoining property, nor divert water onto the property of others.  
23. All fills shall be compacted to provide stability of material and to prevent settlement.  
24. Erosion control measures shall remain in place until all soil disturbing activities have been completed and all disturbed areas are suitably stabilized. A disturbed area shall be deemed to be "suitably stabilized" upon establishment of a uniform perennial vegetative cover (having a density of at least 80%) on all unpaved areas or areas not covered by permanent structures. Areas which are paved or covered by a permanent structures shall also be considered to be "suitably stabilized".  
25. Construction equipment shall not unnecessarily cross live streams except by means of bridges and culverts or other approved methods.  
26. Temporary on-site sedimentation basins for the immediate control of erosion and sediment transport are to be provided when and where required or ordered. The length, width and depth of such basins are to be determined in the field in accordance with the "New York Standards and Specifications for Erosion and Sediment Control," latest edition.  
27. As warranted by field conditions, special additional sedimentation and erosion control measures, as specified by the site Engineer, the Building Inspector, the Town Planner the Town ECI and/or the Town Engineer shall be installed by the Contractor at no cost to the Town.

- B. **Streams**  
1. All construction activities in or around streams are to be provided with temporary erosion control structures, dewatering devices, or temporary stream diversions as approved by the Town of Lewisboro. These structures shall be in place as shown on the approved plans prior to the start of any construction activity.  
2. Construction of temporary erosion control measures shall begin with the installation of devices/measures located farthest downstream, and thence proceed upstream until all required erosion control measures are in place.  
3. After construction, the temporary erosion control measures are to be removed in reverse order, with the erosion control measures located farthest upstream removed first, and thence proceeding downstream.  
4. Construction activities are to begin with the farthest downstream work and proceed to activities farthest upstream. Prior to commencement of upstream activities, all downstream construction must be completed and permanently stabilized.  
5. All temporary erosion control measures are to be left in place, maintained and replaced as needed or as directed, until all work upstream therefrom has been completed and all related temporary erosion control measures have been removed.




**CONSTRUCTION SPECIFICATIONS:**  
1. WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES OR STAPLES. POSTS SHALL BE STEEL WITH 1" OR 1 1/2" TYPE OR HARDWOOD.  
2. FILTER CLOTH TO BE FASTENED SECURELY TO WOVEN WIRE FENCE WITH TIES SPACED EVERY 24" AT TOP AND MID SECTION. FENCE SHALL BE WOVEN WIRE.  
3. MAXIMUM MESH OPENING.  
4. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL BE OVERLAPPED BY SIX INCHES AND FOLDED. FILTER CLOTH SHALL BE EITHER FILTER X, MIRAFI 100X, STABILINKA 140N, OR APPROVED EQUIVALENT.  
5. PRE-FABRICATED UNITS SHALL BE GEOTAP, ENVIRONMENTAL, OR APPROVED EQUIVALENT.  
6. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE.

SILT FENCE DETAIL



MAINTENANCE AND INSPECTION REQUIREMENTS

- A. **Construction Phase**  
Throughout project construction, the responsibility for installation, maintenance and repair of erosion controls and SMP's will rest with the site contractor as the owner's representative. Oversight of the preparedness of erosion controls and SMP's will be conducted by the owner's qualified professional through regular inspections in accordance with NYSDEC SPDES GP-15-002 General Permit requirements. On a daily basis, the project superintendent shall check for damaged silt fence, the need to clean mud tracked onto Route 35. Street sweeping should be conducted as required. Monitor catch basin sumps for sediment accumulation and clean out when one half full.  
Construction debris, such as sheet metal and wood scrap, paper and insulation products, styrofoam cups and paper wrappers can become windblown litter over and off the site if neglected. Such litter is easily controlled and prevented when the project superintendent sets the tone for vigilant litter control at the outset of the project. Suitable and ample refuse containers will be provided on the site and emptied when full. Any scattered debris will be picked up and placed in containers on a daily basis. Heavy equipment will be refueled by daily deliveries to the site. Gasoline and oil for small engine equipment will be stored in construction equipment storage sheds. Refueling will take place at least 100 feet from the drainage swales to preclude any possible escape of spilled fuel to stormwater. In the event of any major spill, its capture and the removal of contaminated soil will be conducted under NYSDEC regulations for spill remediation.  
As work progresses, the superintendent must ensure that the new work area is first protected with perimeter erosion controls. As important as the need to identify areas requiring protection, is the need to determine disturbed areas that can be stabilized with temporary vegetation. Site management responsibilities will include identification of sections in a work phase where active site work will not occur over the next 7 days. If disturbed earth is present, the superintendent will direct the spreading of rye grass seed and mulch for a temporary protective cover.



EXISTING TREE PROTECTION

- NOTES:
1. THE FENCE SHALL BE LOCATED A MINIMUM OF 1' FOOT OUTSIDE THE DRIP LINE OF THE TREE TO BE SAVED AND IN NO CASE CLOSER THAN 5 FEET TO THE TRUNK OF ANY TREE.
  2. FENCE POSTS SHALL BE EITHER STANDARD STEEL OR 2" X 6" WOOD POSTS OR APPROVED EQUAL.
  3. THE FENCE MAY BE EITHER 40" HIGH SNOW FENCE, 40" PLASTIC WEB FENCING OR APPROVED EQUAL.
  4. NO PRUNING SHALL BE PERFORMED EXCEPT BY APPROVED ARBORIST.
  5. NO EQUIPMENT SHALL OPERATE INSIDE THE PROTECTIVE FENCING INCLUDING DURING FENCE INSTALLATION AND REMOVAL.



NOTE: CHECK DAMS SHALL BE SPACED SUCH THAT THE BASE OF ONE SHALL BE ON A LEVEL WITH THE TOP OF THE NEXT ONE DOWN STREAM OF IT.

STONE CHECK DAMS




- B. **Post Construction**  
Following completion of construction, stabilization of the site and establishment of turf material, responsibility and maintenance will remain with the Owner. These items will require the following maintenance tasks:  
Inspection - Following construction, each Infiltration System, detention system, CDS's outlet and diversion MH's will require regular inspections on at least a semi-annual basis and following major storm events to check for:  
a. Evidence of clogging of detention system outlet structure.  
b. Accumulation of sediment at the inlet and around detention system outlet control structure.  
c. Sediment accumulation at the Infiltration Systems.  
d. Accumulation of debris and sediment in the diversion manholes, detention system inlet and equalization piping and catch basins.  
e. Swale erosion.

Debris and Litter Control - Removal of debris and litter should be undertaken during the mowing operation.  
Erosion Control - Eroding soil on slopes, contributory areas noted during inspections and in diversion swales should be stabilized immediately with topsoil replacement, seeding and mulching. Any tirap dislodged at pipe outlets and in swales should be repositioned.

**Sediment Removal** - Sediment deposition in the detention and Infiltration Systems, CDS pretreatments and diversion Manholes will need to be removed in order to maintain capacity for stormwater treatment and prevent clogging of the outlet structures. The need for sediment removal should be determined during routine inspections and the appropriate equipment and manpower scheduled for the task.

**Catch Basin Cleanout** - Catch basins are provided with sumps 18 inches below the pipe inverts for sediment trapping purposes. Catch basin sumps should be cleaned annually using a vacuum cleaning service.



STONE & CONCRETE BLOCK INLET PROTECTION AT CATCH BASIN

(TO BE INSTALLED ON DRIVEWAY AFTER INSTALLATION OF ITEM #4)

Maintenance Item	Frequency of Inspection				
	Short Term				Long Term
	Following Major Rainfall	Daily	Weekly	Monthly	Yearly
Silt Fence (not knocked down or bulging)	X	X			
Construction Entrance (silt accumulation)	X	X			
Soil Stockpile	X			X	
Seeding/Mulching	X			X	
Site Stabilization	X		X		
Catch Basin Inlet Protection	X		X		
Use of Construction Staging Areas	X	X			
General Site Appearance	X	X			
Debris/Litter Control	X	X			
Need to Clean Road Surface	X	X			
Stormwater Discharge Quality	X	X			X

Maintenance Item	Frequency of Inspection				
	Short Term				Long Term
	Following Major Rainfall	Daily	Weekly	Monthly	Yearly
Inflow Pipes & Rings Clear	X		X		X
Sediment Accumulation in Sumps	X		X		X
Accumulation of larger trash	X		X		X
Outlets Unobstructed	X		X		X

Maintenance Item	Frequency of Inspection				
	Short Term				Long Term
	Following Major Rainfall	Daily	Weekly	Monthly	Yearly
Inflow Pipes Clear	X		X		X
Sediment Accumulation in Sumps	X		X		X
Debris Accumulation in Sumps	X		X		X
Outlets Unobstructed	X		X		X

Maintenance Item	Frequency of Inspection				
	Short Term				Long Term
	Following Major Rainfall	Daily	Weekly	Monthly	Yearly
Inflow Pipes & Rings Clear	X		X		X
Sediment Accumulation in Sumps	X		X		X
Accumulation of larger trash	X		X		X
Outlets Unobstructed	X		X		X

Maintenance Item	Frequency of Inspection				
	Short Term				Long Term
	Following Major Rainfall	Daily	Weekly	Monthly	Yearly
Debris Cleanout	X		X		X
Vegetation	X		X		X
Sediment Deposition	X		X		X
Debris Accumulation	X		X		X

Maintenance Item	Frequency of Inspection				
	Short Term				Long Term
	Following Major Rainfall	Daily	Weekly	Monthly	Yearly
Inflow Pipes & Rings Clear	X		X		X
Sediment Accumulation in Sumps	X		X		X
Accumulation of larger trash	X		X		X
Outlets Unobstructed	X		X		X

11-28-23	PLANNING BOARD SUBMISSION	RH/MG	01-16-23	BUILDING DEPARTMENT COMMENTS	RH/MG
10-20-23	NYCDEP COMPLETENESS COMMENTS	RH/MG	02-07-22	WCHD NYCDEP COMMENTS	ZF/ED
04-25-23	PLANNING BOARD SUBMISSION	RH/MG	06-04-21	NYCDEP APPLICATION	RH/MG
02-07-23	PLANNING BOARD SUBMISSION	RH/MG	04-27-21	PLANNING BOARD SUBMISSION	RH/MG
DATE:	DESCRIPTION	BY/CK	DATE:	DESCRIPTION	BY/CK


UNAUTHORIZED ALTERATIONS AND ADDITIONS TO THIS DRAWING ARE A VIOLATION OF SECTION 7-209 (2) OF THE NEW YORK STATE EDUCATION LAW.

COPYRIGHT © 2023 BIBBO ASSOCIATES, LLP ALL RIGHTS RESERVED. ANY REUSE OR REPRODUCTION OF THIS DRAWING IS A VIOLATION OF THE COPYRIGHT LAW.

**SOIL RESTORATION**  
SOIL RESTORATION IS A REQUIRED PRACTICE APPLIED ACROSS AREAS OF A DEVELOPMENT SITE WHERE SOILS HAVE BEEN DISTURBED AND WILL BE VEGETATED IN ORDER TO RECOVER THE ORIGINAL PROPERTIES AND POROSITY OF THE SOIL.  
SOIL RESTORATION IS APPLIED IN THE CLEANUP, RESTORATION, AND LANDSCAPING PHASE OF CONSTRUCTION FOLLOWED BY THE PERMANENT ESTABLISHMENT OF AN APPROPRIATE, DEEP-ROOTED GROUND COVER TO HELP MAINTAIN THE RESTORED SOIL STRUCTURE. SOIL RESTORATION INCLUDES MECHANICAL DECOMPACTION, COMPOST AMENDMENT, OR BOTH.  
DURING PERIODS OF RELATIVELY LOW TO MODERATE SUBSOIL MOISTURE, THE DISTURBED SUBSOILS ARE RETURNED TO ROUGH GRADE AND THE FOLLOWING SOIL RESTORATION STEPS APPLIED:

1. APPLY 3 INCHES OF COMPOST (OVER SUBSOIL)
2. TILL COMPOST INTO SUBSOIL TO A DEPTH OF AT LEAST 12" (INCHES) USING A CAT-MOUNTED RIPPER, TRACTOR-MOUNTED DISC, OR TILLER. MIXING AND CIRCULATING AIR AND COMPOST INTO SUBSOILS.
3. ROCK-PICK UNTIL UNLIFTED STONE/ROCK MATERIALS OF FOUR INCHES AND LARGER SIZE ARE CLEARED OFF THE SITE.
4. APPLY TOPSOIL TO A DEPTH OF 6" (INCHES).
5. VEGETATE AS REQUIRED BY APPROVED PLAN.

COMPOST SHALL BE AGED, FROM PLANT DERIVED MATERIALS, FREE OF VIBABLE WEED SEEDS, HAVE NO VISIBLE FREE WATER OR DUST PRODUCED WHEN HANDLING, PASS THROUGH A HALF INCH SCREEN AND HAVE A PH SUITABLE TO GROW DESIRED PLANTS.




STONE & CONCRETE BLOCK INLET PROTECTION AT CATCH BASIN


(TO BE INSTALLED ON DRIVEWAY AFTER INSTALLATION OF ITEM #4)

Inspection Item	Frequency of Inspection				
	Short Term				Long Term
	Following Major Rain Event	Daily	Weekly	Monthly	Yearly (Following Major Event)
Knocked down or sagging	X	X			
Entrance (silt accumulation)	X	X			
Soil Stockpile	X			X	
Material Storage	X			X	
Site Stabilization			X		
Erosion Control Protection	X		X		
Staging Areas	X	X			
Worker Appearance	X	X			
Worker Control	X	X			
Road Surface	X	X			
Drainage Quality	X	X			X X






MAIN DRIVEWAY PROFILE  
SCALE: 1" = 30' (H)  
1" = 10' (V)



BUS ROUTE PROFILE  
SCALE: 1" = 30' (H)  
1" = 10' (V)




EDUCATION PAVILION PROFILE  
SCALE: 1" = 30' (H)  
1" = 10' (V)

### CALL BEFORE YOU DIG 1-800-962-7962

UNDER THE NY STATE LAW PROTECTING UNDERGROUND FACILITIES,  
THE FOLLOWING RULES AND REGULATIONS ARE IN EFFECT FOR ALL  
EXCAVATORS:

- THEY MUST CALL FOR A UTILITY STAKE-OUT (2) TWO FULL WORKING DAYS PRIOR TO AN EXCAVATION.
- THEY MUST CONFIRM PRECISE LOCATIONS OF UNDERGROUND FACILITIES.
- THEY MUST PRESERVE STAKES AND MARKINGS UNTIL NO LONGER NEEDED AT SITE.
- THEY MUST CONTACT NON-UFPO MEMBER UTILITY OWNERS FOR STAKE-OUTS.

REVISIONS:	DATE:	DESCRIPTION:	BY/CK:	DATE:	DESCRIPTION:	BY/CK:
11-28-23	PLANNING BOARD SUBMISSION	RH/MG	01-16-23	BUILDING DEPARTMENT COMMENTS	RH/MG	
10-20-23	NYCDEP COMPLETENESS COMMENTS	RH/MG	02-07-22	WCHD NYCDEP COMMENTS	ZF/ED	
04-25-23	PLANNING BOARD SUBMISSION	RH/MG	06-04-21	NYCDEP APPLICATION	RH/MG	
02-07-23	PLANNING BOARD SUBMISSION	RH/MG	04-27-21	PLANNING BOARD SUBMISSION	RH/MG	



**ROAD PROFILES**

**WOLF CONSERVATION CENTER**

7 BUCK RUN, SOUTH SALEM, NY 10580  
TOWN OF LEWISBORO, WESTCHESTER COUNTY, NY

**BIBBO ASSOCIATES, LLP**

293 ROUTE 100 SUITE 203  
SONERS, NEW YORK 10589  
TEL. 914 277 5805

DATE: 12-29-2020

SCALE: 1" = 30'

FILE: L5

DSGN / CHK: MGR/RH


DRN. BY: RH

SHT NO. 11 OF 20


DWG NO. **P-1**

UNAUTHORIZED ALTERATIONS AND ADDITIONS  
TO THIS DRAWING IS A VIOLATION OF  
SECTION 2209 (3) OF THE NEW YORK STATE  
EDUCATION LAW.


COPYRIGHT © 2023 BIBBO ASSOCIATES, LLP  
ALL RIGHTS RESERVED. UNAUTHORIZED  
REPRODUCTION IS A VIOLATION OF  
APPLICABLE LAW.




DRAINAGE PROFILE (CB 1 TO INF 1.2)  
SCALE: 1" = 30' (H)  
1" = 10' (V)




DRAINAGE PROFILE (CB 11 TO ES 1)  
SCALE: 1" = 30' (H)  
1" = 10' (V)




DRAINAGE PROFILE (CB 13 TO CB 19)  
SCALE: 1" = 30' (H)  
1" = 10' (V)




DRAINAGE PROFILE (DS 1.2 TO ES 2)  
SCALE: 1" = 30' (H)  
1" = 10' (V)



DRAINAGE PROFILE (CB 17 TO ES 4)  
SCALE: 1" = 30' (H)  
1" = 10' (V)




DRAINAGE PROFILE (CB 22 TO DMH 6)  
SCALE: 1" = 30' (H)  
1" = 10' (V)



DRAINAGE PROFILE (CB 9 TO DMH 2)  
SCALE: 1" = 30' (H)  
1" = 10' (V)

UNAUTHORIZED ALTERATIONS AND ADDITIONS  
TO THIS DRAWING IS A VIOLATION OF  
SECTION 2209 (2) OF THE NEW YORK STATE  
EDUCATION LAW












**DRAINAGE PROFILES**  
**WOLF CONSERVATION CENTER**  
7 BUCK RUN, SOUTH SALEM, NY 10590  
TOWN OF LEWISBORO, WESTCHESTER COUNTY, NY

DATE: 12-29-2020  
SCALE: 1" = 30'  
FILE: L5  
DSGN / MG/RH  
CHK: RH  
DRN. BY: RH  
SHT NO. 12 OF 20  
DWG NO. **P-2**

11-28-23	PLANNING BOARD SUBMISSION	RH/MG	01-16-23	BUILDING DEPARTMENT COMMENTS	RH/MG
10-20-23	NYCDEP COMPLETENESS COMMENTS	RH/MG	02-07-22	WCHD NYCDEP COMMENTS	ZF/ED
04-25-23	PLANNING BOARD SUBMISSION	RH/MG	06-04-21	NYCDEP APPLICATION	RH/MG
02-07-23	PLANNING BOARD SUBMISSION	RH/MG	04-27-21	PLANNING BOARD SUBMISSION	RH/MG
DATE:	DESCRIPTION	BY/CHK	DATE:	DESCRIPTION	BY/CHK






	DESIGN VEHICLE OUTLINE & DIRECTION OF TRAVEL
	DESIGN VEHICLE OUTLINE & DIRECTION OF TRAVEL
	DESIGN VEHICLE OUTLINE & DIRECTION OF TRAVEL
	FORWARD MOVEMENT WHEEL PATH
	REVERSE MOVEMENT WHEEL PATH
	VEHICLE BODY ENVELOPE




DATE:	12-29-2020
SCALE:	1" = 30'
FILE:	L5
DSGN / CHK:	MG/RH
DRN. BY:	RH
SHT NO.	13 OF 20
DWG NO.	<b>T-1</b>





#### LEGEND

EXISTING PROPERTY LINE	—————
WETLAND BUFFER LINE	- - - - -
WETLAND BOUNDARY LINE	—————
EXISTING WOLF ENCLOSURE FENCE	- X - X - X -
EXISTING EASEMENT LINE	- - - - -
PROPOSED RETAINING WALL	—————
PROPOSED ELECTRIC METER	[M]
PROPOSED TRANSFORMER	[T]
PROPOSED T-TAP	[TT]
PROPOSED OVERHEAD ELECTRIC SERVICE	— O-H — O-H —
PROPOSED UNDERGROUND ELECTRIC SERVICE	- E - E - E - E -
PROPOSED ROOF LEADER CONNECTION PIPE	- RD - RD - RD - RD -
PROPOSED PVC DR-18 WATERMAIN	— W — W —
PROPOSED CU WATER SERVICE	— WS — WS — WS —



SPEED LIMIT (mph)	REQUIRED INTERSECTION SIGHT DISTANCE*	PROVIDED SIGHT DISTANCE
45	500' (L)	> 500' (L)
	430' (R)	> 430' (R)

\* Sight Distances measured in accordance with AASHTO "Policy on Geometric Design of Highways and Streets"

BUCK RUN ENTRANCE NOTES:  
1. ANY TREE BRANCHES OR BRUSH WHICH MAY OBSTRUCT SIGHT DISTANCE SHALL BE REMOVED.


UNAUTHORIZED ALTERATIONS AND ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 2209 (2) OF THE NEW YORK STATE EDUCATION LAW.  
COPYRIGHT © 2023 BIBBO ASSOCIATES, LLP  
ALL RIGHTS RESERVED. UNAUTHORIZED REPRODUCTION IS PROHIBITED.  
APPLICABLE LAW.

#### CALL BEFORE YOU DIG 1-800-962-7962


UNDER THE NY STATE LAW PROTECTING UNDERGROUND FACILITIES, THE FOLLOWING RULES AND REGULATIONS ARE IN EFFECT FOR ALL EXCAVATORS:

- THEY MUST CALL FOR A UTILITY STAKE-OUT (2) TWO FULL WORKING DAYS PRIOR TO AN EXCAVATION.
- THEY MUST CONFIRM PRECISE LOCATIONS OF UNDERGROUND FACILITIES.
- THEY MUST PRESERVE STAKES AND MARKINGS UNTIL NO LONGER NEEDED AT SITE.
- THEY MUST CONTACT NON-UFPO MEMBER UTILITY OWNERS FOR STAKE-OUTS.

REVIEWS:	11-28-23	PLANNING BOARD SUBMISSION	RHMG	01-16-23	BUILDING DEPARTMENT COMMENTS	RHMG
	10-20-23	NYCDEP COMPLETENESS COMMENTS	RHMG	02-07-22	WCHD NYCDEP COMMENTS	ZF/ED
	04-25-23	PLANNING BOARD SUBMISSION	RHMG	06-04-21	NYCDEP APPLICATION	RHMG
	02-07-23	PLANNING BOARD SUBMISSION	RHMG	04-27-21	PLANNING BOARD SUBMISSION	RHMG
	DATE:	DESCRIPTION	BY/CK	DATE:	DESCRIPTION	BY/CK

	<b>SIGHT DISTANCE &amp; PROFILES</b>	DATE:	12-29-2020
	<b>WOLF CONSERVATION CENTER</b>	SCALE:	1" = 30'
	7 BUCK RUN, SOUTH SALEM, NY 10580	FILE:	L5
	TOWN OF LEWISBORO , WESTCHESTER COUNTY, NY	DSGN / CHK:	MG/RH
	 <b>BIBBO ASSOCIATES, LLP</b>	DRN. BY:	RH
293 ROUTE 100 SUITE 203 SOMERS, NEW YORK 10589 TEL. 914 277 5805	SHT NO.	14 OF 20	
	DWG NO.	<b>SD-1</b>	





STORMWATER MITIGATION PLANT SCHEDULE					
TREES (OR APPROVED EQUAL)					
Symbol	Code	Quantity	Scientific Name	Common Name	Size at Planting
	AS	15	ACER SACCHARUM	SUGAR MAPLE	2 1/2- 3 IN. CAL.
	UAP	14	ULMUS AMERICANA 'PRINCETON'	PRINCETON ELM	3-3 1/2 IN. CAL.

WETLAND MITIGATION PLANT SCHEDULE					
TREES (OR APPROVED EQUAL)					
Symbol	Code	Quantity	Scientific Name	Common Name	Size at Planting
	AAB	6	AMELANCHIER ARBOREA	SERVICEBERRY	7'-8' HT
	CCF	5	CERCIS CANADENSIS 'FOREST PANSY'	EASTERN REDBUD	6'-7' HT
	CFL	5	CORNUS FLORIDA 'CHEROKEE PRINCESS'	WH. FLOWERING DOGWOOD	6'-12' O.C.

SHRUBS (OR APPROVED EQUAL)					
Symbol	Code	Quantity	Scientific Name	Common Name	Size at Planting
	CA	8	CORNUS AMOMUM	SILKY DOGWOOD	#3 CONT.
	HVI	15	HAMAMELIS VIRGINIANA	COMMON WITCHHAZEL	#3 CONT.
	IV	9	ILEX VERTICILLATA	WINTERBERRY	#3 CONT.

**PLANTING LEGEND**

SEED MIX:  
APPLICATION:  
SUPPLIER:

NEW ENGLAND SEMI-SHADE GRASS AND FORBS MIX.  
1,450 SQ FEET PER LB  
NEW ENGLAND WETLAND PLANTS, INC  
820 WEST STREET  
AMHERST, MA 01002  
PHONE: 413-548-8000

SHRUB SHALL HAVE SAME RELATION TO FINISH GRADE AS IT DID IN THE NURSERY

LOOSEN BURLAP (IF PRESENT) FROM TOP OF SOIL BALL AND BURY

FINISH GRADE

SOIL ROOT BALL

VARIES

TOPSOIL BACKFILL FOR DECIDUOUS SHRUBS: 3 PARTS TOPSOIL 2 PARTS PEAT MOSS FOR EVERGREEN SHRUBS: 1 PART TOP SOIL 4 PARTS PEAT MOSS

**SHRUB PLANTING**  
N.T.S.

NOTE: PRUNE BY THINNING BRANCHES (NOT ALL END TIPS) RETAINING NORMAL SHAPE NEVER CUT EVERGREEN LEADER.

**TREE PLANTING DETAIL**  
N.T.S.

EVERGREEN

DECIDUOUS


REMOVE BURLAP FROM TOP OF BALL

3" WOOD CHIP MULCH

TOPSOIL & COMPOST

LEGEND	
EXISTING PROPERTY LINE	---
WETLAND BUFFER LINE	- - - - -
WETLAND BOUNDARY LINE	- - - - -
EXISTING WOLF ENCLOSURE FENCE	x x x
EXISTING EASEMENT LINE	- - - - -
EXISTING 2' CONTOUR	420
EXISTING 10' CONTOUR	420
PROPOSED 2' CONTOUR	420
PROPOSED 10' CONTOUR	420
PROPOSED RETAINING WALL	---
PROPOSED ELECTRIC METER	M
PROPOSED TRANSFORMER	T
PROPOSED T-TAP	TT
PROPOSED OVERHEAD ELECTRIC SERVICE	---
PROPOSED UNDERGROUND ELECTRIC SERVICE	---

11-28-23	PLANNING BOARD SUBMISSION	RHMG	01-16-23	BUILDING DEPARTMENT COMMENTS	RHMG
10-20-23	NYCDEP COMPLETENESS COMMENTS	RHMG	02-07-22	WCHD NYCDEP COMMENTS	ZF/ED
04-25-23	PLANNING BOARD SUBMISSION	RHMG	06-04-21	NYCDEP APPLICATION	RHMG
02-07-23	PLANNING BOARD SUBMISSION	RHMG	04-27-21	PLANNING BOARD SUBMISSION	RHMG
DATE:	DESCRIPTION	BY/CK	DATE:	DESCRIPTION	BY/CK



**MATTHEW J. GRONDA P.E.**

**MITIGATION PLAN**

**WOLF CONSERVATION CENTER**

7 BUCK RUN, SOUTH SALEM, NY 10580  
TOWN OF LEWISBORO, WESTCHESTER COUNTY, NY

DATE: 12-29-2020  
SCALE: 1" = 20'  
FILE: L5  
DSGN / CHK: MGR/RH  
DRN. BY: RH  
SHT NO. 15 OF 20  
DWG NO. **M-1**




**BIBBO ASSOCIATES, LLP**

293 ROUTE 100 SUITE 203  
SONIERS, NEW YORK 10589  
TEL. 914 277 5805

CALL BEFORE YOU DIG 1-800-962-7962


- UNDER THE NY STATE LAW PROTECTING UNDERGROUND FACILITIES, THE FOLLOWING RULES AND REGULATIONS ARE IN EFFECT FOR ALL EXCAVATORS:
- THEY MUST CALL FOR A UTILITY STAKE-OUT (2) TWO FULL WORKING DAYS PRIOR TO AN EXCAVATION.
  - THEY MUST CONFIRM PRECISE LOCATIONS OF UNDERGROUND FACILITIES.
  - THEY MUST PRESERVE STAKES AND MARKINGS UNTIL NO LONGER NEEDED AT SITE.
  - THEY MUST CONTACT NON-UFPO MEMBER UTILITY OWNERS FOR STAKE-OUTS.




UNAUTHORIZED ALTERATIONS AND ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 2205 (2) OF THE NEW YORK STATE EDUCATION LAW.

COPYING OR REPRODUCING ANY PART OF THIS DRAWING WITHOUT THE WRITTEN PERMISSION OF BIBBO ASSOCIATES, LLP IS PROHIBITED.







LEGEND	
EXISTING PROPERTY LINE	—————
WETLAND BUFFER LINE	- - - - -
WETLAND BOUNDARY LINE	-----
EXISTING WOLF ENCLOSURE FENCE	x x x
EXISTING EASEMENT LINE	-----
PROPOSED RETAINING WALL	=====
PROPOSED ELECTRIC METER	[M]
PROPOSED TRANSFORMER	[T]
PROPOSED T-TAP	[TT]
PROPOSED OVERHEAD ELECTRIC SERVICE	—O—H—O—H—
PROPOSED UNDERGROUND ELECTRIC SERVICE	—E—E—E—E—
PROPOSED ROOF LEADER CONNECTION PIPE	—RD—RD—RD—RD—
PROPOSED PVC DR-18 WATERMAIN	—W—W—W—
PROPOSED CU WATER SERVICE	—WS—WS—WS—



LAMP POST DETAIL  
NTS




BOLLARD DETAIL  
NTS




A-1



BD



A-2



A-3


PHOTOMETRIC LEGEND  
Units are measured in footcandles

LUMINAIRE SCHEDULE						
SYMBOL	QTY	LABEL	ARRANGEMENT	LUMENS /LAMP	WATTS	DESCRIPTION
☼		A-1	SINGLE	6617	64	ALLEGRA MEDIUM ALG-120/277-CSL-M80-30K-CRI 70-4 14R POLE
☼		A-2	SINGLE	6329	64	ALLEGRA MEDIUM ALG-120/277-CSL-M80-30K-CRI 70-4 BLS 14R POLE
☼		A-3	SINGLE	3524	64	ALLEGRA MEDIUM ALG-120/277-CSL-M80-30K-CRI 70-2 14R POLE
□		BD	SINGLE	1600	15 LED	IDAHO WOOD NO. 2271DC-LED15 WATT

CALL BEFORE YOU DIG 1-800-962-7962

- UNDER THE NY STATE LAW PROTECTING UNDERGROUND FACILITIES, THE FOLLOWING RULES AND REGULATIONS ARE IN EFFECT FOR ALL EXCAVATORS:
- THEY MUST CALL FOR A UTILITY STAKE-OUT (2) TWO FULL WORKING DAYS PRIOR TO AN EXCAVATION.
  - THEY MUST CONFIRM PRECISE LOCATIONS OF UNDERGROUND FACILITIES.
  - THEY MUST PRESERVE STAKES AND MARKINGS UNTIL NO LONGER NEEDED AT SITE.
  - THEY MUST CONTACT NON-UPPO MEMBER UTILITY OWNERS FOR STAKE-OUTS.

11-28-23 PLANNING BOARD SUBMISSION	RHMG	01-16-23 BUILDING DEPARTMENT COMMENTS	RHMG
10-20-23 NYCDP COMPLETENESS COMMENTS	RHMG	02-07-22 WCHD NYCDP COMMENTS	ZF/ED
04-25-23 PLANNING BOARD SUBMISSION	RHMG	06-04-21 NYCDP APPLICATION	RHMG
02-07-23 PLANNING BOARD SUBMISSION	RHMG	04-27-21 PLANNING BOARD SUBMISSION	RHMG
DATE:	DESCRIPTION	BY/CK	DATE:



STATE OF NEW YORK  
MAYOR J. GRONDA  
ENGINEER  
No. 09630  
Matthew J. Gronda P.E.

**LIGHTING PLAN**

**WOLF CONSERVATION CENTER**  
7 BUCK RUN, SOUTH SALEM, NY 10580  
TOWN OF LEVISOBORO, WESTCHESTER COUNTY, NY


DATE: 12-29-2020  
SCALE: 1" = 30'  
FILE: L5  
DSGN / CHK: MGR/RH  
DRN. BY: RH  
SHT NO. 16 OF 20  
DWG NO. **LP-1**

UNAUTHORIZED ALTERATIONS AND ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 2209 (3) OF THE NEW YORK STATE EDUCATION LAW.

COPYRIGHT © 2023 BIBBO ASSOCIATES, LLP  
ALL RIGHTS RESERVED. UNAUTHORIZED REPRODUCTION IS PROHIBITED.


**BIBBO ASSOCIATES, LLP**  
293 ROUTE 100 SUITE 203  
SONOMA, NEW YORK 10589  
TEL. 914 277 5805





1. BASE & RISE SECTIONS SHALL BE PRECAST & MONOLITHICALLY POURED.
2. CONCRETE SHALL BE 4,000 PSI AT TIME OF DELIVERY.
3. ALL BASINS SHALL HAVE 18" MINIMUM SLUMPS.
4. PROVIDE PROPER LIFT AND / OR ANCHORING IN CASES OF HIGH GROUND WATER TO PREVENT FLOATATION.
5. LADDER RUNGS CONFORMING TO N.Y.S.D.O.T. SPEC. NO.725-02-01
6. ALL PIPES SHALL BE LAID OR CUT FLUSH WITH THE INSIDE OF THE BASIN WALL & SHALL BE FIRMLY PARGED IN PLACE, BOTH INSIDE AND OUTSIDE.
7. BRICK FRAME & GRATE TO GRADE TO MATCH BOTH CROWN OF ROAD & SLOPE OF ROAD. A MAX. OF TWO (2) CONCRETE BRICKS OR ONE (1) 6" SOLID BLOCK WILL BE PERMITTED, PARGED INSIDE & OUTSIDE.

**TYPICAL CATCH BASIN (FT TYPE)**  
N.T.S.




**SECTION A-A**  
N.T.S.

PARTS LIST : FIRST DEFENSE HC	
ITEM	DESCRIPTION
1	1" DIA. PRECAST MANHOLE
2	LEADER SUPPORT
3	SEPARATION MODULE
4	INLET PIPE (BY OTHERS)
5	OUTLET PIPE (BY OTHERS)
6	FRAME & COVER


STRUCTURE NUMBER	MODEL	DIMENSIONS (FT)				
		A (MANHOLE DIAMETER (I.D.))	B	C	D	E
HDS 1.1	FD-4HC	4	2.25	3.47	4.97	8.0
HDS 1.2	FD-5HC	5	2.40	3.90	5.83	9.33
HDS 1.3	FD-3HC	3	1.83	2.67	3.71	6.46

### FIRST DEFENSE DETAIL


(DESIGNED, MANUFACTURED, AND SUPPLIED BY HYDRO INTERNATIONAL PLC.)




**DIVERSION MANHOLE 1.2 DETAIL**  
N.T.S.



**TYPICAL CATCH BASIN (CI TYPE)**  
N.T.S.




APPLY TO SEWER & DRAINAGE CLEAN-OUTS IN PAVEMENT




APPLY TO SEWER & DRAINAGE CLEAN-OUTS NOT IN PAVEMENT

**TYPICAL CLEANOUT DETAIL**  
N.T.S.




**GRASS LINED SWALE DETAIL**  
N.T.S.



SWALE DIMENSIONS				
SWALE I.D.	Z	B	Y	SLOPE
RIP-RAP	2	2'	1'	VARIES

TO BE USED WHERE FLOWS EXCEED 2 F.P.S. OR GRADES EXCEEDING 15 %

**RIP-RAP SWALE DETAIL**  
N.T.S.




GENERAL NOTES:

1. DRAINAGE PIPES MARKED WITH "HDPE" SHALL BE HIGH DENSITY POLYETHYLENE SMOOTH BORE AS MANUFACTURED BY ADS N-12 OR APPROVED EQUAL.
2. CATCH BASINS, MANHOLES AND ALL CASTINGS SHALL BE IN ACCORDANCE WITH TOWN OF SOMERS REQUIREMENTS, STANDARDS AND SPECIFICATIONS AND AS SHOWN ON PLANS.
3. UNDERDRAINS SHALL BE 6" DIA. PERFORATED CORRUGATED STEEL PIPE OR EQUAL.
4. CATCH BASIN OR DRAIN MANHOLE WITH 3 OR MORE PIPE CONNECTIONS SHALL BE OVERSIZED DIMENSIONS.

### NOTES:


1. 5" OR 6" DIA. PRECAST BASES MAY BE USED WHEN REQUIRED DUE TO SIZE OR NUMBER OF PIPES AT THE MANHOLE. ECCENTRIC PRECAST REDUCERS SHALL BE PLACED ABOVE THE 5" OR 6" BASE AND THE WALL THICKNESS INCREASED 1" FOR EACH 1" OF INSIDE DIAMETER INCREASE.
2. NON-SHRINK GROUT MAY BE UTILIZED IN LIEU OF FLEXIBLE SLEEVES FOR STORM DRAINAGE MANHOLES.
3. LIFTING HOLES IN PRECAST SECTIONS TO BE FILLED WITH MORTAR.
4. FOR SHALLOW MANHOLES, SUBSTITUTE PRECAST SLAB TOP FOR ECCENTRIC CONE. SLAB SHALL BE CAPABLE OF SUPPORTING AN HS-20-44 LOAD.

**PRECAST CONCRETE DRAINAGE MANHOLE**  
N.T.S.




NOTE: EDUCATION PAVILION ROOF DRAINS TO BE 8" SDR 35 PVC, MIN SLOPE 1% CAMPING DEN ROOF DRAINS TO BE 8" SDR 35 PVC, MIN SLOPE 1%

**ROOF LEADER CONNECTION DETAIL**  
N.T.S.




**DRAINAGE PIPE INSTALLATION**  
N.T.S.



### NOTES:


1. PIPE ANCHORS TO BE INSTALLED WHERE PROPOSED DRAINAGE PIPE SLOPE EXCEEDS 15%.
2. ANCHORS SHALL BE PLACED EVERY JOINT.
3. PIPE TO BE INSTALLED PER MANUFACTURERS RECOMMENDATIONS.
4. CONTRACTOR SHALL CONSULT WITH ADVANCED DRAINAGE SYSTEMS, INC. (ADS) FOR SPECIFIC DESIGN AND INSTALLATION REQUIREMENTS.

**CONCRETE DRAIN PIPE ANCHOR**  
N.T.S.




**POST HYDRANT DETAIL**  
NOT TO SCALE


**TANK FILL DETAIL**  
NOT TO SCALE



**YARD DRAIN DETAIL**  
N.T.S.




**ROCK OUTLET PROTECTION (R.O.P.)**  
N.T.S.



INSTALLATION NOTE: TO INSURE TANK STABILITY, PROVIDE FOR SUBSURFACE DRAINAGE OF BEDDING AND BACKFILL AREA AS EXISTING CONDITIONS WARRANT. THE USE OF ANCHORING TIE-BARS WITH STRAPS SHALL ALSO BE USED, IF REQUIRED, BY THE PROJECT ENGINEER AFTER INSPECTION OF SITE CONDITIONS PRIOR TO TANK PLACEMENT.

NOTE: FINAL TANK LOCATION AND CONNECTION DETAILS TO BE COORDINATED WITH THE LOCAL FIRE DEPARTMENT PRIOR TO PURCHASE AND INSTALLATION.

**10,000 GAL. FIRE SUPPRESSION WATER STORAGE TANK**  
N.T.S.



CONCRETE BOLLARD (TYP.)


PART #		ADS PRODUCT DIMENSIONS		BUILDING DEPARTMENT COMMENTS		R/HMG	
PIPE Ø		A	B (MAX)	H	L	W	
1210NP		12"	6.5"	10"	6.5"	25"	29"
1510NP		15"	6.5"	10"	6.5"	25"	29"
1810NP		18"	7.5"	15"	6.5"	32"	35"
2410NP		24"	7.5"	18"	6.5"	36"	45"
3015NP		30"	7.5"	12"	8.6"	36"	63"
3615NP		36"	7.5"	25"	8.6"	58"	63"

### ADS - FLARED END SECTION

(OR APPROVED EQUAL)

NOTE: SHOP DRAWINGS OF ALL CIVIL COMPONENTS SHOULD BE PROVIDED TO OUR OFFICE FOR THEIR REVIEW AND APPROVAL PRIOR TO PRODUCTION / PURCHASING

REVISIONS	DATE	DESCRIPTION	BY/CHK	DATE	DESCRIPTION	BY/CHK
11-28-23	PLANNING BOARD SUBMISSION	R/HMG	01-16-23	BUILDING DEPARTMENT COMMENTS	R/HMG	
10-20-23	NYCDEP COMPLETENESS COMMENTS	R/HMG	02-07-22	WHO NYCDEP COMMENTS	Z/ED	
04-25-23	PLANNING BOARD SUBMISSION	R/HMG	06-04-21	NYCDEP APPLICATION	R/HMG	
02-07-23	PLANNING BOARD SUBMISSION	R/HMG	04-27-21	PLANNING BOARD SUBMISSION	R/HMG	
DATE:			DATE:			



**DETAILS**

**WOLF CONSERVATION CENTER**  
7 BUCK RUN, SOUTH SALEM, NY 10580  
TOWN OF LEVISOBO, WESTCHESTER COUNTY, NY


**BIBBO ASSOCIATES, LLP**  
293 ROUTE 100 SUITE 203  
SOMERS, NEW YORK 10589  
TEL. 914 277 5805

DATE: 12-29-2020  
SCALE: 1" = 30'  
FILE: L5  
DSGN / CHK: MGR/RH  
DRN. BY: RH  
SHT NO. 17 OF 20  
DWG NO. **D-1**

GENERAL NOTES:  
RECHARGER SHALL BE BY CULTEC, INC. OF BROOKFIELD, CT  
REFER TO CULTEC, INC.'S CURRENTLY RECOMMENDED  
INSTALLATION GUIDELINES.  
THE CHAMBER SHALL BE REMOVED TO WITHSTAND TRAFFIC  
LOADS WHEN INSTALLED ACCORDING TO CULTEC'S  
RECOMMENDED INSTALLATION INSTRUCTIONS.

ALL RECHARGER 330XL HD HEAVY DUTY UNITS ARE MARKED  
WITH A COLOR STRIKE FORMED INTO THE PART PLACING THE  
LENGTH OF THE CHAMBER.  
ALL RECHARGERS SHALL TO CHAMBERS MUST BE INSTALLED IN  
ACCORDANCE WITH ALL APPLICABLE LOCAL, STATE AND  
FEDERAL REGULATIONS.

UNAUTHORIZED ALTERATIONS AND ADDITIONS  
TO THIS DRAWING IS A VIOLATION OF  
SECTION 2209 (2) OF THE NEW YORK STATE  
EDUCATION LAW.  
COPYRIGHT © 2013 BIBBO ASSOCIATES, LLP  
ALL RIGHTS RESERVED. NO PART OF THIS  
DRAWING IS TO BE REPRODUCED OR  
TRANSMITTED IN ANY FORM OR BY ANY  
MEANS, ELECTRONIC OR MECHANICAL,  
INCLUDING PHOTOCOPYING, RECORDING,  
OR BY ANY INFORMATION STORAGE AND  
RETRIEVAL SYSTEM.




### STORMWATER BASIN BERM DETAIL

N.T.S.

Whenever a berm is to be constructed on a slope:  
The subgrade shall be bench to provide level  
surfaces for proper operation of compaction  
equipment.

#### CONSTRUCTION SPECIFICATIONS

- EMBANKMENT MATERIAL SHALL CONSIST OF SELECT GLACIAL TILL, COMPRISED OF A MIX OF SILT, SAND, CLAY AND GRAVEL. FILL ON SITE EXCAVATION. THE PERCENTAGE OF FINES PASSING THE 200 SIEVE SHALL BE AT LEAST 20% BY WEIGHT BORROW MATERIAL SHALL BE TESTED FOR OPTIMUM MOISTURE CONTENT AND PROCTOR MAXIMUM DRY DENSITY MATERIAL WITH MOISTURE CONTENT IN EXCESS OF OPTIMUM SHALL BE DRIED TO THE REQUIRED OPTIMUM CONTENT BY SPREADING, HARROWING, BLADING OR OTHER APPROVED MEANS PRIOR TO PLACING IN THE BERM. NO STONES GREATER IN SIZE THAN 6 INCHES IN MAXIMUM DIMENSIONS AND NO ORGANIC MATERIAL SHALL BE ALLOWED IN THE EMBANKMENT.
- THE GROUND SURFACE UNDER THE EMBANKMENT SHALL BE STRIPPED OF ALL VEGETATION, ROOTS, TOPSOIL AND SUBSOIL TO THE DEPTH INDICATED ON THE DETAIL. AFTER STRIPPING TO SUBGRADE THE EARTH SHALL BE MOISTENED, IF DRY, AND COMPACTED BEFORE PLACEMENT OF THE FIRST LAYER OF EMBANKMENT MATERIAL.
- THE EMBANKMENT SHALL BE CONSTRUCTED IN EVEN EIGHTH (8) INCH LIFTS AND MECHANICALLY COMPACTED TO A MINIMUM DRY DENSITY OF 90% OF MAXIMUM DENSITY AS DETERMINED BY THE STANDARD COMPACTION TEST.
- COMPACTION EQUIPMENT
  - EMBANKMENT LIFTS, LIFTS SHALL BE COMPACTED WITH A SMOOTH STEEL WHEEL VIBRATORY ROLLER HAVING A NOMINAL GROSS WEIGHT OF NOT LESS THAN 10 TONS AND EXERT A MINIMUM FORCE OF NOT LESS THAN 300 POUNDS PER INCH OF WIDTH ON THE COMPRESSION ROLL FACES.
  - SPECIALLY COMPACTED EARTH FILL, WHERE COMPACTION BY MEANS OF THE SPECIFIED ROLLER IS IMPRACTICAL AT SUCH LOCATIONS AS STEEP AND IRREGULAR ABUTMENTS, ROADS AND IRREGULAR FOUNDATIONS, ADJACENT TO OUTLET WORKS, COMPACTION EQUIPMENT SHALL INCLUDE IMPACT TAMMERS, SMALL DRUM VIBRATORS, OR OTHER APPROVED MECHANICAL TAMMERS. THE MATERIAL, MOISTURE AND DENSITY SHALL BE AS SPECIFIED ABOVE EXCEPT THAT ROCK SIZE SHALL BE LIMITED TO 2 INCHES, LIFT THICKNESS SHALL BE REDUCED IF NECESSARY TO ACHIEVE THE REQUIRED COMPACTION WITH THE EQUIPMENT USED.
- ANTI-SLEEP COLLARS AS SUPPLIED BY SCHER DRAINAGE PRODUCTS, OREGON, MO. TO BE INSTALLED ON ALL OUTLET PIPES PENETRATING THE BERM.



### X-SECTIONAL VIEW


NTS

STORMWATER TREATMENT BASIN	ELEVATIONS								DIMENSIONS		OUTLET PIPE	
	EL. "A" T.O.B.	EL. "B" GRATE	EL. "C" CAP	EL. "D" ORIFICE	EL. "E" CULVERT	EL. "F" BOTTOM	EL. "G" G / L	EL. "H" 100-YR	EL. "I" EMG. SPWY.	DIM. "B" ORIFICE (Ø INCH)	DIA. MATERIAL (INCH)	LENGTH (LF)
INFILTRATION BASIN 1.1	457.00	455.50	453.00	454.75	450.30	451.00	N/A	455.39	456.00	4	12" HDPE	58

### INFILTRATION BASIN OUTLET CONTROL CONFIGURATION


NTS

NOTE: IN CASE OF INFILTRATION BASIN CLOGGING, TO ALLOW FOR ANY NECESSARY MAINTENANCE, A SUBMERSIBLE PUMP SHALL BE UTILIZED, AND IMPOUNDED WATER SHALL BE PUMPED THROUGH THE OUTLET STRUCTURE'S PRIMARY 18" DIA. CULVERT TO THE PROPOSED ROCK OUTLET PROTECTION.




### INFILTRATION BASIN OUTLET STRUCTURE DETAIL - SECTION VIEW

N.T.S.



### INFILTRATION BASIN OUTLET STRUCTURE DETAIL - PLAN VIEW

N.T.S.



### PERFORATED PIPE AND ORIFICE DETAIL


N.T.S.

FRAMES SHALL BE SET ONE INCH BELOW FINISHED GRADE  
AS MEASURED AT A DISTANCE OF 1 1/2 INCHES IN EITHER  
DIRECTION ALONG THE GUTTER LINE

NOTE:  
SHOP DRAWINGS OF ALL CIVIL COMPONENTS SHOULD BE PROVIDED TO OUR OFFICE  
FOR THEIR REVIEW AND APPROVAL PRIOR TO PRODUCTION / PURCHASING

11-28-23	PLANNING BOARD SUBMISSION	RHMG	01-16-23	BUILDING DEPARTMENT COMMENTS	RHMG
10-20-23	NYCDEP COMPLETENESS COMMENTS	RHMG	02-07-22	WCHD NYCDEP COMMENTS	ZF/ED
04-25-23	PLANNING BOARD SUBMISSION	RHMG	06-04-21	NYCDEP APPLICATION	RHMG
02-07-23	PLANNING BOARD SUBMISSION	RHMG	04-27-21	PLANNING BOARD SUBMISSION	RHMG
DATE:	DESCRIPTION	BY/CK	DATE:	DESCRIPTION	BY/CK

UNAUTHORIZED ALTERATIONS AND ADDITIONS  
TO THIS DRAWING IS A VIOLATION OF  
SECTION 2209 (3) OF THE NEW YORK STATE  
EDUCATION LAW.  
COPYRIGHT © 2023 BIBBO ASSOCIATES, LLP  
ALL RIGHTS RESERVED. UNAUTHORIZED  
REPRODUCTION IS PROHIBITED.  
APPLICABLE LAW.



**DETAILS**  
**WOLF CONSERVATION CENTER**  
7 BUCK RUN, SOUTH SALEM, NY 10580  
TOWN OF LEVISOBORO, WESTCHESTER COUNTY, NY

**BIBBO ASSOCIATES, LLP**  
293 ROUTE 100 SUITE 203  
SOMERS, NEW YORK 10589  
TEL. 914 277 5805

DATE: 12-29-2020  
SCALE: 1" = 30'  
FILE: L5  
DSGN / CHK: MGR/RH  
DRN. BY: RH  
SHT NO. 18 OF 20  
DWG NO. **D-2**



24' WIDE PRIVATE ROAD PAVEMENT SECTION  
(STATION 0+00 - 3+50)  
N.T.S.

20' WIDE DRIVEWAY PAVEMENT SECTION  
(STATION 3+50 - 6+60)  
N.T.S.

14' WIDE DRIVEWAY PAVEMENT SECTION  
(STATION 6+60 - PARKING AREA)  
N.T.S.

PROPOSED PARKING AREA PAVEMENT SECTION

NO PARKING SIGNAGE  
NTS

TYPE "A" SIGN SUPPORT POST  
ACCESSIBLE PARKING SIGNAGE

CONCRETE CURB DETAIL

N.T.S.

CONCRETE FILLED STEEL BOLLARD  
N.T.S.

CONCRETE SIDEWALK DETAIL  
N.T.S.

TIMBER GUIDE RAIL DETAIL  
N.T.S.

NOTE: 2% MAXIMUM GRADE PERMITTED IN ALL DIRECTIONS

## ACCESSIBLE PARKING DIMENSIONS & SIGN PLACEMENT

48. EMPLOYMENT BENEFIT

TYPE "A" SIGN SUPPORT POST  
NO PARKING SIGNAGE  
N.T.S.

TRAIL SECTION DETAIL  
N.T.S.

WOOD CHIP WALKING TRAIL  
N.T.S.

FLUSHING HYDRANT DETAIL  
N.T.S.

**GRAVEL PATH DETAIL**  
N.T.S.

**BOULDER RETAINING WALL DETAIL**  
N.T.S.

TYPICAL SEGMENTAL BLOCK RETAINING WALL DETAIL  
N.T.S.

NOTES:

1. TYPICAL WALL DETAIL IS PROVIDED FOR REFERENCE ONLY. WALL DESIGN DRAWINGS PREPARED BY A NYS LICENSED ENGINEER SHALL BE PROVIDED TO THE PROJECT ENGINEER FOR REVIEW AND APPROVAL PRIOR TO CONSTRUCTION.
2. TYPICAL WALL DESIGN DRAWINGS AND CALCULATIONS SHALL BE BASED ON SITE CONDITIONS.
3. TYPICAL WALL DETAIL PROVIDED ABOVE BASED ON "TYPICAL GRAVITY WALL SECTION" AS MANUFACTURED BY RED ROCK.
4. THE CONSTRUCTION OF RETAINING WALLS GREATER THAN OR EQUAL TO FOUR (4) IN HEIGHT SHALL BE CERTIFIED BY THE DESIGN PROFESSIONAL PRIOR TO ISSUANCE TO A CERTIFICATE OF OCCUPANCY / COMPLETION.

### REINFORCED CONCRETE RETAINING WALL DETAIL- SECTION

RETAINING WALL SCHEDULE										DESCRIPTORS
HW	A	B	C	W	"O" BARS	"D" BARS	"L" BARS	"L" BARS	"P" BARS	
0' to 10'	12"	15"	3'-6"	5'-8"	#5@12"o.c.	#4@12"	6-#5	#5@12"o.c.	#5@12"o.c.	12"

**NOTES:**

1. THE CONSTRUCTION OF RETAINING WALLS GREATER THAN OR EQUAL TO FOUR (4') IN HEIGHT SHALL BE CERTIFIED BY THE DESIGN PROFESSIONAL PRIOR TO ISSUANCE TO A CERTIFICATE OF OCCUPANCY / COMPLETION.


## NOTES

- THE CONTRACTOR SHALL VERIFY THE EXISTING SOIL, TOPOGRAPHIC CONDITIONS, SUBSEQUENT RETAINING WALL HEIGHTS AND SOIL CONDITIONS PRIOR TO STARTING THE WORK. ANY INCONSISTENCIES SHALL BE REPORTED TO THE DESIGN ENGINEER TO DETERMINE IF FIELD CHANGES ARE REQUIRED.
2. REINFORCEMENT SHALL BE ASTM GRADE 60, DEFORMED BILLET-STEEL REBAR FOR CONCRETE REINFORCEMENT COMPLIANCE WITH ASTM A615.
3. ALL POURED IN PLACE CONCRETE SHALL HAVE A 3000 PSI COMPRESSIVE STRENGTH AT 28 DAYS.
4. WHEN THE RETAINING WALL SHALL BE CONSTRUCTED ON A SLOPE, SUFFICIENT LEVEL SHEDDING SHALL BE PROVIDED FOR FOOTING CONSTRUCTION. BOTTOM OF FOOTING SHALL BE CONSTRUCTED AS SHOWN ON THE RETAINING WALL CROSS SECTION.
5. BACKFILL MATERIAL OF THE RETAINING WALL SHALL BE SELECT GRANULAR FILL CONFORMING TO THE GRADATION REQUIREMENTS SPECIFIED IN TABLE 7.7 OF THE NEYTCD STANDARD SPECIFICATIONS AND AS DESCRIBED BELOW.
- | SIZE/SECT | PERCENT PASSING |
|-----------|-----------------|
| 4"        | 100%            |
| No. 40    | 0-70%           |
| No. 200   | 0-15%           |
6. SELECT GRANULAR FILL SHALL BE FREE OF LARGE STONES, ORGANIC MATTER, SOILS CONTAINING LARGE PERCENTAGES OF SILT / CLAY AND FROZEN MATERIALS. BACKFILL SHALL PROVIDE ADEQUATE DRAINAGE FOR THE RETAINING WALL.
7. RETAINING WALL DESIGN IS BASED ON A 2.0 TON/SF SOIL BEARING CAPACITY. THE CONTRACTOR SHALL FIELD VERIFY SOIL CONDITIONS AND BEARING CAPACITIES OF IN-SITU SOIL. IF SOIL TESTING RESULTS INADEQUATE SOIL BEARING CAPACITIES, THE DESIGN ENGINEER SHALL BE NOTIFIED TO CONFIRM WALL DESIGN PARAMETER PRIOR TO CONSTRUCTION.
8. THE RETAINING WALL DESIGN IS BASED ON A "3" CLASS "GRANULAR SILTS, MAX GRAIN SIZES" BACKFILL SOIL CONDITION. ANY ALTERATION FROM THESE SOILS, SUCH AS HIGH GROUNDWATER, HIGH PERCENTAGES OF FINES, SILTS AND CLAYS WILL CONSTITUTE DESIGN CHANGES.
9. CONTRACTOR SHALL TAKE CONCRETE CORE SAMPLES FROM FOOTING AND STEIN POURS SEPARATELY AND HAVE THOSE LABORATORY TESTED FOR COMPRESSIVE STRENGTH FOR 7 AND 28 DAYS.
10. ALL REBAR LAP SPLICES SHALL BE A MINIMUM OF 32" IN LENGTH.
11. WALL CONNECTION JOINTS WILL BE PROVIDED AT EVERY 25' C/S. AS INDICATED ON THE PLANS
12. CHAMFER ALL EXPOSED CORNERS 2"
13. NO WALL DRAINAGE SHALL DISCHARGE DIRECTLY TO ADJOINING PROPERTIES.
14. THE COMPLETED RETAINING WALL CONSTRUCTION SHALL BE CERTIFIED BY A LICENSED NEW YORK STATE PROFESSIONAL ENGINEER TO BE IN CONFORMANCE WITH THE APPROVED PLANS AND MUST INCLUDE LABORATORY TESTING RESULTS FOR SUB GRADE BEARING CAPACITY, BACKFILL GRADATION, COMPACTION, CONCRETE STRENGTH AND REBAR PLACEMENT.
15. RETAINING WALL FOOTING BOTTOM WILL NOT BE ON THE EXISTING GRADE. ALL CONCRETE POURS SHALL BE MONOLITHIC AND NO HORIZONTAL JOINTS WILL BE ALLOWED.
16. CONTRACTOR TO ENSURE PROPER SHORING AND/OR BRACING TO STABILIZE OR PREVENT CAVE-INS OF LOOSE SOIL AT THE EXCAVATION SITE.
17. WHEN BACKFILLING AGAINST THE WALLS, HEAVY COMPACTION EQUIPMENT SHALL BE KEPT AT LEAST 5 FEET AWAY FROM THE WALL TO PREVENT DAMAGE TO THE LIGHTWEIGHT COMPACTION EQUIPMENT SHALL BE USED NEAR THE WALL.
18. TOP OF WALL ELEVATIONS SHOWN ON THE PLANS INCLUDE 2" THICK CAPSTONE. FOR NET CONCRETE ELEVATION SUBTRACT 2" FROM TOP ELEVATIONS.

<u>SIEVE SIZE</u>	<u>PERCENT PASSING</u>
4"	100%
No. 40	0-70%
No. 200	0-15%


**NOTE:**  
SHOP DRAWINGS OF ALL CIVIL COMPONENTS SHOULD BE PROVIDED TO OUR OFFICE  
FOR THEIR REVIEW AND APPROVAL PRIOR TO PRODUCTION / PURCHASING

REVISIONS:	11-28-23	PLANNING BOARD SUBMISSION	RH/MG	01-16-23	BUILDING DEPARTMENT COMMENTS	RH/MG
	10-20-23	NYCDEP COMPLETENESS COMMENTS	RH/MG	02-07-22	WCBD NYCDEP COMMENTS	ZF/ED
	04-23-23	PLANNING BOARD SUBMISSION	RH/MG	06-04-21	NYCDEP APPLICATION	RH/MG
	02-07-23	PLANNING BOARD SUBMISSION	RH/MG	04-27-21	PLANNING BOARD SUBMISSION	RH/MG
	DATE:	DESCRIPTION	BY/CK	DATE:	DESCRIPTION	BY/CK



## DETAILS

**WOLF CONSERVATION CENTER**  
7 BUCK RUN, SOUTH SALEM, NY 10590  
TOWN OF LEWISBORO, WESTCHESTER COUNTY, NY











**BIBBO ASSOCIATES, LLP**  
293 ROUTE 100 SUITE 203  
SOMERS, NEW YORK 10589  
TEL. 914 277 5805

DATE:	12-29-2020
SCALE:	1" = 30'
FILE:	L5
DSGN / CHK:	SB
DRN. BY:	NH
SHT NO.	19 OF 20
DWG NO.	<b>D-3</b>

UNAUTHORIZED ALTERATIONS AND ADDITIONS  
TO THIS DRAWING IS A VIOLATION OF  
SECTION 7209 (2) OF THE NEW YORK STATE  
EDUCATION LAW.

COPYRIGHT © 2023 BIRBO ASSOCIATES, LLP  
ALL RIGHTS RESERVED. UNAUTHORIZED  
DUPLICATION IS A VIOLATION OF  
APPLICABLE LAWS





NOTE:  
SHOP DRAWINGS OF ALL CIVIL COMPONENTS SHOULD BE PROVIDED TO OUR OFFICE FOR THEIR REVIEW AND APPROVAL PRIOR TO PRODUCTION / PURCHASING

11-28-23	PLANNING BOARD SUBMISSION	RHMG	01-16-23	BUILDING DEPARTMENT COMMENTS	RHMG
10-20-23	NYCDEP COMPLETENESS COMMENTS	RHMG	02-07-22	WCHD NYCDEP COMMENTS	ZF/ED
04-25-23	PLANNING BOARD SUBMISSION	RHMG	06-04-21	NYCDEP APPLICATION	RHMG
02-07-23	PLANNING BOARD SUBMISSION	RHMG	04-27-21	PLANNING BOARD SUBMISSION	RHMG
DATE:	DESCRIPTION	BY/CK	DATE:	DESCRIPTION	BY/CK

UNAUTHORIZED ALTERATIONS AND ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 2209 (3) OF THE NEW YORK STATE EDUCATION LAW.  
COPYRIGHT © 2023 BIBBO ASSOCIATES, LLP ALL RIGHTS RESERVED. UNAUTHORIZED REPRODUCTION IS PROHIBITED.  
MATTHEW J. GRONDA P.E.

**ON-SITE WASTEWATER TREATMENT SYSTEM DETAILS**

**WOLF CONSERVATION CENTER**  
7 BUCK RUN, SOUTH SALEM, NY 10580  
TOWN OF LEVISOBORO, WESTCHESTER COUNTY, NY

**BIBBO ASSOCIATES, LLP**  
293 ROUTE 100 SUITE 203  
SOMERS, NEW YORK 10589  
TEL. 914 277 5805

DATE: 12-29-2020  
SCALE: 1" = 30'  
FILE: L5  
DSGN / SB  
CHK: SB  
DRN. BY: NH  
SHT NO. 20 OF 20  
DWG NO. **D-4**

# 72 HOUR WELL PUMP TEST WORK PLAN

for

## Wolf Conservation Center

*Buck Run  
Lewisboro – (T)*

### Supply Well

The Wolf Conservation Center is proposing to construct a new educational pavilion, 12 yurts for overnight camping, and several ancillary site improvements to support their existing operations in the Town of Lewisboro. The project site consists of several tax parcels located on Buck Run in the Town of Lewisboro which were previously developed for single family residential use. The Wolf Center currently utilizes the existing dwellings and large wooded areas for their daily operations as a Private Nature Preserve. It is planned to merge the existing parcels into one large property which will contain the new educational pavilion as well as the existing dwellings, which will be converted to maintenance / office uses to support the preserve. All new and existing structures will be served with water from on-site drilled wells. The anticipated design flow for the campus use is approximately 850 gpd. The peak demand is estimated to be 10 to 12 gpm. The target yield from the well is therefore **12 gpm**.

#### 1) Pump Test Duration

The pump test shall be scheduled in close coordination with the weather forecast. When excessive rainfall is forecast prior to or during the scheduled test period, the test shall be rescheduled for a period of normal weather. No pumping of the well on the site shall be allowed within 24 hours of the start of the pumping test.

The pump test shall be continuously conducted over a minimum period of 24 hours or until yield and water level stabilization is achieved. Stabilization is defined as an unchanging water level within the well for the final 6 hours of pumping accompanied by a constant pumping rate.

#### 2) Schedule of Measurements

##### Time After Pumping Started

0 to 15 minutes  
15 to 50 minutes  
50 to 100 minutes

##### Time Intervals

1 minute  
5 minutes  
10 minutes

**Time After Pumping Started**

100 to 500 minutes  
500 to 1000 minutes  
1000 to 5000 minutes

**Time Intervals**

30 minutes  
1 hours  
4 hours

Water level measurements should be made to the nearest 0.01 foot. A log of weather conditions shall be maintained during the test.

**3) Method of Measurement**

Water level monitoring shall be conducted using either a pressure transducer data recorder or electric drop line. The rate of flow shall be measured from a water meter installed on the discharge pipe followed by a ball or gate valve to regulate flow.

**4) Onsite / Off-Site Well Monitoring**

The three (3) nearest onsite wells to the test location will be monitored during the test and are the existing wells serving the dwellings located at 3, 4 and 7 Buck Run. The wells are located approximately 85 ft, 480 ft and 570 ft. respectively from the test well.

Water level monitoring in the observation wells will begin 24 hours prior to the start of the pump test, continue through the pump test and for 12 hours after the end of the pumping test.

In addition to the observation wells identified above, the owners of the property located at 16 Waccabuc River Lane will be contacted for permission to allow monitoring of their existing well, which is the nearest offsite well location.

**5) Recovery**

The Schedule of Measurements provided above shall be used for the recovery period and recorded in the test and observation wells. Recovery period water level measurements shall commence one minute prior to shut down of the well pump and continue for at least 12 hours. In the test well a check valve shall be installed above the pump at the base of the drop pipe to eliminate backflow of water into the well and its influence on the recovery data.

**6) Erosion Control**



In order to prevent erosion caused by the test pump discharge, it shall be directed into a temporary stone filled sump and velocity dissipator as shown and detailed on the attached sketch.

**7) Water Quality Testing**

Water samples from the Test Well will be taken near the end of the pump test and delivered to a NYS certified laboratory for analysis of water quality parameters required

by Subpart 5-1 of the State Sanitary Code and the Westchester County Health Department. (See attached list of Requirements and Standards)







**CALL BEFORE YOU DIG 1-800-962-7962**

UNDER THE NY STATE LAW PROTECTING UNDERGROUND FACILITIES, THE FOLLOWING RULES AND REGULATIONS ARE IN EFFECT FOR ALL EXCAVATORS:

- \* THEY MUST CALL FOR A UTILITY STAKE-OUT (2) TWO FULL WORKING DAYS PRIOR TO AN EXCAVATION.
- \* THEY MUST CONFIRM PRECISE LOCATIONS OF UNDERGROUND FACILITIES.
- \* THEY MUST PRESERVE STAKES AND MARKINGS UNTIL NO LONGER NEEDED AT SITE.
- \* THEY MUST CONTACT NON-UFPO MEMBER UTILITY OWNERS FOR STAKE-OUTS.

REVISIONS:					
DATE:	DESCRIPTION	BY/CK	DATE:	DESCRIPTION	BY/CK

 MATTHEW J. GRONDA P.E.	<b>WELL TESTING PLAN</b> <b>WOLF CONSERVATION CENTER</b> 7 BUCK RUN, SOUTH SALEM, NY 10590 TOWN OF LEWISBORO, WESTCHESTER COUNTY, NY  <b>BIBBO ASSOCIATES, LLP</b> 293 ROUTE 100 SUITE 203 SOMERS, NEW YORK 10589 TEL. 914 277 5805	DATE: 11-28-2023 SCALE: 1" = 40' FILE: L5 DSGN / CHK: MG/RH DRN. BY: RH SHT NO. 1 OF 1 DWG NO. <b>WT-1</b>
---	---	--



# Stormwater Pollution Prevention Plan

for

## Wolf Conservation Center

1,3,4 & 7 Buck Run  
Town of Lewisboro,  
New York

*Revised: October 20, 2023 (NYCDEP Completeness)*

*Revised: April 25, 2023 (Lewisboro (T))*

*Revised: February 7, 2023 (Lewisboro (T))*

*Revised: June 4, 2021 (NYCDEP Application)*

*Revised: April 27, 2021*

Date: December 29, 2020

Prepared by:

**Bibbo Associates, LLP**

Mill Pond Offices  
293 Route 100- Suite 203  
Somers, New York 10589  
(914) 277-5805



Matthew J. Gironda, P.E.  
NYS License No. 096030

**CONTACT INFORMATION AND CERTIFICATION**

**Applicant:**

Wolf Conservation Center  
7 Buck Run  
South Salem, NY 10590

**Project Engineer & Qualified Inspector:**

Bibbo Associates, LLP  
293 Route 100, Suite 203  
Somers, NY 10589  
Attn: Matthew J. Gironda, P.E., NY License 096030  
mgironda@bibboassociates.com  
(914) 277-5805 ext. 314

**Contractor's Certification:**

"I hereby certify that I understand and agree to comply with the terms and conditions of the SWPPP and agree to implement any corrective actions identified by the qualified inspector during a site inspection. I also understand that the *owner or operator* must comply with the terms and conditions of the New York State Pollutant Discharge Elimination System ("SPDES") General Permit for Stormwater Discharges from Construction Activities and that it is unlawful for any person to cause or contribute to a violation of water quality standards. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of the referenced permit and laws of the State of New York and could subject me to criminal, civil and/or administrative proceedings."

**Name & Title:** \_\_\_\_\_

**Signature:** \_\_\_\_\_

**Company Name:** \_\_\_\_\_

**Company Address** \_\_\_\_\_

**Phone:** \_\_\_\_\_

**Date:** \_\_\_\_\_

**Trained Contractor:** \_\_\_\_\_  
**(On-site, Daily)**

**Project Information:**

Project Title: Wolf Conservation Center  
Project Address: 7 Bick Run  
Tax Map Number: 21-10803-3, 81, 82, 83,88  
Project Area: 32.3 acres

**Applicant/Owner/ Operator Information:**

Wolf Conservation Center  
7 Buck Run  
South Salem, NY 10590  
Attn: Spencer Wilhelm  
(914) 763-2373  
Spencer@nywolf.org

**Certifying Engineer Information:**

Bibbo Associates, LLP  
293 Route 100, Suite 203  
Somers, NY 10589  
Attn: Matthew J. Gironda, P.E., NY License 096030  
mgironda@bibboassociates.com  
(914) 277-5805 ext. 314

**Short-Term Responsible Party for SWPPP Implementation:**

Short-term responsible parties for SWPPP Implementation will be site contractor as the owner's representative.

**Long-Term Responsible Party for SWPPP Implementation:**

Long-term responsible parties for SWPPP Implementation will be the property owner.

**Potential Party Responsible for Inspections as Required Under SPDES Permit:**

T.B.D

**Table of Contents:**

<b>1.0</b>	<b>Introduction</b>	<b>Page 1</b>
1.1	Project Description	Page 1
1.2	Existing Conditions	Page 2
1.3	Proposed Conditions	Page 3
<b>2.0</b>	<b>Stormwater Management</b>	<b>Page 3</b>
2.1	Methodology	Page 3
2.2	NYSDEC Requirements	Page 4
2.3	Water Quality Volume (WQv) / Runoff Reduction Volume (RRv)	
2.4	NYSDEC Redevelopment Requirements	Page 6
2.5	Stream Channel Protection Volume (CPv)	Page 6
2.6	Overbank & Extreme Flood Control	Page 7
2.7	NYCDEP Requirements	Page 8
2.8	Evaluation of the NYSDEC Wetland L-20	Page 8
<b>3.0</b>	<b>Erosion &amp; Sediment Control</b>	<b>Page 9</b>
3.1	Temporary Erosion & Sediment Control Practices	Page 9
3.2	Permanent Erosion & Sediment Control Practices	Page 10
<b>4.0</b>	<b>Maintenance &amp; Inspection Requirements</b>	<b>Page 12</b>
4.1	Short Term Maintenance & Inspection Requirements	Page 11
4.2	Long Term Maintenance & Inspection Requirements	Page 11
<b>5.0</b>	<b>Outstanding Violations or Enforcement Actions</b>	<b>Page 13</b>
<b>6.0</b>	<b>Conclusion</b>	<b>Page 13</b>

**Appendices:**

Appendix A: Water Quality Volume (WQv) / Runoff Reduction Volume (RRv)  
Calculations

Appendix B: Pre Development Peak Flow Analysis -  
(HydroCAD Output for 1, 10 & 100-year Storm Events)

Appendix C: Post Development Peak Flow Analysis -  
(HydroCAD Output for 1, 10 & 100-year Storm Events)

Appendix D: NRCS Soil Mapping

Appendix E: New York Standards and Specifications for Erosion and Sediment Control Construction Site Log Book

Appendix F: Northeast Regional Climate Center Precipitation Estimates

Appendix G: New York State Stormwater Management Design Manual Maintenance and Inspection Checklist.

Appendix H: Cultec Infiltration Chamber Operation and Maintenance Requirements.

Appendix I: Soil Testing Data

Appendix J: First Defense Stormwater Treatment Unit Operation and Maintenance Manual

Appendix K: Construction Sequence

Appendix L: Swale Sizing Calculations

Appendix M: Stormwater Maintenance and Access agreement

***Figures:***

Figure 1: Pre-development Drainage Basin Plan

Figure 2: Post-development Drainage Basin Plan

Figure 3: Redevelopment Map

Figure 4: Swale Sizing Map

## **1.0 Introduction**

### **1.1 Project Description**

The Wolf Conservation Center is proposing to construct a new educational pavilion and related site improvements to support their existing operations on the subject parcel. The project site is located on Buck Run in the Town of Lewisboro and consists of multiple tax parcels which were previously developed for single family residential use. The Wolf Center currently utilizes the existing dwellings and large wooded areas for their daily operations. In order to better facilitate the current use The Wolf Center is seeking to implement the following site improvements:

- Widening of the existing private road (Buck Run) which provides access to the project site from NYS Route 35.
- Demolition of the existing single-family residence located at 4 Buck Run.
- Construction of a new educational pavilion and supporting water supply and wastewater treatment components.
- Construction of new site wide Stormwater Management system.
- Construction of new and expanded parking areas as well as pedestrian access ways to support the new educational pavilion.
- Construction of new freezer building.
- Construction of 12 camping pods / Yurts.

The total land disturbance resulting from the proposed development including all individual lot construction is approximately 4.5 ac.±. As the total land disturbance exceeds 1-acre and the project is located within the NYC East of Hudson Watershed, coverage under the SPDES General Permit for Temporary Stormwater Discharges from Construction Activity (GP-0-20-001) is required and all proposed SMP's must be designed in accordance with the Enhanced Phosphorous Removal standards specified in Chapter 10 of the Design Manual. In addition, the project will also require a SWPPP approval from the NYCDEP per section 18-39 of their Rules and Regulations. For further discussion regarding NYCDEP requirements, refer to section 2.6 of this report.

Assuming a timely permitting process construction is anticipated to begin in the Spring of 2024 and take approximately 36 months to complete.

The following permits are required for the subject project:

**Wolf Conservation Center – Required Approvals**

Agency and Approval Required:	Status:
Town of Lewisboro Planning Board: Subdivision Approval (Preliminary & Final) Site Development Plan Approval Wetland Permit Stormwater Permit	Pending Pending Pending Pending
Westchester County Health Department Realty Subdivision Approval Change of Use Approval Public Water Supply Approval	Pending Pending Pending
New York City Dept. of Environmental Protection: SWPPP Approval	Pending
New York State Dept. of Environmental Conservation: Coverage under SPDES General Permit for Stormwater Discharges from Construction Activity (GP-0-20-001) Freshwater Wetland Activity Permit	Pending Pending Pending
New York State Department of Transportation: Highway Work Permit for Commercial Entrance	Pending

## **1.2 Existing Conditions**

The project site is located on the north side of NYS Rte. 35 at the intersection with Buck Run in the Town of Lewisboro. The site consists of six (6) separate tax parcels, four (4) of which contain existing single-family dwellings. The two (2) remaining parcels are largely undeveloped and are utilized for the wolf enclosures located in the north and northeastern portions of the property.

The majority of the site is wooded, with lawn areas in the vicinity of the existing dwellings. Existing onsite impervious surfaces consist of the private road (Buck Run), individual driveways and dwellings. Slopes onsite range from moderate to steep, and site topography generally directs runoff from north to south towards an offsite NYSDEC regulated wetland located southwest of the project site. The wetland flows from north to south under NYS Rte. 35 through a drainage culvert. The entrance of which was utilized as the design point in the enclosed peak flow analysis.

The Natural Resource Conservation Service Soil Survey identifies the onsite soils

as Charlton Loam (ChC), Paxton Fine Sandy Loam (PnC & PnD), Sutton Loam (SuB), and Woodbridge Loam (WdC). The Charlton soils are specified as Hydrologic Soil Group “B”, the Paxton soils are identified as Hydrologic soil group “C”, and the Sutton Loam as well as Woodbridge Loam are given dual “C/D” hydrologic group classifications.

### **1.3 Proposed Conditions**

As described above the proposed development consists of the following site improvements:

- Widening of the existing private road (Buck Run) which provides access to the project site from NYS Route 35.
- Demolition of the existing single-family residence located at 4 Buck Run.
- Construction of a new educational pavilion and supporting water supply and wastewater treatment components.
- Construction of new site wide Stormwater Management system.
- Construction of new and expanded parking areas as well as pedestrian access ways to support the new educational pavilion.
- Construction of new freezer building.
- Construction of 12 camping pods / Yurts.

Stormwater runoff generated by the proposed impervious surfaces will be captured and treated in two (2) subsurface infiltration systems and one (1) Infiltration Basin sized to provide storage volume for 100% of the contributing WQv to each practice in accordance with the NYSDEC WQV and RRv requirements. In addition to the proposed infiltration practices additional Green Infrastructure will be provided for impervious area reduction purposes in the form of tree planting along the site entrance.

Stormwater peak runoff rates following development will not exceed those in the existing condition. As proposed, stormwater runoff rates following development would have no adverse impacts on downstream properties or stormwater conveying systems. Similarly, considering the nature of the existing site conditions and the level of stormwater treatment proposed in the post-development condition, it is predicted that this development will not result in any adverse impacts to downstream reservoirs, streams, wetlands or watercourses.

## **2.0 Stormwater Management**

### **2.1 Methodology**

Stormwater management computations provided in this report are based upon the Soil Conservation Service (SCS) a.k.a. Natural Resource Conservation Service (NRCS), TR-20 methodologies and recommendations included in the NYSDEC Design Manual and GP-0-20-001 requirements. Pre-and post-development rates for stormwater runoff have been computed for comparison of the 1, 10, and 100-year



storm events using the precip.net, Northeast Regional Climate Center (NRCC) precipitation data website for New York and New England. Extreme precipitation tables for the specific site location for various storms have been provided in appendix I of this report.

The computer software entitled “HydroCAD Version 10.00-21” by Applied Microcomputer Systems has been utilized to determine runoff volumes, peak runoff rates, and high-water elevations in the stormwater treatment facilities. The precipitation values obtained for the above-mentioned storm events are summarized in the Table provided below:

<b>TABLE 1</b> <b>Precipitation Values based on 24-hours</b> <b>Accumulation Period and Recurrence Interval</b>	
<b>Storm Frequency</b>	<b>Precipitation (inches) – 24 hour</b>
1-year	2.83
10-year	4.03
100-year	9.04
90% Rainfall	1.50

## **2.2 NYSDEC Requirements**

The subject project lies within The New York City East of Hudson watershed as identified in Appendix C of GP-0-20-001, and proposes to disturb in excess of 1 acre of land. Therefore, a SWPPP with post construction stormwater management practices must be provided, and all proposed stormwater management practices must conform to the Enhanced Phosphorous Removal Standards specified in Chapter 10 of the NYSDEC Design Manual.

## **2.3 Water Quality Volume (WQv) / Runoff Reduction Volume (RRv)**

The stormwater management practices employed have been sized to satisfy the Water Quality Volume (WQv) and Runoff Reduction Volume (RRv) requirements specified in the Design Manual. In accordance with chapter 10, the minimum WQv/RRv for the subject project was determined based on the volume of runoff generated by the 1 year 24-hour storm event. For the portions of the subject project which consist of redevelopment activities, Water Quality Volume (WQv) sizing criteria was applied based on the Redevelopment rules specified in chapter 9 of the design manual. Figure 3 included at the end of this report has been prepared to illustrate the areas of new development as well as the areas where redevelopment sizing can be applied.

The WQv requirements set forth in the Design Manual specify that the goal for each site is to reduce the entire WQv through the use of green infrastructure practices (GIP's) and standard stormwater management practices (SMP's) with runoff reduction capacity. The proposed stormwater management practices (SMP's) to be utilized for WQv/RRv treatment are two (2) subsurface infiltration systems and one infiltration basin. Each infiltration practice is designated as a standard SMP with RRv capacity.

Calculations for the required WQv can be found in appendix "E" of this report and are summarized in the table provided below. It should be noted that WQv/RRv treatment is proposed for runoff generated by all proposed impervious surfaces as well as areas of existing impervious located within the project disturbance limits.

Calculations for the required water quality volume at design point 1 can be found in Appendix "A" of this report and are summarized in the table provided below. Please note the Impervious areas treated through the application of green infrastructure area reduction practices have been excluded.

<b>TABLE 2</b> <b>Water Quality Volume Summary</b>				
<b>SMP ID #</b>	<b>Watershed Area (Ac.)*</b>	<b>WQv Required (AF)**</b>	<b>RRv Minimum (AF)***</b>	<b>RRv Provided (AF)****</b>
1.1 P	0.722	0.075	0.022	0.075
INF 1.2	1.03	0.167	0.045	0.167
INF 1.3	0.046	0.01	0.003	0.01

(\*) Watershed area identified above is based on contributing drainage area to the proposed infiltration practices. All sub catchments which do not contain proposed impervious surfaces or provide RRv treatment through the use of Green Infrastructure Area Reduction Practices have been excluded from the WQv calculations summarized above.

(\*\*) Refer to HydroCAD output provided in Appendix C for 1-year storm runoff Volumes.

(\*\*\*) Refer to Minimum RRv calculations provided in Appendix A.

(\*\*\*\*) Refer to stage storage tables in HydroCAD routing contained in Appendix C. 100% RRv has been provided through the use of subsurface infiltration systems and infiltration basins.

As indicated in the above table, the project SWPPP provides treatment for 100% of the contributing WQv to the proposed infiltration practices which are designated as standard SMP's with runoff reduction capacity. Storage for 100% of the WQv is provided within each infiltration practice based on the volume of runoff generated by its contributing area. It should be noted that for the purposes of calculating the above summarized required WQv, the proposed gravel parking lot was considered impervious.

The HydroCAD routings contained in Appendix C account for an exfiltration rate utilized for modeling purposes to minimize oscillations within the infiltration system

outflow hydrographs. The exfiltration rate utilized has been confirmed based on soil testing results. The results of which are provided in Appendix I. The test results indicate suitable soils exist for infiltration as well as adequate separation to groundwater or ledge rock. Witnessed deep test descriptions and infiltration testing results will be provided in the final project SWPPP.

The subsurface infiltration systems have been designed offline. Diversion structures have been provided to divert inflow from storms larger than the 1 year to the downstream infiltration basins. In accordance with chapter 3 of the Design Manual extended detention storage has been provided in the infiltration basin and the outlet control structures have been designed peak flow attenuation requirements.

Specifically, stormwater is directed overland or via a piping network to the stormwater treatment facilities. Pipe sizing calculations for the proposed stormwater conveyance system will be included in the final project SWPPP. The diversion structures have been designed to detain stormwater to mitigate the 1-year storm volumes within the facilities. The infiltration basin has also been designed to fully infiltrate the 1-year storm volume prior to utilizing the outlet control structure. Additionally, overflow weirs have been provided over the 1-year, 24-hour storm high water elevation for the infiltration systems to in addition to detaining the 1-year volume also prevent uncontrolled spillage in case of clogging in the outlet control system.

It was the intent of the design to maintain the existing drainage patterns at the site. All stormwater treatment practices were sited at locations that can receive and treat the maximum amount of site areas.

## **2.4 NYSDEC Redevelopment Requirements**

As noted in previous sections of this report, the subject property contains existing impervious surfaces associated with the onsite dwellings, access road and driveways. Portions of these areas will be reconstructed as impervious and as such can be considered “Redevelopment Areas” per NYSDEC requirements.

There are several options listed on chapter 9 of the design manual which can be used to satisfy the redevelopment sizing criteria. This S.W.P.P.P. was prepared based on option II. Which specifies that a minimum of 25% of the WQv generated by the disturbed impervious area is captured and treated by the implementation of a standard SMP or reduced by application of green infrastructure techniques. As the subject project includes both areas of New Development as well as redevelopment activities, treatment is required for a minimum of 25% of the existing disturbed impervious area.

In order to demonstrate that runoff from a minimum of 25% of the existing impervious areas to be disturbed will be captured and treated, a Redevelopment Figure is included at the end of this report (Figure 3). The attached figure clearly illustrates that the project will provide WQv/RRv treatment through the use of standard SMP's with RRv capacity as well as Green Infrastructure area reduction

practices for 100% of all new impervious as well as more than 25% of existing disturbed impervious areas, thus satisfying the requirements of chapter 9.

## 2.5 Stream Channel Protection Volume (CP<sub>v</sub>)

Stream Channel Protection is intended to protect stream channels from erosion and the requirements are met by providing 24-hr extended detention of the 1-yr 24-hr rainfall event. However, this requirement may be waived if the entire Stream Channel Protection Volume (CP<sub>v</sub>) is reduced through the use of green infrastructure practices and or infiltration. Or if the site discharges directly to tidal waters or fifth order or larger streams as determined by the Strahler-Horton methodology (Section 4.3 of the Design Manual).

As a result of the chapter 10 design specifications, this project satisfies the CP<sub>v</sub> requirement as infiltration has been provided for 100% of the required WQ<sub>v</sub> which is equivalent to the 1-year storm runoff volume.

## 2.6 Overbank and Extreme Flood Control

Overbank Flood Control is intended to prevent an increase in the frequency and magnitude of out-of-bank flooding resulting from proposed development. To achieve Overbank Flood Control at a site the post-development peak rate of runoff generated by the 10-yr design storm must be attenuated to pre-development levels. The exception to this is for sites that discharge to fifth order streams or larger.

Extreme Flood Control is intended to prevent the risk of flood damage from large storms, maintain the pre-development 100-yr floodplain boundary, and protect the integrity of stormwater management practices. The requirement for Extreme Flood Control is met by attenuating the post-development peak flow rates generated by the 100-yr storm event to pre-development levels, unless the site discharges to a fifth order or larger stream.

As shown in the HydroCAD routings contained in Appendix C, peak flows from the 10- and 100-year storm events have been reduced to predevelopment levels with modification of summary of the pre development vs post development peak flows is provided below:

<b>TABLE 3</b> <b>Peak Runoff Discharges to Design Point 1</b>		
<b>Design Storm (yr)</b>	<b>Pre-Development Peak Runoff (cfs)</b>	<b>Post-Development Peak Runoff (cfs)</b>
1	8.0	7.5
10	26.4	24.8
100	61.0	57.7

## 2.7 NYCDEP Requirements

The subject project is located within the NYC East of Hudson Watershed and a NYCDEP SWPPP approval is required as it meets or exceeds the following thresholds listed in the Rules and Regulations described below:

**§18-39(b)(3)(iv): A land clearing or land grading project, involving two (2) or more acres, located at least in part within the limiting distance of 100 feet of a watercourse or wetland, or within the limiting distance of 300 feet of a reservoir, reservoir stem or controlled lake or on a slope exceeding 15 percent;**

The proposed site improvements will result in land disturbance in excess of 2 acres, a portion of which will take on slopes exceeding 15% thus exceeding the threshold specified in §18-39(b)(3)(iv) of the Rules and Regulations.

The NYCDEP Rules and Regulations generally match the requirements of the NYSDEC and Town of Lewisboro with several exceptions. There are two (2) exceptions of note discussed below.

The first exception of note being that two (2) different standard SMP's are required in series when the contributing drainage area to that SMP is greater than 20% impervious or an infiltration practice is not provided. As noted previously infiltration practices will provide treatment of stormwater runoff from all proposed impervious surfaces, therefore two (2) SMP's in series are not required.

The second exception is the NYCDEP requires that the minimum required stormwater treatment volume used shall be the greater of the 1-year 24 hour storm event or the volume generated by the 90% storm.

In accordance with chapter 4 of the Design Manual the following equation was used to determine the water quality volume generated by the 90% rainfall event:

$$WQ_v = \frac{(P)(R_v)(A)}{12}$$

Where,

- WQ<sub>v</sub> = Runoff Volume (acre-feet)
- P = 90% Rainfall Value (inches) – (Use 1.5")
- R<sub>v</sub> = 0.05 + 0.009(I), where I is percent Impervious Cover  
(use 0.2 min)
- A = Contributing Drainage Area in acres

A comparison of the Runoff volumes for each infiltration system's respective contributing area are summarized in the table below:

<b>Water Quality Volume Comparison Summary (90% Storm Runoff Volume vs 1-Year Storm Runoff Volume)</b>					
<b>Sub Area</b>	<b>P (in.) Rainfall Value</b>	<b>Rv</b>	<b>Area (Ac.)</b>	<b>WQv (af) (90% Storm)</b>	<b>WQv (af) (1-Yr Storm)</b>
1.1S	1.5	0.43	0.722	0.039	0.075
1.2S	1.5	0.67	0.813	0.088	0.167
1.3S	1.5	0.95	0.046	0.005	0.010

As discussed in previous sections of this report all proposed SMP's have been sized based on their contributing runoff volume generated by the 1-year 24-hour storm event, which as summarized above provides the larger runoff volume.

## **2.8 Stormwater Impact Evaluation of the NYSDEC Wetland L-20**

As shown on the drainage figures, runoff from the Wolf Center property enters into NYSDEC Wetland L-20. The stormwater impacts originated from Wolf Center development on the existing NYSDEC Wetland have been evaluated based on the total runoff volume. The total runoff volume has been increased by the proposed development and the effects of such have been evaluated using the greatest increase distributed over the surface area of the wetland assuming an instantaneous affect. NYSDEC wetland L-20 has an approximate area of 276.2 acres as shown on the NYSDEC Environmental Resource Mapper. The slight increase in runoff volume of 0.085 af associated with the proposed development would yield an instantaneous increase in the vertical water surface elevation of the wetland of approximately 0.003 inches which is insignificant.

## **3.0 Erosion and Sediment Control**

The plans provide for specific erosion and sediment controls to be employed during construction. It is the intent to provide effective erosion control by minimizing land disturbance at one given time, containing sediment from disturbed areas, treating runoff where possible, and stabilizing disturbed soils as soon as possible. The directives specified on the plans and in this report serve as a minimum for erosion and sediment control. Further practices and measures may be required pursuant to onsite inspections in conformance with the requirements of the SPDES #GP-0-15-002 permit. As per the SPDES permit onsite, inspections are to be performed at a rate of at least two (2) site inspections every seven (7) calendar days. The two (2) inspections shall be separated by a minimum of two (2) full calendar days. All erosion and sediment control practices specified for this site shall be in conformance with the New York Standards & Specifications for Erosion & Sediment Control.

### **3.1 Temporary Erosion and Sediment Control Practices**

Listed below are the Temporary Erosion and Sediment Control Practices specified for the subject project. All practices shall be installed and maintained in conformance with the New York Standards & Specifications for Erosion & Sediment Control:

- Stabilized Construction Entrance
- Silt Fence
- Drop Inlet Protection
- Soil Stockpiles
- Debris Control

A stabilized construction entrance should be installed at construction vehicle access points. The construction entrance is designed to prevent outgoing trucks from tracking soil onto the public roadways. Construction details specifying installation requirements can be found on the plan.

The silt fence for the site will consist of a geotextile fabric installed at the toe of all disturbed slopes and parallel to the contours. The silt fence is intended to reduce runoff velocity and intercept sediment-laden runoff. Construction details specifying the proposed installation and type of permissible silt fence can be found on the plans.

Drop inlet protection for the site will consist of stone and concrete block wrapped with wire mesh surrounding the catch basins. The purpose of the stone and block inlet protection is to filter stormwater runoff and prevent sediment laden runoff from entering the drainage system through existing or proposed drain inlet structures.

Soil stockpiles are to be stabilized with vegetation and surrounded with silt fencing. This will ensure the topsoil that is stripped from the site during construction will be protected for use during final grading and that no sediment from the stockpiles will be deposited downstream.

Construction debris, such as sheet metal, wood scrap, paper and insulation products, Styrofoam cups and paper wrappers can become windblown litter over and off the site if neglected. Suitable and ample refuse containers shall be provided on the site and emptied when full. Any scattered debris shall be picked up and placed in containers on an as needed basis.

### **3.2 Permanent Erosion and Sediment Control Practices**

The intent of the permanent erosion and sediment control practices is to permanently stabilize the ground surface via vegetative and structural practices, while controlling and reducing runoff velocities. The following permanent erosion & sediment control practices are proposed for the site:

- Land Grading
- Vegetation

Land grading is the reshaping of the existing land surface in accordance with the grading plan. Proper land grading is an essential component of the erosion control plan, as well as the stormwater pollution prevention plan. Proper grading will ensure the intended drainage areas are directed to the stormwater management practices.

Vegetation will be provided on all disturbed soils not covered by the proposed impervious surfaces. Permanent vegetation will reduce runoff velocities, filter stormwater runoff, and minimize soil erosion. Optimum times for planting are the early spring and fall; however, plantings can be started in the summer provided adequate mulch and moisture is supplied.

#### **4.0 Maintenance & Inspection Requirements**

##### **4.1 Short Term Maintenance and Inspection Requirements**

As per the SPDES permit onsite, inspections are to be performed at a rate of at least two (2) site inspections every seven (7) calendar days. The two (2) inspections shall be separated by a minimum of two (2) full calendar days. All erosion and sediment control practices specified for this site shall be in conformance with the New York Standards & Specifications for Erosion & Sediment Control.

Inspections performed during construction should verify that all practices are functioning properly, correctly maintained, and that accumulated sediment is removed from all control structures. The inspector must also examine the site for any evidence of soil erosion, the potential for pollutants to enter the storm drain system, turbid discharge at all outfalls, and the potential for soil and mud to be transported on the public roadway at the site entrance. In addition to these general guidelines, the project plans will provide more specific erosion control guidelines, as well as a construction sequence to guide the contractor through the construction process. Discussed below are specific maintenance and inspection requirements for the temporary practices to be employed at the site.

During construction, the silt fence should be inspected weekly to ensure correct installation. In addition, any accumulated sediment resulting in “bulges” in the silt fence should be removed and mixed with onsite soil. Any damaged or torn silt fence should be replaced.

The construction entrance should be checked to ensure no sediment is being deposited onto the public roadway. Should sediment be observed, it should be removed from the street, and the stone in the construction entrance replaced.

The drop inlet protection shall be checked for accumulated sediment on a monthly basis and after significant rainfall. Any accumulated sediment shall be removed and the crushed stone shall be replaced as needed.

Once construction is completed and the site has been stabilized, a “Notice of Termination” shall be filed. At this point limited maintenance requirements are



anticipated.

Throughout project construction, the responsibility for installation, maintenance and repair of erosion controls and stormwater management practices (SMP's) will rest with the site contractor as the owner's representative.

#### **4.2 Long Term Maintenance and Inspection Requirements**

Once final stabilization is achieved and construction complete, only limited maintenance will be required. A copy of the Maintenance and Inspection Checklists from Appendix "G" of the New York State Stormwater Management Design Manual is included in Appendix "G" of this report to serve as a guide for maintaining and inspecting the stormwater infiltration practices.

Inspections of the following items should be performed at a minimum annually and following significant rainstorms within a 24 hour period.

##### Infiltration Systems:

Refer to manufacturer's maintenance schedule in Appendix J for more specific maintenance requirements.

- Inspect the infiltration systems to ensure accumulated water is infiltrating into the soil, and debris has not entered the diversion manholes and pretreatment structures; any debris should be removed. Once debris is removed, if stormwater is still not infiltrating contact a professional engineer licensed in the State of New York to examine the system.
- Inspection of the outlet of the overflow pipe to ensure it is not plugged or clogged.

##### Infiltration Basin:

- Inspect emergency spillway and rock outlet protection for any dislodged stones or signs of erosion; additional stone / rip-rap shall be added as needed.
- Inspect outlet structure for clogging and debris/sediment accumulation. Any accumulated sediment/debris shall be removed and properly disposed of.
- Basin berm shall be inspected annually and mowed as needed to prevent woody growth.
- Vegetative establishment within the infiltration basin is critical to its function. Any dead, invasive, or diseased species shall be removed immediately and replaced. Additional seed and mulch shall be used as needed to maintain healthy vegetative cover.

##### Hydrodynamic Separators (CDS) - Pretreatment Units:

Refer to manufacturer's maintenance schedule in Appendix M for more specific

maintenance requirements.

- Inspect after heavy rainfall greater than ½" in 24 hours for the first year to determine an appropriate maintenance schedule. Subsequent inspections are reduced to quarterly.
- When the sediment volume reaches within 24"-30" of the water surface, the system should be maintained.
- Maintenance is to be performed using a vacuum truck and removing the accumulated sediment pile and debris.

Catch Basins and Drain Manholes:

- Inspect monthly and after heavy rain storms >½" in 24 hours for sediment accumulation in sumps. Accumulated sediment should be removed immediately.

## **5.0 Outstanding Violations or Enforcement Actions**

There are no known outstanding violations or enforcement actions against this property, the owner or the applicant. There are no stormwater discharges associated with industrial activity from this site.

## **6.0 Conclusion**

The Stormwater Pollution Prevention Plan prepared for the subject project has been prudently designed to manage stormwater runoff from both qualitative and quantitative standpoints. Proper implementation of this plan will ensure meeting water quality and quantity standards as required by the NYSDEC based on current New York State guidelines as well as most recent guidelines set forth by the NYCDEP.

## Appendix A:

Water Quality Volume (WQv) / Runoff Reduction Volume (RRv)  
Calculations

Project **WOLF CENTER****Water Quality Volume (WQv) Calculation**Basin ID: **Design Point**

Rev. April 25, 2023

Rev. April 27, 2021

February 3, 2023

The required stormwater quality volume will be determined using "New York State Stormwater Management Design Manual – GP 0-20-0001" Unified Stormwater Sizing Criteria. Since the project is located within the NYCDEP Watershed the "Chapter 10- Enhanced Phosphorus Removal Standards" will apply.

Rainfall events for this project have been obtained from "precip.net", Northeast Regional Climate Center - NRCC - Precipitation Data website for New York and New England. Extreme Precipitation Tables for the specific site location for various storms have been downloaded to HydroCAD Version 10.00-24 computer model.

Precipitation distribution curves are generated for each grid directly eliminating the need to use a static Type III curve.

**Original WQv:**

Subcatchment Area (A):	81,969 sq.ft.
Rainfall (P):	2.83 in.
Impervious Area	49,780 sq.ft.
Percent Imperviousness(I):	60.73 %
WQv from HydroCAD =	11,587 cu.ft.
	<b>or</b>
	0.2660 ac.ft.

**Area Reduced WQv:**

Subcatchment Area (A):	79,069 sq.ft.
Rainfall (P):	2.83 in.
Impervious Area	46,880 sq.ft.
Percent Imperviousness(I):	59.29 %
WQv from HydroCAD (Required) =	10,977 cu.ft.
	<b>or</b>
	0.2520 ac.ft.

**Remaining WQv for Standard Treatment:**

Subcatchment Area (A):	0 sq.ft.
Rainfall (P):	2.83 in.
Impervious Area	2,900 sq.ft.
Percent Imperviousness(I):	0.00 %
WQv from HydroCAD =	0 cu.ft.
	<b>or</b>
	0.0000 ac.ft.

Project **WOLF CENTER****Specified Runoff Reduction Volume (S-RRv)**

$$RRv \text{ (in acre-feet of storage)} = [(P)(Rv)(Ai)] / 12$$

Basin ID: **1.1S** HSG: **B**  
P = Rainfall (inches) 2.83 in  
Rv = 0.05+0.009(I) where I is 100% impervious 0.95  
Aic = Total area of new impervious cover 2,856 ft<sup>2</sup>  
S = Hydrologic Soil Group (HSG) Specific Reduction Factor (S) 0.40  
HSG A = 0.55 HSG C = 0.30  
HSG B = 0.40 HSG D = 0.20  
Ai = (S)(Aic) 1,142 ft<sup>2</sup>  
Ai = impervious cover targeted for runoff reduction

therefore:

$$RRv = \frac{[(P)(Rv)(Ai)]}{12} = \frac{2.83 \times 0.95 \times 1,142}{12} = \frac{256 \text{ cu.ft.}}{0.0059 \text{ ac.ft.}}$$

Project **WOLF CENTER****Specified Runoff Reduction Volume (S-RRv)**

$$RRv \text{ (in acre-feet of storage)} = [(P)(Rv)(Ai)] / 12$$

Basin ID: **1.1S** HSG: **C**  
P = Rainfall (inches) 2.83 in  
Rv = 0.05+0.009(I) where I is 100% impervious 0.95  
Aic = Total area of new impervious cover 10,354 ft<sup>2</sup>  
S = Hydrologic Soil Group (HSG) Specific Reduction Factor (S) 0.30  
HSG A = 0.55 HSG C = 0.30  
HSG B = 0.40 HSG D = 0.20  
Ai = (S)(Aic) 3,106 ft<sup>2</sup>  
Ai = impervious cover targeted for runoff reduction

therefore:

$$RRv = \frac{[(P)(Rv)(Ai)]}{12} = \frac{2.83 \times 0.95 \times 3,106}{12} = \frac{696 \text{ cu.ft.}}{12} = 0.0160 \text{ ac.ft.}$$

Project **WOLF CENTER****Specified Runoff Reduction Volume (S-RRv)**

$$RRv \text{ (in acre-feet of storage)} = [(P)(Rv)(Ai)] / 12$$

Basin ID: **1.2S** HSG: **C**  
P = Rainfall (inches) 2.83 in  
Rv = 0.05+0.009(I) where I is 100% impervious 0.95  
Aic = Total area of new impervious cover 31,670 ft<sup>2</sup>  
S = Hydrologic Soil Group (HSG) Specific Reduction Factor (S) 0.30  
HSG A = 0.55 HSG C = 0.30  
HSG B = 0.40 HSG D = 0.20  
Ai = (S)(Aic) 9,501 ft<sup>2</sup>  
Ai = impervious cover targeted for runoff reduction

therefore:

$$RRv = \frac{[(P)(Rv)(Ai)]}{12} = \frac{2.83 \times 0.95 \times 9,501}{12} = \begin{matrix} 2,129 \text{ cu.ft.} \\ 0.0489 \text{ ac.ft} \end{matrix}$$

Project **WOLF CENTER****Specified Runoff Reduction Volume (S-RRv)**

$$RRv \text{ (in acre-feet of storage)} = [(P)(Rv)(Ai)] / 12$$

Basin ID: **1.3S**HSG: **C**

P = Rainfall (inches)

2.83 in

Rv = 0.05+0.009(I) where I is 100% impervious

0.95

Aic = Total area of new impervious cover

2,000 ft<sup>2</sup>

S = Hydrologic Soil Group (HSG) Specific Reduction Factor (S)

0.30

HSG A = 0.55

HSG C = 0.30

HSG B = 0.40

HSG D = 0.20

Ai = (S)(Aic)

600 ft<sup>2</sup>

Ai = impervious cover targeted for runoff reduction

therefore:

**RRv =**

$$\begin{array}{ccccccc} [(P) & (Rv) & (Ai)] & / & 12 \\ 2.83 & 0.95 & 600 & / & 12 = \end{array}$$

**134 cu.ft.**  
**0.0031 ac.ft**



Project **WOLF CENTER****Specified Runoff Reduction Volume (S-RRv)**

$$RRv \text{ (in acre-feet of storage)} = [(P)(Rv)(Ai)] / 12$$

Basin ID: **Total- Design Point**      HSG: **C**  
 P = Rainfall (inches)      2.83 in  
 Rv = 0.05+0.009(I) where I is 100% impervious      0.95  
 Aic = Total area of new impervious cover      44,880 ft<sup>2</sup>  
 S = Hydrologic Soil Group (HSG) Specific Reduction Factor (S)      0.30  
     HSG A = 0.55      HSG C = 0.30  
     HSG B = 0.40      HSG D = 0.20  
 Ai = (S)(Aic)      13,464 ft<sup>2</sup>  
 Ai = impervious cover targeted for runoff reduction

therefore:

$$RRv = [(P) (Rv) (Ai)] / 12$$

1.1S	RRv =	2.83	0.95	1,142	/ 12 =	256 cu.ft. 0.0059 ac.ft
1.1S	RRv =	2.83	0.95	3,106	/ 12 =	696 cu.ft. 0.0160 ac.ft
1.2S	RRv =	2.83	0.95	9,501	/ 12 =	2,129 cu.ft. 0.0489 ac.ft
1.3S	RRv =	2.83	0.95	600	/ 12 =	134 cu.ft. 0.0031 ac.ft
<b>Total</b>	<b>RRv =</b>	<b>2.83</b>	<b>0.95</b>	<b>13,464</b>	<b>/ 12 =</b>	<b>3,016 cu.ft. 0.0692 ac.ft</b>

Project **WOLF CENTER****Area Reduction Practices**Basin ID: **Design Point**

	<b><u>Total Area</u></b>	<b><u>Area of Impervious (AI)</u></b>
<b><i>Original Drainage Area (DA):</i></b>	81,969 sq.ft.	49,780 sq.ft.
Conservation of Natural Areas:	- 0 sq.ft.	- 0 sq.ft.
Riparian Buffers / Filter Strips:	- 0 sq.ft.	- 0 sq.ft.
Tree Planting / Tree Preservation:	- <u>2,900</u> sq.ft.	- <u>2,900</u> sq.ft.
<b>Total Area Reduction:</b>	= 2,900 sq.ft.	
<b>Total AI Reduction:</b>	=	2,900 sq.ft.
<b><i>Remaining DA:</i></b>	<b>79,069 sq.ft.</b>	-
<b><i>Remaining AI:</i></b>	-	<b>46,880 sq.ft.</b>
or	<b>1.8152 ac.ft.</b>	<b>1.0762 ac.ft.</b>

Project **WOLF CENTER****Source Control Practices**Basin ID: **1.1S**HSG: **B & C**Practice Type: **I** = Infiltration

(I)=Infiltration, (B)=Bioretention, (D)=Dry Swale, (V)=Vegetated Swale, (G)=Green Roof, (R)=Rain Garden,  
(S)=Stormwater Planters, (C)=Cisterns/Rain Barrels, (P)=Porous Pavement

**DA Tributary to Practice(s):****AI to Practice(s):****Total Area:**

31,450 sq.ft.

13,210 sq.ft.

Subcatchment Area (A): 31,450 sq.ft.  
Rainfall (P): 2.83 in.  
Impervious Area 13,210 sq.ft.  
Percent Imperviousness(I): 42.00 %

WQv from HydroCAD = **3,267 cu.ft.**  
or  
**0.0750 ac.ft.**

**Allowable Runoff Reduction Volume (RRv)**Practice Type: **I** = Infiltration **HSG: B & C**

Allowable runoff reduction volume for Infiltration is 100%

3,267 x 1.00 = **3,267 cu.ft.**  
or  
**0.0750 ac.ft.**

Project **WOLF CENTER****Source Control Practices**Basin ID: **1.2S**HSG: **C**Practice Type: **I** = Infiltration

(I)=Infiltration, (B)=Bioretention, (D)=Dry Swale, (V)=Vegetated Swale, (G)=Green Roof, (R)=Rain Garden,  
(S)=Stormwater Planters, (C)=Cisterns/Rain Barrels, (P)=Porous Pavement

**DA Tributary to Practice(s):****AI to Practice(s):****Total Area:**

45,619 sq.ft.

31,670 sq.ft.

Subcatchment Area (A): 45,619 sq.ft.  
Rainfall (P): 2.83 in.  
Impervious Area 31,670 sq.ft.  
Percent Imperviousness(I): 69.42 %

WQv from HydroCAD = **7,275 cu.ft.**  
or  
**0.1670 ac.ft.**

**Allowable Runoff Reduction Volume (RRv)**Practice Type: **I** = Infiltration HSG: **C**

Allowable runoff reduction volume for Infiltration in C soil = 100% of WQv

7,275 x 1.00 = **7,275 cu.ft.**  
or  
**0.1670 ac.ft.**

Project **WOLF CENTER****Source Control Practices**Basin ID: **1.3S**HSG: **C**Practice Type: **I** = Infiltration

(I)=Infiltration, (B)=Bioretention, (D)=Dry Swale, (V)=Vegetated Swale, (G)=Green Roof, (R)=Rain Garden,  
(S)=Stormwater Planters, (C)=Cisterns/Rain Barrels, (P)=Porous Pavement

**DA Tributary to Practice(s):****AI to Practice(s):****Total Area:**

2,000 sq.ft.

2,000 sq.ft.

Subcatchment Area (A): 2,000 sq.ft.

Rainfall (P): 2.83 in.

Impervious Area 2,000 sq.ft.

Percent Imperviousness(I): 100.00 %

WQv from HydroCAD = **436 cu.ft.**

or

**0.0100 ac.ft.****Allowable Runoff Reduction Volume (RRv)**Practice Type: **I** = InfiltrationHSG: **C**

Allowable runoff reduction volume for Infiltration in C soil = 100% of WQv

436 x 1.00 = **436 cu.ft.**

or

**0.0100 ac.ft.**

Project WOLF CENTER**Total Runoff Reduction Volume**Basin ID: **Design Point****Total RRv provided:**

Original WQv - Area Reduced WQv: 11,587 - 10,977 =  $\frac{\text{RRv}}{610 \text{ cu.ft.}}$   
 Source Control WQv Treatment Practices:

Basin:

1.1S = 3,267 cu.ft.  
 1.2S = 7,275 cu.ft.  
 1.3S = 436 cu.ft.

**Total RRv provided: 11,587 cu.ft.**  
 or  
**0.266 ac.ft.**

Is RRv provided **11,587 cu.ft.**  $\geq$  Original WQv **11,587 cu.ft.**  
 0.266 ac.ft 0.266 ac.ft

**Yes**

Is RRv provided **11,587 cu.ft.**  $\geq$  S-RRv (min. RRv) **3,016 cu.ft.**  
 0.266 ac.ft 0.069 ac.ft



**Yes**

Total drainage area treated with runoff reduction / source control practices:

Area Reduction Practices: 2,900 sq.ft. or **0.067 Acres**  
 Source Control Practices: 79,069 sq.ft. or **1.815 Acres**  
**Total: 1.882 Acres**

Total impervious area treated with runoff reduction / source control practices:


Area Reduction Practices: 0 sq.ft. or **0.000 Acres**  
 Source Control Practices: 46,880 sq.ft. or **1.076 Acres**  
**Total: 1.076 Acres**



Subcat



Reach



Pond



Link

#### Routing Diagram for Wolf Center - WQV

Prepared by Bibbo Associates, llp., Printed 4/21/2023  
HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

## Wolf Center - WQV

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

Printed 4/21/2023

Page 2

### Area Listing (all nodes)

Area (acres)	CN	Description (subcatchment-numbers)
0.067	98	(1.0WQV)
0.120	61	>75% Grass cover, Good, HSG B (1.1S)
0.619	74	>75% Grass cover, Good, HSG C (1.1S, 1.2S)
0.111	98	Proposed Building (1.2S)
0.043	98	Proposed Courtyard Imp (1.2S)
0.295	98	Proposed Pavement (1.1S)
0.574	98	Proposed Pavement & Walkway (1.2S)
0.046	98	Proposed Pods and Facilities (1.3S)
0.008	98	Proposed Sidewalk (1.1S)



**Wolf Center - WQV**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 1-yr Rainfall=2.83"*

Printed 4/21/2023

Page 3

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN

Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Subcatchment 1.0WQV: 1.0WQV**Runoff Area=2,900 sf 100.00% Impervious Runoff Depth=2.60"  
Flow Length=1,585' Tc=23.5 min CN=98 Runoff=0.1 cfs 0.014 af**Subcatchment 1.1S: 1.1S**Runoff Area=31,450 sf 42.00% Impervious Runoff Depth=1.25"  
Tc=6.0 min CN=82 Runoff=1.1 cfs 0.075 af**Subcatchment 1.2S: 1.2S**Runoff Area=45,619 sf 69.42% Impervious Runoff Depth=1.91"  
Tc=6.0 min CN=91 Runoff=2.5 cfs 0.167 af**Subcatchment 1.3S: 1.3S**Runoff Area=2,000 sf 100.00% Impervious Runoff Depth=2.60"  
Tc=6.0 min CN=98 Runoff=0.1 cfs 0.010 af**Pond 1.1P: Infiltration Basin 1.1**Peak Elev=452.60' Storage=633 cf Inflow=1.1 cfs 0.075 af  
Discarded=0.3 cfs 0.075 af Primary=0.0 cfs 0.000 af Secondary=0.0 cfs 0.000 af Outflow=0.3 cfs 0.075 af**Pond DS1.2: Diversion Structure 1.2**Peak Elev=469.20' Inflow=2.5 cfs 0.167 af  
Primary=2.5 cfs 0.167 af Secondary=0.0 cfs 0.000 af Outflow=2.5 cfs 0.167 af**Pond DS1.3: Diversion Structure 1.3**Peak Elev=593.39' Inflow=0.1 cfs 0.010 af  
Primary=0.1 cfs 0.010 af Secondary=0.0 cfs 0.000 af Outflow=0.1 cfs 0.010 af**Pond INF 1.2: Infiltration System 1.2**Peak Elev=466.22' Storage=0.006 af Inflow=2.5 cfs 0.167 af  
Outflow=1.8 cfs 0.167 af**Pond INF 1.3: Infiltration System 1.3**Peak Elev=593.20' Storage=0.001 af Inflow=0.1 cfs 0.010 af  
Outflow=0.1 cfs 0.010 af**Link DP: Design Point**Inflow=0.1 cfs 0.014 af  
Primary=0.1 cfs 0.014 af

**Wolf Center - WQV**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

Buck Run 24-hr S1 1-yr Rainfall=2.83"

Printed 4/21/2023

Page 4

**Summary for Subcatchment 1.0WQV: 1.0WQV**

Runoff = 0.1 cfs @ 12.26 hrs, Volume= 0.014 af, Depth= 2.60"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Buck Run 24-hr S1 1-yr Rainfall=2.83"

	Area (sf)	CN	Description
*	2,900	98	
	2,900		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.4	100	0.0900	0.15		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.40"
12.1	1,485	0.1670	2.04		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
23.5	1,585	Total			

**Subcatchment 1.0WQV: 1.0WQV****Hydrograph**

**Wolf Center - WQV**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

Buck Run 24-hr S1 1-yr Rainfall=2.83"

Printed 4/21/2023

Page 5

**Summary for Subcatchment 1.1S: 1.1S**


Runoff = 1.1 cfs @ 12.04 hrs, Volume= 0.075 af, Depth= 1.25"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Buck Run 24-hr S1 1-yr Rainfall=2.83"

	Area (sf)	CN	Description
*	12,870	98	Proposed Pavement
*	340	98	Proposed Sidewalk
	5,235	61	>75% Grass cover, Good, HSG B
	13,005	74	>75% Grass cover, Good, HSG C
	31,450	82	Weighted Average
	18,240		58.00% Pervious Area
	13,210		42.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Subcatchment 1.1S: 1.1S****Hydrograph**

**Wolf Center - WQV**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

Buck Run 24-hr S1 1-yr Rainfall=2.83"

Printed 4/21/2023

Page 6

**Summary for Subcatchment 1.2S: 1.2S**


Runoff = 2.5 cfs @ 12.04 hrs, Volume= 0.167 af, Depth= 1.91"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Buck Run 24-hr S1 1-yr Rainfall=2.83"

	Area (sf)	CN	Description
*	24,985	98	Proposed Pavement & Walkway
*	4,815	98	Proposed Building
	10,849	74	>75% Grass cover, Good, HSG C
*	1,870	98	Proposed Courtyard Imp
	3,100	74	>75% Grass cover, Good, HSG C
<hr/>			
	45,619	91	Weighted Average
	13,949		30.58% Pervious Area
	31,670		69.42% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Subcatchment 1.2S: 1.2S****Hydrograph**

### Summary for Subcatchment 1.3S: 1.3S

Runoff = 0.1 cfs @ 12.04 hrs, Volume= 0.010 af, Depth= 2.60"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs


Buck Run 24-hr S1 1-yr Rainfall=2.83"

Area (sf)	CN	Description
*	2,000	98 Proposed Pods and Facilities
2,000		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

### Subcatchment 1.3S: 1.3S

#### Hydrograph



### Summary for Pond 1.1P: Infiltration Basin 1.1

Inflow Area = 0.722 ac, 42.00% Impervious, Inflow Depth = 1.25" for 1-yr event  
 Inflow = 1.1 cfs @ 12.04 hrs, Volume= 0.075 af  
 Outflow = 0.3 cfs @ 12.30 hrs, Volume= 0.075 af, Atten= 70%, Lag= 15.5 min  
 Discarded = 0.3 cfs @ 12.30 hrs, Volume= 0.075 af  
 Primary = 0.0 cfs @ 0.00 hrs, Volume= 0.000 af  
 Secondary = 0.0 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 452.60' @ 12.30 hrs Surf.Area= 718 sf Storage= 633 cf

Plug-Flow detention time= 14.9 min calculated for 0.075 af (100% of inflow)  
 Center-of-Mass det. time= 14.9 min ( 879.1 - 864.2 )

Volume	Invert	Avail.Storage	Storage Description
#1	451.00'	9,077 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
451.00	125	0	0
452.00	447	286	286
454.00	1,356	1,803	2,089
456.00	2,634	3,990	6,079
457.00	3,362	2,998	9,077

Device	Routing	Invert	Outlet Devices
#1	Primary	450.30'	<b>12.0" Round Culvert</b> L= 58.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 450.30' / 449.50' S= 0.0138 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Device 1	454.75'	<b>4.0" Vert. Orifice/Grate</b> C= 0.600
#3	Device 1	455.50'	<b>30.0" x 48.0" Horiz. Orifice/Grate</b> C= 0.600 Limited to weir flow at low heads
#4	Discarded	451.00'	<b>20.000 in/hr Exfiltration over Surface area</b> Phase-In= 0.10'
#5	Secondary	456.00'	<b>10.0' long x 10.0' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.49 2.56 2.70 2.69 2.68 2.69 2.67 2.64


**Discarded OutFlow** Max=0.3 cfs @ 12.30 hrs HW=452.59' (Free Discharge)  
 ↳ **4=Exfiltration** (Exfiltration Controls 0.3 cfs)

**Primary OutFlow** Max=0.0 cfs @ 0.00 hrs HW=451.00' TW=0.00' (Dynamic Tailwater)  
 ↳ **1=Culvert** (Passes 0.0 cfs of 1.7 cfs potential flow)  
 ↳ ↳ **2=Orifice/Grate** ( Controls 0.0 cfs)  
 ↳ ↳ ↳ **3=Orifice/Grate** ( Controls 0.0 cfs)

**Secondary OutFlow** Max=0.0 cfs @ 0.00 hrs HW=451.00' TW=0.00' (Dynamic Tailwater)  
 ↳ **5=Broad-Crested Rectangular Weir** ( Controls 0.0 cfs)

**Pond 1.1P: Infiltration Basin 1.1**

**Hydrograph**



**Wolf Center - WQV**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 1-yr Rainfall=2.83"*

Printed 4/21/2023

Page 10

**Stage-Area-Storage for Pond 1.1P: Infiltration Basin 1.1**

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
451.00	125	0
451.10	157	14
451.20	189	31
451.30	222	52
451.40	254	76
451.50	286	103
451.60	318	133
451.70	350	166
451.80	383	203
451.90	415	243
452.00	447	286
452.10	492	333
452.20	538	384
452.30	583	441
452.40	629	501
452.50	674	566
452.60	720	636
452.70	765	710
452.80	811	789
452.90	856	872
453.00	902	960
453.10	947	1,053
453.20	992	1,150
453.30	1,038	1,251
453.40	1,083	1,357
453.50	1,129	1,468
453.60	1,174	1,583
453.70	1,220	1,703
453.80	1,265	1,827
453.90	1,311	1,956
454.00	1,356	2,089
454.10	1,420	2,228
454.20	1,484	2,373
454.30	1,548	2,525
454.40	1,612	2,683
454.50	1,676	2,847
454.60	1,739	3,018
454.70	1,803	3,195
454.80	1,867	3,378
454.90	1,931	3,568
455.00	1,995	3,765
455.10	2,059	3,967
455.20	2,123	4,176
455.30	2,187	4,392
455.40	2,251	4,614
455.50	2,315	4,842
455.60	2,378	5,077
455.70	2,442	5,318
455.80	2,506	5,565
455.90	2,570	5,819
456.00	2,634	6,079
456.10	2,707	6,346
456.20	2,780	6,620
456.30	2,852	6,902
456.40	2,925	7,191
456.50	2,998	7,487
456.60	3,071	7,790
456.70	3,144	8,101
456.80	3,216	8,419
456.90	3,289	8,744
457.00	<b>3,362</b>	<b>9,077</b>



### Summary for Pond DS1.2: Diversion Structure 1.2

Inflow Area = 1.047 ac, 69.42% Impervious, Inflow Depth = 1.91" for 1-yr event  
 Inflow = 2.5 cfs @ 12.04 hrs, Volume= 0.167 af  
 Outflow = 2.5 cfs @ 12.04 hrs, Volume= 0.167 af, Atten= 0%, Lag= 0.0 min  
 Primary = 2.5 cfs @ 12.04 hrs, Volume= 0.167 af  
 Secondary = 0.0 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 469.20' @ 12.04 hrs


Device	Routing	Invert	Outlet Devices
#1	Primary	466.67'	<b>8.0" Round Culvert</b> L= 6.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 466.67' / 466.60' S= 0.0117 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.35 sf
#2	Device 3	469.35'	<b>2.0' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32
#3	Secondary	462.28'	<b>8.0" Round Culvert</b> L= 103.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 462.28' / 448.16' S= 0.1371 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.35 sf

**Primary OutFlow** Max=2.4 cfs @ 12.04 hrs HW=469.09' TW=466.16' (Dynamic Tailwater)  
 ↑ **1=Culvert** (Inlet Controls 2.4 cfs @ 6.95 fps)

**Secondary OutFlow** Max=0.0 cfs @ 0.00 hrs HW=462.28' TW=0.00' (Dynamic Tailwater)  
 ↑ **3=Culvert** ( Controls 0.0 cfs)  
 ↑ **2=Broad-Crested Rectangular Weir** ( Controls 0.0 cfs)

### Pond DS1.2: Diversion Structure 1.2

Hydrograph



**Stage-Area-Storage for Pond DS1.2: Diversion Structure 1.2**

Elevation (feet)	Storage (cubic-feet)	Elevation (feet)	Storage (cubic-feet)	Elevation (feet)	Storage (cubic-feet)
462.28	0	464.92	0	467.56	0
462.32	0	464.96	0	467.60	0
462.36	0	465.00	0	467.64	0
462.40	0	465.04	0	467.68	0
462.44	0	465.08	0	467.72	0
462.48	0	465.12	0	467.76	0
462.52	0	465.16	0	467.80	0
462.56	0	465.20	0	467.84	0
462.60	0	465.24	0	467.88	0
462.64	0	465.28	0	467.92	0
462.68	0	465.32	0	467.96	0
462.72	0	465.36	0	468.00	0
462.76	0	465.40	0	468.04	0
462.80	0	465.44	0	468.08	0
462.84	0	465.48	0	468.12	0
462.88	0	465.52	0	468.16	0
462.92	0	465.56	0	468.20	0
462.96	0	465.60	0	468.24	0
463.00	0	465.64	0	468.28	0
463.04	0	465.68	0	468.32	0
463.08	0	465.72	0	468.36	0
463.12	0	465.76	0	468.40	0
463.16	0	465.80	0	468.44	0
463.20	0	465.84	0	468.48	0
463.24	0	465.88	0	468.52	0
463.28	0	465.92	0	468.56	0
463.32	0	465.96	0	468.60	0
463.36	0	466.00	0	468.64	0
463.40	0	466.04	0	468.68	0
463.44	0	466.08	0	468.72	0
463.48	0	466.12	0	468.76	0
463.52	0	466.16	0	468.80	0
463.56	0	466.20	0	468.84	0
463.60	0	466.24	0	468.88	0
463.64	0	466.28	0	468.92	0
463.68	0	466.32	0	468.96	0
463.72	0	466.36	0	469.00	0
463.76	0	466.40	0	469.04	0
463.80	0	466.44	0	469.08	0
463.84	0	466.48	0	469.12	0
463.88	0	466.52	0	469.16	0
463.92	0	466.56	0	469.20	0
463.96	0	466.60	0	469.24	0
464.00	0	466.64	0	469.28	0
464.04	0	466.68	0	469.32	0
464.08	0	466.72	0		
464.12	0	466.76	0		
464.16	0	466.80	0		
464.20	0	466.84	0		
464.24	0	466.88	0		
464.28	0	466.92	0		
464.32	0	466.96	0		
464.36	0	467.00	0		
464.40	0	467.04	0		
464.44	0	467.08	0		
464.48	0	467.12	0		
464.52	0	467.16	0		
464.56	0	467.20	0		
464.60	0	467.24	0		
464.64	0	467.28	0		
464.68	0	467.32	0		
464.72	0	467.36	0		
464.76	0	467.40	0		
464.80	0	467.44	0		
464.84	0	467.48	0		
464.88	0	467.52	0		

### Summary for Pond DS1.3: Diversion Structure 1.3

Inflow Area = 0.046 ac, 100.00% Impervious, Inflow Depth = 2.60" for 1-yr event  
 Inflow = 0.1 cfs @ 12.04 hrs, Volume= 0.010 af  
 Outflow = 0.1 cfs @ 12.04 hrs, Volume= 0.010 af, Atten= 0%, Lag= 0.0 min  
 Primary = 0.1 cfs @ 12.04 hrs, Volume= 0.010 af  
 Secondary = 0.0 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 593.39' @ 12.04 hrs


Device	Routing	Invert	Outlet Devices
#1	Primary	593.10'	<b>4.0" Round Culvert</b> L= 6.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 593.10' / 593.00' S= 0.0167 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.09 sf
#2	Secondary	595.20'	<b>8.0" Round Culvert</b> L= 154.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 595.20' / 590.00' S= 0.0338 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.35 sf

**Primary OutFlow** Max=0.1 cfs @ 12.04 hrs HW=593.38' TW=593.14' (Dynamic Tailwater)  
 ↑ **1=Culvert** (Barrel Controls 0.1 cfs @ 2.24 fps)

**Secondary OutFlow** Max=0.0 cfs @ 0.00 hrs HW=593.10' TW=0.00' (Dynamic Tailwater)  
 ↑ **2=Culvert** ( Controls 0.0 cfs)

### Pond DS1.3: Diversion Structure 1.3

#### Hydrograph



**Stage-Area-Storage for Pond DS1.3: Diversion Structure 1.3**

Elevation (feet)	Storage (cubic-feet)	Elevation (feet)	Storage (cubic-feet)	Elevation (feet)	Storage (cubic-feet)
593.10	0	594.42	0	595.74	0
593.12	0	594.44	0	595.76	0
593.14	0	594.46	0	595.78	0
593.16	0	594.48	0	595.80	0
593.18	0	594.50	0	595.82	0
593.20	0	594.52	0	595.84	0
593.22	0	594.54	0	595.86	0
593.24	0	594.56	0		
593.26	0	594.58	0		
593.28	0	594.60	0		
593.30	0	594.62	0		
593.32	0	594.64	0		
593.34	0	594.66	0		
593.36	0	594.68	0		
593.38	0	594.70	0		
593.40	0	594.72	0		
593.42	0	594.74	0		
593.44	0	594.76	0		
593.46	0	594.78	0		
593.48	0	594.80	0		
593.50	0	594.82	0		
593.52	0	594.84	0		
593.54	0	594.86	0		
593.56	0	594.88	0		
593.58	0	594.90	0		
593.60	0	594.92	0		
593.62	0	594.94	0		
593.64	0	594.96	0		
593.66	0	594.98	0		
593.68	0	595.00	0		
593.70	0	595.02	0		
593.72	0	595.04	0		
593.74	0	595.06	0		
593.76	0	595.08	0		
593.78	0	595.10	0		
593.80	0	595.12	0		
593.82	0	595.14	0		
593.84	0	595.16	0		
593.86	0	595.18	0		
593.88	0	595.20	0		
593.90	0	595.22	0		
593.92	0	595.24	0		
593.94	0	595.26	0		
593.96	0	595.28	0		
593.98	0	595.30	0		
594.00	0	595.32	0		
594.02	0	595.34	0		
594.04	0	595.36	0		
594.06	0	595.38	0		
594.08	0	595.40	0		
594.10	0	595.42	0		
594.12	0	595.44	0		
594.14	0	595.46	0		
594.16	0	595.48	0		
594.18	0	595.50	0		
594.20	0	595.52	0		
594.22	0	595.54	0		
594.24	0	595.56	0		
594.26	0	595.58	0		
594.28	0	595.60	0		
594.30	0	595.62	0		
594.32	0	595.64	0		
594.34	0	595.66	0		
594.36	0	595.68	0		
594.38	0	595.70	0		
594.40	0	595.72	0		

### Summary for Pond INF 1.2: Infiltration System 1.2

Inflow Area = 1.047 ac, 69.42% Impervious, Inflow Depth = 1.91" for 1-yr event  
 Inflow = 2.5 cfs @ 12.04 hrs, Volume= 0.167 af  
 Outflow = 1.8 cfs @ 12.05 hrs, Volume= 0.167 af, Atten= 26%, Lag= 0.5 min  
 Discarded = 1.8 cfs @ 12.05 hrs, Volume= 0.167 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 466.22' @ 12.10 hrs Surf.Area= 0.076 ac Storage= 0.006 af

Plug-Flow detention time= 1.3 min calculated for 0.167 af (100% of inflow)  
 Center-of-Mass det. time= 1.3 min ( 821.9 - 820.6 )

Volume	Invert	Avail.Storage	Storage Description
#1A	466.01'	0.064 af	<b>30.50'W x 108.50'L x 3.54'H Field A</b> 0.269 af Overall - 0.109 af Embedded = 0.160 af x 40.0% Voids
#2A	466.51'	0.109 af	<b>Cultec R-330XLHD x 90</b> Inside #1 Effective Size= 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf Overall Size= 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap Row Length Adjustment= +1.50' x 7.45 sf x 6 rows
			0.173 af Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	466.01'	<b>24.000 in/hr Exfiltration over Horizontal area</b> Phase-In= 0.10'

**Discarded OutFlow** Max=1.8 cfs @ 12.05 hrs HW=466.18' (Free Discharge)  
 ↳ **1=Exfiltration** (Exfiltration Controls 1.8 cfs)

### Pond INF 1.2: Infiltration System 1.2

Hydrograph



**Wolf Center - WQV**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 1-yr Rainfall=2.83"*

Printed 4/21/2023

Page 16

**Stage-Area-Storage for Pond INF 1.2: Infiltration System 1.2**

Elevation (feet)	Horizontal (acres)	Storage (acre-feet)	Elevation (feet)	Horizontal (acres)	Storage (acre-feet)	Elevation (feet)	Horizontal (acres)	Storage (acre-feet)
466.01	<b>0.076</b>	0.000	467.33	0.076	0.068	468.65	0.076	0.143
466.03	0.076	0.001	467.35	0.076	0.069	468.67	0.076	0.144
466.05	0.076	0.001	467.37	0.076	0.070	468.69	0.076	0.145
466.07	0.076	0.002	467.39	0.076	0.072	468.71	0.076	0.146
466.09	0.076	0.002	467.41	0.076	0.073	468.73	0.076	0.147
466.11	0.076	0.003	467.43	0.076	0.074	468.75	0.076	0.147
466.13	0.076	0.004	467.45	0.076	0.075	468.77	0.076	0.148
466.15	0.076	0.004	467.47	0.076	0.077	468.79	0.076	0.149
466.17	0.076	0.005	467.49	0.076	0.078	468.81	0.076	0.150
466.19	0.076	0.005	467.51	0.076	0.079	468.83	0.076	0.151
466.21	0.076	0.006	467.53	0.076	0.080	468.85	0.076	0.151
466.23	0.076	0.007	467.55	0.076	0.082	468.87	0.076	0.152
466.25	0.076	0.007	467.57	0.076	0.083	468.89	0.076	0.153
466.27	0.076	0.008	467.59	0.076	0.084	468.91	0.076	0.153
466.29	0.076	0.009	467.61	0.076	0.085	468.93	0.076	0.154
466.31	0.076	0.009	467.63	0.076	0.086	468.95	0.076	0.155
466.33	0.076	0.010	467.65	0.076	0.088	468.97	0.076	0.155
466.35	0.076	0.010	467.67	0.076	0.089	468.99	0.076	0.156
466.37	0.076	0.011	467.69	0.076	0.090	469.01	0.076	0.157
466.39	0.076	0.012	467.71	0.076	0.091	469.03	0.076	0.157
466.41	0.076	0.012	467.73	0.076	0.093	469.05	0.076	0.158
466.43	0.076	0.013	467.75	0.076	0.094	469.07	0.076	0.159
466.45	0.076	0.013	467.77	0.076	0.095	469.09	0.076	0.159
466.47	0.076	0.014	467.79	0.076	0.096	469.11	0.076	0.160
466.49	0.076	0.015	467.81	0.076	0.097	469.13	0.076	0.160
466.51	0.076	0.015	467.83	0.076	0.099	469.15	0.076	0.161
466.53	0.076	0.017	467.85	0.076	0.100	469.17	0.076	0.162
466.55	0.076	0.018	467.87	0.076	0.101	469.19	0.076	0.162
466.57	0.076	0.019	467.89	0.076	0.102	469.21	0.076	0.163
466.59	0.076	0.020	467.91	0.076	0.103	469.23	0.076	0.163
466.61	0.076	0.022	467.93	0.076	0.105	469.25	0.076	0.164
466.63	0.076	0.023	467.95	0.076	0.106	469.27	0.076	0.165
466.65	0.076	0.024	467.97	0.076	0.107	469.29	0.076	0.165
466.67	0.076	0.026	467.99	0.076	0.108	469.31	0.076	0.166
466.69	0.076	0.027	468.01	0.076	0.109	469.33	0.076	0.166
466.71	0.076	0.028	468.03	0.076	0.110	469.35	0.076	0.167
466.73	0.076	0.030	468.05	0.076	0.112	469.37	0.076	0.168
466.75	0.076	0.031	468.07	0.076	0.113	469.39	0.076	0.168
466.77	0.076	0.032	468.09	0.076	0.114	469.41	0.076	0.169
466.79	0.076	0.033	468.11	0.076	0.115	469.43	0.076	0.170
466.81	0.076	0.035	468.13	0.076	0.116	469.45	0.076	0.170
466.83	0.076	0.036	468.15	0.076	0.117	469.47	0.076	0.171
466.85	0.076	0.037	468.17	0.076	0.118	469.49	0.076	0.171
466.87	0.076	0.039	468.19	0.076	0.119	469.51	0.076	0.172
466.89	0.076	0.040	468.21	0.076	0.121	469.53	0.076	0.173
466.91	0.076	0.041	468.23	0.076	0.122	469.55	0.076	<b>0.173</b>
466.93	0.076	0.042	468.25	0.076	0.123			
466.95	0.076	0.044	468.27	0.076	0.124			
466.97	0.076	0.045	468.29	0.076	0.125			
466.99	0.076	0.046	468.31	0.076	0.126			
467.01	0.076	0.048	468.33	0.076	0.127			
467.03	0.076	0.049	468.35	0.076	0.128			
467.05	0.076	0.050	468.37	0.076	0.129			
467.07	0.076	0.051	468.39	0.076	0.130			
467.09	0.076	0.053	468.41	0.076	0.131			
467.11	0.076	0.054	468.43	0.076	0.132			
467.13	0.076	0.055	468.45	0.076	0.133			
467.15	0.076	0.057	468.47	0.076	0.134			
467.17	0.076	0.058	468.49	0.076	0.135			
467.19	0.076	0.059	468.51	0.076	0.136			
467.21	0.076	0.060	468.53	0.076	0.137			
467.23	0.076	0.062	468.55	0.076	0.138			
467.25	0.076	0.063	468.57	0.076	0.139			
467.27	0.076	0.064	468.59	0.076	0.140			
467.29	0.076	0.065	468.61	0.076	0.141			
467.31	0.076	0.067	468.63	0.076	0.142			

### Summary for Pond INF 1.3: Infiltration System 1.3

Inflow Area = 0.046 ac, 100.00% Impervious, Inflow Depth = 2.60" for 1-yr event  
 Inflow = 0.1 cfs @ 12.04 hrs, Volume= 0.010 af  
 Outflow = 0.1 cfs @ 12.05 hrs, Volume= 0.010 af, Atten= 33%, Lag= 0.7 min  
 Discarded = 0.1 cfs @ 12.05 hrs, Volume= 0.010 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 593.20' @ 12.11 hrs Surf.Area= 0.006 ac Storage= 0.001 af

Plug-Flow detention time= 2.3 min calculated for 0.010 af (100% of inflow)  
 Center-of-Mass det. time= 2.3 min ( 764.0 - 761.8 )

Volume	Invert	Avail.Storage	Storage Description
#1A	593.00'	0.006 af	<b>16.00'W x 17.50'L x 3.54'H Field A</b> 0.023 af Overall - 0.008 af Embedded = 0.015 af x 40.0% Voids
#2A	593.50'	0.008 af	<b>Cultec R-330XLHD x 6 Inside #1</b> Effective Size= 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf Overall Size= 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap Row Length Adjustment= +1.50' x 7.45 sf x 3 rows
			0.014 af Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	593.00'	<b>14.000 in/hr Exfiltration over Horizontal area</b> Phase-In= 0.10'

**Discarded OutFlow** Max=0.1 cfs @ 12.05 hrs HW=593.16' (Free Discharge)

↳ **1=Exfiltration** (Exfiltration Controls 0.1 cfs)

### Pond INF 1.3: Infiltration System 1.3

#### Hydrograph



Stage-Area-Storage for Pond INF 1.3: Infiltration System 1.3

Elevation (feet)	Horizontal (acres)	Storage (acre-feet)	Elevation (feet)	Horizontal (acres)	Storage (acre-feet)	Elevation (feet)	Horizontal (acres)	Storage (acre-feet)
593.00	0.006	0.000	594.32	0.006	0.005	595.64	0.006	0.011
593.02	0.006	0.000	594.34	0.006	0.006	595.66	0.006	0.011
593.04	0.006	0.000	594.36	0.006	0.006	595.68	0.006	0.011
593.06	0.006	0.000	594.38	0.006	0.006	595.70	0.006	0.012
593.08	0.006	0.000	594.40	0.006	0.006	595.72	0.006	0.012
593.10	0.006	0.000	594.42	0.006	0.006	595.74	0.006	0.012
593.12	0.006	0.000	594.44	0.006	0.006	595.76	0.006	0.012
593.14	0.006	0.000	594.46	0.006	0.006	595.78	0.006	0.012
593.16	0.006	0.000	594.48	0.006	0.006	595.80	0.006	0.012
593.18	0.006	0.000	594.50	0.006	0.006	595.82	0.006	0.012
593.20	0.006	0.001	594.52	0.006	0.006	595.84	0.006	0.012
593.22	0.006	0.001	594.54	0.006	0.006	595.86	0.006	0.012
593.24	0.006	0.001	594.56	0.006	0.007	595.88	0.006	0.012
593.26	0.006	0.001	594.58	0.006	0.007	595.90	0.006	0.012
593.28	0.006	0.001	594.60	0.006	0.007	595.92	0.006	0.012
593.30	0.006	0.001	594.62	0.006	0.007	595.94	0.006	0.012
593.32	0.006	0.001	594.64	0.006	0.007	595.96	0.006	0.012
593.34	0.006	0.001	594.66	0.006	0.007	595.98	0.006	0.012
593.36	0.006	0.001	594.68	0.006	0.007	596.00	0.006	0.012
593.38	0.006	0.001	594.70	0.006	0.007	596.02	0.006	0.013
593.40	0.006	0.001	594.72	0.006	0.007	596.04	0.006	0.013
593.42	0.006	0.001	594.74	0.006	0.007	596.06	0.006	0.013
593.44	0.006	0.001	594.76	0.006	0.008	596.08	0.006	0.013
593.46	0.006	0.001	594.78	0.006	0.008	596.10	0.006	0.013
593.48	0.006	0.001	594.80	0.006	0.008	596.12	0.006	0.013
593.50	0.006	0.001	594.82	0.006	0.008	596.14	0.006	0.013
593.52	0.006	0.001	594.84	0.006	0.008	596.16	0.006	0.013
593.54	0.006	0.001	594.86	0.006	0.008	596.18	0.006	0.013
593.56	0.006	0.002	594.88	0.006	0.008	596.20	0.006	0.013
593.58	0.006	0.002	594.90	0.006	0.008	596.22	0.006	0.013
593.60	0.006	0.002	594.92	0.006	0.008	596.24	0.006	0.013
593.62	0.006	0.002	594.94	0.006	0.008	596.26	0.006	0.013
593.64	0.006	0.002	594.96	0.006	0.008	596.28	0.006	0.013
593.66	0.006	0.002	594.98	0.006	0.009	596.30	0.006	0.013
593.68	0.006	0.002	595.00	0.006	0.009	596.32	0.006	0.013
593.70	0.006	0.002	595.02	0.006	0.009	596.34	0.006	0.013
593.72	0.006	0.002	595.04	0.006	0.009	596.36	0.006	0.013
593.74	0.006	0.003	595.06	0.006	0.009	596.38	0.006	0.013
593.76	0.006	0.003	595.08	0.006	0.009	596.40	0.006	0.014
593.78	0.006	0.003	595.10	0.006	0.009	596.42	0.006	0.014
593.80	0.006	0.003	595.12	0.006	0.009	596.44	0.006	0.014
593.82	0.006	0.003	595.14	0.006	0.009	596.46	0.006	0.014
593.84	0.006	0.003	595.16	0.006	0.009	596.48	0.006	0.014
593.86	0.006	0.003	595.18	0.006	0.009	596.50	0.006	0.014
593.88	0.006	0.003	595.20	0.006	0.010	596.52	0.006	0.014
593.90	0.006	0.003	595.22	0.006	0.010	596.54	0.006	0.014
593.92	0.006	0.003	595.24	0.006	0.010			
593.94	0.006	0.004	595.26	0.006	0.010			
593.96	0.006	0.004	595.28	0.006	0.010			
593.98	0.006	0.004	595.30	0.006	0.010			
594.00	0.006	0.004	595.32	0.006	0.010			
594.02	0.006	0.004	595.34	0.006	0.010			
594.04	0.006	0.004	595.36	0.006	0.010			
594.06	0.006	0.004	595.38	0.006	0.010			
594.08	0.006	0.004	595.40	0.006	0.010			
594.10	0.006	0.004	595.42	0.006	0.010			
594.12	0.006	0.004	595.44	0.006	0.011			
594.14	0.006	0.005	595.46	0.006	0.011			
594.16	0.006	0.005	595.48	0.006	0.011			
594.18	0.006	0.005	595.50	0.006	0.011			
594.20	0.006	0.005	595.52	0.006	0.011			
594.22	0.006	0.005	595.54	0.006	0.011			
594.24	0.006	0.005	595.56	0.006	0.011			
594.26	0.006	0.005	595.58	0.006	0.011			
594.28	0.006	0.005	595.60	0.006	0.011			
594.30	0.006	0.005	595.62	0.006	0.011			




### Summary for Link DP: Design Point

Inflow Area = 0.789 ac, 46.90% Impervious, Inflow Depth = 0.22" for 1-yr event  
 Inflow = 0.1 cfs @ 12.26 hrs, Volume= 0.014 af  
 Primary = 0.1 cfs @ 12.26 hrs, Volume= 0.014 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs


### Link DP: Design Point

#### Hydrograph



## Appendix B:



Pre Development Peak Flow Analysis -  
(HydroCAD Output for 1, 10 & 100-year Storm Events)



1.0S



Design Point



**Wolf Center - Pre- 4-20-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Wolf Center 24-hr S1 1-yr Rainfall=2.83"*

Printed 10/20/2023

Page 2

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN

Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Subcatchment1.0S: 1.0S**Runoff Area=784,606 sf 5.65% Impervious Runoff Depth=0.75"  
Flow Length=1,750' Tc=25.7 min CN=73 Runoff=8.0 cfs 1.133 af**Link DP: Design Point**Inflow=8.0 cfs 1.133 af  
Primary=8.0 cfs 1.133 af

**Wolf Center - Pre- 4-20-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

Wolf Center 24-hr S1 1-yr Rainfall=2.83"

Printed 10/20/2023

Page 3

**Summary for Subcatchment 1.0S: 1.0S**

Runoff = 8.0 cfs @ 12.34 hrs, Volume= 1.133 af, Depth= 0.75"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Wolf Center 24-hr S1 1-yr Rainfall=2.83"

Area (sf)	CN	Description
* 36,175	98	Existing Pavement
* 8,130	98	Existing Buildings
10,353	61	>75% Grass cover, Good, HSG B
13,090	74	>75% Grass cover, Good, HSG C
8,325	80	>75% Grass cover, Good, HSG D
1,182	89	Gravel roads, HSG C
8,804	87	Dirt roads, HSG C
26,408	55	Woods, Good, HSG B
507,257	70	Woods, Good, HSG C
164,882	77	Woods, Good, HSG D
784,606	73	Weighted Average
740,301		94.35% Pervious Area
44,305		5.65% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.4	100	0.0900	0.15		<b>Sheet Flow,</b> Woods: Light underbrush n= 0.400 P2= 3.40"
6.8	860	0.1800	2.12		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
0.1	20	0.0200	2.87		<b>Shallow Concentrated Flow,</b> Paved Kv= 20.3 fps
7.4	770	0.1200	1.73		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
25.7	1,750	Total			

**Subcatchment 1.0S: 1.0S****Hydrograph**


### Summary for Link DP: Design Point

Inflow Area = 18.012 ac, 5.65% Impervious, Inflow Depth = 0.75" for 1-yr event  
 Inflow = 8.0 cfs @ 12.34 hrs, Volume= 1.133 af  
 Primary = 8.0 cfs @ 12.34 hrs, Volume= 1.133 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

### Link DP: Design Point

#### Hydrograph



**Wolf Center - Pre- 4-20-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Wolf Center 24-hr S1 10-yr Rainfall=5.08"*

Printed 10/20/2023

Page 5

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN

Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Subcatchment1.0S: 1.0S**

Runoff Area=784,606 sf 5.65% Impervious Runoff Depth=2.34"

Flow Length=1,750' Tc=25.7 min CN=73 Runoff=26.4 cfs 3.517 af

**Link DP: Design Point**

Inflow=26.4 cfs 3.517 af

Primary=26.4 cfs 3.517 af

**Wolf Center - Pre- 4-20-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

Wolf Center 24-hr S1 10-yr Rainfall=5.08"

Printed 10/20/2023

Page 6

**Summary for Subcatchment 1.0S: 1.0S**

Runoff = 26.4 cfs @ 12.31 hrs, Volume= 3.517 af, Depth= 2.34"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Wolf Center 24-hr S1 10-yr Rainfall=5.08"

Area (sf)	CN	Description
* 36,175	98	Existing Pavement
* 8,130	98	Existing Buildings
10,353	61	>75% Grass cover, Good, HSG B
13,090	74	>75% Grass cover, Good, HSG C
8,325	80	>75% Grass cover, Good, HSG D
1,182	89	Gravel roads, HSG C
8,804	87	Dirt roads, HSG C
26,408	55	Woods, Good, HSG B
507,257	70	Woods, Good, HSG C
164,882	77	Woods, Good, HSG D
784,606	73	Weighted Average
740,301		94.35% Pervious Area
44,305		5.65% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.4	100	0.0900	0.15		<b>Sheet Flow,</b> Woods: Light underbrush n= 0.400 P2= 3.40"
6.8	860	0.1800	2.12		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
0.1	20	0.0200	2.87		<b>Shallow Concentrated Flow,</b> Paved Kv= 20.3 fps
7.4	770	0.1200	1.73		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
25.7	1,750	Total			

**Subcatchment 1.0S: 1.0S****Hydrograph**




### Summary for Link DP: Design Point

Inflow Area = 18.012 ac, 5.65% Impervious, Inflow Depth = 2.34" for 10-yr event  
 Inflow = 26.4 cfs @ 12.31 hrs, Volume= 3.517 af  
 Primary = 26.4 cfs @ 12.31 hrs, Volume= 3.517 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

### Link DP: Design Point

#### Hydrograph



**Wolf Center - Pre- 4-20-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Wolf Center 24-hr S1 100-yr Rainfall=9.04"*

Printed 10/20/2023

Page 8

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN

Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Subcatchment1.0S: 1.0S**

Runoff Area=784,606 sf 5.65% Impervious Runoff Depth=5.74"

Flow Length=1,750' Tc=25.7 min CN=73 Runoff=61.0 cfs 8.618 af

**Link DP: Design Point**

Inflow=61.0 cfs 8.618 af

Primary=61.0 cfs 8.618 af

**Wolf Center - Pre- 4-20-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

Wolf Center 24-hr S1 100-yr Rainfall=9.04"

Printed 10/20/2023

Page 9

**Summary for Subcatchment 1.0S: 1.0S**

Runoff = 61.0 cfs @ 12.31 hrs, Volume= 8.618 af, Depth= 5.74"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Wolf Center 24-hr S1 100-yr Rainfall=9.04"

Area (sf)	CN	Description
* 36,175	98	Existing Pavement
* 8,130	98	Existing Buildings
10,353	61	>75% Grass cover, Good, HSG B
13,090	74	>75% Grass cover, Good, HSG C
8,325	80	>75% Grass cover, Good, HSG D
1,182	89	Gravel roads, HSG C
8,804	87	Dirt roads, HSG C
26,408	55	Woods, Good, HSG B
507,257	70	Woods, Good, HSG C
164,882	77	Woods, Good, HSG D
784,606	73	Weighted Average
740,301		94.35% Pervious Area
44,305		5.65% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.4	100	0.0900	0.15		<b>Sheet Flow,</b> Woods: Light underbrush n= 0.400 P2= 3.40"
6.8	860	0.1800	2.12		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
0.1	20	0.0200	2.87		<b>Shallow Concentrated Flow,</b> Paved Kv= 20.3 fps
7.4	770	0.1200	1.73		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
25.7	1,750	Total			

**Subcatchment 1.0S: 1.0S****Hydrograph**


### Summary for Link DP: Design Point

Inflow Area = 18.012 ac, 5.65% Impervious, Inflow Depth = 5.74" for 100-yr event  
 Inflow = 61.0 cfs @ 12.31 hrs, Volume= 8.618 af  
 Primary = 61.0 cfs @ 12.31 hrs, Volume= 8.618 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs



### Link DP: Design Point

#### Hydrograph



## Appendix C:


Post Development Peak Flow Analysis –  
(HydroCAD Output for 1, 10 & 100-year Storm Events)



Subcat



Reach



Pond



Link

**Routing Diagram for Wolf Center - Post-4-20- 2023**  
 Prepared by Bibbo Associates, Ilp., Printed 10/20/2023  
 HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

**Wolf Center - Post-4-20- 2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 1-yr Rainfall=2.83"*

Printed 10/20/2023

Page 2

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN

Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Subcatchment1.0S: 1.0S**Runoff Area=705,538 sf 4.54% Impervious Runoff Depth=0.75"  
Flow Length=1,585' Tc=23.5 min CN=73 Runoff=7.5 cfs 1.019 af**Subcatchment1.1S: 1.1S**Runoff Area=31,450 sf 42.00% Impervious Runoff Depth=1.25"  
Tc=6.0 min CN=82 Runoff=1.1 cfs 0.075 af**Subcatchment1.2S: 1.2S**Runoff Area=45,619 sf 69.42% Impervious Runoff Depth=1.91"  
Tc=6.0 min CN=91 Runoff=2.5 cfs 0.167 af**Subcatchment1.3S: 1.3S**Runoff Area=2,000 sf 100.00% Impervious Runoff Depth=2.60"  
Tc=6.0 min CN=98 Runoff=0.1 cfs 0.010 af**Pond 1.1P: Infiltration Basin 1.1**Peak Elev=452.60' Storage=633 cf Inflow=1.1 cfs 0.075 af  
Discarded=0.3 cfs 0.075 af Primary=0.0 cfs 0.000 af Secondary=0.0 cfs 0.000 af Outflow=0.3 cfs 0.075 af**Pond DS1.2: Diversion Structure 1.2**Peak Elev=469.20' Inflow=2.5 cfs 0.167 af  
Primary=2.5 cfs 0.167 af Secondary=0.0 cfs 0.000 af Outflow=2.5 cfs 0.167 af**Pond DS1.3: Diversion Structure 1.3**Peak Elev=593.39' Inflow=0.1 cfs 0.010 af  
Primary=0.1 cfs 0.010 af Secondary=0.0 cfs 0.000 af Outflow=0.1 cfs 0.010 af**Pond INF 1.2: Infiltration System 1.2**Peak Elev=466.22' Storage=0.006 af Inflow=2.5 cfs 0.167 af  
Outflow=1.8 cfs 0.167 af**Pond INF 1.3: Infiltration System 1.3**Peak Elev=593.20' Storage=0.001 af Inflow=0.1 cfs 0.010 af  
Outflow=0.1 cfs 0.010 af**Link DP: Design Point**Inflow=7.5 cfs 1.019 af  
Primary=7.5 cfs 1.019 af

**Wolf Center - Post-4-20- 2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

Buck Run 24-hr S1 1-yr Rainfall=2.83"

Printed 10/20/2023

Page 3

**Summary for Subcatchment 1.0S: 1.0S**


Runoff = 7.5 cfs @ 12.31 hrs, Volume= 1.019 af, Depth= 0.75"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Buck Run 24-hr S1 1-yr Rainfall=2.83"

	Area (sf)	CN	Description
*	18,932	98	Existing Pavement
*	6,135	98	Existing Buildings
	5,607	87	Dirt roads, HSG C
*	6,970	98	Proposed Pavement
*	1,405	61	Existing >75% Grass cover, Good, HSG B
*	3,457	80	Proposed >75% Grass cover, Good, HSG D
*	3,083	61	Proposed >75% Grass cover, Good, HSG B
*	2,900	74	Existing >75% Grass cover, Good, HSG C
*	17,714	74	Proposed >75% Grass cover, Good, HSG C
	13,520	89	Gravel roads, HSG C
	22,115	55	Woods, Good, HSG B
	417,935	70	Woods, Good, HSG C
	150,505	77	Woods, Good, HSG D
	35,260	71	Meadow, non-grazed, HSG C
	705,538	73	Weighted Average
	673,501		95.46% Pervious Area
	32,037		4.54% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.4	100	0.0900	0.15		<b>Sheet Flow,</b>
					Woods: Light underbrush n= 0.400 P2= 3.40"
12.1	1,485	0.1670	2.04		<b>Shallow Concentrated Flow,</b>
					Woodland Kv= 5.0 fps
23.5	1,585	Total			

**Subcatchment 1.0S: 1.0S****Hydrograph**



**Wolf Center - Post-4-20- 2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

Buck Run 24-hr S1 1-yr Rainfall=2.83"

Printed 10/20/2023

Page 4

**Summary for Subcatchment 1.1S: 1.1S**


Runoff = 1.1 cfs @ 12.04 hrs, Volume= 0.075 af, Depth= 1.25"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Buck Run 24-hr S1 1-yr Rainfall=2.83"

	Area (sf)	CN	Description
*	12,870	98	Proposed Pavement
*	340	98	Proposed Sidewalk
	5,235	61	>75% Grass cover, Good, HSG B
	13,005	74	>75% Grass cover, Good, HSG C
	31,450	82	Weighted Average
	18,240		58.00% Pervious Area
	13,210		42.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Subcatchment 1.1S: 1.1S****Hydrograph**

### Summary for Subcatchment 1.2S: 1.2S

Runoff = 2.5 cfs @ 12.04 hrs, Volume= 0.167 af, Depth= 1.91"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs


Buck Run 24-hr S1 1-yr Rainfall=2.83"

	Area (sf)	CN	Description
*	24,985	98	Proposed Pavement & Walkway
*	4,815	98	Proposed Building
	10,849	74	>75% Grass cover, Good, HSG C
*	1,870	98	Proposed Courtyard Imp
	3,100	74	>75% Grass cover, Good, HSG C
	45,619	91	Weighted Average
	13,949		30.58% Pervious Area
	31,670		69.42% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

### Subcatchment 1.2S: 1.2S

#### Hydrograph



### Summary for Subcatchment 1.3S: 1.3S

Runoff = 0.1 cfs @ 12.04 hrs, Volume= 0.010 af, Depth= 2.60"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs


Buck Run 24-hr S1 1-yr Rainfall=2.83"

Area (sf)	CN	Description
*	2,000	98 Proposed Pods and Facilities
2,000		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

### Subcatchment 1.3S: 1.3S

#### Hydrograph



### Summary for Pond 1.1P: Infiltration Basin 1.1

Inflow Area = 0.722 ac, 42.00% Impervious, Inflow Depth = 1.25" for 1-yr event  
 Inflow = 1.1 cfs @ 12.04 hrs, Volume= 0.075 af  
 Outflow = 0.3 cfs @ 12.30 hrs, Volume= 0.075 af, Atten= 70%, Lag= 15.5 min  
 Discarded = 0.3 cfs @ 12.30 hrs, Volume= 0.075 af  
 Primary = 0.0 cfs @ 0.00 hrs, Volume= 0.000 af  
 Secondary = 0.0 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 452.60' @ 12.30 hrs Surf.Area= 718 sf Storage= 633 cf

Plug-Flow detention time= 14.9 min calculated for 0.075 af (100% of inflow)  
 Center-of-Mass det. time= 14.9 min ( 879.1 - 864.2 )

Volume	Invert	Avail.Storage	Storage Description
#1	451.00'	9,077 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
451.00	125	0	0
452.00	447	286	286
454.00	1,356	1,803	2,089
456.00	2,634	3,990	6,079
457.00	3,362	2,998	9,077

Device	Routing	Invert	Outlet Devices
#1	Primary	450.30'	<b>12.0" Round Culvert</b> L= 58.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 450.30' / 449.50' S= 0.0138 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Device 1	454.75'	<b>4.0" Vert. Orifice/Grate</b> C= 0.600
#3	Device 1	455.50'	<b>30.0" x 48.0" Horiz. Orifice/Grate</b> C= 0.600 Limited to weir flow at low heads
#4	Discarded	451.00'	<b>20.000 in/hr Exfiltration over Surface area</b> Phase-In= 0.10'
#5	Secondary	456.00'	<b>10.0' long x 10.0' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.49 2.56 2.70 2.69 2.68 2.69 2.67 2.64


**Discarded OutFlow** Max=0.3 cfs @ 12.30 hrs HW=452.59' (Free Discharge)  
 ↳ **4=Exfiltration** (Exfiltration Controls 0.3 cfs)

**Primary OutFlow** Max=0.0 cfs @ 0.00 hrs HW=451.00' TW=0.00' (Dynamic Tailwater)  
 ↳ **1=Culvert** (Passes 0.0 cfs of 1.7 cfs potential flow)  
 ↳ ↳ **2=Orifice/Grate** ( Controls 0.0 cfs)  
 ↳ ↳ ↳ **3=Orifice/Grate** ( Controls 0.0 cfs)

**Secondary OutFlow** Max=0.0 cfs @ 0.00 hrs HW=451.00' TW=0.00' (Dynamic Tailwater)  
 ↳ **5=Broad-Crested Rectangular Weir**( Controls 0.0 cfs)

**Pond 1.1P: Infiltration Basin 1.1**

**Hydrograph**



**Wolf Center - Post-4-20- 2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 1-yr Rainfall=2.83"*

Printed 10/20/2023

Page 9

**Stage-Area-Storage for Pond 1.1P: Infiltration Basin 1.1**

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
451.00	125	0
451.10	157	14
451.20	189	31
451.30	222	52
451.40	254	76
451.50	286	103
451.60	318	133
451.70	350	166
451.80	383	203
451.90	415	243
452.00	447	286
452.10	492	333
452.20	538	384
452.30	583	441
452.40	629	501
452.50	674	566
452.60	720	636
452.70	765	710
452.80	811	789
452.90	856	872
453.00	902	960
453.10	947	1,053
453.20	992	1,150
453.30	1,038	1,251
453.40	1,083	1,357
453.50	1,129	1,468
453.60	1,174	1,583
453.70	1,220	1,703
453.80	1,265	1,827
453.90	1,311	1,956
454.00	1,356	2,089
454.10	1,420	2,228
454.20	1,484	2,373
454.30	1,548	2,525
454.40	1,612	2,683
454.50	1,676	2,847
454.60	1,739	3,018
454.70	1,803	3,195
454.80	1,867	3,378
454.90	1,931	3,568
455.00	1,995	3,765
455.10	2,059	3,967
455.20	2,123	4,176
455.30	2,187	4,392
455.40	2,251	4,614
455.50	2,315	4,842
455.60	2,378	5,077
455.70	2,442	5,318
455.80	2,506	5,565
455.90	2,570	5,819
456.00	2,634	6,079
456.10	2,707	6,346
456.20	2,780	6,620
456.30	2,852	6,902
456.40	2,925	7,191
456.50	2,998	7,487
456.60	3,071	7,790
456.70	3,144	8,101
456.80	3,216	8,419
456.90	3,289	8,744
457.00	<b>3,362</b>	<b>9,077</b>

### Summary for Pond DS1.2: Diversion Structure 1.2

Inflow Area = 1.047 ac, 69.42% Impervious, Inflow Depth = 1.91" for 1-yr event  
 Inflow = 2.5 cfs @ 12.04 hrs, Volume= 0.167 af  
 Outflow = 2.5 cfs @ 12.04 hrs, Volume= 0.167 af, Atten= 0%, Lag= 0.0 min  
 Primary = 2.5 cfs @ 12.04 hrs, Volume= 0.167 af  
 Secondary = 0.0 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 469.20' @ 12.04 hrs


Device	Routing	Invert	Outlet Devices
#1	Primary	466.67'	<b>8.0" Round Culvert</b> L= 6.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 466.67' / 466.60' S= 0.0117 ' / ' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.35 sf
#2	Device 3	469.35'	<b>2.0' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32
#3	Secondary	462.28'	<b>8.0" Round Culvert</b> L= 103.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 462.28' / 448.16' S= 0.1371 ' / ' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.35 sf

**Primary OutFlow** Max=2.4 cfs @ 12.04 hrs HW=469.09' TW=466.16' (Dynamic Tailwater)  
 1=Culvert (Inlet Controls 2.4 cfs @ 6.95 fps)

**Secondary OutFlow** Max=0.0 cfs @ 0.00 hrs HW=462.28' TW=0.00' (Dynamic Tailwater)  
 3=Culvert ( Controls 0.0 cfs)  
 2=Broad-Crested Rectangular Weir( Controls 0.0 cfs)

### Pond DS1.2: Diversion Structure 1.2

Hydrograph



**Stage-Area-Storage for Pond DS1.2: Diversion Structure 1.2**

Elevation (feet)	Storage (cubic-feet)	Elevation (feet)	Storage (cubic-feet)	Elevation (feet)	Storage (cubic-feet)
462.28	0	464.92	0	467.56	0
462.32	0	464.96	0	467.60	0
462.36	0	465.00	0	467.64	0
462.40	0	465.04	0	467.68	0
462.44	0	465.08	0	467.72	0
462.48	0	465.12	0	467.76	0
462.52	0	465.16	0	467.80	0
462.56	0	465.20	0	467.84	0
462.60	0	465.24	0	467.88	0
462.64	0	465.28	0	467.92	0
462.68	0	465.32	0	467.96	0
462.72	0	465.36	0	468.00	0
462.76	0	465.40	0	468.04	0
462.80	0	465.44	0	468.08	0
462.84	0	465.48	0	468.12	0
462.88	0	465.52	0	468.16	0
462.92	0	465.56	0	468.20	0
462.96	0	465.60	0	468.24	0
463.00	0	465.64	0	468.28	0
463.04	0	465.68	0	468.32	0
463.08	0	465.72	0	468.36	0
463.12	0	465.76	0	468.40	0
463.16	0	465.80	0	468.44	0
463.20	0	465.84	0	468.48	0
463.24	0	465.88	0	468.52	0
463.28	0	465.92	0	468.56	0
463.32	0	465.96	0	468.60	0
463.36	0	466.00	0	468.64	0
463.40	0	466.04	0	468.68	0
463.44	0	466.08	0	468.72	0
463.48	0	466.12	0	468.76	0
463.52	0	466.16	0	468.80	0
463.56	0	466.20	0	468.84	0
463.60	0	466.24	0	468.88	0
463.64	0	466.28	0	468.92	0
463.68	0	466.32	0	468.96	0
463.72	0	466.36	0	469.00	0
463.76	0	466.40	0	469.04	0
463.80	0	466.44	0	469.08	0
463.84	0	466.48	0	469.12	0
463.88	0	466.52	0	469.16	0
463.92	0	466.56	0	469.20	0
463.96	0	466.60	0	469.24	0
464.00	0	466.64	0	469.28	0
464.04	0	466.68	0	469.32	0
464.08	0	466.72	0		
464.12	0	466.76	0		
464.16	0	466.80	0		
464.20	0	466.84	0		
464.24	0	466.88	0		
464.28	0	466.92	0		
464.32	0	466.96	0		
464.36	0	467.00	0		
464.40	0	467.04	0		
464.44	0	467.08	0		
464.48	0	467.12	0		
464.52	0	467.16	0		
464.56	0	467.20	0		
464.60	0	467.24	0		
464.64	0	467.28	0		
464.68	0	467.32	0		
464.72	0	467.36	0		
464.76	0	467.40	0		
464.80	0	467.44	0		
464.84	0	467.48	0		
464.88	0	467.52	0		



### Summary for Pond DS1.3: Diversion Structure 1.3

Inflow Area = 0.046 ac, 100.00% Impervious, Inflow Depth = 2.60" for 1-yr event  
 Inflow = 0.1 cfs @ 12.04 hrs, Volume= 0.010 af  
 Outflow = 0.1 cfs @ 12.04 hrs, Volume= 0.010 af, Atten= 0%, Lag= 0.0 min  
 Primary = 0.1 cfs @ 12.04 hrs, Volume= 0.010 af  
 Secondary = 0.0 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 593.39' @ 12.04 hrs


Device	Routing	Invert	Outlet Devices
#1	Primary	593.10'	<b>4.0" Round Culvert</b> L= 6.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 593.10' / 593.00' S= 0.0167 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.09 sf
#2	Secondary	595.20'	<b>8.0" Round Culvert</b> L= 154.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 595.20' / 590.00' S= 0.0338 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.35 sf

**Primary OutFlow** Max=0.1 cfs @ 12.04 hrs HW=593.38' TW=593.14' (Dynamic Tailwater)  
 ↑ **1=Culvert** (Barrel Controls 0.1 cfs @ 2.24 fps)

**Secondary OutFlow** Max=0.0 cfs @ 0.00 hrs HW=593.10' TW=0.00' (Dynamic Tailwater)  
 ↑ **2=Culvert** ( Controls 0.0 cfs)

### Pond DS1.3: Diversion Structure 1.3

#### Hydrograph



**Stage-Area-Storage for Pond DS1.3: Diversion Structure 1.3**

Elevation (feet)	Storage (cubic-feet)	Elevation (feet)	Storage (cubic-feet)	Elevation (feet)	Storage (cubic-feet)
593.10	0	594.42	0	595.74	0
593.12	0	594.44	0	595.76	0
593.14	0	594.46	0	595.78	0
593.16	0	594.48	0	595.80	0
593.18	0	594.50	0	595.82	0
593.20	0	594.52	0	595.84	0
593.22	0	594.54	0	595.86	0
593.24	0	594.56	0		
593.26	0	594.58	0		
593.28	0	594.60	0		
593.30	0	594.62	0		
593.32	0	594.64	0		
593.34	0	594.66	0		
593.36	0	594.68	0		
593.38	0	594.70	0		
593.40	0	594.72	0		
593.42	0	594.74	0		
593.44	0	594.76	0		
593.46	0	594.78	0		
593.48	0	594.80	0		
593.50	0	594.82	0		
593.52	0	594.84	0		
593.54	0	594.86	0		
593.56	0	594.88	0		
593.58	0	594.90	0		
593.60	0	594.92	0		
593.62	0	594.94	0		
593.64	0	594.96	0		
593.66	0	594.98	0		
593.68	0	595.00	0		
593.70	0	595.02	0		
593.72	0	595.04	0		
593.74	0	595.06	0		
593.76	0	595.08	0		
593.78	0	595.10	0		
593.80	0	595.12	0		
593.82	0	595.14	0		
593.84	0	595.16	0		
593.86	0	595.18	0		
593.88	0	595.20	0		
593.90	0	595.22	0		
593.92	0	595.24	0		
593.94	0	595.26	0		
593.96	0	595.28	0		
593.98	0	595.30	0		
594.00	0	595.32	0		
594.02	0	595.34	0		
594.04	0	595.36	0		
594.06	0	595.38	0		
594.08	0	595.40	0		
594.10	0	595.42	0		
594.12	0	595.44	0		
594.14	0	595.46	0		
594.16	0	595.48	0		
594.18	0	595.50	0		
594.20	0	595.52	0		
594.22	0	595.54	0		
594.24	0	595.56	0		
594.26	0	595.58	0		
594.28	0	595.60	0		
594.30	0	595.62	0		
594.32	0	595.64	0		
594.34	0	595.66	0		
594.36	0	595.68	0		
594.38	0	595.70	0		
594.40	0	595.72	0		

### Summary for Pond INF 1.2: Infiltration System 1.2

Inflow Area = 1.047 ac, 69.42% Impervious, Inflow Depth = 1.91" for 1-yr event  
 Inflow = 2.5 cfs @ 12.04 hrs, Volume= 0.167 af  
 Outflow = 1.8 cfs @ 12.05 hrs, Volume= 0.167 af, Atten= 26%, Lag= 0.5 min  
 Discarded = 1.8 cfs @ 12.05 hrs, Volume= 0.167 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 466.22' @ 12.10 hrs Surf.Area= 0.076 ac Storage= 0.006 af

Plug-Flow detention time= 1.3 min calculated for 0.167 af (100% of inflow)  
 Center-of-Mass det. time= 1.3 min ( 821.9 - 820.6 )

Volume	Invert	Avail.Storage	Storage Description
#1A	466.01'	0.064 af	<b>30.50'W x 108.50'L x 3.54'H Field A</b> 0.269 af Overall - 0.109 af Embedded = 0.160 af x 40.0% Voids
#2A	466.51'	0.109 af	<b>Cultec R-330XLHD x 90</b> Inside #1 Effective Size= 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf Overall Size= 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap Row Length Adjustment= +1.50' x 7.45 sf x 6 rows
			0.173 af Total Available Storage


Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Discarded	466.01'	<b>24.000 in/hr Exfiltration over Horizontal area</b> Phase-In= 0.10'

**Discarded OutFlow** Max=1.8 cfs @ 12.05 hrs HW=466.18' (Free Discharge)  
 ↳ **1=Exfiltration** (Exfiltration Controls 1.8 cfs)

### Pond INF 1.2: Infiltration System 1.2

Hydrograph



**Wolf Center - Post-4-20- 2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 1-yr Rainfall=2.83"*

Printed 10/20/2023

Page 15

**Stage-Area-Storage for Pond INF 1.2: Infiltration System 1.2**

Elevation (feet)	Horizontal (acres)	Storage (acre-feet)	Elevation (feet)	Horizontal (acres)	Storage (acre-feet)	Elevation (feet)	Horizontal (acres)	Storage (acre-feet)
466.01	<b>0.076</b>	0.000	467.33	0.076	0.068	468.65	0.076	0.143
466.03	0.076	0.001	467.35	0.076	0.069	468.67	0.076	0.144
466.05	0.076	0.001	467.37	0.076	0.070	468.69	0.076	0.145
466.07	0.076	0.002	467.39	0.076	0.072	468.71	0.076	0.146
466.09	0.076	0.002	467.41	0.076	0.073	468.73	0.076	0.147
466.11	0.076	0.003	467.43	0.076	0.074	468.75	0.076	0.147
466.13	0.076	0.004	467.45	0.076	0.075	468.77	0.076	0.148
466.15	0.076	0.004	467.47	0.076	0.077	468.79	0.076	0.149
466.17	0.076	0.005	467.49	0.076	0.078	468.81	0.076	0.150
466.19	0.076	0.005	467.51	0.076	0.079	468.83	0.076	0.151
466.21	0.076	0.006	467.53	0.076	0.080	468.85	0.076	0.151
466.23	0.076	0.007	467.55	0.076	0.082	468.87	0.076	0.152
466.25	0.076	0.007	467.57	0.076	0.083	468.89	0.076	0.153
466.27	0.076	0.008	467.59	0.076	0.084	468.91	0.076	0.153
466.29	0.076	0.009	467.61	0.076	0.085	468.93	0.076	0.154
466.31	0.076	0.009	467.63	0.076	0.086	468.95	0.076	0.155
466.33	0.076	0.010	467.65	0.076	0.088	468.97	0.076	0.155
466.35	0.076	0.010	467.67	0.076	0.089	468.99	0.076	0.156
466.37	0.076	0.011	467.69	0.076	0.090	469.01	0.076	0.157
466.39	0.076	0.012	467.71	0.076	0.091	469.03	0.076	0.157
466.41	0.076	0.012	467.73	0.076	0.093	469.05	0.076	0.158
466.43	0.076	0.013	467.75	0.076	0.094	469.07	0.076	0.159
466.45	0.076	0.013	467.77	0.076	0.095	469.09	0.076	0.159
466.47	0.076	0.014	467.79	0.076	0.096	469.11	0.076	0.160
466.49	0.076	0.015	467.81	0.076	0.097	469.13	0.076	0.160
466.51	0.076	0.015	467.83	0.076	0.099	469.15	0.076	0.161
466.53	0.076	0.017	467.85	0.076	0.100	469.17	0.076	0.162
466.55	0.076	0.018	467.87	0.076	0.101	469.19	0.076	0.162
466.57	0.076	0.019	467.89	0.076	0.102	469.21	0.076	0.163
466.59	0.076	0.020	467.91	0.076	0.103	469.23	0.076	0.163
466.61	0.076	0.022	467.93	0.076	0.105	469.25	0.076	0.164
466.63	0.076	0.023	467.95	0.076	0.106	469.27	0.076	0.165
466.65	0.076	0.024	467.97	0.076	0.107	469.29	0.076	0.165
466.67	0.076	0.026	467.99	0.076	0.108	469.31	0.076	0.166
466.69	0.076	0.027	468.01	0.076	0.109	469.33	0.076	0.166
466.71	0.076	0.028	468.03	0.076	0.110	469.35	0.076	0.167
466.73	0.076	0.030	468.05	0.076	0.112	469.37	0.076	0.168
466.75	0.076	0.031	468.07	0.076	0.113	469.39	0.076	0.168
466.77	0.076	0.032	468.09	0.076	0.114	469.41	0.076	0.169
466.79	0.076	0.033	468.11	0.076	0.115	469.43	0.076	0.170
466.81	0.076	0.035	468.13	0.076	0.116	469.45	0.076	0.170
466.83	0.076	0.036	468.15	0.076	0.117	469.47	0.076	0.171
466.85	0.076	0.037	468.17	0.076	0.118	469.49	0.076	0.171
466.87	0.076	0.039	468.19	0.076	0.119	469.51	0.076	0.172
466.89	0.076	0.040	468.21	0.076	0.121	469.53	0.076	0.173
466.91	0.076	0.041	468.23	0.076	0.122	469.55	0.076	<b>0.173</b>
466.93	0.076	0.042	468.25	0.076	0.123			
466.95	0.076	0.044	468.27	0.076	0.124			
466.97	0.076	0.045	468.29	0.076	0.125			
466.99	0.076	0.046	468.31	0.076	0.126			
467.01	0.076	0.048	468.33	0.076	0.127			
467.03	0.076	0.049	468.35	0.076	0.128			
467.05	0.076	0.050	468.37	0.076	0.129			
467.07	0.076	0.051	468.39	0.076	0.130			
467.09	0.076	0.053	468.41	0.076	0.131			
467.11	0.076	0.054	468.43	0.076	0.132			
467.13	0.076	0.055	468.45	0.076	0.133			
467.15	0.076	0.057	468.47	0.076	0.134			
467.17	0.076	0.058	468.49	0.076	0.135			
467.19	0.076	0.059	468.51	0.076	0.136			
467.21	0.076	0.060	468.53	0.076	0.137			
467.23	0.076	0.062	468.55	0.076	0.138			
467.25	0.076	0.063	468.57	0.076	0.139			
467.27	0.076	0.064	468.59	0.076	0.140			
467.29	0.076	0.065	468.61	0.076	0.141			
467.31	0.076	0.067	468.63	0.076	0.142			



### Summary for Pond INF 1.3: Infiltration System 1.3

Inflow Area = 0.046 ac, 100.00% Impervious, Inflow Depth = 2.60" for 1-yr event  
 Inflow = 0.1 cfs @ 12.04 hrs, Volume= 0.010 af  
 Outflow = 0.1 cfs @ 12.05 hrs, Volume= 0.010 af, Atten= 33%, Lag= 0.7 min  
 Discarded = 0.1 cfs @ 12.05 hrs, Volume= 0.010 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 593.20' @ 12.11 hrs Surf.Area= 0.006 ac Storage= 0.001 af

Plug-Flow detention time= 2.3 min calculated for 0.010 af (100% of inflow)  
 Center-of-Mass det. time= 2.3 min ( 764.0 - 761.8 )

Volume	Invert	Avail.Storage	Storage Description
#1A	593.00'	0.006 af	<b>16.00'W x 17.50'L x 3.54'H Field A</b> 0.023 af Overall - 0.008 af Embedded = 0.015 af x 40.0% Voids
#2A	593.50'	0.008 af	<b>Cultec R-330XLHD x 6 Inside #1</b> Effective Size= 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf Overall Size= 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap Row Length Adjustment= +1.50' x 7.45 sf x 3 rows
			0.014 af Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	593.00'	<b>14.000 in/hr Exfiltration over Horizontal area</b> Phase-In= 0.10'

**Discarded OutFlow** Max=0.1 cfs @ 12.05 hrs HW=593.16' (Free Discharge)

↳ **Exfiltration** (Exfiltration Controls 0.1 cfs)

### Pond INF 1.3: Infiltration System 1.3

Hydrograph



**Wolf Center - Post-4-20- 2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 1-yr Rainfall=2.83"*

Printed 10/20/2023

Page 17

**Stage-Area-Storage for Pond INF 1.3: Infiltration System 1.3**

Elevation (feet)	Horizontal (acres)	Storage (acre-feet)	Elevation (feet)	Horizontal (acres)	Storage (acre-feet)	Elevation (feet)	Horizontal (acres)	Storage (acre-feet)
593.00	<b>0.006</b>	0.000	594.32	0.006	0.005	595.64	0.006	0.011
593.02	0.006	0.000	594.34	0.006	0.006	595.66	0.006	0.011
593.04	0.006	0.000	594.36	0.006	0.006	595.68	0.006	0.011
593.06	0.006	0.000	594.38	0.006	0.006	595.70	0.006	0.012
593.08	0.006	0.000	594.40	0.006	0.006	595.72	0.006	0.012
593.10	0.006	0.000	594.42	0.006	0.006	595.74	0.006	0.012
593.12	0.006	0.000	594.44	0.006	0.006	595.76	0.006	0.012
593.14	0.006	0.000	594.46	0.006	0.006	595.78	0.006	0.012
593.16	0.006	0.000	594.48	0.006	0.006	595.80	0.006	0.012
593.18	0.006	0.000	594.50	0.006	0.006	595.82	0.006	0.012
593.20	0.006	0.001	594.52	0.006	0.006	595.84	0.006	0.012
593.22	0.006	0.001	594.54	0.006	0.006	595.86	0.006	0.012
593.24	0.006	0.001	594.56	0.006	0.007	595.88	0.006	0.012
593.26	0.006	0.001	594.58	0.006	0.007	595.90	0.006	0.012
593.28	0.006	0.001	594.60	0.006	0.007	595.92	0.006	0.012
593.30	0.006	0.001	594.62	0.006	0.007	595.94	0.006	0.012
593.32	0.006	0.001	594.64	0.006	0.007	595.96	0.006	0.012
593.34	0.006	0.001	594.66	0.006	0.007	595.98	0.006	0.012
593.36	0.006	0.001	594.68	0.006	0.007	596.00	0.006	0.012
593.38	0.006	0.001	594.70	0.006	0.007	596.02	0.006	0.013
593.40	0.006	0.001	594.72	0.006	0.007	596.04	0.006	0.013
593.42	0.006	0.001	594.74	0.006	0.007	596.06	0.006	0.013
593.44	0.006	0.001	594.76	0.006	0.008	596.08	0.006	0.013
593.46	0.006	0.001	594.78	0.006	0.008	596.10	0.006	0.013
593.48	0.006	0.001	594.80	0.006	0.008	596.12	0.006	0.013
593.50	0.006	0.001	594.82	0.006	0.008	596.14	0.006	0.013
593.52	0.006	0.001	594.84	0.006	0.008	596.16	0.006	0.013
593.54	0.006	0.001	594.86	0.006	0.008	596.18	0.006	0.013
593.56	0.006	0.002	594.88	0.006	0.008	596.20	0.006	0.013
593.58	0.006	0.002	594.90	0.006	0.008	596.22	0.006	0.013
593.60	0.006	0.002	594.92	0.006	0.008	596.24	0.006	0.013
593.62	0.006	0.002	594.94	0.006	0.008	596.26	0.006	0.013
593.64	0.006	0.002	594.96	0.006	0.008	596.28	0.006	0.013
593.66	0.006	0.002	594.98	0.006	0.009	596.30	0.006	0.013
593.68	0.006	0.002	595.00	0.006	0.009	596.32	0.006	0.013
593.70	0.006	0.002	595.02	0.006	0.009	596.34	0.006	0.013
593.72	0.006	0.002	595.04	0.006	0.009	596.36	0.006	0.013
593.74	0.006	0.003	595.06	0.006	0.009	596.38	0.006	0.013
593.76	0.006	0.003	595.08	0.006	0.009	596.40	0.006	0.014
593.78	0.006	0.003	595.10	0.006	0.009	596.42	0.006	0.014
593.80	0.006	0.003	595.12	0.006	0.009	596.44	0.006	0.014
593.82	0.006	0.003	595.14	0.006	0.009	596.46	0.006	0.014
593.84	0.006	0.003	595.16	0.006	0.009	596.48	0.006	0.014
593.86	0.006	0.003	595.18	0.006	0.009	596.50	0.006	0.014
593.88	0.006	0.003	595.20	0.006	0.010	596.52	0.006	0.014
593.90	0.006	0.003	595.22	0.006	0.010	596.54	0.006	<b>0.014</b>
593.92	0.006	0.003	595.24	0.006	0.010			
593.94	0.006	0.004	595.26	0.006	0.010			
593.96	0.006	0.004	595.28	0.006	0.010			
593.98	0.006	0.004	595.30	0.006	0.010			
594.00	0.006	0.004	595.32	0.006	0.010			
594.02	0.006	0.004	595.34	0.006	0.010			
594.04	0.006	0.004	595.36	0.006	0.010			
594.06	0.006	0.004	595.38	0.006	0.010			
594.08	0.006	0.004	595.40	0.006	0.010			
594.10	0.006	0.004	595.42	0.006	0.010			
594.12	0.006	0.004	595.44	0.006	0.011			
594.14	0.006	0.005	595.46	0.006	0.011			
594.16	0.006	0.005	595.48	0.006	0.011			
594.18	0.006	0.005	595.50	0.006	0.011			
594.20	0.006	0.005	595.52	0.006	0.011			
594.22	0.006	0.005	595.54	0.006	0.011			
594.24	0.006	0.005	595.56	0.006	0.011			
594.26	0.006	0.005	595.58	0.006	0.011			
594.28	0.006	0.005	595.60	0.006	0.011			
594.30	0.006	0.005	595.62	0.006	0.011			


### Summary for Link DP: Design Point

Inflow Area = 16.919 ac, 6.14% Impervious, Inflow Depth = 0.72" for 1-yr event  
 Inflow = 7.5 cfs @ 12.31 hrs, Volume= 1.019 af  
 Primary = 7.5 cfs @ 12.31 hrs, Volume= 1.019 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

### Link DP: Design Point

#### Hydrograph



**Wolf Center - Post-4-20- 2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 10-yr Rainfall=5.08"*

Printed 10/20/2023

Page 19

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN

Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Subcatchment1.0S: 1.0S**Runoff Area=705,538 sf 4.54% Impervious Runoff Depth=2.34"  
Flow Length=1,585' Tc=23.5 min CN=73 Runoff=24.8 cfs 3.163 af**Subcatchment1.1S: 1.1S**Runoff Area=31,450 sf 42.00% Impervious Runoff Depth=3.15"  
Tc=6.0 min CN=82 Runoff=2.6 cfs 0.190 af**Subcatchment1.2S: 1.2S**Runoff Area=45,619 sf 69.42% Impervious Runoff Depth=4.06"  
Tc=6.0 min CN=91 Runoff=4.7 cfs 0.354 af**Subcatchment1.3S: 1.3S**Runoff Area=2,000 sf 100.00% Impervious Runoff Depth=4.84"  
Tc=6.0 min CN=98 Runoff=0.2 cfs 0.019 af**Pond 1.1P: Infiltration Basin 1.1**Peak Elev=453.96' Storage=2,030 cf Inflow=2.6 cfs 0.190 af  
Discarded=0.6 cfs 0.190 af Primary=0.0 cfs 0.000 af Secondary=0.0 cfs 0.000 af Outflow=0.6 cfs 0.190 af**Pond DS1.2: Diversion Structure 1.2**Peak Elev=469.81' Inflow=4.7 cfs 0.354 af  
Primary=2.8 cfs 0.338 af Secondary=1.9 cfs 0.016 af Outflow=4.7 cfs 0.354 af**Pond DS1.3: Diversion Structure 1.3**Peak Elev=593.61' Inflow=0.2 cfs 0.019 af  
Primary=0.2 cfs 0.019 af Secondary=0.0 cfs 0.000 af Outflow=0.2 cfs 0.019 af**Pond INF 1.2: Infiltration System 1.2**Peak Elev=466.56' Storage=0.019 af Inflow=2.8 cfs 0.338 af  
Outflow=1.8 cfs 0.338 af**Pond INF 1.3: Infiltration System 1.3**Peak Elev=593.58' Storage=0.002 af Inflow=0.2 cfs 0.019 af  
Outflow=0.1 cfs 0.019 af**Link DP: Design Point**Inflow=24.8 cfs 3.179 af  
Primary=24.8 cfs 3.179 af



**Wolf Center - Post-4-20- 2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 10-yr Rainfall=5.08"*

Printed 10/20/2023

Page 20

**Summary for Subcatchment 1.0S: 1.0S**


Runoff = 24.8 cfs @ 12.29 hrs, Volume= 3.163 af, Depth= 2.34"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Buck Run 24-hr S1 10-yr Rainfall=5.08"

	Area (sf)	CN	Description
*	18,932	98	Existing Pavement
*	6,135	98	Existing Buildings
	5,607	87	Dirt roads, HSG C
*	6,970	98	Proposed Pavement
*	1,405	61	Existing >75% Grass cover, Good, HSG B
*	3,457	80	Proposed >75% Grass cover, Good, HSG D
*	3,083	61	Proposed >75% Grass cover, Good, HSG B
*	2,900	74	Existing >75% Grass cover, Good, HSG C
*	17,714	74	Proposed >75% Grass cover, Good, HSG C
	13,520	89	Gravel roads, HSG C
	22,115	55	Woods, Good, HSG B
	417,935	70	Woods, Good, HSG C
	150,505	77	Woods, Good, HSG D
	35,260	71	Meadow, non-grazed, HSG C
	705,538	73	Weighted Average
	673,501		95.46% Pervious Area
	32,037		4.54% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.4	100	0.0900	0.15		<b>Sheet Flow,</b> Woods: Light underbrush n= 0.400 P2= 3.40"
12.1	1,485	0.1670	2.04		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
23.5	1,585	Total			

**Subcatchment 1.0S: 1.0S****Hydrograph**

**Wolf Center - Post-4-20- 2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

Buck Run 24-hr S1 10-yr Rainfall=5.08"

Printed 10/20/2023

Page 21

**Summary for Subcatchment 1.1S: 1.1S**


Runoff = 2.6 cfs @ 12.04 hrs, Volume= 0.190 af, Depth= 3.15"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Buck Run 24-hr S1 10-yr Rainfall=5.08"

	Area (sf)	CN	Description
*	12,870	98	Proposed Pavement
*	340	98	Proposed Sidewalk
	5,235	61	>75% Grass cover, Good, HSG B
	13,005	74	>75% Grass cover, Good, HSG C
	31,450	82	Weighted Average
	18,240		58.00% Pervious Area
	13,210		42.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Subcatchment 1.1S: 1.1S****Hydrograph**

### Summary for Subcatchment 1.2S: 1.2S

Runoff = 4.7 cfs @ 12.04 hrs, Volume= 0.354 af, Depth= 4.06"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs


Buck Run 24-hr S1 10-yr Rainfall=5.08"

	Area (sf)	CN	Description
*	24,985	98	Proposed Pavement & Walkway
*	4,815	98	Proposed Building
	10,849	74	>75% Grass cover, Good, HSG C
*	1,870	98	Proposed Courtyard Imp
	3,100	74	>75% Grass cover, Good, HSG C
	45,619	91	Weighted Average
	13,949		30.58% Pervious Area
	31,670		69.42% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

### Subcatchment 1.2S: 1.2S

#### Hydrograph



### Summary for Subcatchment 1.3S: 1.3S

Runoff = 0.2 cfs @ 12.04 hrs, Volume= 0.019 af, Depth= 4.84"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs


Buck Run 24-hr S1 10-yr Rainfall=5.08"

Area (sf)	CN	Description
*	2,000	98 Proposed Pods and Facilities
2,000		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

### Subcatchment 1.3S: 1.3S

#### Hydrograph





### Summary for Pond 1.1P: Infiltration Basin 1.1

Inflow Area = 0.722 ac, 42.00% Impervious, Inflow Depth = 3.15" for 10-yr event  
 Inflow = 2.6 cfs @ 12.04 hrs, Volume= 0.190 af  
 Outflow = 0.6 cfs @ 12.45 hrs, Volume= 0.190 af, Atten= 76%, Lag= 24.2 min  
 Discarded = 0.6 cfs @ 12.45 hrs, Volume= 0.190 af  
 Primary = 0.0 cfs @ 0.00 hrs, Volume= 0.000 af  
 Secondary = 0.0 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 453.96' @ 12.45 hrs Surf.Area= 1,336 sf Storage= 2,030 cf

Plug-Flow detention time= 27.6 min calculated for 0.189 af (100% of inflow)  
 Center-of-Mass det. time= 27.6 min ( 860.1 - 832.5 )

Volume	Invert	Avail.Storage	Storage Description
#1	451.00'	9,077 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
451.00	125	0	0
452.00	447	286	286
454.00	1,356	1,803	2,089
456.00	2,634	3,990	6,079
457.00	3,362	2,998	9,077

Device	Routing	Invert	Outlet Devices
#1	Primary	450.30'	<b>12.0" Round Culvert</b> L= 58.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 450.30' / 449.50' S= 0.0138 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Device 1	454.75'	<b>4.0" Vert. Orifice/Grate</b> C= 0.600
#3	Device 1	455.50'	<b>30.0" x 48.0" Horiz. Orifice/Grate</b> C= 0.600 Limited to weir flow at low heads
#4	Discarded	451.00'	<b>20.000 in/hr Exfiltration over Surface area</b> Phase-In= 0.10'
#5	Secondary	456.00'	<b>10.0' long x 10.0' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.49 2.56 2.70 2.69 2.68 2.69 2.67 2.64


**Discarded OutFlow** Max=0.6 cfs @ 12.45 hrs HW=453.96' (Free Discharge)  
 ↳ **4=Exfiltration** (Exfiltration Controls 0.6 cfs)

**Primary OutFlow** Max=0.0 cfs @ 0.00 hrs HW=451.00' TW=0.00' (Dynamic Tailwater)  
 ↳ **1=Culvert** (Passes 0.0 cfs of 1.7 cfs potential flow)  
 ↳ ↳ **2=Orifice/Grate** ( Controls 0.0 cfs)  
 ↳ ↳ ↳ **3=Orifice/Grate** ( Controls 0.0 cfs)

**Secondary OutFlow** Max=0.0 cfs @ 0.00 hrs HW=451.00' TW=0.00' (Dynamic Tailwater)  
 ↳ **5=Broad-Crested Rectangular Weir**( Controls 0.0 cfs)

**Pond 1.1P: Infiltration Basin 1.1**

**Hydrograph**



**Wolf Center - Post-4-20- 2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 10-yr Rainfall=5.08"*

Printed 10/20/2023

Page 26

**Stage-Area-Storage for Pond 1.1P: Infiltration Basin 1.1**

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
451.00	125	0
451.10	157	14
451.20	189	31
451.30	222	52
451.40	254	76
451.50	286	103
451.60	318	133
451.70	350	166
451.80	383	203
451.90	415	243
452.00	447	286
452.10	492	333
452.20	538	384
452.30	583	441
452.40	629	501
452.50	674	566
452.60	720	636
452.70	765	710
452.80	811	789
452.90	856	872
453.00	902	960
453.10	947	1,053
453.20	992	1,150
453.30	1,038	1,251
453.40	1,083	1,357
453.50	1,129	1,468
453.60	1,174	1,583
453.70	1,220	1,703
453.80	1,265	1,827
453.90	1,311	1,956
454.00	1,356	2,089
454.10	1,420	2,228
454.20	1,484	2,373
454.30	1,548	2,525
454.40	1,612	2,683
454.50	1,676	2,847
454.60	1,739	3,018
454.70	1,803	3,195
454.80	1,867	3,378
454.90	1,931	3,568
455.00	1,995	3,765
455.10	2,059	3,967
455.20	2,123	4,176
455.30	2,187	4,392
455.40	2,251	4,614
455.50	2,315	4,842
455.60	2,378	5,077
455.70	2,442	5,318
455.80	2,506	5,565
455.90	2,570	5,819
456.00	2,634	6,079
456.10	2,707	6,346
456.20	2,780	6,620
456.30	2,852	6,902
456.40	2,925	7,191
456.50	2,998	7,487
456.60	3,071	7,790
456.70	3,144	8,101
456.80	3,216	8,419
456.90	3,289	8,744
457.00	<b>3,362</b>	<b>9,077</b>

### Summary for Pond DS1.2: Diversion Structure 1.2

Inflow Area = 1.047 ac, 69.42% Impervious, Inflow Depth = 4.06" for 10-yr event  
 Inflow = 4.7 cfs @ 12.04 hrs, Volume= 0.354 af  
 Outflow = 4.7 cfs @ 12.04 hrs, Volume= 0.354 af, Atten= 0%, Lag= 0.0 min  
 Primary = 2.8 cfs @ 12.04 hrs, Volume= 0.338 af  
 Secondary = 1.9 cfs @ 12.04 hrs, Volume= 0.016 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 469.81' @ 12.04 hrs


Device	Routing	Invert	Outlet Devices
#1	Primary	466.67'	<b>8.0" Round Culvert</b> L= 6.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 466.67' / 466.60' S= 0.0117 ' /' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.35 sf
#2	Device 3	469.35'	<b>2.0' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32
#3	Secondary	462.28'	<b>8.0" Round Culvert</b> L= 103.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 462.28' / 448.16' S= 0.1371 ' /' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.35 sf

**Primary OutFlow** Max=2.8 cfs @ 12.04 hrs HW=469.79' TW=466.31' (Dynamic Tailwater)  
 ↑ **1=Culvert** (Inlet Controls 2.8 cfs @ 8.03 fps)

**Secondary OutFlow** Max=1.7 cfs @ 12.04 hrs HW=469.79' TW=0.00' (Dynamic Tailwater)  
 ↑ **3=Culvert** (Passes 1.7 cfs of 4.5 cfs potential flow)  
 ↑ **2=Broad-Crested Rectangular Weir** (Weir Controls 1.7 cfs @ 1.96 fps)

### Pond DS1.2: Diversion Structure 1.2

Hydrograph





**Stage-Area-Storage for Pond DS1.2: Diversion Structure 1.2**

Elevation (feet)	Storage (cubic-feet)	Elevation (feet)	Storage (cubic-feet)	Elevation (feet)	Storage (cubic-feet)
462.28	0	464.92	0	467.56	0
462.32	0	464.96	0	467.60	0
462.36	0	465.00	0	467.64	0
462.40	0	465.04	0	467.68	0
462.44	0	465.08	0	467.72	0
462.48	0	465.12	0	467.76	0
462.52	0	465.16	0	467.80	0
462.56	0	465.20	0	467.84	0
462.60	0	465.24	0	467.88	0
462.64	0	465.28	0	467.92	0
462.68	0	465.32	0	467.96	0
462.72	0	465.36	0	468.00	0
462.76	0	465.40	0	468.04	0
462.80	0	465.44	0	468.08	0
462.84	0	465.48	0	468.12	0
462.88	0	465.52	0	468.16	0
462.92	0	465.56	0	468.20	0
462.96	0	465.60	0	468.24	0
463.00	0	465.64	0	468.28	0
463.04	0	465.68	0	468.32	0
463.08	0	465.72	0	468.36	0
463.12	0	465.76	0	468.40	0
463.16	0	465.80	0	468.44	0
463.20	0	465.84	0	468.48	0
463.24	0	465.88	0	468.52	0
463.28	0	465.92	0	468.56	0
463.32	0	465.96	0	468.60	0
463.36	0	466.00	0	468.64	0
463.40	0	466.04	0	468.68	0
463.44	0	466.08	0	468.72	0
463.48	0	466.12	0	468.76	0
463.52	0	466.16	0	468.80	0
463.56	0	466.20	0	468.84	0
463.60	0	466.24	0	468.88	0
463.64	0	466.28	0	468.92	0
463.68	0	466.32	0	468.96	0
463.72	0	466.36	0	469.00	0
463.76	0	466.40	0	469.04	0
463.80	0	466.44	0	469.08	0
463.84	0	466.48	0	469.12	0
463.88	0	466.52	0	469.16	0
463.92	0	466.56	0	469.20	0
463.96	0	466.60	0	469.24	0
464.00	0	466.64	0	469.28	0
464.04	0	466.68	0	469.32	0
464.08	0	466.72	0	469.36	0
464.12	0	466.76	0	469.40	0
464.16	0	466.80	0	469.44	0
464.20	0	466.84	0	469.48	0
464.24	0	466.88	0	469.52	0
464.28	0	466.92	0	469.56	0
464.32	0	466.96	0	469.60	0
464.36	0	467.00	0	469.64	0
464.40	0	467.04	0	469.68	0
464.44	0	467.08	0	469.72	0
464.48	0	467.12	0	469.76	0
464.52	0	467.16	0	469.80	0
464.56	0	467.20	0	469.84	0
464.60	0	467.24	0		
464.64	0	467.28	0		
464.68	0	467.32	0		
464.72	0	467.36	0		
464.76	0	467.40	0		
464.80	0	467.44	0		
464.84	0	467.48	0		
464.88	0	467.52	0		

### Summary for Pond DS1.3: Diversion Structure 1.3

Inflow Area = 0.046 ac, 100.00% Impervious, Inflow Depth = 4.84" for 10-yr event  
 Inflow = 0.2 cfs @ 12.04 hrs, Volume= 0.019 af  
 Outflow = 0.2 cfs @ 12.04 hrs, Volume= 0.019 af, Atten= 0%, Lag= 0.0 min  
 Primary = 0.2 cfs @ 12.04 hrs, Volume= 0.019 af  
 Secondary = 0.0 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 593.61' @ 12.20 hrs


Device	Routing	Invert	Outlet Devices
#1	Primary	593.10'	<b>4.0" Round Culvert</b> L= 6.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 593.10' / 593.00' S= 0.0167 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.09 sf
#2	Secondary	595.20'	<b>8.0" Round Culvert</b> L= 154.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 595.20' / 590.00' S= 0.0338 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.35 sf

**Primary OutFlow** Max=0.2 cfs @ 12.04 hrs HW=593.55' TW=593.35' (Dynamic Tailwater)  
 ↑**1=Culvert** (Inlet Controls 0.2 cfs @ 2.14 fps)

**Secondary OutFlow** Max=0.0 cfs @ 0.00 hrs HW=593.10' TW=0.00' (Dynamic Tailwater)  
 ↑**2=Culvert** ( Controls 0.0 cfs)

### Pond DS1.3: Diversion Structure 1.3

#### Hydrograph



**Stage-Area-Storage for Pond DS1.3: Diversion Structure 1.3**

Elevation (feet)	Storage (cubic-feet)	Elevation (feet)	Storage (cubic-feet)	Elevation (feet)	Storage (cubic-feet)
593.10	0	594.42	0	595.74	0
593.12	0	594.44	0	595.76	0
593.14	0	594.46	0	595.78	0
593.16	0	594.48	0	595.80	0
593.18	0	594.50	0	595.82	0
593.20	0	594.52	0	595.84	0
593.22	0	594.54	0	595.86	0
593.24	0	594.56	0		
593.26	0	594.58	0		
593.28	0	594.60	0		
593.30	0	594.62	0		
593.32	0	594.64	0		
593.34	0	594.66	0		
593.36	0	594.68	0		
593.38	0	594.70	0		
593.40	0	594.72	0		
593.42	0	594.74	0		
593.44	0	594.76	0		
593.46	0	594.78	0		
593.48	0	594.80	0		
593.50	0	594.82	0		
593.52	0	594.84	0		
593.54	0	594.86	0		
593.56	0	594.88	0		
593.58	0	594.90	0		
593.60	0	594.92	0		
593.62	0	594.94	0		
593.64	0	594.96	0		
593.66	0	594.98	0		
593.68	0	595.00	0		
593.70	0	595.02	0		
593.72	0	595.04	0		
593.74	0	595.06	0		
593.76	0	595.08	0		
593.78	0	595.10	0		
593.80	0	595.12	0		
593.82	0	595.14	0		
593.84	0	595.16	0		
593.86	0	595.18	0		
593.88	0	595.20	0		
593.90	0	595.22	0		
593.92	0	595.24	0		
593.94	0	595.26	0		
593.96	0	595.28	0		
593.98	0	595.30	0		
594.00	0	595.32	0		
594.02	0	595.34	0		
594.04	0	595.36	0		
594.06	0	595.38	0		
594.08	0	595.40	0		
594.10	0	595.42	0		
594.12	0	595.44	0		
594.14	0	595.46	0		
594.16	0	595.48	0		
594.18	0	595.50	0		
594.20	0	595.52	0		
594.22	0	595.54	0		
594.24	0	595.56	0		
594.26	0	595.58	0		
594.28	0	595.60	0		
594.30	0	595.62	0		
594.32	0	595.64	0		
594.34	0	595.66	0		
594.36	0	595.68	0		
594.38	0	595.70	0		
594.40	0	595.72	0		

### Summary for Pond INF 1.2: Infiltration System 1.2

Inflow Area = 1.047 ac, 69.42% Impervious, Inflow Depth = 3.88" for 10-yr event  
 Inflow = 2.8 cfs @ 12.04 hrs, Volume= 0.338 af  
 Outflow = 1.8 cfs @ 11.95 hrs, Volume= 0.338 af, Atten= 35%, Lag= 0.0 min  
 Discarded = 1.8 cfs @ 11.95 hrs, Volume= 0.338 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 466.56' @ 12.21 hrs Surf.Area= 0.076 ac Storage= 0.019 af

Plug-Flow detention time= 2.1 min calculated for 0.338 af (100% of inflow)  
 Center-of-Mass det. time= 2.1 min ( 801.0 - 798.8 )

Volume	Invert	Avail.Storage	Storage Description
#1A	466.01'	0.064 af	<b>30.50'W x 108.50'L x 3.54'H Field A</b> 0.269 af Overall - 0.109 af Embedded = 0.160 af x 40.0% Voids
#2A	466.51'	0.109 af	<b>Cultec R-330XLHD x 90 Inside #1</b> Effective Size= 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf Overall Size= 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap Row Length Adjustment= +1.50' x 7.45 sf x 6 rows
			0.173 af Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	466.01'	<b>24.000 in/hr Exfiltration over Horizontal area</b> Phase-In= 0.10'

**Discarded OutFlow** Max=1.8 cfs @ 11.95 hrs HW=466.12' (Free Discharge)

↳ **1=Exfiltration** (Exfiltration Controls 1.8 cfs)

### Pond INF 1.2: Infiltration System 1.2

Hydrograph





**Wolf Center - Post-4-20- 2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 10-yr Rainfall=5.08"*

Printed 10/20/2023

Page 32

**Stage-Area-Storage for Pond INF 1.2: Infiltration System 1.2**

Elevation (feet)	Horizontal (acres)	Storage (acre-feet)	Elevation (feet)	Horizontal (acres)	Storage (acre-feet)	Elevation (feet)	Horizontal (acres)	Storage (acre-feet)
466.01	<b>0.076</b>	0.000	467.33	0.076	0.068	468.65	0.076	0.143
466.03	0.076	0.001	467.35	0.076	0.069	468.67	0.076	0.144
466.05	0.076	0.001	467.37	0.076	0.070	468.69	0.076	0.145
466.07	0.076	0.002	467.39	0.076	0.072	468.71	0.076	0.146
466.09	0.076	0.002	467.41	0.076	0.073	468.73	0.076	0.147
466.11	0.076	0.003	467.43	0.076	0.074	468.75	0.076	0.147
466.13	0.076	0.004	467.45	0.076	0.075	468.77	0.076	0.148
466.15	0.076	0.004	467.47	0.076	0.077	468.79	0.076	0.149
466.17	0.076	0.005	467.49	0.076	0.078	468.81	0.076	0.150
466.19	0.076	0.005	467.51	0.076	0.079	468.83	0.076	0.151
466.21	0.076	0.006	467.53	0.076	0.080	468.85	0.076	0.151
466.23	0.076	0.007	467.55	0.076	0.082	468.87	0.076	0.152
466.25	0.076	0.007	467.57	0.076	0.083	468.89	0.076	0.153
466.27	0.076	0.008	467.59	0.076	0.084	468.91	0.076	0.153
466.29	0.076	0.009	467.61	0.076	0.085	468.93	0.076	0.154
466.31	0.076	0.009	467.63	0.076	0.086	468.95	0.076	0.155
466.33	0.076	0.010	467.65	0.076	0.088	468.97	0.076	0.155
466.35	0.076	0.010	467.67	0.076	0.089	468.99	0.076	0.156
466.37	0.076	0.011	467.69	0.076	0.090	469.01	0.076	0.157
466.39	0.076	0.012	467.71	0.076	0.091	469.03	0.076	0.157
466.41	0.076	0.012	467.73	0.076	0.093	469.05	0.076	0.158
466.43	0.076	0.013	467.75	0.076	0.094	469.07	0.076	0.159
466.45	0.076	0.013	467.77	0.076	0.095	469.09	0.076	0.159
466.47	0.076	0.014	467.79	0.076	0.096	469.11	0.076	0.160
466.49	0.076	0.015	467.81	0.076	0.097	469.13	0.076	0.160
466.51	0.076	0.015	467.83	0.076	0.099	469.15	0.076	0.161
466.53	0.076	0.017	467.85	0.076	0.100	469.17	0.076	0.162
466.55	0.076	0.018	467.87	0.076	0.101	469.19	0.076	0.162
466.57	0.076	0.019	467.89	0.076	0.102	469.21	0.076	0.163
466.59	0.076	0.020	467.91	0.076	0.103	469.23	0.076	0.163
466.61	0.076	0.022	467.93	0.076	0.105	469.25	0.076	0.164
466.63	0.076	0.023	467.95	0.076	0.106	469.27	0.076	0.165
466.65	0.076	0.024	467.97	0.076	0.107	469.29	0.076	0.165
466.67	0.076	0.026	467.99	0.076	0.108	469.31	0.076	0.166
466.69	0.076	0.027	468.01	0.076	0.109	469.33	0.076	0.166
466.71	0.076	0.028	468.03	0.076	0.110	469.35	0.076	0.167
466.73	0.076	0.030	468.05	0.076	0.112	469.37	0.076	0.168
466.75	0.076	0.031	468.07	0.076	0.113	469.39	0.076	0.168
466.77	0.076	0.032	468.09	0.076	0.114	469.41	0.076	0.169
466.79	0.076	0.033	468.11	0.076	0.115	469.43	0.076	0.170
466.81	0.076	0.035	468.13	0.076	0.116	469.45	0.076	0.170
466.83	0.076	0.036	468.15	0.076	0.117	469.47	0.076	0.171
466.85	0.076	0.037	468.17	0.076	0.118	469.49	0.076	0.171
466.87	0.076	0.039	468.19	0.076	0.119	469.51	0.076	0.172
466.89	0.076	0.040	468.21	0.076	0.121	469.53	0.076	0.173
466.91	0.076	0.041	468.23	0.076	0.122	469.55	0.076	<b>0.173</b>
466.93	0.076	0.042	468.25	0.076	0.123			
466.95	0.076	0.044	468.27	0.076	0.124			
466.97	0.076	0.045	468.29	0.076	0.125			
466.99	0.076	0.046	468.31	0.076	0.126			
467.01	0.076	0.048	468.33	0.076	0.127			
467.03	0.076	0.049	468.35	0.076	0.128			
467.05	0.076	0.050	468.37	0.076	0.129			
467.07	0.076	0.051	468.39	0.076	0.130			
467.09	0.076	0.053	468.41	0.076	0.131			
467.11	0.076	0.054	468.43	0.076	0.132			
467.13	0.076	0.055	468.45	0.076	0.133			
467.15	0.076	0.057	468.47	0.076	0.134			
467.17	0.076	0.058	468.49	0.076	0.135			
467.19	0.076	0.059	468.51	0.076	0.136			
467.21	0.076	0.060	468.53	0.076	0.137			
467.23	0.076	0.062	468.55	0.076	0.138			
467.25	0.076	0.063	468.57	0.076	0.139			
467.27	0.076	0.064	468.59	0.076	0.140			
467.29	0.076	0.065	468.61	0.076	0.141			
467.31	0.076	0.067	468.63	0.076	0.142			

### Summary for Pond INF 1.3: Infiltration System 1.3

Inflow Area = 0.046 ac, 100.00% Impervious, Inflow Depth = 4.84" for 10-yr event  
 Inflow = 0.2 cfs @ 12.04 hrs, Volume= 0.019 af  
 Outflow = 0.1 cfs @ 12.00 hrs, Volume= 0.019 af, Atten= 60%, Lag= 0.0 min  
 Discarded = 0.1 cfs @ 12.00 hrs, Volume= 0.019 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 593.58' @ 12.20 hrs Surf.Area= 0.006 ac Storage= 0.002 af

Plug-Flow detention time= 4.0 min calculated for 0.019 af (100% of inflow)  
 Center-of-Mass det. time= 4.0 min ( 752.8 - 748.8 )

Volume	Invert	Avail.Storage	Storage Description
#1A	593.00'	0.006 af	<b>16.00'W x 17.50'L x 3.54'H Field A</b> 0.023 af Overall - 0.008 af Embedded = 0.015 af x 40.0% Voids
#2A	593.50'	0.008 af	<b>Cultec R-330XLHD x 6 Inside #1</b> Effective Size= 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf Overall Size= 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap Row Length Adjustment= +1.50' x 7.45 sf x 3 rows
			0.014 af Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	593.00'	<b>14.000 in/hr Exfiltration over Horizontal area</b> Phase-In= 0.10'

**Discarded OutFlow** Max=0.1 cfs @ 12.00 hrs HW=593.20' (Free Discharge)

↳ **1=Exfiltration** (Exfiltration Controls 0.1 cfs)

### Pond INF 1.3: Infiltration System 1.3

#### Hydrograph



**Wolf Center - Post-4-20- 2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 10-yr Rainfall=5.08"*

Printed 10/20/2023

Page 34

**Stage-Area-Storage for Pond INF 1.3: Infiltration System 1.3**

Elevation (feet)	Horizontal (acres)	Storage (acre-feet)	Elevation (feet)	Horizontal (acres)	Storage (acre-feet)	Elevation (feet)	Horizontal (acres)	Storage (acre-feet)
593.00	<b>0.006</b>	0.000	594.32	0.006	0.005	595.64	0.006	0.011
593.02	0.006	0.000	594.34	0.006	0.006	595.66	0.006	0.011
593.04	0.006	0.000	594.36	0.006	0.006	595.68	0.006	0.011
593.06	0.006	0.000	594.38	0.006	0.006	595.70	0.006	0.012
593.08	0.006	0.000	594.40	0.006	0.006	595.72	0.006	0.012
593.10	0.006	0.000	594.42	0.006	0.006	595.74	0.006	0.012
593.12	0.006	0.000	594.44	0.006	0.006	595.76	0.006	0.012
593.14	0.006	0.000	594.46	0.006	0.006	595.78	0.006	0.012
593.16	0.006	0.000	594.48	0.006	0.006	595.80	0.006	0.012
593.18	0.006	0.000	594.50	0.006	0.006	595.82	0.006	0.012
593.20	0.006	0.001	594.52	0.006	0.006	595.84	0.006	0.012
593.22	0.006	0.001	594.54	0.006	0.006	595.86	0.006	0.012
593.24	0.006	0.001	594.56	0.006	0.007	595.88	0.006	0.012
593.26	0.006	0.001	594.58	0.006	0.007	595.90	0.006	0.012
593.28	0.006	0.001	594.60	0.006	0.007	595.92	0.006	0.012
593.30	0.006	0.001	594.62	0.006	0.007	595.94	0.006	0.012
593.32	0.006	0.001	594.64	0.006	0.007	595.96	0.006	0.012
593.34	0.006	0.001	594.66	0.006	0.007	595.98	0.006	0.012
593.36	0.006	0.001	594.68	0.006	0.007	596.00	0.006	0.012
593.38	0.006	0.001	594.70	0.006	0.007	596.02	0.006	0.013
593.40	0.006	0.001	594.72	0.006	0.007	596.04	0.006	0.013
593.42	0.006	0.001	594.74	0.006	0.007	596.06	0.006	0.013
593.44	0.006	0.001	594.76	0.006	0.008	596.08	0.006	0.013
593.46	0.006	0.001	594.78	0.006	0.008	596.10	0.006	0.013
593.48	0.006	0.001	594.80	0.006	0.008	596.12	0.006	0.013
593.50	0.006	0.001	594.82	0.006	0.008	596.14	0.006	0.013
593.52	0.006	0.001	594.84	0.006	0.008	596.16	0.006	0.013
593.54	0.006	0.001	594.86	0.006	0.008	596.18	0.006	0.013
593.56	0.006	0.002	594.88	0.006	0.008	596.20	0.006	0.013
593.58	0.006	0.002	594.90	0.006	0.008	596.22	0.006	0.013
593.60	0.006	0.002	594.92	0.006	0.008	596.24	0.006	0.013
593.62	0.006	0.002	594.94	0.006	0.008	596.26	0.006	0.013
593.64	0.006	0.002	594.96	0.006	0.008	596.28	0.006	0.013
593.66	0.006	0.002	594.98	0.006	0.009	596.30	0.006	0.013
593.68	0.006	0.002	595.00	0.006	0.009	596.32	0.006	0.013
593.70	0.006	0.002	595.02	0.006	0.009	596.34	0.006	0.013
593.72	0.006	0.002	595.04	0.006	0.009	596.36	0.006	0.013
593.74	0.006	0.003	595.06	0.006	0.009	596.38	0.006	0.013
593.76	0.006	0.003	595.08	0.006	0.009	596.40	0.006	0.014
593.78	0.006	0.003	595.10	0.006	0.009	596.42	0.006	0.014
593.80	0.006	0.003	595.12	0.006	0.009	596.44	0.006	0.014
593.82	0.006	0.003	595.14	0.006	0.009	596.46	0.006	0.014
593.84	0.006	0.003	595.16	0.006	0.009	596.48	0.006	0.014
593.86	0.006	0.003	595.18	0.006	0.009	596.50	0.006	0.014
593.88	0.006	0.003	595.20	0.006	0.010	596.52	0.006	0.014
593.90	0.006	0.003	595.22	0.006	0.010	596.54	0.006	<b>0.014</b>
593.92	0.006	0.003	595.24	0.006	0.010			
593.94	0.006	0.004	595.26	0.006	0.010			
593.96	0.006	0.004	595.28	0.006	0.010			
593.98	0.006	0.004	595.30	0.006	0.010			
594.00	0.006	0.004	595.32	0.006	0.010			
594.02	0.006	0.004	595.34	0.006	0.010			
594.04	0.006	0.004	595.36	0.006	0.010			
594.06	0.006	0.004	595.38	0.006	0.010			
594.08	0.006	0.004	595.40	0.006	0.010			
594.10	0.006	0.004	595.42	0.006	0.010			
594.12	0.006	0.004	595.44	0.006	0.011			
594.14	0.006	0.005	595.46	0.006	0.011			
594.16	0.006	0.005	595.48	0.006	0.011			
594.18	0.006	0.005	595.50	0.006	0.011			
594.20	0.006	0.005	595.52	0.006	0.011			
594.22	0.006	0.005	595.54	0.006	0.011			
594.24	0.006	0.005	595.56	0.006	0.011			
594.26	0.006	0.005	595.58	0.006	0.011			
594.28	0.006	0.005	595.60	0.006	0.011			
594.30	0.006	0.005	595.62	0.006	0.011			


### Summary for Link DP: Design Point

Inflow Area = 16.919 ac, 6.14% Impervious, Inflow Depth = 2.25" for 10-yr event  
 Inflow = 24.8 cfs @ 12.29 hrs, Volume= 3.179 af  
 Primary = 24.8 cfs @ 12.29 hrs, Volume= 3.179 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

### Link DP: Design Point

#### Hydrograph





**Wolf Center - Post-4-20- 2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 100-yr Rainfall=9.04"*

Printed 10/20/2023

Page 36

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN

Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

**Subcatchment1.0S: 1.0S**Runoff Area=705,538 sf 4.54% Impervious Runoff Depth=5.74"  
Flow Length=1,585' Tc=23.5 min CN=73 Runoff=57.2 cfs 7.750 af**Subcatchment1.1S: 1.1S**Runoff Area=31,450 sf 42.00% Impervious Runoff Depth=6.85"  
Tc=6.0 min CN=82 Runoff=4.9 cfs 0.412 af**Subcatchment1.2S: 1.2S**Runoff Area=45,619 sf 69.42% Impervious Runoff Depth=7.95"  
Tc=6.0 min CN=91 Runoff=7.9 cfs 0.694 af**Subcatchment1.3S: 1.3S**Runoff Area=2,000 sf 100.00% Impervious Runoff Depth=8.80"  
Tc=6.0 min CN=98 Runoff=0.4 cfs 0.034 af**Pond 1.1P: Infiltration Basin 1.1**Peak Elev=455.39' Storage=4,587 cf Inflow=4.9 cfs 0.412 af  
Discarded=1.0 cfs 0.395 af Primary=0.3 cfs 0.018 af Secondary=0.0 cfs 0.000 af Outflow=1.3 cfs 0.412 af**Pond DS1.2: Diversion Structure 1.2**Peak Elev=470.47' Inflow=7.9 cfs 0.694 af  
Primary=3.1 cfs 0.628 af Secondary=4.8 cfs 0.066 af Outflow=7.9 cfs 0.694 af**Pond DS1.3: Diversion Structure 1.3**Peak Elev=594.27' Inflow=0.4 cfs 0.034 af  
Primary=0.4 cfs 0.034 af Secondary=0.0 cfs 0.000 af Outflow=0.4 cfs 0.034 af**Pond INF 1.2: Infiltration System 1.2**Peak Elev=467.00' Storage=0.047 af Inflow=3.1 cfs 0.628 af  
Outflow=1.8 cfs 0.628 af**Pond INF 1.3: Infiltration System 1.3**Peak Elev=594.19' Storage=0.005 af Inflow=0.4 cfs 0.034 af  
Outflow=0.1 cfs 0.034 af**Link DP: Design Point**Inflow=57.7 cfs 7.834 af  
Primary=57.7 cfs 7.834 af

**Wolf Center - Post-4-20- 2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 100-yr Rainfall=9.04"*

Printed 10/20/2023

Page 37

**Summary for Subcatchment 1.0S: 1.0S**


Runoff = 57.2 cfs @ 12.28 hrs, Volume= 7.750 af, Depth= 5.74"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Buck Run 24-hr S1 100-yr Rainfall=9.04"

	Area (sf)	CN	Description
*	18,932	98	Existing Pavement
*	6,135	98	Existing Buildings
	5,607	87	Dirt roads, HSG C
*	6,970	98	Proposed Pavement
*	1,405	61	Existing >75% Grass cover, Good, HSG B
*	3,457	80	Proposed >75% Grass cover, Good, HSG D
*	3,083	61	Proposed >75% Grass cover, Good, HSG B
*	2,900	74	Existing >75% Grass cover, Good, HSG C
*	17,714	74	Proposed >75% Grass cover, Good, HSG C
	13,520	89	Gravel roads, HSG C
	22,115	55	Woods, Good, HSG B
	417,935	70	Woods, Good, HSG C
	150,505	77	Woods, Good, HSG D
	35,260	71	Meadow, non-grazed, HSG C
	705,538	73	Weighted Average
	673,501		95.46% Pervious Area
	32,037		4.54% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
11.4	100	0.0900	0.15		<b>Sheet Flow,</b>
					Woods: Light underbrush n= 0.400 P2= 3.40"
12.1	1,485	0.1670	2.04		<b>Shallow Concentrated Flow,</b>
					Woodland Kv= 5.0 fps
23.5	1,585	Total			

**Subcatchment 1.0S: 1.0S****Hydrograph**

### Summary for Subcatchment 1.1S: 1.1S

Runoff = 4.9 cfs @ 12.04 hrs, Volume= 0.412 af, Depth= 6.85"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs


Buck Run 24-hr S1 100-yr Rainfall=9.04"

	Area (sf)	CN	Description
*	12,870	98	Proposed Pavement
*	340	98	Proposed Sidewalk
	5,235	61	>75% Grass cover, Good, HSG B
	13,005	74	>75% Grass cover, Good, HSG C
	31,450	82	Weighted Average
	18,240		58.00% Pervious Area
	13,210		42.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

### Subcatchment 1.1S: 1.1S

#### Hydrograph



### Summary for Subcatchment 1.2S: 1.2S

Runoff = 7.9 cfs @ 12.04 hrs, Volume= 0.694 af, Depth= 7.95"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs


Buck Run 24-hr S1 100-yr Rainfall=9.04"

	Area (sf)	CN	Description
*	24,985	98	Proposed Pavement & Walkway
*	4,815	98	Proposed Building
	10,849	74	>75% Grass cover, Good, HSG C
*	1,870	98	Proposed Courtyard Imp
	3,100	74	>75% Grass cover, Good, HSG C
	45,619	91	Weighted Average
	13,949		30.58% Pervious Area
	31,670		69.42% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

### Subcatchment 1.2S: 1.2S

#### Hydrograph





### Summary for Subcatchment 1.3S: 1.3S

Runoff = 0.4 cfs @ 12.04 hrs, Volume= 0.034 af, Depth= 8.80"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs


Buck Run 24-hr S1 100-yr Rainfall=9.04"

Area (sf)	CN	Description
* 2,000	98	Proposed Pods and Facilities
2,000		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

### Subcatchment 1.3S: 1.3S

#### Hydrograph



### Summary for Pond 1.1P: Infiltration Basin 1.1

Inflow Area = 0.722 ac, 42.00% Impervious, Inflow Depth = 6.85" for 100-yr event  
 Inflow = 4.9 cfs @ 12.04 hrs, Volume= 0.412 af  
 Outflow = 1.3 cfs @ 12.41 hrs, Volume= 0.412 af, Atten= 73%, Lag= 22.4 min  
 Discarded = 1.0 cfs @ 12.41 hrs, Volume= 0.395 af  
 Primary = 0.3 cfs @ 12.41 hrs, Volume= 0.018 af  
 Secondary = 0.0 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 455.39' @ 12.41 hrs Surf.Area= 2,243 sf Storage= 4,587 cf

Plug-Flow detention time= 38.9 min calculated for 0.412 af (100% of inflow)  
 Center-of-Mass det. time= 38.9 min ( 845.0 - 806.1 )

Volume	Invert	Avail.Storage	Storage Description
#1	451.00'	9,077 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
451.00	125	0	0
452.00	447	286	286
454.00	1,356	1,803	2,089
456.00	2,634	3,990	6,079
457.00	3,362	2,998	9,077

Device	Routing	Invert	Outlet Devices
#1	Primary	450.30'	<b>12.0" Round Culvert</b> L= 58.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 450.30' / 449.50' S= 0.0138 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Device 1	454.75'	<b>4.0" Vert. Orifice/Grate</b> C= 0.600
#3	Device 1	455.50'	<b>30.0" x 48.0" Horiz. Orifice/Grate</b> C= 0.600 Limited to weir flow at low heads
#4	Discarded	451.00'	<b>20.000 in/hr Exfiltration over Surface area</b> Phase-In= 0.10'
#5	Secondary	456.00'	<b>10.0' long x 10.0' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 1.20 1.40 1.60 Coef. (English) 2.49 2.56 2.70 2.69 2.68 2.69 2.67 2.64


**Discarded OutFlow** Max=1.0 cfs @ 12.41 hrs HW=455.39' (Free Discharge)  
 ↳ **4=Exfiltration** (Exfiltration Controls 1.0 cfs)

**Primary OutFlow** Max=0.3 cfs @ 12.41 hrs HW=455.39' TW=0.00' (Dynamic Tailwater)  
 ↳ **1=Culvert** (Passes 0.3 cfs of 7.6 cfs potential flow)  
 ↳ ↳ **2=Orifice/Grate** (Orifice Controls 0.3 cfs @ 3.30 fps)  
 ↳ ↳ ↳ **3=Orifice/Grate** ( Controls 0.0 cfs)

**Secondary OutFlow** Max=0.0 cfs @ 0.00 hrs HW=451.00' TW=0.00' (Dynamic Tailwater)  
 ↳ **5=Broad-Crested Rectangular Weir** ( Controls 0.0 cfs)

**Pond 1.1P: Infiltration Basin 1.1**

**Hydrograph**



**Wolf Center - Post-4-20- 2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 100-yr Rainfall=9.04"*

Printed 10/20/2023

Page 43

**Stage-Area-Storage for Pond 1.1P: Infiltration Basin 1.1**

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
451.00	125	0
451.10	157	14
451.20	189	31
451.30	222	52
451.40	254	76
451.50	286	103
451.60	318	133
451.70	350	166
451.80	383	203
451.90	415	243
452.00	447	286
452.10	492	333
452.20	538	384
452.30	583	441
452.40	629	501
452.50	674	566
452.60	720	636
452.70	765	710
452.80	811	789
452.90	856	872
453.00	902	960
453.10	947	1,053
453.20	992	1,150
453.30	1,038	1,251
453.40	1,083	1,357
453.50	1,129	1,468
453.60	1,174	1,583
453.70	1,220	1,703
453.80	1,265	1,827
453.90	1,311	1,956
454.00	1,356	2,089
454.10	1,420	2,228
454.20	1,484	2,373
454.30	1,548	2,525
454.40	1,612	2,683
454.50	1,676	2,847
454.60	1,739	3,018
454.70	1,803	3,195
454.80	1,867	3,378
454.90	1,931	3,568
455.00	1,995	3,765
455.10	2,059	3,967
455.20	2,123	4,176
455.30	2,187	4,392
455.40	2,251	4,614
455.50	2,315	4,842
455.60	2,378	5,077
455.70	2,442	5,318
455.80	2,506	5,565
455.90	2,570	5,819
456.00	2,634	6,079
456.10	2,707	6,346
456.20	2,780	6,620
456.30	2,852	6,902
456.40	2,925	7,191
456.50	2,998	7,487
456.60	3,071	7,790
456.70	3,144	8,101
456.80	3,216	8,419
456.90	3,289	8,744
457.00	<b>3,362</b>	<b>9,077</b>



### Summary for Pond DS1.2: Diversion Structure 1.2

Inflow Area = 1.047 ac, 69.42% Impervious, Inflow Depth = 7.95" for 100-yr event  
 Inflow = 7.9 cfs @ 12.04 hrs, Volume= 0.694 af  
 Outflow = 7.9 cfs @ 12.04 hrs, Volume= 0.694 af, Atten= 0%, Lag= 0.0 min  
 Primary = 3.1 cfs @ 12.05 hrs, Volume= 0.628 af  
 Secondary = 4.8 cfs @ 12.04 hrs, Volume= 0.066 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 470.47' @ 12.05 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	466.67'	<b>8.0" Round Culvert</b> L= 6.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 466.67' / 466.60' S= 0.0117 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.35 sf
#2	Device 3	469.35'	<b>2.0' long x 0.5' breadth Broad-Crested Rectangular Weir</b> Head (feet) 0.20 0.40 0.60 0.80 1.00 Coef. (English) 2.80 2.92 3.08 3.30 3.32
#3	Secondary	462.28'	<b>8.0" Round Culvert</b> L= 103.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 462.28' / 448.16' S= 0.1371 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.35 sf

**Primary OutFlow** Max=3.1 cfs @ 12.05 hrs HW=470.44' TW=466.62' (Dynamic Tailwater)

↑ **1=Culvert** (Inlet Controls 3.1 cfs @ 8.92 fps)


**Secondary OutFlow** Max=4.7 cfs @ 12.04 hrs HW=470.38' TW=0.00' (Dynamic Tailwater)

↑ **3=Culvert** (Inlet Controls 4.7 cfs @ 13.42 fps)

↑ **2=Broad-Crested Rectangular Weir** (Passes 4.7 cfs of 6.9 cfs potential flow)

### Pond DS1.2: Diversion Structure 1.2

#### Hydrograph



**Stage-Area-Storage for Pond DS1.2: Diversion Structure 1.2**

Elevation (feet)	Storage (cubic-feet)	Elevation (feet)	Storage (cubic-feet)	Elevation (feet)	Storage (cubic-feet)	Elevation (feet)	Storage (cubic-feet)
462.28	0	464.92	0	467.56	0	470.20	0
462.32	0	464.96	0	467.60	0	470.24	0
462.36	0	465.00	0	467.64	0	470.28	0
462.40	0	465.04	0	467.68	0	470.32	0
462.44	0	465.08	0	467.72	0	470.36	0
462.48	0	465.12	0	467.76	0	470.40	0
462.52	0	465.16	0	467.80	0	470.44	0
462.56	0	465.20	0	467.84	0	470.48	0
462.60	0	465.24	0	467.88	0		
462.64	0	465.28	0	467.92	0		
462.68	0	465.32	0	467.96	0		
462.72	0	465.36	0	468.00	0		
462.76	0	465.40	0	468.04	0		
462.80	0	465.44	0	468.08	0		
462.84	0	465.48	0	468.12	0		
462.88	0	465.52	0	468.16	0		
462.92	0	465.56	0	468.20	0		
462.96	0	465.60	0	468.24	0		
463.00	0	465.64	0	468.28	0		
463.04	0	465.68	0	468.32	0		
463.08	0	465.72	0	468.36	0		
463.12	0	465.76	0	468.40	0		
463.16	0	465.80	0	468.44	0		
463.20	0	465.84	0	468.48	0		
463.24	0	465.88	0	468.52	0		
463.28	0	465.92	0	468.56	0		
463.32	0	465.96	0	468.60	0		
463.36	0	466.00	0	468.64	0		
463.40	0	466.04	0	468.68	0		
463.44	0	466.08	0	468.72	0		
463.48	0	466.12	0	468.76	0		
463.52	0	466.16	0	468.80	0		
463.56	0	466.20	0	468.84	0		
463.60	0	466.24	0	468.88	0		
463.64	0	466.28	0	468.92	0		
463.68	0	466.32	0	468.96	0		
463.72	0	466.36	0	469.00	0		
463.76	0	466.40	0	469.04	0		
463.80	0	466.44	0	469.08	0		
463.84	0	466.48	0	469.12	0		
463.88	0	466.52	0	469.16	0		
463.92	0	466.56	0	469.20	0		
463.96	0	466.60	0	469.24	0		
464.00	0	466.64	0	469.28	0		
464.04	0	466.68	0	469.32	0		
464.08	0	466.72	0	469.36	0		
464.12	0	466.76	0	469.40	0		
464.16	0	466.80	0	469.44	0		
464.20	0	466.84	0	469.48	0		
464.24	0	466.88	0	469.52	0		
464.28	0	466.92	0	469.56	0		
464.32	0	466.96	0	469.60	0		
464.36	0	467.00	0	469.64	0		
464.40	0	467.04	0	469.68	0		
464.44	0	467.08	0	469.72	0		
464.48	0	467.12	0	469.76	0		
464.52	0	467.16	0	469.80	0		
464.56	0	467.20	0	469.84	0		
464.60	0	467.24	0	469.88	0		
464.64	0	467.28	0	469.92	0		
464.68	0	467.32	0	469.96	0		
464.72	0	467.36	0	470.00	0		
464.76	0	467.40	0	470.04	0		
464.80	0	467.44	0	470.08	0		
464.84	0	467.48	0	470.12	0		
464.88	0	467.52	0	470.16	0		

### Summary for Pond DS1.3: Diversion Structure 1.3

Inflow Area = 0.046 ac, 100.00% Impervious, Inflow Depth = 8.80" for 100-yr event  
 Inflow = 0.4 cfs @ 12.04 hrs, Volume= 0.034 af  
 Outflow = 0.4 cfs @ 12.04 hrs, Volume= 0.034 af, Atten= 0%, Lag= 0.0 min  
 Primary = 0.4 cfs @ 12.04 hrs, Volume= 0.034 af  
 Secondary = 0.0 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 594.27' @ 12.06 hrs


Device	Routing	Invert	Outlet Devices
#1	Primary	593.10'	<b>4.0" Round Culvert</b> L= 6.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 593.10' / 593.00' S= 0.0167 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.09 sf
#2	Secondary	595.20'	<b>8.0" Round Culvert</b> L= 154.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 595.20' / 590.00' S= 0.0338 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.35 sf

**Primary OutFlow** Max=0.3 cfs @ 12.04 hrs HW=594.17' TW=593.69' (Dynamic Tailwater)  
 ↑ **1=Culvert** (Inlet Controls 0.3 cfs @ 3.34 fps)

**Secondary OutFlow** Max=0.0 cfs @ 0.00 hrs HW=593.10' TW=0.00' (Dynamic Tailwater)  
 ↑ **2=Culvert** ( Controls 0.0 cfs)

### Pond DS1.3: Diversion Structure 1.3

#### Hydrograph



**Stage-Area-Storage for Pond DS1.3: Diversion Structure 1.3**

Elevation (feet)	Storage (cubic-feet)	Elevation (feet)	Storage (cubic-feet)	Elevation (feet)	Storage (cubic-feet)
593.10	0	594.42	0	595.74	0
593.12	0	594.44	0	595.76	0
593.14	0	594.46	0	595.78	0
593.16	0	594.48	0	595.80	0
593.18	0	594.50	0	595.82	0
593.20	0	594.52	0	595.84	0
593.22	0	594.54	0	595.86	0
593.24	0	594.56	0		
593.26	0	594.58	0		
593.28	0	594.60	0		
593.30	0	594.62	0		
593.32	0	594.64	0		
593.34	0	594.66	0		
593.36	0	594.68	0		
593.38	0	594.70	0		
593.40	0	594.72	0		
593.42	0	594.74	0		
593.44	0	594.76	0		
593.46	0	594.78	0		
593.48	0	594.80	0		
593.50	0	594.82	0		
593.52	0	594.84	0		
593.54	0	594.86	0		
593.56	0	594.88	0		
593.58	0	594.90	0		
593.60	0	594.92	0		
593.62	0	594.94	0		
593.64	0	594.96	0		
593.66	0	594.98	0		
593.68	0	595.00	0		
593.70	0	595.02	0		
593.72	0	595.04	0		
593.74	0	595.06	0		
593.76	0	595.08	0		
593.78	0	595.10	0		
593.80	0	595.12	0		
593.82	0	595.14	0		
593.84	0	595.16	0		
593.86	0	595.18	0		
593.88	0	595.20	0		
593.90	0	595.22	0		
593.92	0	595.24	0		
593.94	0	595.26	0		
593.96	0	595.28	0		
593.98	0	595.30	0		
594.00	0	595.32	0		
594.02	0	595.34	0		
594.04	0	595.36	0		
594.06	0	595.38	0		
594.08	0	595.40	0		
594.10	0	595.42	0		
594.12	0	595.44	0		
594.14	0	595.46	0		
594.16	0	595.48	0		
594.18	0	595.50	0		
594.20	0	595.52	0		
594.22	0	595.54	0		
594.24	0	595.56	0		
594.26	0	595.58	0		
594.28	0	595.60	0		
594.30	0	595.62	0		
594.32	0	595.64	0		
594.34	0	595.66	0		
594.36	0	595.68	0		
594.38	0	595.70	0		
594.40	0	595.72	0		

### Summary for Pond INF 1.2: Infiltration System 1.2

Inflow Area = 1.047 ac, 69.42% Impervious, Inflow Depth = 7.20" for 100-yr event  
 Inflow = 3.1 cfs @ 12.05 hrs, Volume= 0.628 af  
 Outflow = 1.8 cfs @ 11.75 hrs, Volume= 0.628 af, Atten= 41%, Lag= 0.0 min  
 Discarded = 1.8 cfs @ 11.75 hrs, Volume= 0.628 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 467.00' @ 12.49 hrs Surf.Area= 0.076 ac Storage= 0.047 af

Plug-Flow detention time= 4.5 min calculated for 0.628 af (100% of inflow)  
 Center-of-Mass det. time= 4.5 min ( 784.9 - 780.4 )

Volume	Invert	Avail.Storage	Storage Description
#1A	466.01'	0.064 af	<b>30.50'W x 108.50'L x 3.54'H Field A</b> 0.269 af Overall - 0.109 af Embedded = 0.160 af x 40.0% Voids
#2A	466.51'	0.109 af	<b>Cultec R-330XLHD x 90 Inside #1</b> Effective Size= 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf Overall Size= 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap Row Length Adjustment= +1.50' x 7.45 sf x 6 rows
			0.173 af Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	466.01'	<b>24.000 in/hr Exfiltration over Horizontal area</b> Phase-In= 0.10'

**Discarded OutFlow** Max=1.8 cfs @ 11.75 hrs HW=466.13' (Free Discharge)

↳ **1=Exfiltration** (Exfiltration Controls 1.8 cfs)

### Pond INF 1.2: Infiltration System 1.2

Hydrograph





**Stage-Area-Storage for Pond INF 1.2: Infiltration System 1.2**

Elevation (feet)	Horizontal (acres)	Storage (acre-feet)	Elevation (feet)	Horizontal (acres)	Storage (acre-feet)	Elevation (feet)	Horizontal (acres)	Storage (acre-feet)
466.01	<b>0.076</b>	0.000	467.33	0.076	0.068	468.65	0.076	0.143
466.03	0.076	0.001	467.35	0.076	0.069	468.67	0.076	0.144
466.05	0.076	0.001	467.37	0.076	0.070	468.69	0.076	0.145
466.07	0.076	0.002	467.39	0.076	0.072	468.71	0.076	0.146
466.09	0.076	0.002	467.41	0.076	0.073	468.73	0.076	0.147
466.11	0.076	0.003	467.43	0.076	0.074	468.75	0.076	0.147
466.13	0.076	0.004	467.45	0.076	0.075	468.77	0.076	0.148
466.15	0.076	0.004	467.47	0.076	0.077	468.79	0.076	0.149
466.17	0.076	0.005	467.49	0.076	0.078	468.81	0.076	0.150
466.19	0.076	0.005	467.51	0.076	0.079	468.83	0.076	0.151
466.21	0.076	0.006	467.53	0.076	0.080	468.85	0.076	0.151
466.23	0.076	0.007	467.55	0.076	0.082	468.87	0.076	0.152
466.25	0.076	0.007	467.57	0.076	0.083	468.89	0.076	0.153
466.27	0.076	0.008	467.59	0.076	0.084	468.91	0.076	0.153
466.29	0.076	0.009	467.61	0.076	0.085	468.93	0.076	0.154
466.31	0.076	0.009	467.63	0.076	0.086	468.95	0.076	0.155
466.33	0.076	0.010	467.65	0.076	0.088	468.97	0.076	0.155
466.35	0.076	0.010	467.67	0.076	0.089	468.99	0.076	0.156
466.37	0.076	0.011	467.69	0.076	0.090	469.01	0.076	0.157
466.39	0.076	0.012	467.71	0.076	0.091	469.03	0.076	0.157
466.41	0.076	0.012	467.73	0.076	0.093	469.05	0.076	0.158
466.43	0.076	0.013	467.75	0.076	0.094	469.07	0.076	0.159
466.45	0.076	0.013	467.77	0.076	0.095	469.09	0.076	0.159
466.47	0.076	0.014	467.79	0.076	0.096	469.11	0.076	0.160
466.49	0.076	0.015	467.81	0.076	0.097	469.13	0.076	0.160
466.51	0.076	0.015	467.83	0.076	0.099	469.15	0.076	0.161
466.53	0.076	0.017	467.85	0.076	0.100	469.17	0.076	0.162
466.55	0.076	0.018	467.87	0.076	0.101	469.19	0.076	0.162
466.57	0.076	0.019	467.89	0.076	0.102	469.21	0.076	0.163
466.59	0.076	0.020	467.91	0.076	0.103	469.23	0.076	0.163
466.61	0.076	0.022	467.93	0.076	0.105	469.25	0.076	0.164
466.63	0.076	0.023	467.95	0.076	0.106	469.27	0.076	0.165
466.65	0.076	0.024	467.97	0.076	0.107	469.29	0.076	0.165
466.67	0.076	0.026	467.99	0.076	0.108	469.31	0.076	0.166
466.69	0.076	0.027	468.01	0.076	0.109	469.33	0.076	0.166
466.71	0.076	0.028	468.03	0.076	0.110	469.35	0.076	0.167
466.73	0.076	0.030	468.05	0.076	0.112	469.37	0.076	0.168
466.75	0.076	0.031	468.07	0.076	0.113	469.39	0.076	0.168
466.77	0.076	0.032	468.09	0.076	0.114	469.41	0.076	0.169
466.79	0.076	0.033	468.11	0.076	0.115	469.43	0.076	0.170
466.81	0.076	0.035	468.13	0.076	0.116	469.45	0.076	0.170
466.83	0.076	0.036	468.15	0.076	0.117	469.47	0.076	0.171
466.85	0.076	0.037	468.17	0.076	0.118	469.49	0.076	0.171
466.87	0.076	0.039	468.19	0.076	0.119	469.51	0.076	0.172
466.89	0.076	0.040	468.21	0.076	0.121	469.53	0.076	0.173
466.91	0.076	0.041	468.23	0.076	0.122	469.55	0.076	<b>0.173</b>
466.93	0.076	0.042	468.25	0.076	0.123			
466.95	0.076	0.044	468.27	0.076	0.124			
466.97	0.076	0.045	468.29	0.076	0.125			
466.99	0.076	0.046	468.31	0.076	0.126			
467.01	0.076	0.048	468.33	0.076	0.127			
467.03	0.076	0.049	468.35	0.076	0.128			
467.05	0.076	0.050	468.37	0.076	0.129			
467.07	0.076	0.051	468.39	0.076	0.130			
467.09	0.076	0.053	468.41	0.076	0.131			
467.11	0.076	0.054	468.43	0.076	0.132			
467.13	0.076	0.055	468.45	0.076	0.133			
467.15	0.076	0.057	468.47	0.076	0.134			
467.17	0.076	0.058	468.49	0.076	0.135			
467.19	0.076	0.059	468.51	0.076	0.136			
467.21	0.076	0.060	468.53	0.076	0.137			
467.23	0.076	0.062	468.55	0.076	0.138			
467.25	0.076	0.063	468.57	0.076	0.139			
467.27	0.076	0.064	468.59	0.076	0.140			
467.29	0.076	0.065	468.61	0.076	0.141			
467.31	0.076	0.067	468.63	0.076	0.142			

### Summary for Pond INF 1.3: Infiltration System 1.3

Inflow Area = 0.046 ac, 100.00% Impervious, Inflow Depth = 8.80" for 100-yr event  
 Inflow = 0.4 cfs @ 12.04 hrs, Volume= 0.034 af  
 Outflow = 0.1 cfs @ 11.80 hrs, Volume= 0.034 af, Atten= 75%, Lag= 0.0 min  
 Discarded = 0.1 cfs @ 11.80 hrs, Volume= 0.034 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs  
 Peak Elev= 594.19' @ 12.42 hrs Surf.Area= 0.006 ac Storage= 0.005 af

Plug-Flow detention time= 10.2 min calculated for 0.034 af (100% of inflow)  
 Center-of-Mass det. time= 10.1 min ( 750.1 - 739.9 )

Volume	Invert	Avail.Storage	Storage Description
#1A	593.00'	0.006 af	<b>16.00'W x 17.50'L x 3.54'H Field A</b> 0.023 af Overall - 0.008 af Embedded = 0.015 af x 40.0% Voids
#2A	593.50'	0.008 af	<b>Cultec R-330XLHD x 6 Inside #1</b> Effective Size= 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf Overall Size= 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap Row Length Adjustment= +1.50' x 7.45 sf x 3 rows
			0.014 af Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	593.00'	<b>14.000 in/hr Exfiltration over Horizontal area</b> Phase-In= 0.10'

**Discarded OutFlow** Max=0.1 cfs @ 11.80 hrs HW=593.11' (Free Discharge)

↳ **1=Exfiltration** (Exfiltration Controls 0.1 cfs)

### Pond INF 1.3: Infiltration System 1.3

Hydrograph



**Wolf Center - Post-4-20- 2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 100-yr Rainfall=9.04"*

Printed 10/20/2023

Page 51

**Stage-Area-Storage for Pond INF 1.3: Infiltration System 1.3**

Elevation (feet)	Horizontal (acres)	Storage (acre-feet)	Elevation (feet)	Horizontal (acres)	Storage (acre-feet)	Elevation (feet)	Horizontal (acres)	Storage (acre-feet)
593.00	<b>0.006</b>	0.000	594.32	0.006	0.005	595.64	0.006	0.011
593.02	0.006	0.000	594.34	0.006	0.006	595.66	0.006	0.011
593.04	0.006	0.000	594.36	0.006	0.006	595.68	0.006	0.011
593.06	0.006	0.000	594.38	0.006	0.006	595.70	0.006	0.012
593.08	0.006	0.000	594.40	0.006	0.006	595.72	0.006	0.012
593.10	0.006	0.000	594.42	0.006	0.006	595.74	0.006	0.012
593.12	0.006	0.000	594.44	0.006	0.006	595.76	0.006	0.012
593.14	0.006	0.000	594.46	0.006	0.006	595.78	0.006	0.012
593.16	0.006	0.000	594.48	0.006	0.006	595.80	0.006	0.012
593.18	0.006	0.000	594.50	0.006	0.006	595.82	0.006	0.012
593.20	0.006	0.001	594.52	0.006	0.006	595.84	0.006	0.012
593.22	0.006	0.001	594.54	0.006	0.006	595.86	0.006	0.012
593.24	0.006	0.001	594.56	0.006	0.007	595.88	0.006	0.012
593.26	0.006	0.001	594.58	0.006	0.007	595.90	0.006	0.012
593.28	0.006	0.001	594.60	0.006	0.007	595.92	0.006	0.012
593.30	0.006	0.001	594.62	0.006	0.007	595.94	0.006	0.012
593.32	0.006	0.001	594.64	0.006	0.007	595.96	0.006	0.012
593.34	0.006	0.001	594.66	0.006	0.007	595.98	0.006	0.012
593.36	0.006	0.001	594.68	0.006	0.007	596.00	0.006	0.012
593.38	0.006	0.001	594.70	0.006	0.007	596.02	0.006	0.013
593.40	0.006	0.001	594.72	0.006	0.007	596.04	0.006	0.013
593.42	0.006	0.001	594.74	0.006	0.007	596.06	0.006	0.013
593.44	0.006	0.001	594.76	0.006	0.008	596.08	0.006	0.013
593.46	0.006	0.001	594.78	0.006	0.008	596.10	0.006	0.013
593.48	0.006	0.001	594.80	0.006	0.008	596.12	0.006	0.013
593.50	0.006	0.001	594.82	0.006	0.008	596.14	0.006	0.013
593.52	0.006	0.001	594.84	0.006	0.008	596.16	0.006	0.013
593.54	0.006	0.001	594.86	0.006	0.008	596.18	0.006	0.013
593.56	0.006	0.002	594.88	0.006	0.008	596.20	0.006	0.013
593.58	0.006	0.002	594.90	0.006	0.008	596.22	0.006	0.013
593.60	0.006	0.002	594.92	0.006	0.008	596.24	0.006	0.013
593.62	0.006	0.002	594.94	0.006	0.008	596.26	0.006	0.013
593.64	0.006	0.002	594.96	0.006	0.008	596.28	0.006	0.013
593.66	0.006	0.002	594.98	0.006	0.009	596.30	0.006	0.013
593.68	0.006	0.002	595.00	0.006	0.009	596.32	0.006	0.013
593.70	0.006	0.002	595.02	0.006	0.009	596.34	0.006	0.013
593.72	0.006	0.002	595.04	0.006	0.009	596.36	0.006	0.013
593.74	0.006	0.003	595.06	0.006	0.009	596.38	0.006	0.013
593.76	0.006	0.003	595.08	0.006	0.009	596.40	0.006	0.014
593.78	0.006	0.003	595.10	0.006	0.009	596.42	0.006	0.014
593.80	0.006	0.003	595.12	0.006	0.009	596.44	0.006	0.014
593.82	0.006	0.003	595.14	0.006	0.009	596.46	0.006	0.014
593.84	0.006	0.003	595.16	0.006	0.009	596.48	0.006	0.014
593.86	0.006	0.003	595.18	0.006	0.009	596.50	0.006	0.014
593.88	0.006	0.003	595.20	0.006	0.010	596.52	0.006	0.014
593.90	0.006	0.003	595.22	0.006	0.010	596.54	0.006	<b>0.014</b>
593.92	0.006	0.003	595.24	0.006	0.010			
593.94	0.006	0.004	595.26	0.006	0.010			
593.96	0.006	0.004	595.28	0.006	0.010			
593.98	0.006	0.004	595.30	0.006	0.010			
594.00	0.006	0.004	595.32	0.006	0.010			
594.02	0.006	0.004	595.34	0.006	0.010			
594.04	0.006	0.004	595.36	0.006	0.010			
594.06	0.006	0.004	595.38	0.006	0.010			
594.08	0.006	0.004	595.40	0.006	0.010			
594.10	0.006	0.004	595.42	0.006	0.010			
594.12	0.006	0.004	595.44	0.006	0.011			
594.14	0.006	0.005	595.46	0.006	0.011			
594.16	0.006	0.005	595.48	0.006	0.011			
594.18	0.006	0.005	595.50	0.006	0.011			
594.20	0.006	0.005	595.52	0.006	0.011			
594.22	0.006	0.005	595.54	0.006	0.011			
594.24	0.006	0.005	595.56	0.006	0.011			
594.26	0.006	0.005	595.58	0.006	0.011			
594.28	0.006	0.005	595.60	0.006	0.011			
594.30	0.006	0.005	595.62	0.006	0.011			


### Summary for Link DP: Design Point

Inflow Area = 16.919 ac, 6.14% Impervious, Inflow Depth = 5.56" for 100-yr event  
 Inflow = 57.7 cfs @ 12.27 hrs, Volume= 7.834 af  
 Primary = 57.7 cfs @ 12.27 hrs, Volume= 7.834 af, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

### Link DP: Design Point



#### Hydrograph



Appendix D:  
NRCS Soil Mapping



# Hydrologic Soil Group—Westchester County, New York (WOLF CENTER SOILS)



**Natural Resources  
Conservation Service**

Web Soil Survey  
National Cooperative Soil Survey

2/11/2016  
Page 1 of 4

Hydrologic Soil Group—Westchester County, New York  
(WOLF CENTER SOILS)

## MAP LEGEND

### Area of Interest (AOI)









 Area of Interest (AOI)

### Soils

#### Soil Rating Polygons





 A  
 A/D  
 B  
 B/D  
 C  
 C/D  
 D  
 Not rated or not available

#### Soil Rating Lines


 A  
 A/D  
 B  
 B/D  
 C  
 C/D  
 D  
 Not rated or not available

#### Soil Rating Points






 A  
 A/D  
 B  
 B/D

 C  
 C/D  
 D  
 Not rated or not available

### Water Features

 Streams and Canals

### Transportation

 Rails  
 Interstate Highways  
 US Routes  
 Major Roads  
 Local Roads

### Background

 Aerial Photography

## MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:12,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service  
 Web Soil Survey URL: <http://websoilsurvey.nrcs.usda.gov>  
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Westchester County, New York  
 Survey Area Data: Version 11, Sep 25, 2015

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Mar 26, 2011—Apr 16, 2012

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

## Hydrologic Soil Group

Hydrologic Soil Group— Summary by Map Unit — Westchester County, New York (NY119)				
Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
Ce	Catden muck, 0 to 2 percent slopes	B/D	1.5	0.9%
ChC	Charlton loam, 8 to 15 percent slopes	B	5.4	3.2%
Pa	Palms muck	A/D	2.9	1.8%
PnB	Paxton fine sandy loam, 3 to 8 percent slopes	C	20.0	12.0%
PnC	Paxton fine sandy loam, 8 to 15 percent slopes	C	20.1	12.0%
PnD	Paxton fine sandy loam, 15 to 25 percent slopes	C	41.1	24.6%
RdB	Ridgebury loam, 3 to 8 percent slopes	B/D	30.7	18.3%
RgB	Ridgebury loam, 2 to 8 percent slopes, very stony	B/D	1.3	0.8%
Sh	Sun loam	C/D	11.4	6.8%
SuB	Sutton loam, 3 to 8 percent slopes	B	10.9	6.5%
Ub	Udorthents, smoothed	B	1.1	0.7%
W	Water		0.2	0.1%
WdA	Woodbridge loam, 0 to 3 percent slopes	C/D	0.1	0.0%
WdB	Woodbridge loam, 3 to 8 percent slopes	C/D	16.6	9.9%
WdC	Woodbridge loam, 8 to 15 percent slopes	C/D	3.8	2.2%
<b>Totals for Area of Interest</b>			<b>167.2</b>	<b>100.0%</b>



## Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

## Rating Options

*Aggregation Method:* Dominant Condition

*Component Percent Cutoff:* None Specified

*Tie-break Rule:* Higher

## Appendix E:

New York Standards and Specifications for Erosion and Sediment  
Control Construction Site Log Book



**APPENDIX F**  
**CONSTRUCTION SITE INSPECTION**  
**AND MAINTENANCE LOG BOOK**

**STATE POLLUTANT DISCHARGE ELIMINATION SYSTEM FOR CONSTRUCTION  
ACTIVITIES**

**SAMPLE CONSTRUCTION SITE LOG BOOK**

Table of Contents

---

- I. Pre-Construction Meeting Documents
  - a. Preamble to Site Assessment and Inspections
  - b. Pre-Construction Site Assessment Checklist
  
- II. Construction Duration Inspections
  - a. Directions
  - b. Modification to the SWPPP

## I. PRE-CONSTRUCTION MEETING DOCUMENTS

**Project Name** \_\_\_\_\_  
**Permit No.** \_\_\_\_\_ **Date of Authorization** \_\_\_\_\_  
**Name of Operator** \_\_\_\_\_  
**Prime Contractor** \_\_\_\_\_

### a. Preamble to Site Assessment and Inspections

The Following Information To Be Read By All Person's Involved in The Construction of Stormwater Related Activities:

The Operator agrees to have a qualified inspector<sup>1</sup> conduct an assessment of the site prior to the commencement of construction<sup>2</sup> and certify in this inspection report that the appropriate erosion and sediment controls described in the SWPPP have been adequately installed or implemented to ensure overall preparedness of the site for the commencement of construction.

Prior to the commencement of construction, the Operator shall certify in this site logbook that the SWPPP has been prepared in accordance with the State's standards and meets all Federal, State and local erosion and sediment control requirements. A preconstruction meeting should be held to review all of the SWPPP requirements with construction personnel.

When construction starts, site inspections shall be conducted by the qualified inspector at least every 7 calendar days. The Operator shall maintain a record of all inspection reports in this site logbook. The site logbook shall be maintained on site and be made available to the permitting authorities upon request.

Prior to filing the Notice of Termination or the end of permit term, the Operator shall have a qualified inspector perform a final site inspection. The qualified inspector shall certify that the site has undergone final stabilization<sup>3</sup> using either vegetative or structural stabilization methods and that all temporary erosion and sediment controls (such as silt fencing) not needed for long-term erosion control have been removed. In addition, the Operator must identify and certify that all permanent structures described in the SWPPP have been constructed and provide the owner(s) with an operation and maintenance plan that ensures the structure(s) continuously functions as designed.

1 Refer to "Qualified Inspector" inspection requirements in the current SPDES General Permit for Stormwater Discharges from Construction Activity for complete list of inspection requirements.

2 "Commencement of construction" means the initial removal of vegetation and disturbance of soils associated with clearing, grading or excavating activities or other construction activities.

3 "Final stabilization" means that all soil-disturbing activities at the site have been completed and a uniform, perennial vegetative cover with a density of eighty (80) percent has been established or equivalent stabilization measures (such as the use of mulches or geotextiles) have been employed on all unpaved areas and areas not covered by permanent structures.

## **b. Pre-construction Site Assessment Checklist**

**(NOTE: Provide comments below as necessary)**

### **1. Notice of Intent, SWPPP, and Contractors Certification:**

**Yes No NA**

- ☐ ☐ ☐ Has a Notice of Intent been filed with the NYS Department of Conservation?
- ☐ ☐ ☐ Is the SWPPP on-site? Where? \_\_\_\_\_
- ☐ ☐ ☐ Is the Plan current? What is the latest revision date? \_\_\_\_\_
- ☐ ☐ ☐ Is a copy of the NOI (with brief description) onsite? Where? \_\_\_\_\_
- ☐ ☐ ☐ Have all contractors involved with stormwater related activities signed a contractor's certification?

### **2. Resource Protection**

**Yes No NA**

- ☐ ☐ ☐ Are construction limits clearly flagged or fenced?
- ☐ ☐ ☐ Important trees and associated rooting zones, on-site septic system absorption fields, existing vegetated areas suitable for filter strips, especially in perimeter areas, have been flagged for protection.
- ☐ ☐ ☐ Creek crossings installed prior to land-disturbing activity, including clearing and blasting.

### **3. Surface Water Protection**

**Yes No NA**

- ☐ ☐ ☐ Clean stormwater runoff has been diverted from areas to be disturbed.
- ☐ ☐ ☐ Bodies of water located either on site or in the vicinity of the site have been identified and protected.
- ☐ ☐ ☐ Appropriate practices to protect on-site or downstream surface water are installed.
- ☐ ☐ ☐ Are clearing and grading operations divided into areas <5 acres?

### **4. Stabilized Construction Access**

**Yes No NA**

- ☐ ☐ ☐ A temporary construction entrance to capture mud and debris from construction vehicles before they enter the public highway has been installed.
- ☐ ☐ ☐ Other access areas (entrances, construction routes, equipment parking areas) are stabilized immediately as work takes place with gravel or other cover.
- ☐ ☐ ☐ Sediment tracked onto public streets is removed or cleaned on a regular basis.

### **5. Sediment Controls**

**Yes No NA**

- ☐ ☐ ☐ Silt fence material and installation comply with the standard drawing and specifications.
- ☐ ☐ ☐ Silt fences are installed at appropriate spacing intervals
- ☐ ☐ ☐ Sediment/detention basin was installed as first land disturbing activity.
- ☐ ☐ ☐ Sediment traps and barriers are installed.

### **6. Pollution Prevention for Waste and Hazardous Materials**

**Yes No NA**

- ☐ ☐ ☐ The Operator or designated representative has been assigned to implement the spill prevention avoidance and response plan.
- ☐ ☐ ☐ The plan is contained in the SWPPP on page \_\_\_\_\_
- ☐ ☐ ☐ Appropriate materials to control spills are onsite. Where? \_\_\_\_\_

## II. CONSTRUCTION DURATION INSPECTIONS

### a. Directions:

**Inspection Forms will be filled out during the entire construction phase of the project.**

Required Elements:

- 1) On a site map, indicate the extent of all disturbed site areas and drainage pathways. Indicate site areas that are expected to undergo initial disturbance or significant site work within the next 14-day period;
- 2) Indicate on a site map all areas of the site that have undergone temporary or permanent stabilization;
- 3) Indicate all disturbed site areas that have not undergone active site work during the previous 14-day period;
- 4) Inspect all sediment control practices and record the approximate degree of sediment accumulation as a percentage of sediment storage volume (for example, 10 percent, 20 percent, 50 percent);
- 5) Inspect all erosion and sediment control practices and record all maintenance requirements such as verifying the integrity of barrier or diversion systems (earthen berms or silt fencing) and containment systems (sediment basins and sediment traps). Identify any evidence of rill or gully erosion occurring on slopes and any loss of stabilizing vegetation or seeding/mulching. Document any excessive deposition of sediment or ponding water along barrier or diversion systems. Record the depth of sediment within containment structures, any erosion near outlet and overflow structures, and verify the ability of rock filters around perforated riser pipes to pass water; and
- 6) Immediately report to the Operator any deficiencies that are identified with the implementation of the SWPPP.

**SITE PLAN/SKETCH**

\_\_\_\_\_  
**Inspector (print name)**

\_\_\_\_\_  
**Date of Inspection**

\_\_\_\_\_  
**Qualified Inspector (print name)**

\_\_\_\_\_  
**Qualified Inspector Signature**

The above signed acknowledges that, to the best of his/her knowledge, all information provided on the forms is accurate and complete.



**Maintaining Water Quality****Yes No NA**

- ☐ ☐ ☐ Is there an increase in turbidity causing a substantial visible contrast to natural conditions at the outfalls?
- ☐ ☐ ☐ Is there residue from oil and floating substances, visible oil film, or globules or grease at the outfalls?
- ☐ ☐ ☐ All disturbance is within the limits of the approved plans.
- ☐ ☐ ☐ Have receiving lake/bay, stream, and/or wetland been impacted by silt from project?

**Housekeeping**

## 1. General Site Conditions

**Yes No NA**

- ☐ ☐ ☐ Is construction site litter, debris and spoils appropriately managed?
- ☐ ☐ ☐ Are facilities and equipment necessary for implementation of erosion and sediment control in working order and/or properly maintained?
- ☐ ☐ ☐ Is construction impacting the adjacent property?
- ☐ ☐ ☐ Is dust adequately controlled?

## 2. Temporary Stream Crossing

**Yes No NA**

- ☐ ☐ ☐ Maximum diameter pipes necessary to span creek without dredging are installed.
- ☐ ☐ ☐ Installed non-woven geotextile fabric beneath approaches.
- ☐ ☐ ☐ Is fill composed of aggregate (no earth or soil)?
- ☐ ☐ ☐ Rock on approaches is clean enough to remove mud from vehicles & prevent sediment from entering stream during high flow.

## 3. Stabilized Construction Access

**Yes No NA**

- ☐ ☐ ☐ Stone is clean enough to effectively remove mud from vehicles.
- ☐ ☐ ☐ Installed per standards and specifications?
- ☐ ☐ ☐ Does all traffic use the stabilized entrance to enter and leave site?
- ☐ ☐ ☐ Is adequate drainage provided to prevent ponding at entrance?

**Runoff Control Practices**

## 1. Excavation Dewatering

**Yes No NA**

- ☐ ☐ ☐ Upstream and downstream berms (sandbags, inflatable dams, etc.) are installed per plan.
- ☐ ☐ ☐ Clean water from upstream pool is being pumped to the downstream pool.
- ☐ ☐ ☐ Sediment laden water from work area is being discharged to a silt-trapping device.
- ☐ ☐ ☐ Constructed upstream berm with one-foot minimum freeboard.

**Runoff Control Practices (continued)**

## 2. Flow Spreader

**Yes No NA**

- ☐ ☐ ☐ Installed per plan.  
☐ ☐ ☐ Constructed on undisturbed soil, not on fill, receiving only clear, non-sediment laden flow.  
☐ ☐ ☐ Flow sheets out of level spreader without erosion on downstream edge.

## 3. Interceptor Dikes and Swales

**Yes No NA**

- ☐ ☐ ☐ Installed per plan with minimum side slopes 2H:1V or flatter.  
☐ ☐ ☐ Stabilized by geotextile fabric, seed, or mulch with no erosion occurring.  
☐ ☐ ☐ Sediment-laden runoff directed to sediment trapping structure

## 4. Stone Check Dam

**Yes No NA**

- ☐ ☐ ☐ Is channel stable? (flow is not eroding soil underneath or around the structure).  
☐ ☐ ☐ Check is in good condition (rocks in place and no permanent pools behind the structure).  
☐ ☐ ☐ Has accumulated sediment been removed?.

## 5. Rock Outlet Protection

**Yes No NA**

- ☐ ☐ ☐ Installed per plan.  
☐ ☐ ☐ Installed concurrently with pipe installation.

**Soil Stabilization**

## 1. Topsoil and Spoil Stockpiles

**Yes No NA**

- ☐ ☐ ☐ Stockpiles are stabilized with vegetation and/or mulch.  
☐ ☐ ☐ Sediment control is installed at the toe of the slope.

## 2. Revegetation

**Yes No NA**

- ☐ ☐ ☐ Temporary seedings and mulch have been applied to idle areas.  
☐ ☐ ☐ 4 inches minimum of topsoil has been applied under permanent seedings

**Sediment Control Practices**

## 1. Silt Fence and Linear Barriers

**Yes No NA**

- ☐ ☐ ☐ Installed on Contour, 10 feet from toe of slope (not across conveyance channels).  
☐ ☐ ☐ Joints constructed by wrapping the two ends together for continuous support.  
☐ ☐ ☐ Fabric buried 6 inches minimum.  
☐ ☐ ☐ Posts are stable, fabric is tight and without rips or frayed areas.

Sediment accumulation is \_\_\_\_% of design capacity.

**Sediment Control Practices (continued)**

2. Storm Drain Inlet Protection (Use for Stone & Block; Filter Fabric; Curb; or, Excavated; Filter Sock or Manufactured practices)

**Yes No NA**

- ☐ ☐ ☐ Installed concrete blocks lengthwise so open ends face outward, not upward.  
☐ ☐ ☐ Placed wire screen between No. 3 crushed stone and concrete blocks.  
☐ ☐ ☐ Drainage area is 1 acre or less.  
☐ ☐ ☐ Excavated area is 900 cubic feet.  
☐ ☐ ☐ Excavated side slopes should be 2:1.  
☐ ☐ ☐ 2" x 4" frame is constructed and structurally sound.  
☐ ☐ ☐ Posts 3-foot maximum spacing between posts.  
☐ ☐ ☐ Fabric is embedded 1 to 1.5 feet below ground and secured to frame/posts with staples at max 8-inch spacing.  
☐ ☐ ☐ Posts are stable, fabric is tight and without rips or frayed areas.  
☐ ☐ ☐ Manufactured insert fabric is free of tears and punctures.  
☐ ☐ ☐ Filter Sock is not torn or flattened and fill material is contained within the mesh sock.

Sediment accumulation \_\_\_\_% of design capacity.

3. Temporary Sediment Trap

**Yes No NA**

- ☐ ☐ ☐ Outlet structure is constructed per the approved plan or drawing.  
☐ ☐ ☐ Geotextile fabric has been placed beneath rock fill.  
☐ ☐ ☐ Sediment trap slopes and disturbed areas are stabilized.

Sediment accumulation is \_\_\_\_% of design capacity.

4. Temporary Sediment Basin

**Yes No NA**

- ☐ ☐ ☐ Basin and outlet structure constructed per the approved plan.  
☐ ☐ ☐ Basin side slopes are stabilized with seed/mulch.  
☐ ☐ ☐ Drainage structure flushed and basin surface restored upon removal of sediment basin facility.  
☐ ☐ ☐ Sediment basin dewatering pool is dewatering at appropriate rate.

Sediment accumulation is \_\_\_\_% of design capacity.

Note: Not all erosion and sediment control practices are included in this listing. Add additional pages to this list as required by site specific design. All practices shall be maintained in accordance with their respective standards.

Construction inspection checklists for post-development stormwater management practices can be found in Appendix F of the New York Stormwater Management Design Manual.

## CONSTRUCTION DURATION INSPECTIONS

**b. Modifications to the SWPPP (To be completed as described below)**

The Operator shall amend the SWPPP whenever:

1. There is a significant change in design, construction, operation, or maintenance which may have a significant effect on the potential for the discharge of pollutants to the waters of the United States and which has not otherwise been addressed in the SWPPP; or
2. The SWPPP proves to be ineffective in:
  - a. Eliminating or significantly minimizing pollutants from sources identified in the SWPPP and as required by this permit; or
  - b. Achieving the general objectives of controlling pollutants in stormwater discharges from permitted construction activity; and
3. Additionally, the SWPPP shall be amended to identify any new contractor or subcontractor that will implement any measure of the SWPPP.

**Modification & Reason:**This image shows a full page of blank white paper with horizontal ruling lines. The lines are evenly spaced and run across the width of the page, providing a template for writing or drawing. There are no margins, text, or other markings present.

## Appendix F:

### Northeast Regional Climate Center Precipitation Estimates



# Extreme Precipitation Tables

## Northeast Regional Climate Center

Data represents point estimates calculated from partial duration series. All precipitation amounts are displayed in inches.

<b>Smoothing</b>	No
<b>State</b>	New York
<b>Location</b>	
<b>Longitude</b>	73.585 degrees West
<b>Latitude</b>	41.279 degrees North
<b>Elevation</b>	0 feet
<b>Date/Time</b>	Mon, 28 Dec 2020 10:36:47 -0500

## Extreme Precipitation Estimates

	5min	10min	15min	30min	60min	120min		1hr	2hr	3hr	6hr	12hr	24hr	48hr		1day	2day	4day	7day	10day	
<b>1yr</b>	0.33	0.51	0.63	0.84	1.03	1.25	<b>1yr</b>	0.89	1.22	1.43	1.82	2.28	2.83	3.18	<b>1yr</b>	2.50	3.06	3.53	4.23	4.87	<b>1yr</b>
<b>2yr</b>	0.39	0.61	0.75	1.02	1.25	1.50	<b>2yr</b>	1.08	1.46	1.71	2.20	2.76	3.40	3.82	<b>2yr</b>	3.01	3.67	4.21	4.98	5.63	<b>2yr</b>
<b>5yr</b>	0.46	0.71	0.89	1.22	1.55	1.84	<b>5yr</b>	1.33	1.80	2.11	2.72	3.42	4.27	4.82	<b>5yr</b>	3.78	4.64	5.35	6.23	7.00	<b>5yr</b>
<b>10yr</b>	0.53	0.81	1.00	1.40	1.81	2.16	<b>10yr</b>	1.56	2.11	2.46	3.20	4.03	5.08	5.76	<b>10yr</b>	4.49	5.54	6.41	7.38	8.25	<b>10yr</b>
<b>25yr</b>	0.63	0.96	1.19	1.71	2.24	2.67	<b>25yr</b>	1.94	2.61	3.03	3.97	5.00	6.38	7.29	<b>25yr</b>	5.65	7.01	8.16	9.24	10.25	<b>25yr</b>
<b>50yr</b>	0.72	1.10	1.37	1.96	2.64	3.13	<b>50yr</b>	2.28	3.06	3.55	4.68	5.90	7.59	8.71	<b>50yr</b>	6.72	8.37	9.80	10.96	12.09	<b>50yr</b>
<b>100yr</b>	0.83	1.26	1.57	2.27	3.11	3.68	<b>100yr</b>	2.69	3.60	4.16	5.52	6.96	9.04	10.41	<b>100yr</b>	8.00	10.01	11.78	13.00	14.27	<b>100yr</b>
<b>200yr</b>	0.96	1.44	1.82	2.63	3.67	4.33	<b>200yr</b>	3.17	4.23	4.88	6.52	8.21	10.76	12.46	<b>200yr</b>	9.52	11.98	14.15	15.43	16.84	<b>200yr</b>
<b>500yr</b>	1.16	1.72	2.22	3.22	4.58	5.36	<b>500yr</b>	3.96	5.24	6.03	8.13	10.23	13.56	15.80	<b>500yr</b>	12.00	15.19	18.06	19.35	20.98	<b>500yr</b>

## Lower Confidence Limits

	5min	10min	15min	30min	60min	120min		1hr	2hr	3hr	6hr	12hr	24hr	48hr		1day	2day	4day	7day	10day	
<b>1yr</b>	0.24	0.37	0.45	0.61	0.75	0.95	<b>1yr</b>	0.65	0.93	1.21	1.58	2.03	2.53	2.77	<b>1yr</b>	2.24	2.66	3.28	3.71	4.57	<b>1yr</b>
<b>2yr</b>	0.38	0.59	0.73	0.98	1.21	1.46	<b>2yr</b>	1.05	1.42	1.66	2.12	2.69	3.31	3.70	<b>2yr</b>	2.93	3.56	4.09	4.83	5.47	<b>2yr</b>
<b>5yr</b>	0.42	0.65	0.80	1.10	1.40	1.71	<b>5yr</b>	1.21	1.67	1.95	2.51	3.15	3.93	4.44	<b>5yr</b>	3.48	4.27	4.93	5.72	6.44	<b>5yr</b>
<b>10yr</b>	0.45	0.70	0.86	1.20	1.56	1.92	<b>10yr</b>	1.34	1.88	2.20	2.87	3.55	4.48	5.06	<b>10yr</b>	3.96	4.87	5.68	6.47	7.27	<b>10yr</b>
<b>25yr</b>	0.49	0.74	0.92	1.32	1.74	2.20	<b>25yr</b>	1.50	2.15	2.57	3.41	4.15	5.31	6.01	<b>25yr</b>	4.70	5.78	6.85	7.65	8.53	<b>25yr</b>
<b>50yr</b>	0.51	0.78	0.97	1.39	1.88	2.42	<b>50yr</b>	1.62	2.36	2.93	3.90	4.67	6.05	6.86	<b>50yr</b>	5.36	6.60	7.91	8.68	9.62	<b>50yr</b>
<b>100yr</b>	0.54	0.82	1.03	1.48	2.03	2.65	<b>100yr</b>	1.76	2.59	3.33	4.47	5.16	6.92	7.83	<b>100yr</b>	6.12	7.53	9.18	9.85	10.86	<b>100yr</b>
<b>200yr</b>	0.57	0.86	1.09	1.57	2.19	2.91	<b>200yr</b>	1.89	2.84	3.79	5.15	5.81	7.88	8.98	<b>200yr</b>	6.98	8.63	10.67	11.18	12.28	<b>200yr</b>
<b>500yr</b>	0.61	0.90	1.16	1.69	2.40	3.30	<b>500yr</b>	2.08	3.23	4.53	6.26	6.79	9.38	10.80	<b>500yr</b>	8.30	10.38	13.05	13.27	14.44	<b>500yr</b>

## Upper Confidence Limits

	5min	10min	15min	30min	60min	120min		1hr	2hr	3hr	6hr	12hr	24hr	48hr		1day	2day	4day	7day	10day	
<b>1yr</b>	0.37	0.57	0.70	0.94	1.15	1.38	<b>1yr</b>	0.99	1.35	1.59	2.03	2.53	3.07	3.43	<b>1yr</b>	2.72	3.30	3.80	4.51	5.19	<b>1yr</b>
<b>2yr</b>	0.42	0.65	0.80	1.09	1.34	1.56	<b>2yr</b>	1.16	1.52	1.78	2.27	2.85	3.52	4.01	<b>2yr</b>	3.12	3.85	4.38	5.18	5.84	<b>2yr</b>
<b>5yr</b>	0.50	0.77	0.96	1.32	1.68	1.98	<b>5yr</b>	1.45	1.93	2.28	2.94	3.68	4.63	5.24	<b>5yr</b>	4.10	5.04	5.78	6.75	7.54	<b>5yr</b>
<b>10yr</b>	0.59	0.91	1.12	1.57	2.03	2.38	<b>10yr</b>	1.75	2.33	2.77	3.57	4.50	5.71	6.47	<b>10yr</b>	5.05	6.22	7.16	8.28	9.18	<b>10yr</b>
<b>25yr</b>	0.74	1.13	1.40	2.01	2.64	3.08	<b>25yr</b>	2.28	3.01	3.56	4.62	5.85	7.53	8.57	<b>25yr</b>	6.66	8.24	9.49	10.83	11.91	<b>25yr</b>
<b>50yr</b>	0.88	1.34	1.66	2.39	3.22	3.73	<b>50yr</b>	2.78	3.65	4.32	5.59	7.16	9.29	10.58	<b>50yr</b>	8.22	10.18	11.74	13.30	14.52	<b>50yr</b>
<b>100yr</b>	1.05	1.59	1.99	2.88	3.95	4.53	<b>100yr</b>	3.41	4.43	5.23	6.79	9.35	11.46	13.08	<b>100yr</b>	10.14	12.58	14.47	16.33	17.71	<b>100yr</b>
<b>200yr</b>	1.26	1.89	2.40	3.47	4.85	5.50	<b>200yr</b>	4.18	5.38	6.32	8.22	11.55	14.14	16.18	<b>200yr</b>	12.52	15.55	17.89	20.02	21.60	<b>200yr</b>
<b>500yr</b>	1.62	2.41	3.10	4.50	6.40	7.10	<b>500yr</b>	5.52	6.94	8.13	10.58	15.34	18.66	21.41	<b>500yr</b>	16.51	20.59	23.57	26.16	28.04	<b>500yr</b>

## Appendix G:

New York State Stormwater Management Design Manual  
Maintenance and Inspection Checklist.

**Stormwater Pond/Wetland Operation, Maintenance and Management Inspection Checklist**

Project \_\_\_\_\_  
Location: \_\_\_\_\_  
Site Status: \_\_\_\_\_  
  
Date: \_\_\_\_\_  
Time: \_\_\_\_\_  
  
Inspector: \_\_\_\_\_

Maintenance Item	Satisfactory/ Unsatisfactory	Comments
<b>1. Embankment and emergency spillway (Annual, After Major Storms)</b>		
1. Vegetation and ground cover adequate		
2. Embankment erosion		
3. Animal burrows		
4. Unauthorized planting		
5. Cracking, bulging, or sliding of dam		
a. Upstream face		
b. Downstream face		
c. At or beyond toe		
downstream		
upstream		
d. Emergency spillway		
6. Pond, toe & chimney drains clear and functioning		
7. Seeps/leaks on downstream face		
8. Slope protection or riprap failure		
9. Vertical/horizontal alignment of top of dam "As-Built"		

Maintenance Item	Satisfactory/ Unsatisfactory	Comments
10. Emergency spillway clear of obstructions and debris		
11. Other (specify)		
<b>2. Riser and principal spillway (Annual)</b>		
Type: Reinforced concrete _____ Corrugated pipe _____ Masonry _____		
1. Low flow orifice obstructed		
2. Low flow trash rack. a. Debris removal necessary		
b. Corrosion control		
3. Weir trash rack maintenance a. Debris removal necessary		
b. corrosion control		
4. Excessive sediment accumulation insider riser		
5. Concrete/masonry condition riser and barrels a. cracks or displacement		
b. Minor spalling (<1" )		
c. Major spalling (rebars exposed)		
d. Joint failures		
e. Water tightness		
6. Metal pipe condition		
7. Control valve a. Operational/exercised		
b. Chained and locked		
8. Pond drain valve a. Operational/exercised		
b. Chained and locked		
9. Outfall channels functioning		
10. Other (specify)		

Maintenance Item	Satisfactory/ Unsatisfactory	Comments
<b>3. Permanent Pool (Wet Ponds) (monthly)</b>		
1. Undesirable vegetative growth		
2. Floating or floatable debris removal required		
3. Visible pollution		
4. Shoreline problem		
5. Other (specify)		
<b>4. Sediment Forebays</b>		
1. Sedimentation noted		
2. Sediment cleanout when depth < 50% design depth		
<b>5. Dry Pond Areas</b>		
1. Vegetation adequate		
2. Undesirable vegetative growth		
3. Undesirable woody vegetation		
4. Low flow channels clear of obstructions		
5. Standing water or wet spots		
6. Sediment and / or trash accumulation		
7. Other (specify)		
<b>6. Condition of Outfalls (Annual , After Major Storms)</b>		
1. Riprap failures		
2. Slope erosion		
3. Storm drain pipes		
4. Endwalls / Headwalls		
5. Other (specify)		
<b>7. Other ( Monthly)</b>		
1. Encroachment on pond, wetland or easement area		



Maintenance Item	Satisfactory/ Unsatisfactory	Comments
2. Complaints from residents		
3. Aesthetics		
a. Grass growing required		
b. Graffiti removal needed		
c. Other (specify)		
4. Conditions of maintenance access routes.		
5. Signs of hydrocarbon build-up		
6. Any public hazards (specify)		
<b>8. Wetland Vegetation (Annual)</b>		
1. Vegetation healthy and growing Wetland maintaining 50% surface area coverage of wetland plants after the second growing season. (If unsatisfactory, reinforcement plantings needed)		
2. Dominant wetland plants: Survival of desired wetland plant species Distribution according to landscaping plan?		
3. Evidence of invasive species		
4. Maintenance of adequate water depths for desired wetland plant species		
5. Harvesting of emergent plantings needed		
6. Have sediment accumulations reduced pool volume significantly or are plants "choked" with sediment		
7. Eutrophication level of the wetland.		
8. Other (specify)		

**Comments:**


---



---



---



---



---

**Actions to be Taken:**

---

---

---

---

## Infiltration Trench Operation, Maintenance, and Management Inspection Checklist

Project:

Location:

Site Status:

Date:

Time:

Inspector:

MAINTENANCE ITEM	SATISFACTORY / UNSATISFACTORY	COMMENTS
<b>1. Debris Cleanout (Monthly)</b>		
Trench surface clear of debris		
Inflow pipes clear of debris		
Overflow spillway clear of debris		
Inlet area clear of debris		
<b>2. Sediment Traps or Forebays (Annual)</b>		
Obviously trapping sediment		
Greater than 50% of storage volume remaining		
<b>3. Dewatering (Monthly)</b>		
Trench dewaterers between storms		
<b>4. Sediment Cleanout of Trench (Annual)</b>		
No evidence of sedimentation in trench		
Sediment accumulation doesn't yet require cleanout		
<b>5. Inlets (Annual)</b>		

MAINTENANCE ITEM	SATISFACTORY / UNSATISFACTORY	COMMENTS
Good condition		
No evidence of erosion		
<b>6. Outlet/Overflow Spillway (Annual)</b>		
Good condition, no need for repair		
No evidence of erosion		
<b>7. Aggregate Repairs (Annual)</b>		
Surface of aggregate clean		
Top layer of stone does not need replacement		
Trench does not need rehabilitation		

**Comments:**


---

---

---

---

---

---

---

---

**Actions to be Taken:**


---

---

---

---

---

---

---

---

## Open Channel Operation, Maintenance, and Management Inspection Checklist

Project:  
Location:  
Site Status:

Date:

Time:

Inspector:

MAINTENANCE ITEM	SATISFACTORY/ UNSATISFACTORY	COMMENTS
<b>1. Debris Cleanout (Monthly)</b>		
Contributing areas clean of debris		
<b>2. Check Dams or Energy Dissipators (Annual, After Major Storms)</b>		
No evidence of flow going around structures		
No evidence of erosion at downstream toe		
Soil permeability		
Groundwater / bedrock		
<b>3. Vegetation (Monthly)</b>		
Mowing done when needed		
Minimum mowing depth not exceeded		
No evidence of erosion		
Fertilized per specification		
<b>4. Dewatering (Monthly)</b>		
Dewaters between storms		



MAINTENANCE ITEM	SATISFACTORY/ UNSATISFACTORY	COMMENTS
<b>5. Sediment deposition      (Annual)</b>		
Clean of sediment		
<b>6. Outlet/Overflow Spillway    (Annual)</b>		
Good condition, no need for repairs		
No evidence of erosion		

**Comments:**

**Actions to be Taken:**

## Appendix H:

Cultec Infiltration Chamber Operation and Maintenance  
Requirements.



# Contactor® & Recharger® Stormwater Chambers



## Operation and Maintenance Guidelines for CULTEC Stormwater Management Systems

The Founder of Plastic Chamber Technology

[www.cultec.com](http://www.cultec.com) | 1(800) 4-CULTEC | [f](#) [in](#)





# Operations and Maintenance Guidelines

Published by  
**CULTEC, Inc.**  
P.O. Box 280  
878 Federal Road  
Brookfield, Connecticut 06804 USA  
[www.cultec.com](http://www.cultec.com)

## Copyright Notice

© 2017 CULTEC, Inc.  
All rights reserved.  
Printed in the USA.

This document and any accompanying CULTEC products are copyrighted by CULTEC, Inc. Any reproduction and/or distribution without prior written consent from CULTEC, Inc. is strictly prohibited.

## Disclaimers:

The drawings, photographs and illustrations shown in this document are for illustrative purposes only and are not necessarily to scale. Actual designs may vary.

CULTEC reserves the right to make design and/or specification changes at any time without notice at CULTEC's sole discretion.

CULTEC is not responsible for typographical errors.

## Protected by one or more of the following patents:

Protected by one or more of the following patents:

U.S. Patents 6,129,482; 6,322,288; 6,854,925; 7,226,241; 7,806,627; 8,366,346; 8,425,148; and others; U.S. Designs D613819; D638,095; D668,318 and others; Canadian Patent 2,591,255 and others; Community Designs 1092191; 1745209; and others.

CULTEC, the CULTEC logo, RECHARGER, CONTACTOR, HVLV, PAC, STORMFILTER, STORMGENIE and The Chamber with The Stripe are registered trademarks of CULTEC, Inc.

Chamber of Choice, 902, HD, 100, 125, 150, 150XL, 180, 280, 330, 330XL, V8, 902, Field Drain Panel, C-1, C-2, C-3, C-4, EZ-24, Landscape Series are trademarks of CULTEC, Inc. All rights reserved.

## Contact Information:

For general information on our other products and services, please contact our offices within the United States at (800)428-5832, (203)775-4416 ext. 202, or e-mail us at [custservice@cultec.com](mailto:custservice@cultec.com).

For technical support, please call (203)775-4416 ext. 203 or e-mail [tech@cultec.com](mailto:tech@cultec.com).

Visit [www.cultec.com/downloads.html](http://www.cultec.com/downloads.html) for Product Downloads and CAD details.

Doc ID: CULG008 05-17  
May 2017

*These instructions are for single-layer traffic applications only. For multi-layer applications, contact CULTEC.  
All illustrations and photos shown herein are examples of typical situations. Be sure to follow the engineer's drawings.  
Actual designs may vary.*



*This manual contains guidelines recommended by CULTEC, Inc. and may be used in conjunction with, but not to supersede, local regulations or regulatory authorities. OSHA Guidelines must be followed when inspecting or cleaning any structure.*

## Introduction

The CULTEC Subsurface Stormwater Management System is a high-density polyethylene (HDPE) chamber system arranged in parallel rows surrounded by washed stone. The CULTEC chambers create arch-shaped voids within the washed stone to provide stormwater detention, retention, infiltration, and reclamation. Filter fabric is placed between the native soil and stone interface to prevent the intrusion of fines into the system. In order to minimize the amount of sediment which may enter the CULTEC system, a sediment collection device (stormwater pretreatment device) is recommended upstream from the CULTEC chamber system. Examples of pretreatment devices include, but are not limited to, an appropriately sized catch basin with sump, pretreatment catchment device, oil grit separator, or baffled distribution box. Manufactured pretreatment devices may also be used in accordance with CULTEC chambers. Installation, operation, and maintenance of these devices shall be in accordance with manufacturer's recommendations. Almost all of the sediment entering the stormwater management system will be collected within the pretreatment device.

Best Management Practices allow for the maintenance of the preliminary collection systems prior to feeding the CULTEC chambers. The pretreatment structures shall be inspected for any debris that will restrict inlet flow rates. Outfall structures, if any, such as outlet control must also be inspected for any obstructions that would restrict outlet flow rates. OSHA Guidelines must be followed when inspecting or cleaning any structure.

## Operation and Maintenance Requirements

### I. Operation

CULTEC stormwater management systems shall be operated to receive only stormwater run-off in accordance with applicable local regulations. CULTEC subsurface stormwater management chambers operate at peak performance when installed in series with pretreatment. Pretreatment of suspended solids is superior to treatment of solids once they have been introduced into the system. The use of pretreatment is adequate as long as the structure is maintained and the site remains stable with finished impervious surfaces such as parking lots, walkways, and pervious areas are properly maintained. If there is to be an unstable condition, such as improvements to buildings or parking areas, all proper silt control measures shall be implemented according to local regulations.

### II. Inspection and Maintenance Options

- A. The CULTEC system may be equipped with an inspection port located on the inlet row. The inspection port is a circular cast box placed in a rectangular concrete collar. When the lid is removed, a 6-inch (150 mm) pipe with a screw-in plug will be exposed. Remove the plug. This will provide access to the CULTEC Chamber row below. From the surface, through this access, the sediment may be measured at this location. A stadia rod may be used to measure the depth of sediment if any in this row. If the depth of sediment is in excess of 3 inches (76 mm), then this row should be cleaned with high pressure water through a culvert cleaning nozzle. This would be carried out through an upstream manhole or through the CULTEC StormFilter Unit (or other pretreatment device). CCTV inspection of this row can be deployed through this access port to determine if any sediment has accumulated in the inlet row.
- B. If the CULTEC bed is not equipped with an inspection port, then access to the inlet row will be through an upstream manhole or the CULTEC StormFilter.
  1. **Manhole Access**  
This inspection should only be carried out by persons trained in confined space entry and sewer inspection services. After the manhole cover has been removed a gas detector must be lowered into the manhole to ensure that there are not high concentrations of toxic gases present. The inspector should be lowered into the manhole with the proper safety equipment as per OSHA requirements. The inspector may be able to observe sediment from this location. If this is not possible, the inspector will need to deploy a CCTV robot to permit viewing of the sediment.



## 2. StormFilter Access

Remove the manhole cover to allow access to the unit. Typically a 30-inch (750 mm) pipe is used as a riser from the StormFilter to the surface. As in the case with manhole access, this access point requires a technician trained in confined space entry with proper gas detection equipment. This individual must be equipped with the proper safety equipment for entry into the StormFilter. The technician will be lowered onto the StormFilter unit. The hatch on the unit must be removed. Inside the unit are two filters which may be removed according to StormFilter maintenance guidelines. Once these filters are removed the inspector can enter the StormFilter unit to launch the CCTV camera robot.

- C. The inlet row of the CULTEC system is placed on a polyethylene liner to prevent scouring of the washed stone beneath this row. This also facilitates the flushing of this row with high pressure water through a culvert cleaning nozzle. The nozzle is deployed through a manhole or the StormFilter and extended to the end of the row. The water is turned on and the inlet row is back-flushed into the manhole or StormFilter. This water is to be removed from the manhole or StormFilter using a vacuum truck.

## III. Maintenance Guidelines

The following guidelines shall be adhered to for the operation and maintenance of the CULTEC stormwater management system:

- A. The owner shall keep a maintenance log which shall include details of any events which would have an effect on the system's operational capacity.
- B. The operation and maintenance procedure shall be reviewed periodically and changed to meet site conditions.
- C. Maintenance of the stormwater management system shall be performed by qualified workers and shall follow applicable occupational health and safety requirements.
- D. Debris removed from the stormwater management system shall be disposed of in accordance with applicable laws and regulations.

## IV. Suggested Maintenance Schedules

### A. Minor Maintenance

The following suggested schedule shall be followed for routine maintenance during the regular operation of the stormwater system:

Frequency	Action
Monthly in first year	Check inlets and outlets for clogging and remove any debris, as required.
Spring and Fall	Check inlets and outlets for clogging and remove any debris, as required.
One year after commissioning and every third year following	Check inlets and outlets for clogging and remove any debris, as required.

### B. Major Maintenance

The following suggested maintenance schedule shall be followed to maintain the performance of the CULTEC stormwater management chambers. Additional work may be necessary due to insufficient performance and other issues that might be found during the inspection of the stormwater management chambers. (See table on next page)

	Frequency	Action
Inlets and Outlets	Every 3 years	<ul style="list-style-type: none"> <li>Obtain documentation that the inlets, outlets and vents have been cleaned and will function as intended.</li> </ul>
	Spring and Fall	<ul style="list-style-type: none"> <li>Check inlet and outlets for clogging and remove any debris as required.</li> </ul>
CULTEC Stormwater Chambers	2 years after commissioning	<ul style="list-style-type: none"> <li>Inspect the interior of the stormwater management chambers through inspection port for deficiencies using CCTV or comparable technique.</li> <li>Obtain documentation that the stormwater management chambers and feed connectors will function as anticipated.</li> </ul>
	9 years after commissioning every 9 years following	<ul style="list-style-type: none"> <li>Clean stormwater management chambers and feed connectors of any debris.</li> <li>Inspect the interior of the stormwater management structures for deficiencies using CCTV or comparable technique.</li> <li>Obtain documentation that the stormwater management chambers and feed connectors have been cleaned and will function as intended.</li> </ul>
	45 years after commissioning	<ul style="list-style-type: none"> <li>Clean stormwater management chambers and feed connectors of any debris.</li> <li>Determine the remaining life expectancy of the stormwater management chambers and recommended schedule and actions to rehabilitate the stormwater management chambers as required.</li> <li>Inspect the interior of the stormwater management chambers for deficiencies using CCTV or comparable technique.</li> <li>Replace or restore the stormwater management chambers in accordance with the schedule determined at the 45-year inspection.</li> <li>Attain the appropriate approvals as required.</li> <li>Establish a new operation and maintenance schedule.</li> </ul>
Surrounding Site	Monthly in 1 <sup>st</sup> year	<ul style="list-style-type: none"> <li>Check for depressions in areas over and surrounding the stormwater management system.</li> </ul>
	Spring and Fall	<ul style="list-style-type: none"> <li>Check for depressions in areas over and surrounding the stormwater management system.</li> </ul>
	Yearly	<ul style="list-style-type: none"> <li>Confirm that no unauthorized modifications have been performed to the site.</li> </ul>

For additional information concerning the maintenance of CULTEC Subsurface Stormwater Management Chambers, please contact CULTEC, Inc. at 1-800-428-5832.

# WQMP

## Operation & Maintenance (O&M) Plan

Project Name: \_\_\_\_\_

### Prepared for:

Project Name: \_\_\_\_\_

Address: \_\_\_\_\_

City, State Zip: \_\_\_\_\_

### Prepared on:

Date: \_\_\_\_\_

This O&M Plan describes the designated responsible party for implementation of this WQMP, including: operation and maintenance of all the structural BMP(s), conducting the training/educational program and duties, and any other necessary activities. The O&M Plan includes detailed inspection and maintenance requirements for all structural BMPs, including copies of any maintenance contract agreements, manufacturer's maintenance requirements, permits, etc.

### 8.1.1 Project Information

Project name	
Address	
City, State Zip	
Site size	
List of structural BMPs, number of each	
Other notes	

### 8.1.2 Responsible Party

The responsible party for implementation of this WQMP is:

Name of Person or HOA Property Manager	
Address	
City, State Zip	
Phone number	
24-Hour Emergency Contact number	
Email	

### 8.1.3 Record Keeping

Parties responsible for the O&M plan shall retain records for at least 5 years.

All training and educational activities and BMP operation and maintenance shall be documented to verify compliance with this O&M Plan. A sample Training Log and Inspection and Maintenance Log are included in this document.

### 8.1.4 Electronic Data Submittal

This document along with the Site Plan and Attachments shall be provided in PDF format. AutoCAD files and/or GIS coordinates of BMPs shall also be submitted to the City.

## Appendix \_\_\_\_

### **BMP SITE PLAN**

Site plan is preferred on minimum 11" by 17" colored sheets, as long as legible.





BMP OPERATION & MAINTENANCE LOG

Project Name: \_\_\_\_\_

Today’s Date:\_\_\_\_\_

Name of Person Performing Activity (Printed):\_\_\_\_\_

Signature: \_\_\_\_\_

BMP Name (As Shown in O&M Plan)	Brief Description of Implementation, Maintenance, and Inspection Activity Performed

## Minor Maintenance

Frequency		Action
<b>Monthly in first year</b>		Check inlets and outlets for clogging and remove any debris, as required.
		Notes
<input type="checkbox"/> Month 1	Date:	
<input type="checkbox"/> Month 2	Date:	
<input type="checkbox"/> Month 3	Date:	
<input type="checkbox"/> Month 4	Date:	
<input type="checkbox"/> Month 5	Date:	
<input type="checkbox"/> Month 6	Date:	
<input type="checkbox"/> Month 7	Date:	
<input type="checkbox"/> Month 8	Date:	
<input type="checkbox"/> Month 9	Date:	
<input type="checkbox"/> Month 10	Date:	
<input type="checkbox"/> Month 11	Date:	
<input type="checkbox"/> Month 12	Date:	
<b>Spring and Fall</b>		Check inlets and outlets for clogging and remove any debris, as required.
		Notes
<input type="checkbox"/> Spring	Date:	
<input type="checkbox"/> Fall	Date:	
<input type="checkbox"/> Spring	Date:	
<input type="checkbox"/> Fall	Date:	
<input type="checkbox"/> Spring	Date:	
<input type="checkbox"/> Fall	Date:	
<input type="checkbox"/> Spring	Date:	
<input type="checkbox"/> Fall	Date:	
<input type="checkbox"/> Spring	Date:	
<input type="checkbox"/> Fall	Date:	
<input type="checkbox"/> Spring	Date:	
<input type="checkbox"/> Fall	Date:	
<b>One year after commissioning and every third year following</b>		Check inlets and outlets for clogging and remove any debris, as required.
		Notes
<input type="checkbox"/> Year 1	Date:	
<input type="checkbox"/> Year 4	Date:	
<input type="checkbox"/> Year 7	Date:	
<input type="checkbox"/> Year 10	Date:	
<input type="checkbox"/> Year 13	Date:	
<input type="checkbox"/> Year 16	Date:	
<input type="checkbox"/> Year 19	Date:	
<input type="checkbox"/> Year 22	Date:	

## Major Maintenance

Frequency		Action
Inlets and Outlets	<b>Every 3 years</b>	Obtain documentation that the inlets, outlets and vents have been cleaned and will function as intended.
		Notes
	<input type="checkbox"/> Year 1	Date:
	<input type="checkbox"/> Year 4	Date:
	<input type="checkbox"/> Year 7	Date:
	<input type="checkbox"/> Year 10	Date:
	<input type="checkbox"/> Year 13	Date:
	<input type="checkbox"/> Year 16	Date:
	<input type="checkbox"/> Year 19	Date:
	<input type="checkbox"/> Year 22	Date:
	<b>Spring and Fall</b>	Check inlet and outlets for clogging and remove any debris, as required.
		Notes
	<input type="checkbox"/> Spring	Date:
	<input type="checkbox"/> Fall	Date:
	<input type="checkbox"/> Spring	Date:
	<input type="checkbox"/> Fall	Date:
	<input type="checkbox"/> Spring	Date:
	<input type="checkbox"/> Fall	Date:
	<input type="checkbox"/> Spring	Date:
	<input type="checkbox"/> Fall	Date:
	<input type="checkbox"/> Spring	Date:
	<input type="checkbox"/> Fall	Date:
CULTEC Stormwater Chambers	<b>2 years after commissioning</b>	<input type="checkbox"/> Inspect the interior of the stormwater management chambers through inspection port for deficiencies using CCTV or comparable technique. <input type="checkbox"/> Obtain documentation that the stormwater management chambers and feed connectors will function as anticipated.
		Notes
	<input type="checkbox"/> Year 2	Date:

## Major Maintenance

Frequency		Action
CULTEC Stormwater Chambers	<b>9 years after commissioning every 9 years following</b>	<input type="checkbox"/> Clean stormwater management chambers and feed connectors of any debris.  <input type="checkbox"/> Inspect the interior of the stormwater management structures for deficiencies using CCTV or comparable technique.  <input type="checkbox"/> Obtain documentation that the stormwater management chambers and feed connectors have been cleaned and will function as intended.
	Notes	
	<input type="checkbox"/> Year 9	Date:
	<input type="checkbox"/> Year 18	Date:
	<input type="checkbox"/> Year 27	Date:
	<input type="checkbox"/> Year 36	Date:
	<b>45 years after commissioning</b>	<input type="checkbox"/> Clean stormwater management chambers and feed connectors of any debris.  <input type="checkbox"/> Determine the remaining life expectancy of the stormwater management chambers and recommended schedule and actions to rehabilitate the stormwater management chambers as required.  <input type="checkbox"/> Inspect the interior of the stormwater management chambers for deficiencies using CCTV or comparable technique.  <input type="checkbox"/> Replace or restore the stormwater management chambers in accordance with the schedule determined at the 45-year inspection.  <input type="checkbox"/> Attain the appropriate approvals as required.  <input type="checkbox"/> Establish a new operation and maintenance schedule.
	Notes	
	<input type="checkbox"/> Year 45	Date:

## Major Maintenance

Frequency		Action	
Surrounding Site	<b>Monthly in 1<sup>st</sup> year</b>		
	<input type="checkbox"/> Check for depressions in areas over and surrounding the stormwater management system.		
	Notes		
	<input type="checkbox"/> Month 1	Date:	
	<input type="checkbox"/> Month 2	Date:	
	<input type="checkbox"/> Month 3	Date:	
	<input type="checkbox"/> Month 4	Date:	
	<input type="checkbox"/> Month 5	Date:	
	<input type="checkbox"/> Month 6	Date:	
	<input type="checkbox"/> Month 7	Date:	
	<input type="checkbox"/> Month 8	Date:	
	<input type="checkbox"/> Month 9	Date:	
	<input type="checkbox"/> Month 10	Date:	
	<input type="checkbox"/> Month 11	Date:	
	<input type="checkbox"/> Month 12	Date:	
	<b>Spring and Fall</b>		
	<input type="checkbox"/> Check for depressions in areas over and surrounding the stormwater management system.		
	Notes		
	<input type="checkbox"/> Spring	Date:	
	<input type="checkbox"/> Fall	Date:	
	<input type="checkbox"/> Spring	Date:	
	<input type="checkbox"/> Fall	Date:	
	<input type="checkbox"/> Spring	Date:	
	<input type="checkbox"/> Fall	Date:	
	<input type="checkbox"/> Spring	Date:	
	<input type="checkbox"/> Fall	Date:	
	<input type="checkbox"/> Spring	Date:	
	<input type="checkbox"/> Fall	Date:	
	<input type="checkbox"/> Spring	Date:	
	<input type="checkbox"/> Fall	Date:	
	<b>Yearly</b>		
	<input type="checkbox"/> Confirm that no unauthorized modifications have been performed to the site.		
Notes			
<input type="checkbox"/> Year 1	Date:		
<input type="checkbox"/> Year 2	Date:		
<input type="checkbox"/> Year 3	Date:		
<input type="checkbox"/> Year 4	Date:		
<input type="checkbox"/> Year 5	Date:		
<input type="checkbox"/> Year 6	Date:		
<input type="checkbox"/> Year 7	Date:		





**The Founder of Plastic Chamber Technology**

[www.cultec.com](http://www.cultec.com) | 1(800) 4-CULTEC |  

878 Federal Road | P.O. Box 280 | Brookfield, CT 06804 USA

CULG008 05-17



Appendix I:  
Soil Testing Data



**BIBBO ASSOCIATES, LLP**  
*Consulting Engineers*

Project: Wolf Conservation Center  
Feature: Deep Test Results

Sheet: 1 of 2  
Recorded By: Matthew Gironda  
Date: May 25, 2021

<p>Hole ID: <u>TP D-1</u></p> <p>Depth:                      Description:</p> <p>0-24"                      Top Soil</p> <p>24"-56"                  Light Brown Fine Sandy Loam</p> <p>56"-96"                  Dark Brown Fine Sandy Loam</p> <p>                                 No Rock</p> <p>                                 or Water at Full Depth</p>	<p>Hole ID: <u>TP D-2</u></p> <p>Depth:                      Description:</p> <p>0-18"                      Top Soil</p> <p>18"-30"                  Red/Brown Fine Sandy Loam</p> <p>30"-104"                Brown Medium/Fine Sand</p> <p>                                 w/ Silt and Cobbles</p> <p>                                 No Rock</p> <p>                                 or Water at Full Depth</p>
<p>Hole ID: <u>TP D-3</u></p> <p>Depth:                      Description:</p> <p>0-24"                      Top Soil</p> <p>24"-48"                  Red/Brown Fine Sandy Loam</p> <p>48"-120"                Brown Fine/Medium Sand</p> <p>                                 w/ Silt and Cobbles</p> <p>                                 No Rock</p> <p>                                 or Water at Full Depth</p>	<p>Hole ID: <u>TP D-4</u></p> <p>Depth:                      Description:</p> <p>0-18"                      Top Soil</p> <p>18"-30"                  Red/Brown Fine Sandy Loam</p> <p>30"-104"                Brown Medium/Fine Sand w/</p> <p>                                 traces of Silt and some cobbles</p> <p>                                 No Rock</p> <p>                                 or Water at Full Depth</p>



**BIBBO ASSOCIATES, LLP**  
*Consulting Engineers*

Project: Wolf Conservation Center  
 Feature: Infiltration Percolation  
Test Results

Sheet: 2 of 2  
 Recorded By: Matthew Gironda  
 Date: May 25, 2021

Hole ID:	Run #	Time Start (Min.)	Time Stop (Min.)	Depth to Water From Ground Surface		Time (Min.)	Drop (In.)	( Rate ) (In. / Hr.)
				From (In.)	To (In.)			
IT I-1	1	10:30 AM	11:30 AM	48.00	62.00	60	14.00	14.00
	2	11:33 AM	12:03 PM	48.00	60.50	60	12.50	12.50
	3	12:34 PM	1:34 PM	48.00	60.50	60	12.50	12.50
	4	1:36 PM	2:36 PM	48.00	60.50	60	12.50	12.50
IT I-2	1	9:45 AM	10:45 AM	48.00	67.00	60	19.00	19.00
	2	10:47 AM	11:47 AM	48.00	68.00	60	20.00	20.00
	3	11:48 AM	12:48 PM	48.00	68.50	60	20.50	20.50
	4	12:49 PM	1:49 PM	48.00	66.00	60	18.00	18.00
IT I-3	1	9:36 AM	10:36 AM	76.00	97.50	60	21.50	21.50
	2	10:38 AM	11:38 AM	76.00	100.00	60	24.00	24.00
	3	11:40 AM	12:40 PM	76.00	97.00	60	21.00	21.00
	4	12:42 PM	1:42 PM	76.00	97.00	60	21.00	21.00
IT I-4	1	9:30 AM	10:30 AM	52.00	71.50	60	19.50	19.50
	2	10:32 AM	11:32 AM	52.00	71.00	60	19.00	19.00
	3	11:33 AM	12:33 PM	52.00	70.00	60	18.00	18.00
	4	12:34 PM	1:34 PM	52.00	70.00	60	18.00	18.00



## Appendix J:

### First Defense Stormwater Treatment Unit Operation and Maintenance Manual





BIBBO ASSOCIATES, LLP  
Consulting Engineers - Planners

**Wolf Conservation Center**  
**Hydrointernational First Defense Sizing Summary**


<b>Structure Number</b>	<b>First Defense HDS Unit Model No.</b>	<b>NJDEP Certified Treatment Capacity * (cfs)</b>	<b>1-Year Storm Peak Flow ** (cfs)</b>	<b>100-Year Storm Peak Flow *** (cfs)</b>
HDS #1.1	FD-4HC	1.50	1.1	4.9
H.D.S. #1.2	FD-5HC	2.34	2.3	3.0
H.D.S. #1.3	FD-3HC	0.84	0.1	0.4

\* NJDEP Certified Treatment Rates Provided by manufacturer. Refer to detail provided on project drawings


\*\* 1-Year Storm Peak Flow rates obtained from HydroCAD model included in Appendix C

\*\*\* 100 Year Peak Flow obtained from HydroCAD model in Appendix C.

Manufacturer rated Peak Hydraulic Flow for Model # FD-3HC = 15.0 cfs. Manufacturer rated Peak Hydraulic Flow for Model # FD-4HC = 18.0 cfs. Manufacturer rated Peak Hydraulic Flow for Model # FD-5HC = 20.0 cfs.



PLAN VIEW




HYDRO FRAME AND COVER (INCLUDED)

GRADE RINGS BY OTHERS  
AS REQUIRED

T.O.S.: 6.46 ft [1.969 m] (MINIMUM)  
NOTE: ADDITIONAL HEIGHT MAYBE  
REQUIRED DEPENDING ON PIPE SIZE

PIPE INVERTS: 3.71 ft [1.131 m] (MINIMUM)  
PREASSEMBLY REFERENCE: 2.67 ft [.813 m]  
BOTTOM OF INTERNALS: 1.83 ft [.559 m]

SUMP: .00 ft [.000 m]



SECTION A-A

PRODUCT SPECIFICATION:


1. PEAK HYDRAULIC FLOW: 15.0 cfs (424 l/s)
2. MIN SEDIMENT STORAGE CAPACITY: 0.4 cu. yd. (0.3 cu. m.)
3. OIL STORAGE CAPACITY: 125 gal. (473 liters)
4. MAXIMUM INLET/OUTLET PIPE DIAMETERS: 18 in. (450 mm)
5. THE TREATMENT SYSTEM SHALL USE AN INDUCED VORTEX TO SEPARATE POLLUTANTS FROM STORMWATER RUNOFF.
6. FOR MORE PRODUCT INFORMATION INCLUDING REGULATORY ACCEPTANCES, PLEASE VISIT <https://hydro-int.com/en/products/first-defense>

GENERAL NOTES:

1. General Arrangement drawings only. Contact Hydro International for site specific drawings.
2. The diameter of the inlet and outlet pipes may be no more than 18".
3. Multiple inlet pipes possible (refer to project plan).
4. Inlet/outlet pipe angle can vary to align with drainage network (refer to project plan.s)
5. Peak flow rate and minimum height limited by available cover and pipe diameter.
6. Larger sediment storage capacity may be provided with a deeper sump depth.

ANY WARRANTY GIVEN BY HYDRO INTERNATIONAL WILL APPLY ONLY TO THOSE ITEMS SUPPLIED BY IT. ACCORDINGLY HYDRO INTERNATIONAL CANNOT ACCEPT ANY RESPONSIBILITY FOR ANY STRUCTURE, PLANT, OR EQUIPMENT, (OR THE PERFORMANCE THERE OF) DESIGNED, BUILT, MANUFACTURED, OR SUPPLIED BY ANY THIRD PARTY. HYDRO INTERNATIONAL HAVE A POLICY OF CONTINUOUS DEVELOPMENT AND RESERVE THE RIGHT TO AMEND THE SPECIFICATION. HYDRO INTERNATIONAL CANNOT ACCEPT LIABILITY FOR PERFORMANCE OF ITS EQUIPMENT, (OR ANY PART THEREOF), IF THE EQUIPMENT IS SUBJECT TO CONDITIONS OUTSIDE ANY DESIGN SPECIFICATION. HYDRO INTERNATIONAL OWNS THE COPYRIGHT OF THIS DRAWING, WHICH IS SUPPLIED IN CONFIDENCE. IT MUST NOT BE USED FOR ANY PURPOSE OTHER THAN THAT FOR WHICH IT IS SUPPLIED AND MUST NOT BE REPRODUCED, IN WHOLE OR IN PART, WITHOUT PRIOR PERMISSION IN WRITING FROM HYDRO INTERNATIONAL.

PROJECTION



IF IN DOUBT ASK

COMMENTS:

1. MANHOLE WALL AND SLAB THICKNESSES ARE NOT TO SCALE.
2. CONTACT HYDRO INTERNATIONAL FOR A BOTTOM OF STRUCTURE ELEVATION PRIOR TO SETTING FIRST DEFENSE MANHOLE.
3. CONTRACTOR TO CONFIRM RIM, PIPE INVERTS, PIPE DIA. AND PIPE ORIENTATION PRIOR TO RELEASE OF UNIT TO FABRICATION.

DATE:  
11/8/2019

SCALE:  
1:30

DRAWN BY:  
JLL3

CHECKED BY:  
-

APPROVED BY

Title  
3-ft DIAMETER

FIRST DEFENSE HIGH CAPACITY

GENERAL ARRANGEMENT

**Hydro**  
**International**

hydro-int.com

HYDRO INTERNATIONAL

**DO NOT SCALE DRAWING**  
**STEEL FABRICATION TOLERANCES**  
UNLESS OTHERWISE SPECIFIED,  
DIMENSIONS ARE IN INCHES.

LINEAR	ANGULAR
000 - 012in = ±0.04in	000 - 120in = ±1°
012 - 024in = ±0.06in	120 - 240in = ±0.5°
024 - 048in = ±0.08in	240in >>>> = ±0.25°
048 - 120in = ±0.12in	
120in >>>> = ±0.20in	

WEIGHT:

N/A

MATERIAL:

STOCK NUMBER:

DRAWING NO.:


3FDHC\_FDHC GA

SHEET SIZE:  
B


SHEET:  
1 OF 1

Rev:  
-

PARTS LIST				
ITEM	QTY	SIZE (in)	SIZE (mm)	DESCRIPTION
1	1	36	900	I.D. PRECAST MANHOLE
2	1			INTERNAL COMPONENTS (PRE-INSTALLED)
3	1	30	750	FRAME AND COVER (ROUND)
4	1	18 (MAX)	450 (MAX)	OUTLET PIPE (BY OTHERS)
5	1	18 (MAX)	450 (MAX)	INLET PIPE (BY OTHERS)




PLAN VIEW



## HYDRO FRAME AND COVER (INCLUDED)

GRADE RINGS BY OTHERS  
AS REQUIRED



SECTION A-A

### PRODUCT SPECIFICATION:


1. PEAK HYDRAULIC FLOW: 18.0 cfs (510 l/s)
2. MIN SEDIMENT STORAGE CAPACITY: 0.7 cu. yd. (0.5 cu. m.)
3. OIL STORAGE CAPACITY: 191 gal. (723 liters)
4. MAXIMUM INLET/OUTLET PIPE DIAMETERS: 24 in. (600 mm)
5. THE TREATMENT SYSTEM SHALL USE AN INDUCED VORTEX TO SEPARATE POLLUTANTS FROM STORMWATER RUNOFF.
6. FOR MORE PRODUCT INFORMATION INCLUDING REGULATORY ACCEPTANCES, PLEASE VISIT <https://hydro-int.com/en/products/first-defense>

### GENERAL NOTES:

1. General Arrangement drawings only. Contact Hydro International for site specific drawings.
2. The diameter of the inlet and outlet pipes may be no more than 24".
3. Multiple inlet pipes possible (refer to project plan).
4. Inlet/outlet pipe angle can vary to align with drainage network (refer to project plan.s)
5. Peak flow rate and minimum height limited by available cover and pipe diameter.
6. Larger sediment storage capacity may be provided with a deeper sump depth.

ANY WARRANTY GIVEN BY HYDRO INTERNATIONAL WILL APPLY ONLY TO THOSE ITEMS SUPPLIED BY IT. ACCORDINGLY HYDRO INTERNATIONAL CANNOT ACCEPT ANY RESPONSIBILITY FOR ANY STRUCTURE, PLANT, OR EQUIPMENT, (OR THE PERFORMANCE THERE OF) DESIGNED, BUILT, MANUFACTURED, OR SUPPLIED BY ANY THIRD PARTY. HYDRO INTERNATIONAL HAVE A POLICY OF CONTINUOUS DEVELOPMENT AND RESERVE THE RIGHT TO AMEND THE SPECIFICATION. HYDRO INTERNATIONAL CANNOT ACCEPT LIABILITY FOR PERFORMANCE OF ITS EQUIPMENT, (OR ANY PART THEREOF), IF THE EQUIPMENT IS SUBJECT TO CONDITIONS OUTSIDE ANY DESIGN SPECIFICATION. HYDRO INTERNATIONAL OWNS THE COPYRIGHT OF THIS DRAWING, WHICH IS SUPPLIED IN CONFIDENCE. IT MUST NOT BE USED FOR ANY PURPOSE OTHER THAN THAT FOR WHICH IT IS SUPPLIED AND MUST NOT BE REPRODUCED, IN WHOLE OR IN PART, WITHOUT PRIOR PERMISSION IN WRITING FROM HYDRO INTERNATIONAL.

PROJECTION



### IF IN DOUBT ASK

COMMENTS:

1. MANHOLE WALL AND SLAB THICKNESSES ARE NOT TO SCALE.

2. CONTACT HYDRO INTERNATIONAL FOR A BOTTOM OF STRUCTURE ELEVATION PRIOR TO SETTING FIRST DEFENSE MANHOLE.

3. CONTRACTOR TO CONFIRM RIM, PIPE INVERTS, PIPE DIA. AND PIPE ORIENTATION PRIOR TO RELEASE OF UNIT TO FABRICATION.

DATE:  
11/8/2019

SCALE:  
1:30

DRAWN BY:  
JLL3

CHECKED BY:  
-

APPROVED BY:  
-

Title  
4-ft DIAMETER

FIRST DEFENSE HIGH CAPACITY

GENERAL ARRANGEMENT

**Hydro**  
**International**

hydro-int.com

HYDRO INTERNATIONAL

**DO NOT SCALE DRAWING**  
**STEEL FABRICATION TOLERANCES**  
UNLESS OTHERWISE SPECIFIED,  
DIMENSIONS ARE IN INCHES.

LINEAR  
000 - 012in = ±0.04in  
012 - 024in = ±0.06in  
024 - 048in = ±0.08in  
048 - 120in = ±0.12in  
120in >>> = ±0.20in

ANGULAR  
000 - 120in = ±1°  
120 - 240in = ±0.5°  
240in >>> = ±0.25°

WEIGHT:

N/A

MATERIAL:

STOCK NUMBER:

DRAWING NO.:


4FDHC\_FDHC GA STD

SHEET SIZE:  
B


SHEET:  
1 OF 1

Rev:  
-

PARTS LIST				
ITEM	QTY	SIZE (in)	SIZE (mm)	DESCRIPTION
1	1	48	1200	I.D. PRECAST MANHOLE
2	1			INTERNAL COMPONENTS (PRE-INSTALLED)
3	1	30	750	FRAME AND COVER (ROUND)
4	1	24 (MAX)	600 (MAX)	OUTLET PIPE (BY OTHERS)
5	1	24 (MAX)	600 (MAX)	INLET PIPE (BY OTHERS)



PLAN VIEW



## HYDRO FRAME AND COVER (INCLUDED)


GRADE RINGS BY OTHERS  
AS REQUIRED

### PRODUCT SPECIFICATION:

1. PEAK HYDRAULIC FLOW: 20.0 cfs (566 l/s)
2. MIN SEDIMENT STORAGE CAPACITY: 1.1 cu. yd. (0.8 cu. m.)
3. OIL STORAGE CAPACITY: 300 gal. (1135 liters)
4. MAXIMUM INLET/OUTLET PIPE DIAMETERS: 24 in. (600 mm)
5. THE TREATMENT SYSTEM SHALL USE AN INDUCED VORTEX TO SEPARATE POLLUTANTS FROM STORMWATER RUNOFF.
6. FOR MORE PRODUCT INFORMATION INCLUDING REGULATORY ACCEPTANCES, PLEASE VISIT <https://hydro-int.com/en/products/first-defense>

### GENERAL NOTES:


1. General Arrangement drawings only. Contact Hydro International for site specific drawings.
2. The diameter of the inlet and outlet pipes may be no more than 24".
3. Multiple inlet pipes possible (refer to project plan).
4. Inlet/outlet pipe angle can vary to align with drainage network (refer to project plan.s)
5. Peak flow rate and minimum height limited by available cover and pipe diameter.
6. Larger sediment storage capacity may be provided with a deeper sump depth.



SECTION A-A

PARTS LIST				
ITEM	QTY	SIZE (in)	SIZE (mm)	DESCRIPTION
1	1	60	1500	I.D. PRECAST MANHOLE
2	1			INTERNAL COMPONENTS (PRE-INSTALLED)
3	1	30	750	FRAME AND COVER (ROUND)
4	1	24 (MAX)	600 (MAX)	OUTLET PIPE (BY OTHERS)
5	1	24 (MAX)	600 (MAX)	INLET PIPE (BY OTHERS)

PROJECTION



### IF IN DOUBT ASK

COMMENTS:

1. MANHOLE WALL AND SLAB THICKNESSES ARE NOT TO SCALE.

2. CONTACT HYDRO INTERNATIONAL FOR A BOTTOM OF STRUCTURE ELEVATION PRIOR TO SETTING FIRST DEFENSE MANHOLE.

3. CONTRACTOR TO CONFIRM RIM, PIPE INVERTS, PIPE DIA. AND PIPE ORIENTATION PRIOR TO RELEASE OF UNIT TO FABRICATION.

DATE:  
11/8/2019

SCALE:  
1:30

DRAWN BY:  
JLL3

CHECKED BY:  
-

APPROVED BY:  
-

Title  
5-ft DIAMETER

FIRST DEFENSE HIGH CAPACITY

GENERAL ARRANGEMENT

**Hydro**  
**International**

hydro-int.com

HYDRO INTERNATIONAL

**DO NOT SCALE DRAWING**  
**STEEL FABRICATION TOLERANCES**  
UNLESS OTHERWISE SPECIFIED,  
DIMENSIONS ARE IN INCHES.

LINEAR  
000 - 012in = ±0.04in  
012 - 024in = ±0.06in  
024 - 048in = ±0.08in  
048 - 120in = ±0.12in  
120in >>> = ±0.20in

ANGULAR  
000 - 120in = ±1°  
120 - 240in = ±0.5°  
240in >>> = ±0.25°

WEIGHT:  
N/A

MATERIAL:

STOCK NUMBER:


DRAWING NO.:  
Eng\_5FDHC\_FDHC GA

SHEET SIZE:  
B

SHEET:  
1 OF 1

Rev:  
-

ANY WARRANTY GIVEN BY HYDRO INTERNATIONAL WILL APPLY ONLY TO THOSE ITEMS SUPPLIED BY IT. ACCORDINGLY HYDRO INTERNATIONAL CANNOT ACCEPT ANY RESPONSIBILITY FOR ANY STRUCTURE, PLANT, OR EQUIPMENT, (OR THE PERFORMANCE THERE OF) DESIGNED, BUILT, MANUFACTURED, OR SUPPLIED BY ANY THIRD PARTY. HYDRO INTERNATIONAL HAVE A POLICY OF CONTINUOUS DEVELOPMENT AND RESERVE THE RIGHT TO AMEND THE SPECIFICATION. HYDRO INTERNATIONAL CANNOT ACCEPT LIABILITY FOR PERFORMANCE OF ITS EQUIPMENT, (OR ANY PART THEREOF), IF THE EQUIPMENT IS SUBJECT TO CONDITIONS OUTSIDE ANY DESIGN SPECIFICATION. HYDRO INTERNATIONAL OWNS THE COPYRIGHT OF THIS DRAWING, WHICH IS SUPPLIED IN CONFIDENCE. IT MUST NOT BE USED FOR ANY PURPOSE OTHER THAN THAT FOR WHICH IT IS SUPPLIED AND MUST NOT BE REPRODUCED, IN WHOLE OR IN PART, WITHOUT PRIOR PERMISSION IN WRITING FROM HYDRO INTERNATIONAL.



## Operation and Maintenance Manual

**First Defense® High Capacity and First Defense® Optimum**

---

Vortex Separator for Stormwater Treatment



## Table of Contents

<b>3</b>	<b>FIRST DEFENSE® BY HYDRO INTERNATIONAL</b> <ul style="list-style-type: none"><li>- INTRODUCTION</li><li>- OPERATION</li><li>- POLLUTANT CAPTURE AND RETENTION</li></ul>
<b>4</b>	<b>MODEL SIZES &amp; CONFIGURATIONS</b> <ul style="list-style-type: none"><li>- FIRST DEFENSE® COMPONENTS</li></ul>
<b>5</b>	<b>MAINTENANCE</b> <ul style="list-style-type: none"><li>- OVERVIEW</li><li>- MAINTENANCE EQUIPMENT CONSIDERATIONS</li><li>- DETERMINING YOUR MAINTENANCE SCHEDULE</li></ul>
<b>6</b>	<b>MAINTENANCE PROCEDURES</b> <ul style="list-style-type: none"><li>- INSPECTION</li><li>- FLOATABLES AND SEDIMENT CLEAN OUT</li></ul>
<b>8</b>	<b>FIRST DEFENSE® INSTALLATION LOG</b>
<b>9</b>	<b>FIRST DEFENSE® INSPECTION AND MAINTENANCE LOG</b>

---

**COPYRIGHT STATEMENT:** The contents of this manual, including the graphics contained herein, are intended for the use of the recipient to whom the document and all associated information are directed. Hydro International plc owns the copyright of this document, which is supplied in confidence. It must not be used for any purpose other than that for which it is supplied and must not be reproduced, in whole or in part stored in a retrieval system or transmitted in any form or by any means without prior permission in writing from Hydro International plc. First Defense® is a trademarked hydrodynamic vortex separation device of Hydro International plc. A patent covering the First Defense® has been granted.

**DISCLAIMER:** Information and data contained in this manual is exclusively for the purpose of assisting in the operation and maintenance of Hydro International plc's First Defense®. No warranty is given nor can liability be accepted for use of this information for any other purpose. Hydro International plc has a policy of continuous product development and reserves the right to amend specifications without notice.

# I. First Defense® by Hydro International

## Introduction

The First Defense® is an enhanced vortex separator that combines an effective and economical stormwater treatment chamber with an integral peak flow bypass. It efficiently removes total suspended solids (TSS), trash and hydrocarbons from stormwater runoff without washing out previously captured pollutants. The First Defense® is available in several model configurations to accommodate a wide range of pipe sizes, peak flows and depth constraints.

The two product models described in this guide are the First Defense® High Capacity and the First Defense® Optimum; they are inspected and maintained identically.

## Operation

The First Defense® operates on simple fluid hydraulics. It is self-activating, has no moving parts, no external power requirement and is fabricated with durable non-corrosive components. No manual procedures are required to operate the unit and maintenance is limited to monitoring accumulations of stored pollutants and periodic clean-outs. The First Defense® has been designed to allow for easy and safe access for inspection, monitoring and clean-out procedures. Neither entry into the unit nor removal of the internal components is necessary for maintenance, thus safety concerns related to confined-space-entry are avoided.

## Pollutant Capture and Retention

The internal components of the First Defense® have been designed to optimize pollutant capture. Sediment is captured and retained in the base of the unit, while oil and floatables are stored on the water surface in the inner volume (Fig. 1).

The pollutant storage volumes are isolated from the built-in bypass chamber to prevent washout during high-flow storm events. The sump of the First Defense® retains a standing water level between storm events. This ensures a quiescent flow regime at the onset of a storm, preventing resuspension and washout of pollutants captured during previous events.

Accessories such as oil absorbent pads are available for enhanced oil removal and storage. Due to the separation of the oil and floatable storage volume from the outlet, the potential for washout of stored pollutants between clean-outs is minimized.

## Applications

- Stormwater treatment at the point of entry into the drainage line
- Sites constrained by space, topography or drainage profiles with limited slope and depth of cover
- Retrofit installations where stormwater treatment is placed on or tied into an existing storm drain line
- Pretreatment for filters, infiltration and storage

## Advantages

- Inlet options include surface grate or multiple inlet pipes
- Integral high capacity bypass conveys large peak flows without the need for "offline" arrangements using separate junction manholes
- Long flow path through the device ensures a long residence time within the treatment chamber, enhancing pollutant settling
- Delivered to site pre-assembled and ready for installation




Fig. 1 Pollutant storage volumes in the First Defense®.

## II. Model Sizes & Configurations

The First Defense® inlet and internal bypass arrangements are available in several model sizes and configurations. The components have modified geometries allowing greater design flexibility to accommodate various site constraints.

All First Defense® models include the internal components that are designed to remove and retain total suspended solids (TSS), gross solids, floatable trash and hydrocarbons (Fig.2). First Defense® model sizes (diameter) are shown in Table 1.

## III. Maintenance

### First Defense® Components

1. Built-In Bypass

2. Inlet Pipe

3. Inlet Chute
4. Floatables Draw-off Port

5. Outlet Pipe

6. Floatables Storage
7. Sediment Storage

8. Inlet Grate or Cover




Table 1

First Defense® Model Sizes
(ft / m) diameter
3 / 0.9
4 / 1.2
5 / 1.5
6 / 1.8
7 / 2.1
8 / 2.4
10 / 3.0

## Overview


The First Defense® protects the environment by removing a wide range of pollutants from stormwater runoff. Periodic removal of these captured pollutants is essential to the continuous, long-term functioning of the First Defense®. The First Defense® will capture and retain sediment and oil until the sediment and oil storage volumes are full to capacity. When sediment and oil storage capacities are reached, the First Defense® will no longer be able to store removed sediment and oil.

The First Defense® allows for easy and safe inspection, monitoring and clean-out procedures. A commercially or municipally owned sump-vac is used to remove captured sediment and floatables. Access ports are located in the top of the manhole.

Maintenance events may include Inspection, Oil & Floatables Removal, and Sediment Removal. Maintenance events do not require entry into the First Defense®, nor do they require the internal components of the First Defense® to be removed. In the case of inspection and floatables removal, a vactor truck is not required. However, a vactor truck is required if the maintenance event is to include oil removal and/or sediment removal.

## Maintenance Equipment Considerations

The internal components of the First Defense® have a centrally located circular shaft through which the sediment storage sump can be accessed with a sump vac hose. The open diameter of this access shaft is 15 inches in diameter (Fig.3). Therefore, the nozzle fitting of any vactor hose used for maintenance should be less than 15 inches in diameter.



*Fig.3 The central opening to the sump of the First Defense® is 15 inches in diameter.*

## Determining Your Maintenance Schedule

The frequency of clean out is determined in the field after installation. During the first year of operation, the unit should be inspected every six months to determine the rate of sediment and floatables accumulation. A simple probe such as a Sludge-Judge® can be used to determine the level of accumulated solids stored in the sump. This information can be recorded in the maintenance log (see page 9) to establish a routine maintenance schedule.

The vactor procedure, including both sediment and oil / floatables removal, for First Defense® typically takes less than 30 minutes and removes a combined water/oil volume of about 765 gallons.

### Inspection Procedures

1. Set up any necessary safety equipment around the access port or grate of the First Defense® as stipulated by local ordinances. Safety equipment should notify passing pedestrian and road traffic that work is being done.
2. Remove the grate or lid to the manhole.
3. Without entering the vessel, look down into the chamber to inspect the inside. Make note of any irregularities. Fig.4 shows the standing water level that should be observed.
4. Without entering the vessel, use the pole with the skimmer net to remove floatables and loose debris from the components and water surface.
5. Using a sediment probe such as a Sludge Judge®, measure the depth of sediment that has collected in the sump of the vessel.
6. On the Maintenance Log (see page 9), record the date, unit location, estimated volume of floatables and gross debris removed, and the depth of sediment measured. Also note any apparent irregularities such as damaged components or blockages.
7. Securely replace the grate or lid.
8. Take down safety equipment.
9. Notify Hydro International of any irregularities noted during inspection.

### Floatables and Sediment Clean Out

Floatables clean out is typically done in conjunction with sediment removal. A commercially or municipally owned sump-vac is used to remove captured sediment and floatables (Fig.4).

Floatables and loose debris can also be netted with a skimmer and pole. The access port located at the top of the manhole provides unobstructed access for a vector hose to be lowered to the base of the sump.

### Scheduling

- Floatables and sump clean out are typically conducted once a year during any season.
- Floatables and sump clean out should occur as soon as possible following a spill in the contributing drainage area.



Fig.4 Floatables are removed with a vector hose

### Recommended Equipment

- Safety Equipment (traffic cones, etc)
- Crow bar or other tool to remove grate or lid
- Pole with skimmer or net (if only floatables are being removed)
- Sediment probe (such as a Sludge Judge®)
- Vector truck (flexible hose recommended)
- First Defense® Maintenance Log



### *Floatables and Sediment Clean Out Procedures*

1. Set up any necessary safety equipment around the access port or grate of the First Defense® as stipulated by local ordinances. Safety equipment should notify passing pedestrian and road traffic that work is being done.
2. Remove the grate or lid to the manhole.
3. Without entering the vessel, look down into the chamber to inspect the inside. Make note of any irregularities.
4. Remove oil and floatables stored on the surface of the water with the vactor hose or with the skimmer or net
5. Using a sediment probe such as a Sludge Judge®, measure the depth of sediment that has collected in the sump of the vessel and record it in the Maintenance Log (page 9).
6. Once all floatables have been removed, drop the vactor hose to the base of the sump. Vactor out the sediment and gross debris off the sump floor
7. Retract the vactor hose from the vessel.
8. On the Maintenance Log provided by Hydro International, record the date, unit location, estimated volume of floatables and gross debris removed, and the depth of sediment measured. Also note any apparent irregularities such as damaged components, blockages, or irregularly high or low water levels.
9. Securely replace the grate or lid.

## Maintenance at a Glance

Inspection	<ul style="list-style-type: none"> <li>- Regularly during first year of installation</li> <li>- Every 6 months after the first year of installation</li> </ul>
Oil and Floatables Removal	<ul style="list-style-type: none"> <li>- Once per year, with sediment removal</li> <li>- Following a spill in the drainage area</li> </ul>
Sediment Removal	<ul style="list-style-type: none"> <li>- Once per year or as needed</li> <li>- Following a spill in the drainage area</li> </ul>

NOTE: For most clean outs the entire volume of liquid does not need to be removed from the manhole. Only remove the first few inches of oils and floatables from the water surface to reduce the total volume of liquid removed during a clean out.



## First Defense® Installation Log

HYDRO INTERNATIONAL REFERENCE NUMBER:	
SITE NAME:	
SITE LOCATION:	
OWNER:	CONTRACTOR:
CONTACT NAME:	CONTACT NAME:
COMPANY NAME:	COMPANY NAME:
ADDRESS:	ADDRESS:
TELEPHONE:	TELEPHONE:
FAX:	FAX:

INSTALLATION DATE:     /     /

MODEL SIZE (CIRCLE ONE):     [3-FT]     [4-FT]     [5-FT]     [6-FT]     [7-FT]     [8-FT]     [10-FT]

INLET (CIRCLE ALL THAT APPLY):     GRATED INLET (CATCH BASIN)     INLET PIPE (FLOW THROUGH)

# First Defense® Inspection and Maintenance Log

[illegible]







## Stormwater Solutions

94 Hutchins Drive  
Portland, ME 04102

Tel: (207) 756-6200

Fax: (207) 756-6212

[stormwaterinquiry@hydro-int.com](mailto:stormwaterinquiry@hydro-int.com)

[www.hydro-int.com](http://www.hydro-int.com)

Turning Water Around...®

FD\_O+M\_K\_2105

Appendix K:  
Construction sequence

### **CONSTRUCTION SEQUENCING:**

1. SURVEY LOCATE THE CENTERLINE OF THE PROPOSED BUCK RUN DRIVEWAY EXTENSION, CENTERLINE OF THE PROPOSED DRIVEWAY TO PROPOSED BUILDING 1 AND 2 AND CENTERLINE OF THE PROPOSED GRAVEL PARKING AREA.
2. SURVEY LOCATE AND STAKE THE PROPOSED LIMITS OF DISTURBANCE, BERM OF THE INFILTRATION BASIN AND LOWER PROPOSED INFILTRATION SYSTEMS.
3. CORDON OFF LOWER INFILTRATION SYSTEMS AND EXISTING SSTS' ADJACENT TO PROPOSED BUILDING 1 WITH CONSTRUCTION FENCING.
4. IDENTIFY TREES TO REMAIN AND PROVIDE PROTECTIVE FENCING. CLEAR TREES WITHIN THE LIMITS OF DISTURBANCE (NOTE: MAINTAIN EXISTING VEGETATIVE GROUND COVER FOR AS LONG AS POSSIBLE ON AREAS NOT REQUIRING GRADING).
5. INSTALL STABILIZED CONSTRUCTION ENTRANCE FROM OLD POST ROAD (ROUTE 35).
6. INSTALL ALL SILT FENCE AS SHOWN.
7. DEMOLISH EXISTING STRUCTURES AS NEEDED AS CONSTRUCTION PROGRESSES FROM OLD POST ROAD NORTH INTO THE SITE.
8. STRIP TOPSOIL FROM THE DRIVEWAY SHOULDERS AND GRAVEL PARKING AREA AND STOCKPILE.
9. STRIP DRIVEWAY SURFACE OF BUCK RUN TO STA. 4+00, EXCAVATE AND FILL TO FORM EMBANKMENTS AND ROUGH GRADE GRAVEL PARKING AREA AND INFILTRATION BASIN.
10. CONSTRUCT PORTION OF DRIVEWAY TO STA. 4+00 AND GRAVEL PARKING AREA TO SUBGRADE. INSTALL CATCH BASIN(S), DRAIN MANHOLE(S), AND DRAINAGE PIPE, FROM STA. 0+00 TO 4+00. INSTALL INFILTRATION SYSTEM INCLUDING DIVERSION STRUCTURES AND HDS UNITS. PROVIDE INLET PROTECTION FOR CATCH BASINS.
11. REINSTALL CONSTRUCTION FENCING TO PROTECT INFILTRATION SYSTEM AREA.
12. ESTABLISH CONSTRUCTION STAGING AREA IN AREA OF GRAVEL PARKING AREA.
13. CONSTRUCT INFILTRATION BASIN.
14. INSTALL CURB AND BINDER COURSE OF PAVEMENT ON PORTION OF COMPLETED DRIVEWAY. BACK-UP CURBS WITH TOPSOIL AND APPLY SEED AND MULCH.
15. DEMOLISH EXISTING STRUCTURES IN AREA OF BUILDINGS 1 AND 2.
16. STRIP DRIVEWAY SURFACE OF BUCK RUN FROM STA. 4+00 TO 7+00, EXCAVATE AND FILL TO FORM EMBANKMENTS AND ROUGH GRADE AS NEEDED. CONSTRUCTION RETAINING WALL AND INSTALL SIDEWALK.

17. CONSTRUCT DRIVEWAY TO SUBGRADE AND RETAINING WALLS ASSOCIATED WITH ACCESS TO BUILDING'S 1 AND 2.
18. CONSTRUCT BUILDING 1 AND 2 AND ASSOCIATED IMPROVEMENTS AND INSTALL ELECTRICAL, TELEPHONE, AND CABLE UTILITIES.
19. INSTALL CATCH BASIN(S), DRAIN MANHOLE(S), AND DRAINAGE PIPE, FROM STA. 4+00 TO 7+00 AND PROPOSED DRIVEWAY TO NEW BUILDINGS. PROVIDE INLET PROTECTION FOR CATCH BASINS.
20. INSTALL CURB AND BINDER COURSE OF PAVEMENT ON PORTION OF COMPLETED DRIVEWAY. BACK-UP CURBS WITH TOPSOIL AND APPLY SEED AND MULCH.
21. STRIP DRIVEWAY SURFACE OF THE REMAINDER OF BUCK RUN, EXCAVATE AND FILL TO FORM EMBANKMENTS AND ROUGH GRADE AS NEEDED. CONSTRUCTION RETAINING WALLS AND PARKING AREA.
22. DEMOLISH EXISTING STRUCTURES AND CONSTRUCT PROPOSED FREEZER FACILITY.
23. INSTALL REMAINING CATCH BASIN(S), DRAIN MANHOLE(S), AND DRAINAGE PIPE ASSOCIATED WITH THE DRIVEWAY IMPROVEMENTS. PROVIDE INLET PROTECTION FOR CATCH BASINS.
24. INSTALL REMAINING ELECTRICAL, TELEPHONE, AND CABLE UTILITIES.
25. INSTALL CURB AND BINDER COURSE OF PAVEMENT ON PORTION OF COMPLETED DRIVEWAY. BACK-UP CURBS WITH TOPSOIL AND APPLY SEED AND MULCH.
26. CONSTRUCT UPPER SITE IMPROVEMENTS (CAMPING PODS AND RESTROOM FACILITIES) AND GRAVEL PATH RESURFACING AND REALIGNMENT.
27. FINE GRADE DRIVEWAY SHOULDERS, LAWN AREA, AND ALL OTHER DISTURBED AREAS TO BE RESTORED TO VEGETATIVE COVER AND COMPLETE RESTORATION OF THESE AREAS WITH SEED AND MULCH. INSTALL LANDSCAPE PLANTINGS AND MULCH BEDS. INDIVIDUAL INFILTRATION SYSTEMS SHALL BE PLACED INTO OPERATION ONLY AFTER FINAL STABILIZATION OF DISTURBED AREA FROM CONTRIBUTING AREA. REMOVE THE SEALS FROM THE PIPE OUTLETS IN DIVERSION STRUCTURES.
28. INSTALL GRAVEL COURSE OF GRAVEL PARKING AREA.
29. CLEANOUT CATCH BASINS AND REMOVE EROSION CONTROLS.
30. INSTALL TOP COURSE OF PAVEMENT.
31. INSTALL PAVEMENT MARKINGS AS NEEDED.
32. RE-VEGETATE ROAD SHOULDERS AND YARD AREAS AS NEEDED.


NOTE: SITE STABILIZATION (80% UNIFORM DENSITY OF PERMANENT VEGETATION OR PERMANENT MULCH/STONE) MUST BE ACHIEVED PRIOR TO REMOVING TEMPORARY EROSION CONTROL MEASURES.



## Appendix L:




### Swale Sizing

**Wolf Conservation Center**  
**Swale Sizing Summary**



Swale # Number	Swale Type	Tributary Area (AF)	10-Year Storm Peak Inflow (cfs)	Average Flow Depth (ft)	Swale Parameters			Freeboard (ft.)
					Z	B (ft.)	Y (ft.)	
Swale 1	Grass	0.229	1.8	0.19	2	2	1	0.81
Swale 2	Rip-rap	0.315	2.3	0.31	2	2	1	0.69
Swale 3	Rip-rap	0.770	5.7	0.48	2	2	1	0.52
Swale 4	Rip-rap	0.164	1.6	0.20	2	2	1	0.80
Swale 5	Rip-rap	0.314	3.2	0.38	2	2	1	0.62
Swale 6	Rip-rap	0.274	2.6	0.30	2	2	1	0.70

Note: The minimum freeboard for lined waterways shall be 0.25 feet above design high water in areas where erosion resistant vegetation cannot be grown adjacent to the paved side slopes. No freeboard is required where good vegetation can be grown and is maintained



**Routing Diagram for Wolf Center - SWALES 10-2023**  
 Prepared by Bibbo Associates, llp., Printed 10/20/2023  
 HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

**Wolf Center - SWALES 10-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 10-yr Rainfall=5.08"*

Printed 10/20/2023

Page 2

Time span=0.00-72.00 hrs, dt=0.05 hrs, 1441 points x 3

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN

Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

<b>Subcatchment1.01S: 1.01S</b>	Runoff Area=54,906 sf 0.00% Impervious Runoff Depth=2.18" Flow Length=762' Tc=23.5 min CN=71 Runoff=1.8 cfs 0.229 af
<b>Subcatchment1.02S: 1.02S</b>	Runoff Area=72,889 sf 0.00% Impervious Runoff Depth=2.26" Flow Length=960' Tc=27.4 min CN=72 Runoff=2.3 cfs 0.315 af
<b>Subcatchment1.03S: 1.03S</b>	Runoff Area=30,431 sf 0.00% Impervious Runoff Depth=2.34" Flow Length=488' Tc=8.8 min CN=73 Runoff=1.6 cfs 0.136 af
<b>Subcatchment1.04S: 1.04S</b>	Runoff Area=65,878 sf 0.00% Impervious Runoff Depth=2.18" Flow Length=755' Tc=16.6 min CN=71 Runoff=2.5 cfs 0.274 af
<b>Subcatchment1.05S: 1.05S</b>	Runoff Area=9,104 sf 5.18% Impervious Runoff Depth=2.51" Tc=6.0 min CN=75 Runoff=0.6 cfs 0.044 af
<b>Subcatchment1.06S: 1.06S</b>	Runoff Area=40,950 sf 0.00% Impervious Runoff Depth=2.10" Flow Length=746' Tc=14.4 min CN=70 Runoff=1.6 cfs 0.164 af
<b>Subcatchment1.07S: 1.07S</b>	Runoff Area=35,857 sf 0.00% Impervious Runoff Depth=2.18" Flow Length=390' Tc=9.6 min CN=71 Runoff=1.7 cfs 0.149 af
<b>Subcatchment1.08S: 1.08S</b>	Runoff Area=68,349 sf 0.00% Impervious Runoff Depth=2.10" Flow Length=904' Tc=15.7 min CN=70 Runoff=2.6 cfs 0.274 af
<b>Subcatchment1.3S: 1.3S</b>	Runoff Area=2,000 sf 100.00% Impervious Runoff Depth=4.84" Tc=6.0 min CN=98 Runoff=0.2 cfs 0.019 af
<b>Reach 1.03R:</b>	Avg. Flow Depth=0.19' Max Vel=0.66 fps Inflow=1.6 cfs 0.136 af n=0.400 L=242.0' S=0.3202 ' Capacity=7.1 cfs Outflow=1.4 cfs 0.136 af
<b>Reach SWALE 1:</b>	Avg. Flow Depth=0.31' Max Vel=2.20 fps Inflow=1.8 cfs 0.229 af n=0.030 L=150.0' S=0.0133 ' Capacity=16.6 cfs Outflow=1.8 cfs 0.229 af
<b>Reach SWALE 2:</b>	Avg. Flow Depth=0.27' Max Vel=3.25 fps Inflow=2.3 cfs 0.315 af n=0.069 L=285.0' S=0.1754 ' Capacity=26.2 cfs Outflow=2.3 cfs 0.315 af
<b>Reach SWALE 3:</b>	Avg. Flow Depth=0.48' Max Vel=4.02 fps Inflow=5.7 cfs 0.770 af n=0.069 L=110.0' S=0.1455 ' Capacity=23.8 cfs Outflow=5.7 cfs 0.770 af
<b>Reach SWALE 4:</b>	Avg. Flow Depth=0.20' Max Vel=3.30 fps Inflow=1.6 cfs 0.164 af n=0.069 L=78.0' S=0.2564 ' Capacity=31.6 cfs Outflow=1.6 cfs 0.164 af
<b>Reach SWALE 5:</b>	Avg. Flow Depth=0.38' Max Vel=2.94 fps Inflow=3.2 cfs 0.314 af n=0.069 L=150.0' S=0.1000 ' Capacity=19.8 cfs Outflow=3.1 cfs 0.314 af
<b>Reach SWALE 6:</b>	Avg. Flow Depth=0.30' Max Vel=3.31 fps Inflow=2.6 cfs 0.274 af n=0.069 L=90.0' S=0.1667 ' Capacity=25.5 cfs Outflow=2.6 cfs 0.274 af
<b>Pond CB 17: CB 17</b>	Peak Elev=511.68' Storage=4 cf Inflow=3.1 cfs 0.452 af Outflow=3.1 cfs 0.452 af
<b>Pond CB 22: CB 22</b>	Peak Elev=527.65' Storage=5 cf Inflow=2.5 cfs 0.274 af Outflow=2.5 cfs 0.274 af
<b>Pond CB 9: CB 9</b>	Peak Elev=467.84' Storage=17 cf Inflow=8.6 cfs 1.083 af Outflow=8.6 cfs 1.083 af
<b>Pond DMH 6: DMH 6</b>	Peak Elev=499.45' Inflow=5.5 cfs 0.726 af 15.0" Round Culvert n=0.013 L=127.0' S=0.1094 ' Outflow=5.5 cfs 0.726 af

## Wolf Center - SWALES 10-2023

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 10-yr Rainfall=5.08"*

Printed 10/20/2023

Page 3

### Pond DS1.3: Diversion Structure 1.3

Peak Elev=593.68' Inflow=0.2 cfs 0.019 af

Primary=0.2 cfs 0.019 af Secondary=0.0 cfs 0.000 af Outflow=0.2 cfs 0.019 af

### Pond INF 1.3: Infiltration System 1.3

Peak Elev=593.58' Storage=0.002 af Inflow=0.2 cfs 0.019 af

Outflow=0.1 cfs 0.019 af



**Wolf Center - SWALES 10-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 10-yr Rainfall=5.08"*

Printed 10/20/2023

Page 4

**Summary for Subcatchment 1.01S: 1.01S**

Runoff = 1.8 cfs @ 12.29 hrs, Volume= 0.229 af, Depth= 2.18"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Buck Run 24-hr S1 10-yr Rainfall=5.08"

Area (sf)	CN	Description
3,700	87	Dirt roads, HSG C
4,789	74	>75% Grass cover, Good, HSG C
46,417	70	Woods, Good, HSG C
54,906	71	Weighted Average
54,906		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
17.7	100	0.0300	0.09		<b>Sheet Flow,</b> Woods: Light underbrush n= 0.400 P2= 3.40"
5.8	662	0.1450	1.90		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
23.5	762	Total			

**Subcatchment 1.01S: 1.01S****Hydrograph**

**Wolf Center - SWALES 10-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

Buck Run 24-hr S1 10-yr Rainfall=5.08"

Printed 10/20/2023

Page 5

**Summary for Subcatchment 1.02S: 1.02S**

Runoff = 2.3 cfs @ 12.34 hrs, Volume= 0.315 af, Depth= 2.26"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Buck Run 24-hr S1 10-yr Rainfall=5.08"

Area (sf)	CN	Description
5,326	87	Dirt roads, HSG C
19,189	74	>75% Grass cover, Good, HSG C
48,374	70	Woods, Good, HSG C
72,889	72	Weighted Average
72,889		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
20.8	100	0.0200	0.08		<b>Sheet Flow,</b> Woods: Light underbrush n= 0.400 P2= 3.40"
4.2	485	0.1460	1.91		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
1.0	157	0.1400	2.62		<b>Shallow Concentrated Flow,</b> Short Grass Pasture Kv= 7.0 fps
1.3	202	0.2870	2.68		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
0.1	16	0.3130	3.92		<b>Shallow Concentrated Flow,</b> Short Grass Pasture Kv= 7.0 fps
27.4	960	Total			

**Subcatchment 1.02S: 1.02S****Hydrograph**

**Wolf Center - SWALES 10-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

Buck Run 24-hr S1 10-yr Rainfall=5.08"

Printed 10/20/2023

Page 6

**Summary for Subcatchment 1.03S: 1.03S**

Runoff = 1.6 cfs @ 12.08 hrs, Volume= 0.136 af, Depth= 2.34"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Buck Run 24-hr S1 10-yr Rainfall=5.08"

Area (sf)	CN	Description
2,873	87	Dirt roads, HSG C
10,613	74	>75% Grass cover, Good, HSG C
16,945	70	Woods, Good, HSG C
30,431	73	Weighted Average
30,431		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
2.6	20	0.1500	0.13		<b>Sheet Flow,</b> Woods: Light underbrush n= 0.400 P2= 3.40"
4.0	80	0.1125	0.33		<b>Sheet Flow,</b> Grass: Short n= 0.150 P2= 3.40"
0.2	35	0.2850	3.74		<b>Shallow Concentrated Flow,</b> Short Grass Pasture Kv= 7.0 fps
0.1	30	0.1330	5.87		<b>Shallow Concentrated Flow,</b> Unpaved Kv= 16.1 fps
0.5	81	0.1600	2.80		<b>Shallow Concentrated Flow,</b> Short Grass Pasture Kv= 7.0 fps
1.3	214	0.2850	2.67		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
0.1	28	0.3570	4.18		<b>Shallow Concentrated Flow,</b> Short Grass Pasture Kv= 7.0 fps
8.8	488	Total			

**Subcatchment 1.03S: 1.03S****Hydrograph**

**Wolf Center - SWALES 10-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 10-yr Rainfall=5.08"*

Printed 10/20/2023

Page 7

**Summary for Subcatchment 1.04S: 1.04S**

Runoff = 2.5 cfs @ 12.19 hrs, Volume= 0.274 af, Depth= 2.18"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Buck Run 24-hr S1 10-yr Rainfall=5.08"


Area (sf)	CN	Description
2,166	87	Dirt roads, HSG C
6,623	74	>75% Grass cover, Good, HSG C
57,089	70	Woods, Good, HSG C
65,878	71	Weighted Average
65,878		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
12.0	100	0.0800	0.14		<b>Sheet Flow,</b> Woods: Light underbrush n= 0.400 P2= 3.40"
4.5	620	0.2085	2.28		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
0.1	35	0.6850	5.79		<b>Shallow Concentrated Flow,</b> Short Grass Pasture Kv= 7.0 fps
16.6	755	Total			

**Subcatchment 1.04S: 1.04S**

Hydrograph



**Summary for Subcatchment 1.05S: 1.05S**

Runoff = 0.6 cfs @ 12.04 hrs, Volume= 0.044 af, Depth= 2.51"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs


Buck Run 24-hr S1 10-yr Rainfall=5.08"

Area (sf)	CN	Description
472	98	Paved parking, HSG C
1,149	70	Woods, Good, HSG C
7,483	74	>75% Grass cover, Good, HSG C
9,104	75	Weighted Average
8,632		94.82% Pervious Area
472		5.18% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

**Subcatchment 1.05S: 1.05S**

**Hydrograph**





**Wolf Center - SWALES 10-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

Buck Run 24-hr S1 10-yr Rainfall=5.08"

Printed 10/20/2023

Page 9

**Summary for Subcatchment 1.06S: 1.06S**

Runoff = 1.6 cfs @ 12.16 hrs, Volume= 0.164 af, Depth= 2.10"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Buck Run 24-hr S1 10-yr Rainfall=5.08"

Area (sf)	CN	Description
3,043	74	>75% Grass cover, Good, HSG C
37,907	70	Woods, Good, HSG C
40,950	70	Weighted Average
40,950		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
9.9	100	0.1300	0.17		<b>Sheet Flow,</b> Woods: Light underbrush n= 0.400 P2= 3.40"
4.4	616	0.2190	2.34		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
0.1	30	0.4330	4.61		<b>Shallow Concentrated Flow,</b> Short Grass Pasture Kv= 7.0 fps
14.4	746	Total			

**Subcatchment 1.06S: 1.06S****Hydrograph**

**Wolf Center - SWALES 10-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

Buck Run 24-hr S1 10-yr Rainfall=5.08"

Printed 10/20/2023

Page 10

**Summary for Subcatchment 1.07S: 1.07S**

Runoff = 1.7 cfs @ 12.09 hrs, Volume= 0.149 af, Depth= 2.18"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Buck Run 24-hr S1 10-yr Rainfall=5.08"

Area (sf)	CN	Description
27,283	70	Woods, Good, HSG C
8,574	74	>75% Grass cover, Good, HSG C
35,857	71	Weighted Average
35,857		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
7.7	100	0.2400	0.22		<b>Sheet Flow,</b> Woods: Light underbrush n= 0.400 P2= 3.40"
1.9	290	0.2680	2.59		<b>Shallow Concentrated Flow,</b> Woodland Kv= 5.0 fps
9.6	390	Total			

**Subcatchment 1.07S: 1.07S****Hydrograph**

**Wolf Center - SWALES 10-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

Buck Run 24-hr S1 10-yr Rainfall=5.08"

Printed 10/20/2023

Page 11

**Summary for Subcatchment 1.08S: 1.08S**

Runoff = 2.6 cfs @ 12.18 hrs, Volume= 0.274 af, Depth= 2.10"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs

Buck Run 24-hr S1 10-yr Rainfall=5.08"

Area (sf)	CN	Description
68,349	70	Woods, Good, HSG C
68,349		100.00% Pervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
10.2	100	0.1200	0.16		Sheet Flow, Woods: Light underbrush n= 0.400 P2= 3.40"
5.5	804	0.2370	2.43		Shallow Concentrated Flow, Woodland Kv= 5.0 fps
15.7	904	Total			

**Subcatchment 1.08S: 1.08S****Hydrograph**

### Summary for Subcatchment 1.3S: 1.3S

Runoff = 0.2 cfs @ 12.04 hrs, Volume= 0.019 af, Depth= 4.84"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs


Buck Run 24-hr S1 10-yr Rainfall=5.08"

Area (sf)	CN	Description
*	2,000	98 Proposed Pods and Facilities
2,000		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry,

### Subcatchment 1.3S: 1.3S

#### Hydrograph



### Summary for Reach 1.03R:

Inflow Area = 0.699 ac, 0.00% Impervious, Inflow Depth = 2.34" for 10-yr event  
 Inflow = 1.6 cfs @ 12.08 hrs, Volume= 0.136 af  
 Outflow = 1.4 cfs @ 12.15 hrs, Volume= 0.136 af, Atten= 15%, Lag= 4.1 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs / 3  
 Max. Velocity= 0.66 fps, Min. Travel Time= 6.1 min  
 Avg. Velocity = 0.16 fps, Avg. Travel Time= 24.7 min


Peak Storage= 496 cf @ 12.15 hrs  
 Average Depth at Peak Storage= 0.19'  
 Bank-Full Depth= 0.50' Flow Area= 6.0 sf, Capacity= 7.1 cfs

10.00' x 0.50' deep channel, n= 0.400 Sheet flow: Woods+light brush  
 Side Slope Z-value= 4.0 '/' Top Width= 14.00'  
 Length= 242.0' Slope= 0.3202 '/'  
 Inlet Invert= 594.50', Outlet Invert= 517.00'



### Reach 1.03R:

#### Hydrograph





**Wolf Center - SWALES 10-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 10-yr Rainfall=5.08"*

Printed 10/20/2023

Page 14

**Stage-Area-Storage for Reach 1.03R:**

Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)
594.50	0.0	0
594.51	0.1	24
594.52	0.2	49
594.53	0.3	73
594.54	0.4	98
594.55	0.5	123
594.56	0.6	149
594.57	0.7	174
594.58	0.8	200
594.59	0.9	226
594.60	1.0	252
594.61	1.1	278
594.62	1.3	304
594.63	1.4	331
594.64	1.5	358
594.65	1.6	385
594.66	1.7	412
594.67	1.8	439
594.68	1.9	467
594.69	2.0	495
594.70	2.2	523
594.71	2.3	551
594.72	2.4	579
594.73	2.5	608
594.74	2.6	637
594.75	2.8	666
594.76	2.9	695
594.77	3.0	724
594.78	3.1	753
594.79	3.2	783
594.80	3.4	813
594.81	3.5	843
594.82	3.6	874
594.83	3.7	904
594.84	3.9	935
594.85	4.0	966
594.86	4.1	997
594.87	4.2	1,028
594.88	4.4	1,059
594.89	4.5	1,091
594.90	4.6	1,123
594.91	4.8	1,155
594.92	4.9	1,187
594.93	5.0	1,220
594.94	5.2	1,252
594.95	5.3	1,285
594.96	5.4	1,318
594.97	5.6	1,351
594.98	5.7	1,385
594.99	5.9	1,418
595.00	<b>6.0</b>	<b>1,452</b>

### Summary for Reach SWALE 1:

Inflow Area = 1.260 ac, 0.00% Impervious, Inflow Depth = 2.18" for 10-yr event  
 Inflow = 1.8 cfs @ 12.29 hrs, Volume= 0.229 af  
 Outflow = 1.8 cfs @ 12.30 hrs, Volume= 0.229 af, Atten= 0%, Lag= 0.8 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs / 3

Max. Velocity= 2.20 fps, Min. Travel Time= 1.1 min

Avg. Velocity= 0.82 fps, Avg. Travel Time= 3.0 min

Peak Storage= 121 cf @ 12.30 hrs

Average Depth at Peak Storage= 0.31'

Bank-Full Depth= 1.00' Flow Area= 4.0 sf, Capacity= 16.6 cfs

2.00' x 1.00' deep channel, n= 0.030 Earth, grassed & winding

Side Slope Z-value= 2.0 '/ Top Width= 6.00'


Length= 150.0' Slope= 0.0133 '/

Inlet Invert= 584.00', Outlet Invert= 582.00'



### Reach SWALE 1:

#### Hydrograph



**Wolf Center - SWALES 10-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 10-yr Rainfall=5.08"*

Printed 10/20/2023

Page 16

**Stage-Area-Storage for Reach SWALE 1:**

Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)	Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)
584.00	0.0	0	584.66	2.2	329
584.01	0.0	3	584.67	2.2	336
584.02	0.0	6	584.68	2.3	343
584.03	0.1	9	584.69	2.3	350
584.04	0.1	12	584.70	2.4	357
584.05	0.1	16	584.71	2.4	364
584.06	0.1	19	584.72	2.5	372
584.07	0.1	22	584.73	2.5	379
584.08	0.2	26	584.74	2.6	386
584.09	0.2	29	584.75	2.6	394
584.10	0.2	33	584.76	2.7	401
584.11	0.2	37	584.77	2.7	409
584.12	0.3	40	584.78	2.8	417
584.13	0.3	44	584.79	2.8	424
584.14	0.3	48	584.80	2.9	432
584.15	0.3	52	584.81	2.9	440
584.16	0.4	56	584.82	3.0	448
584.17	0.4	60	584.83	3.0	456
584.18	0.4	64	584.84	3.1	464
584.19	0.5	68	584.85	3.1	472
584.20	0.5	72	584.86	3.2	480
584.21	0.5	76	584.87	3.3	488
584.22	0.5	81	584.88	3.3	496
584.23	0.6	85	584.89	3.4	505
584.24	0.6	89	584.90	3.4	513
584.25	0.6	94	584.91	3.5	521
584.26	0.7	98	584.92	3.5	530
584.27	0.7	103	584.93	3.6	538
584.28	0.7	108	584.94	3.6	547
584.29	0.7	112	584.95	3.7	556
584.30	0.8	117	584.96	3.8	564
584.31	0.8	122	584.97	3.8	573
584.32	0.8	127	584.98	3.9	582
584.33	0.9	132	584.99	3.9	591
584.34	0.9	137	585.00	<b>4.0</b>	<b>600</b>
584.35	0.9	142			
584.36	1.0	147			
584.37	1.0	152			
584.38	1.0	157			
584.39	1.1	163			
584.40	1.1	168			
584.41	1.2	173			
584.42	1.2	179			
584.43	1.2	184			
584.44	1.3	190			
584.45	1.3	196			
584.46	1.3	201			
584.47	1.4	207			
584.48	1.4	213			
584.49	1.5	219			
584.50	1.5	225			
584.51	1.5	231			
584.52	1.6	237			
584.53	1.6	243			
584.54	1.7	249			
584.55	1.7	256			
584.56	1.7	262			
584.57	1.8	268			
584.58	1.8	275			
584.59	1.9	281			
584.60	1.9	288			
584.61	2.0	295			
584.62	2.0	301			
584.63	2.1	308			
584.64	2.1	315			
584.65	2.1	322			

### Summary for Reach SWALE 2:

Inflow Area = 1.673 ac, 0.00% Impervious, Inflow Depth = 2.26" for 10-yr event  
 Inflow = 2.3 cfs @ 12.34 hrs, Volume= 0.315 af  
 Outflow = 2.3 cfs @ 12.36 hrs, Volume= 0.315 af, Atten= 0%, Lag= 1.0 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs / 3

Max. Velocity= 3.25 fps, Min. Travel Time= 1.5 min

Avg. Velocity = 1.22 fps, Avg. Travel Time= 3.9 min

Peak Storage= 199 cf @ 12.36 hrs

Average Depth at Peak Storage= 0.27'

Bank-Full Depth= 1.00' Flow Area= 4.0 sf, Capacity= 26.2 cfs

2.00' x 1.00' deep channel, n= 0.069 Riprap, 6-inch

Side Slope Z-value= 2.0 '/' Top Width= 6.00'


Length= 285.0' Slope= 0.1754 '/'

Inlet Invert= 562.00', Outlet Invert= 512.00'



### Reach SWALE 2:

#### Hydrograph



— Inflow  
 — Outflow

**Wolf Center - SWALES 10-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 10-yr Rainfall=5.08"*

Printed 10/20/2023

Page 18

**Stage-Area-Storage for Reach SWALE 2:**

Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)	Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)
562.00	0.0	0	562.66	2.2	624
562.01	0.0	6	562.67	2.2	638
562.02	0.0	12	562.68	2.3	651
562.03	0.1	18	562.69	2.3	665
562.04	0.1	24	562.70	2.4	678
562.05	0.1	30	562.71	2.4	692
562.06	0.1	36	562.72	2.5	706
562.07	0.1	43	562.73	2.5	720
562.08	0.2	49	562.74	2.6	734
562.09	0.2	56	562.75	2.6	748
562.10	0.2	63	562.76	2.7	762
562.11	0.2	70	562.77	2.7	777
562.12	0.3	77	562.78	2.8	791
562.13	0.3	84	562.79	2.8	806
562.14	0.3	91	562.80	2.9	821
562.15	0.3	98	562.81	2.9	836
562.16	0.4	106	562.82	3.0	851
562.17	0.4	113	562.83	3.0	866
562.18	0.4	121	562.84	3.1	881
562.19	0.5	129	562.85	3.1	896
562.20	0.5	137	562.86	3.2	912
562.21	0.5	145	562.87	3.3	927
562.22	0.5	153	562.88	3.3	943
562.23	0.6	161	562.89	3.4	959
562.24	0.6	170	562.90	3.4	975
562.25	0.6	178	562.91	3.5	991
562.26	0.7	187	562.92	3.5	1,007
562.27	0.7	195	562.93	3.6	1,023
562.28	0.7	204	562.94	3.6	1,039
562.29	0.7	213	562.95	3.7	1,056
562.30	0.8	222	562.96	3.8	1,073
562.31	0.8	231	562.97	3.8	1,089
562.32	0.8	241	562.98	3.9	1,106
562.33	0.9	250	562.99	3.9	1,123
562.34	0.9	260	563.00	<b>4.0</b>	<b>1,140</b>
562.35	0.9	269			
562.36	1.0	279			
562.37	1.0	289			
562.38	1.0	299			
562.39	1.1	309			
562.40	1.1	319			
562.41	1.2	330			
562.42	1.2	340			
562.43	1.2	350			
562.44	1.3	361			
562.45	1.3	372			
562.46	1.3	383			
562.47	1.4	394			
562.48	1.4	405			
562.49	1.5	416			
562.50	1.5	428			
562.51	1.5	439			
562.52	1.6	451			
562.53	1.6	462			
562.54	1.7	474			
562.55	1.7	486			
562.56	1.7	498			
562.57	1.8	510			
562.58	1.8	522			
562.59	1.9	535			
562.60	1.9	547			
562.61	2.0	560			
562.62	2.0	573			
562.63	2.1	585			
562.64	2.1	598			
562.65	2.1	611			



### Summary for Reach SWALE 3:

Inflow Area = 4.093 ac, 0.26% Impervious, Inflow Depth = 2.26" for 10-yr event  
 Inflow = 5.7 cfs @ 12.21 hrs, Volume= 0.770 af  
 Outflow = 5.7 cfs @ 12.22 hrs, Volume= 0.770 af, Atten= 0%, Lag= 0.3 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs / 3  
 Max. Velocity= 4.02 fps, Min. Travel Time= 0.5 min  
 Avg. Velocity= 1.30 fps, Avg. Travel Time= 1.4 min


Peak Storage= 157 cf @ 12.22 hrs  
 Average Depth at Peak Storage= 0.48'  
 Bank-Full Depth= 1.00' Flow Area= 4.0 sf, Capacity= 23.8 cfs

2.00' x 1.00' deep channel, n= 0.069 Riprap, 6-inch  
 Side Slope Z-value= 2.0 '/' Top Width= 6.00'  
 Length= 110.0' Slope= 0.1455 '/'  
 Inlet Invert= 484.00', Outlet Invert= 468.00'



### Reach SWALE 3:

#### Hydrograph



**Wolf Center - SWALES 10-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 10-yr Rainfall=5.08"*

Printed 10/20/2023

Page 20

**Stage-Area-Storage for Reach SWALE 3:**

Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)	Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)
484.00	0.0	0	484.66	2.2	241
484.01	0.0	2	484.67	2.2	246
484.02	0.0	4	484.68	2.3	251
484.03	0.1	7	484.69	2.3	257
484.04	0.1	9	484.70	2.4	262
484.05	0.1	12	484.71	2.4	267
484.06	0.1	14	484.72	2.5	272
484.07	0.1	16	484.73	2.5	278
484.08	0.2	19	484.74	2.6	283
484.09	0.2	22	484.75	2.6	289
484.10	0.2	24	484.76	2.7	294
484.11	0.2	27	484.77	2.7	300
484.12	0.3	30	484.78	2.8	305
484.13	0.3	32	484.79	2.8	311
484.14	0.3	35	484.80	2.9	317
484.15	0.3	38	484.81	2.9	323
484.16	0.4	41	484.82	3.0	328
484.17	0.4	44	484.83	3.0	334
484.18	0.4	47	484.84	3.1	340
484.19	0.5	50	484.85	3.1	346
484.20	0.5	53	484.86	3.2	352
484.21	0.5	56	484.87	3.3	358
484.22	0.5	59	484.88	3.3	364
484.23	0.6	62	484.89	3.4	370
484.24	0.6	65	484.90	3.4	376
484.25	0.6	69	484.91	3.5	382
484.26	0.7	72	484.92	3.5	389
484.27	0.7	75	484.93	3.6	395
484.28	0.7	79	484.94	3.6	401
484.29	0.7	82	484.95	3.7	408
484.30	0.8	86	484.96	3.8	414
484.31	0.8	89	484.97	3.8	420
484.32	0.8	93	484.98	3.9	427
484.33	0.9	97	484.99	3.9	433
484.34	0.9	100	485.00	<b>4.0</b>	<b>440</b>
484.35	0.9	104			
484.36	1.0	108			
484.37	1.0	112			
484.38	1.0	115			
484.39	1.1	119			
484.40	1.1	123			
484.41	1.2	127			
484.42	1.2	131			
484.43	1.2	135			
484.44	1.3	139			
484.45	1.3	144			
484.46	1.3	148			
484.47	1.4	152			
484.48	1.4	156			
484.49	1.5	161			
484.50	1.5	165			
484.51	1.5	169			
484.52	1.6	174			
484.53	1.6	178			
484.54	1.7	183			
484.55	1.7	188			
484.56	1.7	192			
484.57	1.8	197			
484.58	1.8	202			
484.59	1.9	206			
484.60	1.9	211			
484.61	2.0	216			
484.62	2.0	221			
484.63	2.1	226			
484.64	2.1	231			
484.65	2.1	236			

### Summary for Reach SWALE 4:

Inflow Area = 0.940 ac, 0.00% Impervious, Inflow Depth = 2.10" for 10-yr event  
 Inflow = 1.6 cfs @ 12.16 hrs, Volume= 0.164 af  
 Outflow = 1.6 cfs @ 12.16 hrs, Volume= 0.164 af, Atten= 0%, Lag= 0.2 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs / 3  
 Max. Velocity= 3.30 fps, Min. Travel Time= 0.4 min  
 Avg. Velocity = 1.15 fps, Avg. Travel Time= 1.1 min


Peak Storage= 38 cf @ 12.16 hrs  
 Average Depth at Peak Storage= 0.20'  
 Bank-Full Depth= 1.00' Flow Area= 4.0 sf, Capacity= 31.6 cfs

2.00' x 1.00' deep channel, n= 0.069 Riprap, 6-inch  
 Side Slope Z-value= 2.0 '/' Top Width= 6.00'  
 Length= 78.0' Slope= 0.2564 '/'  
 Inlet Invert= 530.00', Outlet Invert= 510.00'



### Reach SWALE 4:

#### Hydrograph



**Wolf Center - SWALES 10-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 10-yr Rainfall=5.08"*

Printed 10/20/2023

Page 22

**Stage-Area-Storage for Reach SWALE 4:**

Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)	Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)
530.00	0.0	0	530.66	2.2	171
530.01	0.0	2	530.67	2.2	175
530.02	0.0	3	530.68	2.3	178
530.03	0.1	5	530.69	2.3	182
530.04	0.1	6	530.70	2.4	186
530.05	0.1	8	530.71	2.4	189
530.06	0.1	10	530.72	2.5	193
530.07	0.1	12	530.73	2.5	197
530.08	0.2	13	530.74	2.6	201
530.09	0.2	15	530.75	2.6	205
530.10	0.2	17	530.76	2.7	209
530.11	0.2	19	530.77	2.7	213
530.12	0.3	21	530.78	2.8	217
530.13	0.3	23	530.79	2.8	221
530.14	0.3	25	530.80	2.9	225
530.15	0.3	27	530.81	2.9	229
530.16	0.4	29	530.82	3.0	233
530.17	0.4	31	530.83	3.0	237
530.18	0.4	33	530.84	3.1	241
530.19	0.5	35	530.85	3.1	245
530.20	0.5	37	530.86	3.2	250
530.21	0.5	40	530.87	3.3	254
530.22	0.5	42	530.88	3.3	258
530.23	0.6	44	530.89	3.4	262
530.24	0.6	46	530.90	3.4	267
530.25	0.6	49	530.91	3.5	271
530.26	0.7	51	530.92	3.5	276
530.27	0.7	53	530.93	3.6	280
530.28	0.7	56	530.94	3.6	284
530.29	0.7	58	530.95	3.7	289
530.30	0.8	61	530.96	3.8	294
530.31	0.8	63	530.97	3.8	298
530.32	0.8	66	530.98	3.9	303
530.33	0.9	68	530.99	3.9	307
530.34	0.9	71	531.00	<b>4.0</b>	<b>312</b>
530.35	0.9	74			
530.36	1.0	76			
530.37	1.0	79			
530.38	1.0	82			
530.39	1.1	85			
530.40	1.1	87			
530.41	1.2	90			
530.42	1.2	93			
530.43	1.2	96			
530.44	1.3	99			
530.45	1.3	102			
530.46	1.3	105			
530.47	1.4	108			
530.48	1.4	111			
530.49	1.5	114			
530.50	1.5	117			
530.51	1.5	120			
530.52	1.6	123			
530.53	1.6	127			
530.54	1.7	130			
530.55	1.7	133			
530.56	1.7	136			
530.57	1.8	140			
530.58	1.8	143			
530.59	1.9	146			
530.60	1.9	150			
530.61	2.0	153			
530.62	2.0	157			
530.63	2.1	160			
530.64	2.1	164			
530.65	2.1	167			

## Wolf Center - SWALES 10-2023

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

Buck Run 24-hr S1 10-yr Rainfall=5.08"

Printed 10/20/2023

Page 23

### Summary for Reach SWALE 5:

Inflow Area = 1.763 ac, 0.00% Impervious, Inflow Depth = 2.13" for 10-yr event  
Inflow = 3.2 cfs @ 12.12 hrs, Volume= 0.314 af  
Outflow = 3.1 cfs @ 12.13 hrs, Volume= 0.314 af, Atten= 1%, Lag= 0.8 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs / 3

Max. Velocity= 2.94 fps, Min. Travel Time= 0.8 min

Avg. Velocity = 1.04 fps, Avg. Travel Time= 2.4 min

Peak Storage= 159 cf @ 12.13 hrs

Average Depth at Peak Storage= 0.38'

Bank-Full Depth= 1.00' Flow Area= 4.0 sf, Capacity= 19.8 cfs

2.00' x 1.00' deep channel, n= 0.069 Riprap, 6-inch

Side Slope Z-value= 2.0 '/' Top Width= 6.00'


Length= 150.0' Slope= 0.1000 '/'

Inlet Invert= 483.00', Outlet Invert= 468.00'



### Reach SWALE 5:

#### Hydrograph





**Wolf Center - SWALES 10-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 10-yr Rainfall=5.08"*

Printed 10/20/2023

Page 24

**Stage-Area-Storage for Reach SWALE 5:**

Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)	Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)
483.00	0.0	0	483.66	2.2	329
483.01	0.0	3	483.67	2.2	336
483.02	0.0	6	483.68	2.3	343
483.03	0.1	9	483.69	2.3	350
483.04	0.1	12	483.70	2.4	357
483.05	0.1	16	483.71	2.4	364
483.06	0.1	19	483.72	2.5	372
483.07	0.1	22	483.73	2.5	379
483.08	0.2	26	483.74	2.6	386
483.09	0.2	29	483.75	2.6	394
483.10	0.2	33	483.76	2.7	401
483.11	0.2	37	483.77	2.7	409
483.12	0.3	40	483.78	2.8	417
483.13	0.3	44	483.79	2.8	424
483.14	0.3	48	483.80	2.9	432
483.15	0.3	52	483.81	2.9	440
483.16	0.4	56	483.82	3.0	448
483.17	0.4	60	483.83	3.0	456
483.18	0.4	64	483.84	3.1	464
483.19	0.5	68	483.85	3.1	472
483.20	0.5	72	483.86	3.2	480
483.21	0.5	76	483.87	3.3	488
483.22	0.5	81	483.88	3.3	496
483.23	0.6	85	483.89	3.4	505
483.24	0.6	89	483.90	3.4	513
483.25	0.6	94	483.91	3.5	521
483.26	0.7	98	483.92	3.5	530
483.27	0.7	103	483.93	3.6	538
483.28	0.7	108	483.94	3.6	547
483.29	0.7	112	483.95	3.7	556
483.30	0.8	117	483.96	3.8	564
483.31	0.8	122	483.97	3.8	573
483.32	0.8	127	483.98	3.9	582
483.33	0.9	132	483.99	3.9	591
483.34	0.9	137	484.00	<b>4.0</b>	<b>600</b>
483.35	0.9	142			
483.36	1.0	147			
483.37	1.0	152			
483.38	1.0	157			
483.39	1.1	163			
483.40	1.1	168			
483.41	1.2	173			
483.42	1.2	179			
483.43	1.2	184			
483.44	1.3	190			
483.45	1.3	196			
483.46	1.3	201			
483.47	1.4	207			
483.48	1.4	213			
483.49	1.5	219			
483.50	1.5	225			
483.51	1.5	231			
483.52	1.6	237			
483.53	1.6	243			
483.54	1.7	249			
483.55	1.7	256			
483.56	1.7	262			
483.57	1.8	268			
483.58	1.8	275			
483.59	1.9	281			
483.60	1.9	288			
483.61	2.0	295			
483.62	2.0	301			
483.63	2.1	308			
483.64	2.1	315			
483.65	2.1	322			

**Summary for Reach SWALE 6:**

Inflow Area = 1.569 ac, 0.00% Impervious, Inflow Depth = 2.10" for 10-yr event  
Inflow = 2.6 cfs @ 12.18 hrs, Volume= 0.274 af  
Outflow = 2.6 cfs @ 12.18 hrs, Volume= 0.274 af, Atten= 0%, Lag= 0.4 min

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs / 3

Max. Velocity= 3.31 fps, Min. Travel Time= 0.5 min

Avg. Velocity= 1.20 fps, Avg. Travel Time= 1.3 min

Peak Storage= 69 cf @ 12.18 hrs

Average Depth at Peak Storage= 0.30'


Bank-Full Depth= 1.00' Flow Area= 4.0 sf, Capacity= 25.5 cfs

2.00' x 1.00' deep channel, n= 0.069 Riprap, 6-inch

Side Slope Z-value= 2.0 '/' Top Width= 6.00'

Length= 90.0' Slope= 0.1667 '/'

Inlet Invert= 483.00', Outlet Invert= 468.00'

**Reach SWALE 6:****Hydrograph**

**Wolf Center - SWALES 10-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 10-yr Rainfall=5.08"*

Printed 10/20/2023

Page 26

**Stage-Area-Storage for Reach SWALE 6:**

Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)	Elevation (feet)	End-Area (sq-ft)	Storage (cubic-feet)
483.00	0.0	0	483.66	2.2	197
483.01	0.0	2	483.67	2.2	201
483.02	0.0	4	483.68	2.3	206
483.03	0.1	6	483.69	2.3	210
483.04	0.1	7	483.70	2.4	214
483.05	0.1	9	483.71	2.4	219
483.06	0.1	11	483.72	2.5	223
483.07	0.1	13	483.73	2.5	227
483.08	0.2	16	483.74	2.6	232
483.09	0.2	18	483.75	2.6	236
483.10	0.2	20	483.76	2.7	241
483.11	0.2	22	483.77	2.7	245
483.12	0.3	24	483.78	2.8	250
483.13	0.3	26	483.79	2.8	255
483.14	0.3	29	483.80	2.9	259
483.15	0.3	31	483.81	2.9	264
483.16	0.4	33	483.82	3.0	269
483.17	0.4	36	483.83	3.0	273
483.18	0.4	38	483.84	3.1	278
483.19	0.5	41	483.85	3.1	283
483.20	0.5	43	483.86	3.2	288
483.21	0.5	46	483.87	3.3	293
483.22	0.5	48	483.88	3.3	298
483.23	0.6	51	483.89	3.4	303
483.24	0.6	54	483.90	3.4	308
483.25	0.6	56	483.91	3.5	313
483.26	0.7	59	483.92	3.5	318
483.27	0.7	62	483.93	3.6	323
483.28	0.7	65	483.94	3.6	328
483.29	0.7	67	483.95	3.7	333
483.30	0.8	70	483.96	3.8	339
483.31	0.8	73	483.97	3.8	344
483.32	0.8	76	483.98	3.9	349
483.33	0.9	79	483.99	3.9	355
483.34	0.9	82	484.00	<b>4.0</b>	<b>360</b>
483.35	0.9	85			
483.36	1.0	88			
483.37	1.0	91			
483.38	1.0	94			
483.39	1.1	98			
483.40	1.1	101			
483.41	1.2	104			
483.42	1.2	107			
483.43	1.2	111			
483.44	1.3	114			
483.45	1.3	117			
483.46	1.3	121			
483.47	1.4	124			
483.48	1.4	128			
483.49	1.5	131			
483.50	1.5	135			
483.51	1.5	139			
483.52	1.6	142			
483.53	1.6	146			
483.54	1.7	150			
483.55	1.7	153			
483.56	1.7	157			
483.57	1.8	161			
483.58	1.8	165			
483.59	1.9	169			
483.60	1.9	173			
483.61	2.0	177			
483.62	2.0	181			
483.63	2.1	185			
483.64	2.1	189			
483.65	2.1	193			

### Summary for Pond CB 17: CB 17

Inflow Area = 2.372 ac, 0.00% Impervious, Inflow Depth = 2.28" for 10-yr event  
 Inflow = 3.1 cfs @ 12.29 hrs, Volume= 0.452 af  
 Outflow = 3.1 cfs @ 12.29 hrs, Volume= 0.452 af, Atten= 0%, Lag= 0.0 min  
 Primary = 3.1 cfs @ 12.29 hrs, Volume= 0.452 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs / 3  
 Peak Elev= 511.68' @ 12.29 hrs Surf.Area= 31 sf Storage= 4 cf

Plug-Flow detention time= 0.0 min calculated for 0.451 af (100% of inflow)  
 Center-of-Mass det. time= 0.0 min ( 885.3 - 885.3 )

Volume	Invert	Avail.Storage	Storage Description
#1	511.50'	20 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)

Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
511.50	10	0	0
512.00	70	20	20

Device	Routing	Invert	Outlet Devices
#1	Primary	505.39'	<b>15.0" Round Culvert</b> L= 56.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 505.39' / 500.95' S= 0.0793 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 1.23 sf
#2	Device 1	511.50'	<b>30.0" x 48.0" Horiz. Orifice/Grate</b> C= 0.600 Limited to weir flow at low heads


**Primary OutFlow** Max=3.1 cfs @ 12.29 hrs HW=511.68' TW=499.37' (Dynamic Tailwater)

1=Culvert (Passes 3.1 cfs of 14.1 cfs potential flow)

2=Orifice/Grate (Weir Controls 3.1 cfs @ 1.37 fps)

### Pond CB 17: CB 17

#### Hydrograph



**Wolf Center - SWALES 10-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 10-yr Rainfall=5.08"*

Printed 10/20/2023

Page 28

**Stage-Area-Storage for Pond CB 17: CB 17**

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
511.50	10	0
511.51	11	0
511.52	12	0
511.53	14	0
511.54	15	0
511.55	16	1
511.56	17	1
511.57	18	1
511.58	20	1
511.59	21	1
511.60	22	2
511.61	23	2
511.62	24	2
511.63	26	2
511.64	27	3
511.65	28	3
511.66	29	3
511.67	30	3
511.68	32	4
511.69	33	4
511.70	34	4
511.71	35	5
511.72	36	5
511.73	38	5
511.74	39	6
511.75	40	6
511.76	41	7
511.77	42	7
511.78	44	8
511.79	45	8
511.80	46	8
511.81	47	9
511.82	48	9
511.83	50	10
511.84	51	10
511.85	52	11
511.86	53	11
511.87	54	12
511.88	56	12
511.89	57	13
511.90	58	14
511.91	59	14
511.92	60	15
511.93	62	15
511.94	63	16
511.95	64	17
511.96	65	17
511.97	66	18
511.98	68	19
511.99	69	19
512.00	<b>70</b>	<b>20</b>



**Wolf Center - SWALES 10-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

Buck Run 24-hr S1 10-yr Rainfall=5.08"

Printed 10/20/2023

Page 29

**Summary for Pond CB 22: CB 22**

Inflow Area = 1.512 ac, 0.00% Impervious, Inflow Depth = 2.18" for 10-yr event  
 Inflow = 2.5 cfs @ 12.19 hrs, Volume= 0.274 af  
 Outflow = 2.5 cfs @ 12.19 hrs, Volume= 0.274 af, Atten= 0%, Lag= 0.0 min  
 Primary = 2.5 cfs @ 12.19 hrs, Volume= 0.274 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs / 3  
 Peak Elev= 527.65' @ 12.19 hrs Surf.Area= 59 sf Storage= 5 cf

Plug-Flow detention time= 0.0 min calculated for 0.274 af (100% of inflow)  
 Center-of-Mass det. time= 0.0 min ( 878.4 - 878.3 )

Volume	Invert	Avail.Storage	Storage Description
#1	527.50'	46 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)


Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
527.50	10	0	0
528.00	173	46	46

Device	Routing	Invert	Outlet Devices
#1	Primary	519.80'	<b>12.0" Round Culvert</b> L= 46.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 519.80' / 515.54' S= 0.0926 ' / ' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.79 sf
#2	Device 1	527.50'	<b>30.0" x 48.0" Horiz. Orifice/Grate</b> C= 0.600 Limited to weir flow at low heads

**Primary OutFlow** Max=2.5 cfs @ 12.19 hrs HW=527.65' TW=499.42' (Dynamic Tailwater)

1=Culvert (Passes 2.5 cfs of 10.3 cfs potential flow)

2=Orifice/Grate (Weir Controls 2.5 cfs @ 1.27 fps)

**Pond CB 22: CB 22****Hydrograph**

**Wolf Center - SWALES 10-2023***Buck Run 24-hr S1 10-yr Rainfall=5.08"*

Prepared by Bibbo Associates, llp.

Printed 10/20/2023

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

Page 30

**Stage-Area-Storage for Pond CB 22: CB 22**

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
527.50	10	0
527.51	13	0
527.52	17	0
527.53	20	0
527.54	23	1
527.55	26	1
527.56	30	1
527.57	33	1
527.58	36	2
527.59	39	2
527.60	43	3
527.61	46	3
527.62	49	4
527.63	52	4
527.64	56	5
527.65	59	5
527.66	62	6
527.67	65	6
527.68	69	7
527.69	72	8
527.70	75	9
527.71	78	9
527.72	82	10
527.73	85	11
527.74	88	12
527.75	92	13
527.76	95	14
527.77	98	15
527.78	101	16
527.79	105	17
527.80	108	18
527.81	111	19
527.82	114	20
527.83	118	21
527.84	121	22
527.85	124	23
527.86	127	25
527.87	131	26
527.88	134	27
527.89	137	29
527.90	140	30
527.91	144	32
527.92	147	33
527.93	150	34
527.94	153	36
527.95	157	38
527.96	160	39
527.97	163	41
527.98	166	42
527.99	170	44
528.00	<b>173</b>	<b>46</b>

**Wolf Center - SWALES 10-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

Buck Run 24-hr S1 10-yr Rainfall=5.08"

Printed 10/20/2023

Page 31

**Summary for Pond CB 9: CB 9**

Inflow Area = 5.856 ac, 0.19% Impervious, Inflow Depth = 2.22" for 10-yr event  
 Inflow = 8.6 cfs @ 12.18 hrs, Volume= 1.083 af  
 Outflow = 8.6 cfs @ 12.18 hrs, Volume= 1.083 af, Atten= 0%, Lag= 0.1 min  
 Primary = 8.6 cfs @ 12.18 hrs, Volume= 1.083 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs / 3  
 Peak Elev= 467.84' @ 12.18 hrs Surf.Area= 90 sf Storage= 17 cf

Plug-Flow detention time= 0.0 min calculated for 1.082 af (100% of inflow)  
 Center-of-Mass det. time= 0.0 min ( 880.9 - 880.8 )

Volume	Invert	Avail.Storage	Storage Description
#1	467.50'	220 cf	<b>Custom Stage Data (Prismatic)</b> Listed below (Recalc)


Elevation (feet)	Surf.Area (sq-ft)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)
467.50	10	0	0
468.00	127	34	34
469.00	244	186	220

Device	Routing	Invert	Outlet Devices
#1	Primary	463.50'	<b>15.0" Round Culvert</b> L= 80.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 463.50' / 456.00' S= 0.0938 ' / Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 1.23 sf
#2	Device 1	467.50'	<b>30.0" x 48.0" Horiz. Orifice/Grate</b> C= 0.600 Limited to weir flow at low heads

**Primary OutFlow** Max=8.5 cfs @ 12.18 hrs HW=467.84' (Free Discharge)

1=Culvert (Passes 8.5 cfs of 11.4 cfs potential flow)

2=Orifice/Grate (Weir Controls 8.5 cfs @ 1.91 fps)

**Pond CB 9: CB 9****Hydrograph**

**Wolf Center - SWALES 10-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 10-yr Rainfall=5.08"*

Printed 10/20/2023

Page 32

**Stage-Area-Storage for Pond CB 9: CB 9**

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
467.50	10	0	468.82	223	178
467.52	15	0	468.84	225	182
467.54	19	1	468.86	228	187
467.56	24	1	468.88	230	191
467.58	29	2	468.90	232	196
467.60	33	2	468.92	235	201
467.62	38	3	468.94	237	205
467.64	43	4	468.96	239	210
467.66	47	5	468.98	242	215
467.68	52	6	469.00	<b>244</b>	<b>220</b>
467.70	57	7			
467.72	61	8			
467.74	66	9			
467.76	71	11			
467.78	76	12			
467.80	80	14			
467.82	85	15			
467.84	90	17			
467.86	94	19			
467.88	99	21			
467.90	104	23			
467.92	108	25			
467.94	113	27			
467.96	118	29			
467.98	122	32			
468.00	127	34			
468.02	129	37			
468.04	132	39			
468.06	134	42			
468.08	136	45			
468.10	139	48			
468.12	141	50			
468.14	143	53			
468.16	146	56			
468.18	148	59			
468.20	150	62			
468.22	153	65			
468.24	155	68			
468.26	157	71			
468.28	160	74			
468.30	162	78			
468.32	164	81			
468.34	167	84			
468.36	169	88			
468.38	171	91			
468.40	174	94			
468.42	176	98			
468.44	178	101			
468.46	181	105			
468.48	183	109			
468.50	186	112			
468.52	188	116			
468.54	190	120			
468.56	193	124			
468.58	195	128			
468.60	197	132			
468.62	200	135			
468.64	202	139			
468.66	204	144			
468.68	207	148			
468.70	209	152			
468.72	211	156			
468.74	214	160			
468.76	216	165			
468.78	218	169			
468.80	221	173			

### Summary for Pond DMH 6: DMH 6

Inflow Area = 3.884 ac, 0.00% Impervious, Inflow Depth = 2.24" for 10-yr event  
 Inflow = 5.5 cfs @ 12.22 hrs, Volume= 0.726 af  
 Outflow = 5.5 cfs @ 12.22 hrs, Volume= 0.726 af, Atten= 0%, Lag= 0.0 min  
 Primary = 5.5 cfs @ 12.22 hrs, Volume= 0.726 af


Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs / 3  
 Peak Elev= 499.45' @ 12.22 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	497.96'	<b>15.0" Round Culvert</b> L= 127.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 497.96' / 484.06' S= 0.1094 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 1.23 sf

**Primary OutFlow** Max=5.4 cfs @ 12.22 hrs HW=499.44' TW=484.48' (Dynamic Tailwater)  
 ↑ **1=Culvert** (Inlet Controls 5.4 cfs @ 4.44 fps)

### Pond DMH 6: DMH 6

#### Hydrograph





**Wolf Center - SWALES 10-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 10-yr Rainfall=5.08"*

Printed 10/20/2023

Page 34

**Stage-Area-Storage for Pond DMH 6: DMH 6**

Elevation (feet)	Storage (cubic-feet)	Elevation (feet)	Storage (cubic-feet)	Elevation (feet)	Storage (cubic-feet)
497.96	0	498.62	0	499.28	0
497.97	0	498.63	0	499.29	0
497.98	0	498.64	0	499.30	0
497.99	0	498.65	0	499.31	0
498.00	0	498.66	0	499.32	0
498.01	0	498.67	0	499.33	0
498.02	0	498.68	0	499.34	0
498.03	0	498.69	0	499.35	0
498.04	0	498.70	0	499.36	0
498.05	0	498.71	0	499.37	0
498.06	0	498.72	0	499.38	0
498.07	0	498.73	0	499.39	0
498.08	0	498.74	0	499.40	0
498.09	0	498.75	0	499.41	0
498.10	0	498.76	0	499.42	0
498.11	0	498.77	0	499.43	0
498.12	0	498.78	0	499.44	0
498.13	0	498.79	0	499.45	0
498.14	0	498.80	0		
498.15	0	498.81	0		
498.16	0	498.82	0		
498.17	0	498.83	0		
498.18	0	498.84	0		
498.19	0	498.85	0		
498.20	0	498.86	0		
498.21	0	498.87	0		
498.22	0	498.88	0		
498.23	0	498.89	0		
498.24	0	498.90	0		
498.25	0	498.91	0		
498.26	0	498.92	0		
498.27	0	498.93	0		
498.28	0	498.94	0		
498.29	0	498.95	0		
498.30	0	498.96	0		
498.31	0	498.97	0		
498.32	0	498.98	0		
498.33	0	498.99	0		
498.34	0	499.00	0		
498.35	0	499.01	0		
498.36	0	499.02	0		
498.37	0	499.03	0		
498.38	0	499.04	0		
498.39	0	499.05	0		
498.40	0	499.06	0		
498.41	0	499.07	0		
498.42	0	499.08	0		
498.43	0	499.09	0		
498.44	0	499.10	0		
498.45	0	499.11	0		
498.46	0	499.12	0		
498.47	0	499.13	0		
498.48	0	499.14	0		
498.49	0	499.15	0		
498.50	0	499.16	0		
498.51	0	499.17	0		
498.52	0	499.18	0		
498.53	0	499.19	0		
498.54	0	499.20	0		
498.55	0	499.21	0		
498.56	0	499.22	0		
498.57	0	499.23	0		
498.58	0	499.24	0		
498.59	0	499.25	0		
498.60	0	499.26	0		
498.61	0	499.27	0		

### Summary for Pond DS1.3: Diversion Structure 1.3

Inflow Area = 0.046 ac, 100.00% Impervious, Inflow Depth = 4.84" for 10-yr event  
 Inflow = 0.2 cfs @ 12.04 hrs, Volume= 0.019 af  
 Outflow = 0.2 cfs @ 12.04 hrs, Volume= 0.019 af, Atten= 0%, Lag= 0.0 min  
 Primary = 0.2 cfs @ 12.04 hrs, Volume= 0.019 af  
 Secondary = 0.0 cfs @ 0.00 hrs, Volume= 0.000 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs / 3

Peak Elev= 593.68' @ 12.08 hrs

Device	Routing	Invert	Outlet Devices
#1	Primary	593.10'	<b>4.0" Round Culvert</b> L= 6.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 593.10' / 593.00' S= 0.0167 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.09 sf
#2	Secondary	595.20'	<b>8.0" Round Culvert</b> L= 154.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 595.20' / 590.00' S= 0.0338 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 0.35 sf

**Primary OutFlow** Max=0.2 cfs @ 12.04 hrs HW=593.63' TW=593.35' (Dynamic Tailwater)


↑**1=Culvert** (Inlet Controls 0.2 cfs @ 2.55 fps)

**Secondary OutFlow** Max=0.0 cfs @ 0.00 hrs HW=593.10' TW=594.50' (Dynamic Tailwater)

↑**2=Culvert** ( Controls 0.0 cfs)

### Pond DS1.3: Diversion Structure 1.3

#### Hydrograph



**Wolf Center - SWALES 10-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 10-yr Rainfall=5.08"*

Printed 10/20/2023

Page 36

**Stage-Area-Storage for Pond DS1.3: Diversion Structure 1.3**

Elevation (feet)	Storage (cubic-feet)	Elevation (feet)	Storage (cubic-feet)	Elevation (feet)	Storage (cubic-feet)
593.10	0	594.42	0	595.74	0
593.12	0	594.44	0	595.76	0
593.14	0	594.46	0	595.78	0
593.16	0	594.48	0	595.80	0
593.18	0	594.50	0	595.82	0
593.20	0	594.52	0	595.84	0
593.22	0	594.54	0	595.86	0
593.24	0	594.56	0		
593.26	0	594.58	0		
593.28	0	594.60	0		
593.30	0	594.62	0		
593.32	0	594.64	0		
593.34	0	594.66	0		
593.36	0	594.68	0		
593.38	0	594.70	0		
593.40	0	594.72	0		
593.42	0	594.74	0		
593.44	0	594.76	0		
593.46	0	594.78	0		
593.48	0	594.80	0		
593.50	0	594.82	0		
593.52	0	594.84	0		
593.54	0	594.86	0		
593.56	0	594.88	0		
593.58	0	594.90	0		
593.60	0	594.92	0		
593.62	0	594.94	0		
593.64	0	594.96	0		
593.66	0	594.98	0		
593.68	0	595.00	0		
593.70	0	595.02	0		
593.72	0	595.04	0		
593.74	0	595.06	0		
593.76	0	595.08	0		
593.78	0	595.10	0		
593.80	0	595.12	0		
593.82	0	595.14	0		
593.84	0	595.16	0		
593.86	0	595.18	0		
593.88	0	595.20	0		
593.90	0	595.22	0		
593.92	0	595.24	0		
593.94	0	595.26	0		
593.96	0	595.28	0		
593.98	0	595.30	0		
594.00	0	595.32	0		
594.02	0	595.34	0		
594.04	0	595.36	0		
594.06	0	595.38	0		
594.08	0	595.40	0		
594.10	0	595.42	0		
594.12	0	595.44	0		
594.14	0	595.46	0		
594.16	0	595.48	0		
594.18	0	595.50	0		
594.20	0	595.52	0		
594.22	0	595.54	0		
594.24	0	595.56	0		
594.26	0	595.58	0		
594.28	0	595.60	0		
594.30	0	595.62	0		
594.32	0	595.64	0		
594.34	0	595.66	0		
594.36	0	595.68	0		
594.38	0	595.70	0		
594.40	0	595.72	0		

### Summary for Pond INF 1.3: Infiltration System 1.3

Inflow Area = 0.046 ac, 100.00% Impervious, Inflow Depth = 4.84" for 10-yr event  
 Inflow = 0.2 cfs @ 12.04 hrs, Volume= 0.019 af  
 Outflow = 0.1 cfs @ 12.00 hrs, Volume= 0.019 af, Atten= 60%, Lag= 0.0 min  
 Discarded = 0.1 cfs @ 12.00 hrs, Volume= 0.019 af

Routing by Dyn-Stor-Ind method, Time Span= 0.00-72.00 hrs, dt= 0.05 hrs / 3  
 Peak Elev= 593.58' @ 12.20 hrs Surf.Area= 0.006 ac Storage= 0.002 af

Plug-Flow detention time= 4.0 min calculated for 0.019 af (100% of inflow)  
 Center-of-Mass det. time= 4.0 min ( 752.8 - 748.8 )

Volume	Invert	Avail.Storage	Storage Description
#1A	593.00'	0.006 af	<b>16.00'W x 17.50'L x 3.54'H Field A</b> 0.023 af Overall - 0.008 af Embedded = 0.015 af x 40.0% Voids
#2A	593.50'	0.008 af	<b>Cultec R-330XLHD x 6 Inside #1</b> Effective Size= 47.8"W x 30.0"H => 7.45 sf x 7.00'L = 52.2 cf Overall Size= 52.0"W x 30.5"H x 8.50'L with 1.50' Overlap Row Length Adjustment= +1.50' x 7.45 sf x 3 rows
			0.014 af Total Available Storage

Storage Group A created with Chamber Wizard


Device	Routing	Invert	Outlet Devices
#1	Discarded	593.00'	<b>14.000 in/hr Exfiltration over Horizontal area</b> Phase-In= 0.10'

**Discarded OutFlow** Max=0.1 cfs @ 12.00 hrs HW=593.20' (Free Discharge)

↳ **1=Exfiltration** (Exfiltration Controls 0.1 cfs)

### Pond INF 1.3: Infiltration System 1.3

#### Hydrograph



**Wolf Center - SWALES 10-2023**

Prepared by Bibbo Associates, llp.

HydroCAD® 10.00-24 s/n 02226 © 2018 HydroCAD Software Solutions LLC

*Buck Run 24-hr S1 10-yr Rainfall=5.08"*

Printed 10/20/2023

Page 38

**Stage-Area-Storage for Pond INF 1.3: Infiltration System 1.3**

Elevation (feet)	Horizontal (acres)	Storage (acre-feet)	Elevation (feet)	Horizontal (acres)	Storage (acre-feet)	Elevation (feet)	Horizontal (acres)	Storage (acre-feet)
593.00	<b>0.006</b>	0.000	594.32	0.006	0.005	595.64	0.006	0.011
593.02	0.006	0.000	594.34	0.006	0.006	595.66	0.006	0.011
593.04	0.006	0.000	594.36	0.006	0.006	595.68	0.006	0.011
593.06	0.006	0.000	594.38	0.006	0.006	595.70	0.006	0.012
593.08	0.006	0.000	594.40	0.006	0.006	595.72	0.006	0.012
593.10	0.006	0.000	594.42	0.006	0.006	595.74	0.006	0.012
593.12	0.006	0.000	594.44	0.006	0.006	595.76	0.006	0.012
593.14	0.006	0.000	594.46	0.006	0.006	595.78	0.006	0.012
593.16	0.006	0.000	594.48	0.006	0.006	595.80	0.006	0.012
593.18	0.006	0.000	594.50	0.006	0.006	595.82	0.006	0.012
593.20	0.006	0.001	594.52	0.006	0.006	595.84	0.006	0.012
593.22	0.006	0.001	594.54	0.006	0.006	595.86	0.006	0.012
593.24	0.006	0.001	594.56	0.006	0.007	595.88	0.006	0.012
593.26	0.006	0.001	594.58	0.006	0.007	595.90	0.006	0.012
593.28	0.006	0.001	594.60	0.006	0.007	595.92	0.006	0.012
593.30	0.006	0.001	594.62	0.006	0.007	595.94	0.006	0.012
593.32	0.006	0.001	594.64	0.006	0.007	595.96	0.006	0.012
593.34	0.006	0.001	594.66	0.006	0.007	595.98	0.006	0.012
593.36	0.006	0.001	594.68	0.006	0.007	596.00	0.006	0.012
593.38	0.006	0.001	594.70	0.006	0.007	596.02	0.006	0.013
593.40	0.006	0.001	594.72	0.006	0.007	596.04	0.006	0.013
593.42	0.006	0.001	594.74	0.006	0.007	596.06	0.006	0.013
593.44	0.006	0.001	594.76	0.006	0.008	596.08	0.006	0.013
593.46	0.006	0.001	594.78	0.006	0.008	596.10	0.006	0.013
593.48	0.006	0.001	594.80	0.006	0.008	596.12	0.006	0.013
593.50	0.006	0.001	594.82	0.006	0.008	596.14	0.006	0.013
593.52	0.006	0.001	594.84	0.006	0.008	596.16	0.006	0.013
593.54	0.006	0.001	594.86	0.006	0.008	596.18	0.006	0.013
593.56	0.006	0.002	594.88	0.006	0.008	596.20	0.006	0.013
593.58	0.006	0.002	594.90	0.006	0.008	596.22	0.006	0.013
593.60	0.006	0.002	594.92	0.006	0.008	596.24	0.006	0.013
593.62	0.006	0.002	594.94	0.006	0.008	596.26	0.006	0.013
593.64	0.006	0.002	594.96	0.006	0.008	596.28	0.006	0.013
593.66	0.006	0.002	594.98	0.006	0.009	596.30	0.006	0.013
593.68	0.006	0.002	595.00	0.006	0.009	596.32	0.006	0.013
593.70	0.006	0.002	595.02	0.006	0.009	596.34	0.006	0.013
593.72	0.006	0.002	595.04	0.006	0.009	596.36	0.006	0.013
593.74	0.006	0.003	595.06	0.006	0.009	596.38	0.006	0.013
593.76	0.006	0.003	595.08	0.006	0.009	596.40	0.006	0.014
593.78	0.006	0.003	595.10	0.006	0.009	596.42	0.006	0.014
593.80	0.006	0.003	595.12	0.006	0.009	596.44	0.006	0.014
593.82	0.006	0.003	595.14	0.006	0.009	596.46	0.006	0.014
593.84	0.006	0.003	595.16	0.006	0.009	596.48	0.006	0.014
593.86	0.006	0.003	595.18	0.006	0.009	596.50	0.006	0.014
593.88	0.006	0.003	595.20	0.006	0.010	596.52	0.006	0.014
593.90	0.006	0.003	595.22	0.006	0.010	596.54	0.006	<b>0.014</b>
593.92	0.006	0.003	595.24	0.006	0.010			
593.94	0.006	0.004	595.26	0.006	0.010			
593.96	0.006	0.004	595.28	0.006	0.010			
593.98	0.006	0.004	595.30	0.006	0.010			
594.00	0.006	0.004	595.32	0.006	0.010			
594.02	0.006	0.004	595.34	0.006	0.010			
594.04	0.006	0.004	595.36	0.006	0.010			
594.06	0.006	0.004	595.38	0.006	0.010			
594.08	0.006	0.004	595.40	0.006	0.010			
594.10	0.006	0.004	595.42	0.006	0.010			
594.12	0.006	0.004	595.44	0.006	0.011			
594.14	0.006	0.005	595.46	0.006	0.011			
594.16	0.006	0.005	595.48	0.006	0.011			
594.18	0.006	0.005	595.50	0.006	0.011			
594.20	0.006	0.005	595.52	0.006	0.011			
594.22	0.006	0.005	595.54	0.006	0.011			
594.24	0.006	0.005	595.56	0.006	0.011			
594.26	0.006	0.005	595.58	0.006	0.011			
594.28	0.006	0.005	595.60	0.006	0.011			
594.30	0.006	0.005	595.62	0.006	0.011			



## Appendix M:

### Stormwater Maintenance and Access Agreement

**SCHEDULE "A" TO STORMWATER CONTROL FACILITY  
MAINTENANCE AND ACCESS AGREEMENT  
BY AND BETWEEN  
THE WOLF CENTER AND THE TOWN OF LEWISBORO**

As used herein, "Short Term Maintenance Requirements" are those stormwater control measures to be undertaken during such time as the construction activities. "Long Term Maintenance Requirements" are those stormwater control measures to be undertaken following the completion of construction. Maintenance and inspections shall be performed in accordance with the SWPPP and as described herein.

**Maintenance and Inspection Requirements:**

Maintenance and inspections are required in order to ensure the stormwater and erosion and sediment control practices are acting as designed. Inspections will be performed twice every 7 calendar days and/or significant rainfall during construction. Upon completion of construction and the subsequent filing of the Notice of Termination, maintenance and inspections are expected to be minimal. Temporary and permanent maintenance and inspection requirements are further discussed below. Proper maintenance and inspections will ensure the longevity and effectiveness of the stormwater pollution prevention plan, and erosion and sediment control plan.

**Short Term Maintenance and Inspection Requirements:**

The Developer will be responsible for maintenance of all erosion controls during construction.

Inspections performed during construction should verify all practices are functioning properly, correctly maintained, and accumulated sediment is removed from all control structures. The inspector must also examine the site for any evidence of soil erosion, turbid discharge at all outfalls, and the potential for soil and mud to be transported on the public roadway at the site entrance. Discussed below are specific maintenance and inspection requirements for the temporary practices to be employed at the site.

During construction, the silt fence should be inspected to ensure correct installation. In addition, any accumulated sediment resulting in "bulges" in the silt fence should be removed. Any damaged or torn silt fence should be replaced.

The construction entrance should be checked to ensure no sediment is being deposited onto

the public roadway. Should sediment be observed, it should be removed from the street, and the stone in the construction entrance replaced.

Stormwater Treatment Area monitoring and maintenance will be the responsibility of the developer throughout the proposed operations. As a minimum, Bibbo Associates, LLP recommends the following maintenance:

Inspection - Inspections are to be performed by a “Qualified Inspector” basis of twice every 7 calendar days or following a significant rainfall event, consistent with the SPDES General Permit. A copy of the “NYSDEC Construction Site Log Book” shall be used as a template for the weekly site inspection reports. Following construction inspections will be required on an annual basis as a minimum and following major storm events to check for:

- a. Evidence of clogging of the outlet structure
- b. Accumulation of sediment at inlets and around the outlet structure
- c. Erosion of the berm, slope and other areas contributing to the basin
- d. Condition of the emergency spillway

Repairs, as needed, shall be undertaken to restore facility to proper function. In the case of infiltration basin clogging, to allow for any necessary maintenance a submersible pump shall be utilized and impounded water shall be pumped through the outlet structure’s primary culvert to the proposed rock outlet protection. (See also Sediment Removal below.)

Mowing – The berm crest and slopes, as well as the basin bottom should be mowed at least twice a year to discourage woody growth.

Debris and Litter Control - Removal of debris and litter should be undertaken during the mowing operation. Particular attention should be given to removal of debris and branches around the outlet structure.

Erosion Control - Eroding soil on the berm, slope, or other contributory areas noted during inspections should be stabilized immediately with topsoil replacement, seeding and mulching. Any riprap dislodged on the emergency spillway should be repositioned.

Sediment Removal - Sediment deposition in the temporary sediment trap will need to be removed

in order to maintain the necessary capacity for capturing sediment. The need for sediment removal should be determined during routine inspections and the appropriate equipment and manpower scheduled for the task.

Catch Basin Clean Out - Sediment deposition in the basin can be reduced by regular clean out of catch basin sumps located in the common driveway (*accumulated sediment shall be removed from catch basin if it reaches a level of  $\frac{1}{2}$  the available sump*). More frequent clean out will be necessary during home construction along the common driveway. It will be the developer's responsibility to monitor the accumulation in the sumps and clean out sediment as required.

Hydrodynamic Separator – The Hydrodynamic Separator shall be inspected semiannually for accumulated sediment and to ensure all systems components are functioning properly. Inspection frequency may have to be adjusted based on winter sanding operations. Accumulated sediment shall be removed when it reaches a level of  $\frac{3}{4}$  the available sump. It will be the developer's responsibility to monitor the accumulation in the sumps and clean out sediment as required during home construction.

Stormwater Infiltration Basin - Remove sediment/gross solids from the infiltration surface annually. The vegetative cover needs to be regularly maintained. Grass cover may be mowed and bare areas should be reseeded. Disc, aerate or scrape the basin bottom to restore original cross section and infiltration rate every one to five years. To avoid soil compaction concerns, infiltration areas should not be used for recreational purposes. (Refer to 10.4.3.5 Maintenance of Chapter 10 of the NYSSMDM)

All maintenance and inspection requirements of the NYSDEC Stormwater Management Design Manual "Phase II" August 2010 are adopted by reference into this report. Sample construction and maintenance checklists may be found in the Appendix.

### **Long Term Maintenance and Inspection Requirements:**


Long Term Maintenance requirements are the same as listed above for Short Term Maintenance.



Figure 1:

Pre-development Drainage Basin Plan






**CALL BEFORE YOU DIG 1-800-962-7962**

UNDER THE NY STATE LAW PROTECTING UNDERGROUND FACILITIES, THE FOLLOWING RULES AND REGULATIONS ARE IN EFFECT FOR ALL EXCAVATORS:

- \* THEY MUST CALL FOR A UTILITY STAKE-OUT (2) TWO FULL WORKING DAYS PRIOR TO AN EXCAVATION.
- \* THEY MUST CONFIRM PRECISE LOCATIONS OF UNDERGROUND FACILITIES.
- \* THEY MUST PRESERVE STAKES AND MARKINGS UNTIL NO LONGER NEEDED AT SITE.
- \* THEY MUST CONTACT NON-UFPO MEMBER UTILITY OWNERS FOR STAKE-OUTS.



**DRAINAGE BASIN LEGEND:**

ChC	SOIL TYPE
B	SOIL CLASSIFICATION
---	SOIL BOUNDARY
---	BASIN BOUNDARY
Tc	TIME OF CONCENTRATION PATH (TC)


	<b>PREDEVELOPMENT DRAINAGE BASIN MAP</b>	DATE: 12-29-2020
	<b>WOLF CONSERVATION CENTER</b>	SCALE: 1" = 40'
	7 BUCK RUN, SOUTH SALEM, NY 10690	FILE: L5
	TOWN OF LEWISBORO, WESTCHESTER COUNTY, NY	DSGN / CHIC: MG/RH
	<b>BIBBO ASSOCIATES, LLP</b>	DRN. BY: RH
	293 ROUTE 100 SUITE 203	SHT NO. FIGURE 1
	SONERS, NEW YORK 10690	DWG NO. <b>PRE</b>
TEL. 914 277 5805		



Figure 2:

Post-development Drainage Basin Plan






LEGEND

- EXISTING PROPERTY LINE
- WETLAND BUFFER LINE
- WETLAND BOUNDARY LINE
- EXISTING WOLF ENCLOSURE FENCE
- EXISTING EASEMENT LINE
- EXISTING 2' CONTOUR
- EXISTING 10' CONTOUR
- PROPOSED 2' CONTOUR
- PROPOSED 10' CONTOUR
- PROPOSED RETAINING WALL
- PROPOSED ELECTRIC METER
- PROPOSED TRANSFORMER
- PROPOSED T-TAP
- PROPOSED OVERHEAD ELECTRIC SERVICE
- PROPOSED UNDERGROUND ELECTRIC SERVICE
- PROPOSED ROOF LEADER CONNECTION PIPE
- PROPOSED PVC DR-18 WATERMAIN
- PROPOSED CU WATER SERVICE

DRAINAGE BASIN LEGEND:

- Soil Type: ChC, B
- Soil Classification: B
- Soil Boundary: Dashed line
- Basin Boundary: Red dashed line
- Time of Concentration Path (TC): Blue dashed line



CALL BEFORE YOU DIG 1-800-962-7962

UNDER THE NY STATE LAW PROTECTING UNDERGROUND FACILITIES, THE FOLLOWING RULES AND REGULATIONS ARE IN EFFECT FOR ALL EXCAVATORS:  
\* THEY MUST CALL FOR A UTILITY STAKE-OUT (2) TWO FULL WORKING DAYS PRIOR TO AN EXCAVATION.  
\* THEY MUST CONFIRM PRECISE LOCATIONS OF UNDERGROUND FACILITIES.  
\* THEY MUST PRESERVE STAKES AND MARKINGS UNTIL NO LONGER NEEDED AT SITE.  
\* THEY MUST CONTACT NON-UPFO MEMBER UTILITY OWNERS FOR STAKE-OUTS.

UNAUTHORIZED ALTERATIONS AND ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 2209 (2) OF THE NEW YORK STATE EDUCATION LAW.  
BIBBO ASSOCIATES, LLP  
ALL RIGHTS RESERVED. UNAUTHORIZED REPRODUCTION OR TRANSMISSION IS PROHIBITED.

10-20-23 NYCDEP COMPLETENESS COMMENTS RH/MG		01-16-23 BUILDING DEPARTMENT COMMENTS RH/MG	
04-25-23 PLANNING BOARD SUBMISSION RH/MG		02-07-22 WCHD NYCDEP COMMENTS ZF/ED	
02-07-23 PLANNING BOARD SUBMISSION RH/MG		06-04-21 NYCDEP APPLICATION RH/MG	
DATE:	DESCRIPTION	BY/CK:	DATE:

**POST DEVELOPMENT DRAINAGE BASIN MAP**  
**WOLF CONSERVATION CENTER**  
7 BUCK RUN, SOUTH SALEM, NY 10580  
TOWN OF LEWISBORO, WESTCHESTER COUNTY, NY

**BIBBO ASSOCIATES, LLP**  
283 ROUTE 100 SUITE 203  
SONNERS, NEW YORK 10589  
TEL. 914 277 5805

DATE:	1-31-2019
SCALE:	1" = 40'
FILE:	L5
DSGN / CHK:	MG/RH
DRN. BY:	RH
SHT NO.	FIGURE 2
DWG NO.	POST






Figure 3:  
Redevelopment Map



CALL BEFORE YOU DIG 1-800-962-7962

UNDER THE NY STATE LAW PROTECTING UNDERGROUND FACILITIES,  
THE FOLLOWING RULES AND REGULATIONS ARE IN EFFECT FOR ALL  
EXCAVATORS:  
\* THEY MUST CALL FOR A UTILITY STAKE-OUT (2) TWO FULL WORKING DAYS  
PRIOR TO AN EXCAVATION.  
\* THEY MUST CONFIRM PRECISE LOCATIONS OF UNDERGROUND FACILITIES.  
\* THEY MUST PRESERVE STAKES AND MARKINGS UNTIL NO LONGER NEEDED AT SITE.  
\* THEY MUST CONTACT NON-UPFO MEMBER UTILITY OWNERS FOR STAKE-OUTS.



STORMWATER MITIGATION PLANT SCHEDULE						
TREES (OR APPROVED EQUAL)						
Symbol	Code	Quantity	Scientific Name	Common Name	Size at Planting	Remarks
	AS	15	ACER SACCHARUM	SUGAR MAPLE	2 1/2- 3 IN. CAL.	
	UAP	14	ULMUS AMERICANA 'PRINCETON'	PRINCETON ELM	3-3 1/2 IN. CAL.	

LEGEND	
EXISTING PROPERTY LINE	---
WETLAND BUFFER LINE	---
WETLAND BOUNDARY LINE	---
EXISTING WOLF ENCLOSURE FENCE	x x x
EXISTING EASEMENT LINE	---
EXISTING 2' CONTOUR	---
EXISTING 10' CONTOUR	---
PROPOSED 2' CONTOUR	---
PROPOSED 10' CONTOUR	---
PROPOSED RETAINING WALL	---
PROPOSED ELECTRIC METER	M
PROPOSED TRANSFORMER	T
PROPOSED T-TAP	TT
PROPOSED OVERHEAD ELECTRIC SERVICE	OHW
PROPOSED UNDERGROUND ELECTRIC SERVICE	UG-E

DRAINAGE BASIN LEGEND:	
ChC	SOIL TYPE
B	SOIL CLASSIFICATION
---	SOIL BOUNDARY
---	BASIN BOUNDARY
---	TIME OF CONCENTRATION PATH (TC)

REVISIONS		DATE		DESCRIPTION	
10-20-23	NYCDEP COMPLETENESS COMMENTS	RH/MG	02-07-22	WCHD NYCDEP COMMENTS	ZF/ED
04-25-23	PLANNING BOARD SUBMISSION	RH/MG	06-04-21	NYCDEP APPLICATION	RH/MG
02-07-23	PLANNING BOARD SUBMISSION	RH/MG	04-27-21	PLANNING BOARD SUBMISSION	RH/MG
DATE:	DESCRIPTION	BY/CK	DATE:	DESCRIPTION	BY/CK



	<b>REDEVELOPMENT DRAINAGE BASIN MAP</b> <b>WOLF CONSERVATION CENTER</b> 7 BUCK RUN, SOUTH SALEM, NY 10580 TOWN OF LEWISBORO, WESTCHESTER COUNTY, NY	DATE: 4-24-2020 SCALE: 1" = 40' FILE: L5 DSGN / CHK: MG/RH DRN. BY: RH SHT NO. 1 OF 1 DWG NO. FIGURE 3
	<b>BIBBO ASSOCIATES, LLP</b> 203 ROUTE 100 SUITE 203 SONERS, NEW YORK 10580 TEL. 914 277 5805	




Figure 4:

Swale and Pipe Sizing Basin Map



AREA LEGEND

- TRIBUTARY AREA TO SWALE 1
- TRIBUTARY AREA TO SWALE 2
- TRIBUTARY AREA TO SWALE 3
- TRIBUTARY AREA TO SWALE 4
- TRIBUTARY AREA TO SWALE 5
- TRIBUTARY AREA TO SWALE 6
- OVERLAND TRIBUTARY AREA TO CB 17
- OVERLAND TRIBUTARY AREA TO CB 22
- OVERLAND TRIBUTARY AREA TO DMH 2
- OVERLAND TRIBUTARY AREA TO DMH 3



CALL BEFORE YOU DIG 1-800-962-7962

UNDER THE NY STATE LAW PROTECTING UNDERGROUND FACILITIES, THE FOLLOWING RULES AND REGULATIONS ARE IN EFFECT FOR ALL EXCAVATORS:

- \* THEY MUST CALL FOR A UTILITY STAKE-OUT (2) TWO FULL WORKING DAYS PRIOR TO AN EXCAVATION.
- \* THEY MUST CONFIRM PRECISE LOCATIONS OF UNDERGROUND FACILITIES.
- \* THEY MUST PRESERVE STAKES AND MARKINGS UNTIL NO LONGER NEEDED AT SITE.
- \* THEY MUST CONTACT NON-UPFO MEMBER UTILITY OWNERS FOR STAKE-OUTS.

NOTE: ALL PORTIONS OF EXISTING ROAD WIDENING WITHIN 100' LIMITING DISTANCE OF NYSDEC WETLAND WILL BE PERFORMED ON THE SIDE OF THE ROAD FURTHEST FROM THE NYSDEC WETLAND

DETERMINED BY  
OBSERVATION  
BY BETH EVANS, PWS  
9/17/20

150' LOCAL  
WETLAND BUFFER

100' STATE WETLAND  
BUFFER

LEGEND


- EXISTING PROPERTY LINE
- WETLAND BUFFER LINE
- WETLAND BOUNDARY LINE
- EXISTING WOLF ENCLOSURE FENCE
- EXISTING EASEMENT LINE
- EXISTING 2' CONTOUR
- EXISTING 10' CONTOUR
- PROPOSED 2' CONTOUR
- PROPOSED 10' CONTOUR
- PROPOSED RETAINING WALL
- PROPOSED ELECTRIC METER
- PROPOSED TRANSFORMER
- PROPOSED T-TAP
- PROPOSED OVERHEAD ELECTRIC SERVICE
- PROPOSED UNDERGROUND ELECTRIC SERVICE
- PROPOSED ROOF LEADER CONNECTION PIPE
- PROPOSED PVC DR-18 WATERMAIN
- PROPOSED CU WATER SERVICE

DRAINAGE BASIN LEGEND:

- SOIL TYPE
- SOIL CLASSIFICATION
- SOIL BOUNDARY
- BASIN BOUNDARY
- TIME OF CONCENTRATION PATH (TC)

PLAN

GRAPHIC SCALE



UNAUTHORIZED ALTERATIONS AND ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 2005 (2) OF THE NEW YORK STATE EDUCATION LAW.

OWNER: BIBBO ASSOCIATES, LLP  
ALL RIGHTS RESERVED. UNAUTHORIZED REPRODUCTION OR ALTERATION OF ANY PART OF THIS DRAWING IS PROHIBITED.



SWALE SIZING BASIN MAP


WOLF CONSERVATION CENTER  
7 BUCK RUN, SOUTH SALEM, NY 10580  
TOWN OF LEWISBORO, WESTCHESTER COUNTY, NY

**BIBBO ASSOCIATES, LLP**  
203 ROUTE 100 SUITE 203  
SONOMA, NEW YORK 10589  
TEL. 914 277 5805

DATE: 10-18-2023  
SCALE: 1" = 40'  
FILE: L5  
DSGN / CHK: MG/RH  
DRN. BY: RH  
SHT NO. FIGURE 4  
DWG NO. **SW**



# NOTICE OF INTENT



**New York State Department of Environmental Conservation**

## Division of Water

**625 Broadway, 4th Floor**

**Albany, New York 12233-3505**

NYR

--	--	--	--	--	--

(for DEC use only)

**Stormwater Discharges Associated with Construction Activity Under State Pollutant Discharge Elimination System (SPDES) General Permit # GP-0-20-001**

**All sections must be completed unless otherwise noted.** Failure to complete all items may result in this form being returned to you, thereby delaying your coverage under this General Permit. Applicants must read and understand the conditions of the permit and prepare a Stormwater Pollution Prevention Plan prior to submitting this NOI. Applicants are responsible for identifying and obtaining other DEC permits that may be required.

**- IMPORTANT -**

**RETURN THIS FORM TO THE ADDRESS ABOVE**

**OWNER/OPERATOR MUST SIGN FORM**

### Owner/Operator Information

Owner/Operator (Company Name/Private Owner Name/Municipality Name)

[illegible]

Owner/Operator Contact Person Last Name (NOT CONSULTANT)

[illegible]

Owner/Operator Contact Person First Name

[illegible]

Owner/Operator Mailing Address

[illegible]

City

[illegible]

State

--	--

Zip

					-				
--	--	--	--	--	---	--	--	--	--

Phone (Owner/Operator)

			-				-			
--	--	--	---	--	--	--	---	--	--	--

Fax (Owner/Operator)

			-				-			
--	--	--	---	--	--	--	---	--	--	--

Email (Owner/Operator)

[illegible][illegible]

FED TAX ID

		-							
--	--	---	--	--	--	--	--	--	--

(not required for individuals)

## Project Site Information

Project/Site Name

[illegible]

Street Address (NOT P.O. BOX)

[illegible]

Side of Street

☐ North    ☐ South    ☐ East    ☐ West

City/Town/Village (THAT ISSUES BUILDING PERMIT)

[illegible]

State

--	--

Zip

--	--	--	--	--

—

--	--	--	--

County

[illegible]DEC Region

--	--

Name of Nearest Cross Street

[illegible]

Distance to Nearest Cross Street (Feet)

--	--	--	--	--

Project In Relation to Cross Street

☐ North    ☐ South    ☐ East    ☐ West

Tax Map Numbers  
Section-Block-Parcel

[illegible]

## Tax Map Numbers

[illegible]

1. Provide the Geographic Coordinates for the project site. To do this, go to the NYSDEC Stormwater Interactive Map on the DEC website at:

<https://giservices.dec.ny.gov/gis/stormwater/>

Zoom into your Project Location such that you can accurately click on the centroid of your site. Once you have located the centroid of your project site, go to the bottom right hand corner of the map for the X, Y coordinates. Enter the coordinates into the boxes below. For problems with the interactive map use the help function.

X Coordinates (Easting)

-7

--	--	--	--	--	--

Ex. -73.749

Y Coordinates (Northing)

--	--	--	--	--	--	--

Ex. 42.652

2. What is the nature of this construction project?

- New Construction

- Redevelopment with increase in impervious area

- Redevelopment with no increase in impervious area

3. Select the predominant land use for both pre and post development conditions.

**SELECT ONLY ONE CHOICE FOR EACH**

**Pre-Development  
Existing Land Use**

- ☐ FOREST  
☐ PASTURE/OPEN LAND  
☐ CULTIVATED LAND  
☐ SINGLE FAMILY HOME  
☐ SINGLE FAMILY SUBDIVISION  
☐ TOWN HOME RESIDENTIAL  
☐ MULTIFAMILY RESIDENTIAL  
☐ INSTITUTIONAL/SCHOOL  
☐ INDUSTRIAL  
☐ COMMERCIAL  
☐ ROAD/HIGHWAY  
☐ RECREATIONAL/SPORTS FIELD  
☐ BIKE PATH/TRAIL  
☐ LINEAR UTILITY  
☐ PARKING LOT  
☐ OTHER

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

**Post-Development  
Future Land Use**

- ☐ SINGLE FAMILY HOME  
☐ SINGLE FAMILY SUBDIVISION  
☐ TOWN HOME RESIDENTIAL  
☐ MULTIFAMILY RESIDENTIAL  
☐ INSTITUTIONAL/SCHOOL  
☐ INDUSTRIAL  
☐ COMMERCIAL  
☐ MUNICIPAL  
☐ ROAD/HIGHWAY  
☐ RECREATIONAL/SPORTS FIELD  
☐ BIKE PATH/TRAIL  
☐ LINEAR UTILITY (water, sewer, gas, etc.)  
☐ PARKING LOT  
☐ CLEARING/GRADING ONLY  
☐ DEMOLITION, NO REDEVELOPMENT  
☐ WELL DRILLING ACTIVITY \*(Oil, Gas, etc.)  
☐ OTHER

Number of Lots

--	--	--

--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--

**\*Note:** for gas well drilling, non-high volume hydraulic fractured wells only

4. In accordance with the larger common plan of development or sale, enter the total project site area; the total area to be disturbed; existing impervious area to be disturbed (for redevelopment activities); and the future impervious area constructed within the disturbed area. (Round to the nearest tenth of an acre.)

**Total Site  
Area**

					.	
--	--	--	--	--	---	--

**Total Area To  
Be Disturbed**

					.	
--	--	--	--	--	---	--

**Existing Impervious  
Area To Be Disturbed**

					.	
--	--	--	--	--	---	--

**Future Impervious  
Area Within  
Disturbed Area**

					.	
--	--	--	--	--	---	--

5. Do you plan to disturb more than 5 acres of soil at any one time? ☐ Yes ☐ No

6. Indicate the percentage of each Hydrologic Soil Group(HSG) at the site.

**A**  

--	--	--

 %

**B**  

--	--	--

 %

**C**  

--	--	--

 %

**D**  

--	--	--

 %

7. Is this a phased project? ☐ Yes ☐ No

8. Enter the planned start and end dates of the disturbance activities.

**Start Date**

		/			/				
--	--	---	--	--	---	--	--	--	--

**End Date**

		/			/				
--	--	---	--	--	---	--	--	--	--



[illegible]

☐ Wetland / State Jurisdiction On Site (Answer 9b)  
☐ Wetland / State Jurisdiction Off Site  
☐ Wetland / Federal Jurisdiction On Site (Answer 9b)  
☐ Wetland / Federal Jurisdiction Off Site  
☐ Stream / Creek On Site  
☐ Stream / Creek Off Site  
☐ River On Site  
☐ River Off Site  
☐ Lake On Site  
☐ Lake Off Site  
☐ Other Type On Site  
☐ Other Type Off Site

- ☐ Regulatory Map
- ☐ Delineated by Consultant
- ☐ Delineated by Army Corps of Engineers
- ☐ Other (identify)

[illegible][illegible]

11. Is this project located in one of the Watersheds identified in Appendix C of GP-0-20-001? ☐ **Yes** ☐ **No**

If no, skip question 13.

If Yes, what is the acreage to be disturbed?

--	--	--	--	--	--

Page 4 of 14

15. Does the site runoff enter a separate storm sewer system (including roadside drains, swales, ditches, culverts, etc)? ☐ Yes ☐ No ☐ Unknown

- [illegible]

17. Does any runoff from the site enter a sewer classified as a Combined Sewer? ☐ **Yes** ☐ **No** ☐ **Unknown**

18. Will future use of this site be an agricultural property as defined by the NYS Agriculture and Markets Law? ☐ Yes ☐ No

19. Is this property owned by a state authority, state agency, federal government or local government? ☐ Yes ☐ No

20. Is this a remediation project being done under a Department approved work plan? (i.e. CERCLA, RCRA, Voluntary Cleanup Agreement, etc.) ☐ **Yes** ☐ **No**

21. Has the required Erosion and Sediment Control component of the SWPPP been developed in conformance with the current NYS Standards and Specifications for Erosion and Sediment Control (aka Blue Book)? ☐ Yes ☐ No

22. Does this construction activity require the development of a SWPPP that includes the post-construction stormwater management practice component (i.e. Runoff Reduction, Water Quality and Quantity Control practices/techniques)? ☐ **Yes** ☐ **No**
- If No, skip questions 23 and 27-39.**

23. Has the post-construction stormwater management practice component of the SWPPP been developed in conformance with the current NYS Stormwater Management Design Manual? ☐ Yes ☐ No

24. The Stormwater Pollution Prevention Plan (SWPPP) was prepared by:

- ☐ Professional Engineer (P.E.)
- ☐ Soil and Water Conservation District (SWCD)
- ☐ Registered Landscape Architect (R.L.A.)
- ☐ Certified Professional in Erosion and Sediment Control (CPESC)
- ☐ Owner/Operator
- ☐ Other

[illegible]

SWPPP Preparer

[illegible]

Contact Name (Last, Space, First)

[illegible]

Mailing Address

[illegible]

City

[illegible]

State Zip

					-				
--	--	--	--	--	---	--	--	--	--

Phone

--	--	--	--

Fax

			-				-				
--	--	--	---	--	--	--	---	--	--	--	--

Email

[illegible][illegible]

## SWPPP Preparer Certification

I hereby certify that the Stormwater Pollution Prevention Plan (SWPPP) for this project has been prepared in accordance with the terms and conditions of the GP-0-20-001. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of this permit and the laws of the State of New York and could subject me to criminal, civil and/or administrative proceedings.

First Name

[illegible]

MI

--	--

Last Name

[illegible]

Signature

Date \_\_\_\_\_

--	--

/

--	--

/

--	--	--	--

25. Has a construction sequence schedule for the planned management practices been prepared? ☐ Yes ☐ No

☐ Yes      ☐ No

26. Select **all** of the erosion and sediment control practices that will be employed on the project site:

## Temporary Structural

- ☐ Check Dams
- ☐ Construction Road Stabilization
- ☐ Dust Control
- ☐ Earth Dike
- ☐ Level Spreader
- ☐ Perimeter Dike/Swale
- ☐ Pipe Slope Drain
- ☐ Portable Sediment Tank
- ☐ Rock Dam
- ☐ Sediment Basin
- ☐ Sediment Traps
- ☐ Silt Fence
- ☐ Stabilized Construction Entrance
- ☐ Storm Drain Inlet Protection
- ☐ Straw/Hay Bale Dike
- ☐ Temporary Access Waterway Crossing
- ☐ Temporary Stormdrain Diversion
- ☐ Temporary Swale
- ☐ Turbidity Curtain
- ☐ Water bars

## Biotechnical

- Brush Matting
- Wattling

Other

[illegible]

## Vegetative Measures

- ☐ Brush Matting
- ☐ Dune Stabilization
- ☐ Grassed Waterway
- ☐ Mulching
- ☐ Protecting Vegetation
- ☐ Recreation Area Improvement
- ☐ Seeding
- ☐ Sodding
- ☐ Straw/Hay Bale Dike
- ☐ Streambank Protection
- ☐ Temporary Swale
- ☐ Topsoiling
- ☐ Vegetating Waterways

## Permanent Structural

- ☐ Debris Basin
- ☐ Diversion
- ☐ Grade Stabilization Structure
- ☐ Land Grading
- ☐ Lined Waterway (Rock)
- ☐ Paved Channel (Concrete)
- ☐ Paved Flume
- ☐ Retaining Wall
- ☐ Riprap Slope Protection
- ☐ Rock Outlet Protection
- ☐ Streambank Protection

**Post-construction Stormwater Management Practice (SMP) Requirements**

**Important: Completion of Questions 27-39 is not required  
if response to Question 22 is No.**

27. Identify all site planning practices that were used to prepare the final site plan/layout for the project.

- ☐ Preservation of Undisturbed Areas
- ☐ Preservation of Buffers
- ☐ Reduction of Clearing and Grading
- ☐ Locating Development in Less Sensitive Areas
- ☐ Roadway Reduction
- ☐ Sidewalk Reduction
- ☐ Driveway Reduction
- ☐ Cul-de-sac Reduction
- ☐ Building Footprint Reduction
- ☐ Parking Reduction

27a. Indicate which of the following soil restoration criteria was used to address the requirements in Section 5.1.6("Soil Restoration") of the Design Manual (2010 version).

- ☐ All disturbed areas will be restored in accordance with the Soil Restoration requirements in Table 5.3 of the Design Manual (see page 5-22).
- ☐ Compacted areas were considered as impervious cover when calculating the **WQv Required**, and the compacted areas were assigned a post-construction Hydrologic Soil Group (HSG) designation that is one level less permeable than existing conditions for the hydrology analysis.

28. Provide the total Water Quality Volume (WQv) required for this project (based on final site plan/layout).

**Total WQv Required**

.     acre-feet

29. Identify the RR techniques (Area Reduction), RR techniques(Volume Reduction) and Standard SMPs with RRv Capacity in Table 1 (See Page 9) that were used to reduce the Total WQv Required(#28).

Also, provide in Table 1 the total impervious area that contributes runoff to each technique/practice selected. For the Area Reduction Techniques, provide the total contributing area (includes pervious area) and, if applicable, the total impervious area that contributes runoff to the technique/practice.

**Note:** Redevelopment projects shall use Tables 1 and 2 to identify the SMPs used to treat and/or reduce the WQv required. If runoff reduction techniques will not be used to reduce the required WQv, skip to question 33a after identifying the SMPs.



Table 1 - Runoff Reduction (RR) Techniques  
and Standard Stormwater Management  
Practices (SMPs)

RR Techniques (Area Reduction)	Total Contributing Area (acres)	Total Contributing Impervious Area(acres)
○ Conservation of Natural Areas (RR-1) ...	<input type="text"/> <input type="text"/> <input type="text"/> . <input type="text"/> <input type="text"/> <input type="text"/>	and/or <input type="text"/> <input type="text"/> <input type="text"/> . <input type="text"/> <input type="text"/> <input type="text"/>
○ Sheetflow to Riparian Buffers/Filters Strips (RR-2) .....	<input type="text"/> <input type="text"/> <input type="text"/> . <input type="text"/> <input type="text"/> <input type="text"/>	and/or <input type="text"/> <input type="text"/> <input type="text"/> . <input type="text"/> <input type="text"/> <input type="text"/>
○ Tree Planting/Tree Pit (RR-3) .....	<input type="text"/> <input type="text"/> <input type="text"/> . <input type="text"/> <input type="text"/> <input type="text"/>	and/or <input type="text"/> <input type="text"/> <input type="text"/> . <input type="text"/> <input type="text"/> <input type="text"/>
○ Disconnection of Rooftop Runoff (RR-4) ..	<input type="text"/> <input type="text"/> <input type="text"/> . <input type="text"/> <input type="text"/> <input type="text"/>	and/or <input type="text"/> <input type="text"/> <input type="text"/> . <input type="text"/> <input type="text"/> <input type="text"/>
<u>RR Techniques (Volume Reduction)</u>		
○ Vegetated Swale (RR-5) .....	<input type="text"/> <input type="text"/> <input type="text"/>	<input type="text"/> <input type="text"/> <input type="text"/>
○ Rain Garden (RR-6) .....	<input type="text"/> <input type="text"/> <input type="text"/>	<input type="text"/> <input type="text"/> <input type="text"/>
○ Stormwater Planter (RR-7) .....	<input type="text"/> <input type="text"/> <input type="text"/>	<input type="text"/> <input type="text"/> <input type="text"/>
○ Rain Barrel/Cistern (RR-8) .....	<input type="text"/> <input type="text"/> <input type="text"/>	<input type="text"/> <input type="text"/> <input type="text"/>
○ Porous Pavement (RR-9) .....	<input type="text"/> <input type="text"/> <input type="text"/>	<input type="text"/> <input type="text"/> <input type="text"/>
○ Green Roof (RR-10) .....	<input type="text"/> <input type="text"/> <input type="text"/>	<input type="text"/> <input type="text"/> <input type="text"/>
<u>Standard SMPs with RRv Capacity</u>		
○ Infiltration Trench (I-1) .....	<input type="text"/> <input type="text"/> <input type="text"/>	<input type="text"/> <input type="text"/> <input type="text"/>
○ Infiltration Basin (I-2) .....	<input type="text"/> <input type="text"/> <input type="text"/>	<input type="text"/> <input type="text"/> <input type="text"/>
○ Dry Well (I-3) .....	<input type="text"/> <input type="text"/> <input type="text"/>	<input type="text"/> <input type="text"/> <input type="text"/>
○ Underground Infiltration System (I-4) .....	<input type="text"/> <input type="text"/> <input type="text"/>	<input type="text"/> <input type="text"/> <input type="text"/>
○ Bioretention (F-5) .....	<input type="text"/> <input type="text"/> <input type="text"/>	<input type="text"/> <input type="text"/> <input type="text"/>
○ Dry Swale (O-1) .....	<input type="text"/> <input type="text"/> <input type="text"/>	<input type="text"/> <input type="text"/> <input type="text"/>
<u>Standard SMPs</u>		
○ Micropool Extended Detention (P-1) .....	<input type="text"/> <input type="text"/> <input type="text"/>	<input type="text"/> <input type="text"/> <input type="text"/>
○ Wet Pond (P-2) .....	<input type="text"/> <input type="text"/> <input type="text"/>	<input type="text"/> <input type="text"/> <input type="text"/>
○ Wet Extended Detention (P-3) .....	<input type="text"/> <input type="text"/> <input type="text"/>	<input type="text"/> <input type="text"/> <input type="text"/>
○ Multiple Pond System (P-4) .....	<input type="text"/> <input type="text"/> <input type="text"/>	<input type="text"/> <input type="text"/> <input type="text"/>
○ Pocket Pond (P-5) .....	<input type="text"/> <input type="text"/> <input type="text"/>	<input type="text"/> <input type="text"/> <input type="text"/>
○ Surface Sand Filter (F-1) .....	<input type="text"/> <input type="text"/> <input type="text"/>	<input type="text"/> <input type="text"/> <input type="text"/>
○ Underground Sand Filter (F-2) .....	<input type="text"/> <input type="text"/> <input type="text"/>	<input type="text"/> <input type="text"/> <input type="text"/>
○ Perimeter Sand Filter (F-3) .....	<input type="text"/> <input type="text"/> <input type="text"/>	<input type="text"/> <input type="text"/> <input type="text"/>
○ Organic Filter (F-4) .....	<input type="text"/> <input type="text"/> <input type="text"/>	<input type="text"/> <input type="text"/> <input type="text"/>
○ Shallow Wetland (W-1) .....	<input type="text"/> <input type="text"/> <input type="text"/>	<input type="text"/> <input type="text"/> <input type="text"/>
○ Extended Detention Wetland (W-2) .....	<input type="text"/> <input type="text"/> <input type="text"/>	<input type="text"/> <input type="text"/> <input type="text"/>
○ Pond/Wetland System (W-3) .....	<input type="text"/> <input type="text"/> <input type="text"/>	<input type="text"/> <input type="text"/> <input type="text"/>
○ Pocket Wetland (W-4) .....	<input type="text"/> <input type="text"/> <input type="text"/>	<input type="text"/> <input type="text"/> <input type="text"/>
○ Wet Swale (O-2) .....	<input type="text"/> <input type="text"/> <input type="text"/>	<input type="text"/> <input type="text"/> <input type="text"/>

Table 2 - Alternative SMPs (DO NOT INCLUDE PRACTICES BEING USED FOR PRETREATMENT ONLY)																												
<u>Alternative SMP</u>	<u>Total Contributing Impervious Area(acres)</u>																											
<input type="radio"/> Hydrodynamic .....	<table border="1" style="display: inline-table; vertical-align: middle;"><tr><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr></table> <span style="font-size: 0.8em; vertical-align: middle;">=</span> <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr></table>																											
<input type="radio"/> Wet Vault .....	<table border="1" style="display: inline-table; vertical-align: middle;"><tr><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr></table> <span style="font-size: 0.8em; vertical-align: middle;">=</span> <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr></table>																											
<input type="radio"/> Media Filter .....	<table border="1" style="display: inline-table; vertical-align: middle;"><tr><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr></table> <span style="font-size: 0.8em; vertical-align: middle;">=</span> <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr></table>																											
<input type="radio"/> Other <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr></table> .....																<table border="1" style="display: inline-table; vertical-align: middle;"><tr><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr></table> <span style="font-size: 0.8em; vertical-align: middle;">=</span> <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td></td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr></table>												

Provide the name and manufacturer of the Alternative SMPs (i.e.  
proprietary practice(s)) being used for WQv treatment.

Name	<table border="1" style="width: 100%; height: 20px;"></table>
Manufacturer	<table border="1" style="width: 100%; height: 20px;"></table>

**Note:** Redevelopment projects which do not use RR techniques, shall use questions 28, 29, 33 and 33a to provide SMPs used, total WQv required and total WQv provided for the project.

[illegible]

--	--	--

 · 

--	--	--

 acre-feet

--	--	--

 . 

--	--	--

**acre-feet**

---

Page 10 of 14

33. Identify the Standard SMPs in Table 1 and, if applicable, the Alternative SMPs in Table 2 that were used to treat the remaining total WQv(=Total WQv Required in 28 - Total RRv Provided in 30).

Also, provide in Table 1 and 2 the total impervious area that contributes runoff to each practice selected.

**Note:** Use Tables 1 and 2 to identify the SMPs used on Redevelopment projects.

- 33a. Indicate the Total WQv provided (i.e. WQv treated) by the SMPs identified in question #33 and Standard SMPs with RRv Capacity identified in question 29.

**WQv Provided**

.  acre-feet

**Note:** For the standard SMPs with RRv capacity, the WQv provided by each practice = the WQv calculated using the contributing drainage area to the practice - RRv provided by the practice. (See Table 3.5 in Design Manual)

34. Provide the sum of the Total RRv provided (#30) and the WQv provided (#33a).

.

35. Is the sum of the RRv provided (#30) and the WQv provided (#33a) greater than or equal to the total WQv required (#28)? ☐ Yes ☐ No

If Yes, go to question 36.

If No, sizing criteria has not been met, so NOI can not be processed. SWPPP preparer must modify design to meet sizing criteria.

36. Provide the total Channel Protection Storage Volume (CPv) required and provided or select waiver (36a), if applicable.

**CPv Required**

.  acre-feet

**CPv Provided**

.  acre-feet

- 36a. The need to provide channel protection has been waived because:

- ☐ Site discharges directly to tidal waters or a fifth order or larger stream.
- ☐ Reduction of the total CPv is achieved on site through runoff reduction techniques or infiltration systems.

37. Provide the Overbank Flood (Qp) and Extreme Flood (Qf) control criteria or select waiver (37a), if applicable.

**Total Overbank Flood Control Criteria (Qp)**

**Pre-Development**

.  CFS

**Post-development**

.  CFS

**Total Extreme Flood Control Criteria (Qf)**

**Pre-Development**

.  CFS

**Post-development**

.  CFS

37a. The need to meet the Qp and Qf criteria has been waived because:

- ☐ Site discharges directly to tidal waters or a fifth order or larger stream.
- ☐ Downstream analysis reveals that the Qp and Qf controls are not required

- 37a. The need to meet the Qp and Qf criteria has been waived because:
- ☐ Site discharges directly to tidal waters or a fifth order or larger stream.
  - ☐ Downstream analysis reveals that the Qp and Qf controls are not required

38. Has a long term Operation and Maintenance Plan for the post-construction stormwater management practice(s) been developed? ☐ **Yes** ☐ **No**

38. Has a long term Operation and Maintenance Plan for the post-construction stormwater management practice(s) been developed? ☐ **Yes** ☐ **No**

If Yes, Identify the entity responsible for the long term  
Operation and Maintenance

[illegible]

39. Use this space to summarize the specific site limitations and justification for not reducing 100% of WQv required(#28). (See question 32a)  
This space can also be used for other pertinent project information.



40. Identify other DEC permits, existing and new, that are required for this project/facility.

- [illegible]

41. Does this project require a US Army Corps of Engineers Wetland Permit? ☐ ☐ ☐ ☐ ☐ ☐

☐ Yes    ☐ No

If Yes, Indicate Size of Impact.

--	--	--	--	--	--	--

42. Is this project subject to the requirements of a regulated, traditional land use control MS4?  
(If No, skip question 43)

☐ Yes      ☐ No

43. Has the "MS4 SWPPP Acceptance" form been signed by the principal executive officer or ranking elected official and submitted along with this NOI?

☐ Yes    ☐ No

44. If this NOI is being submitted for the purpose of continuing or transferring coverage under a general permit for stormwater runoff from construction activities, please indicate the former SPDES number assigned.

--	--	--	--	--	--	--	--	--

<b>Owner/Operator Certification</b>	
<p>I have read or been advised of the permit conditions and believe that I understand them. I also understand that, under the terms of the permit, there may be reporting requirements. I hereby certify that this document and the corresponding documents were prepared under my direction or supervision. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations. I further understand that coverage under the general permit will be identified in the acknowledgment that I will receive as a result of submitting this NOI and can be as long as sixty (60) business days as provided for in the general permit. I also understand that, by submitting this NOI, I am acknowledging that the SWPPP has been developed and will be implemented as the first element of construction, and agreeing to comply with all the terms and conditions of the general permit for which this NOI is being submitted.</p>	
<b>Print First Name</b> <div style="border: 1px solid black; height: 30px; width: 100%; position: relative;"> <div style="position: absolute; top: 0; left: 0; right: 0; bottom: 0; border: 1px solid black; display: flex; flex-wrap: wrap;"> <!-- 20 empty boxes for first name --> <!-- This is a simplified representation of the grid --> </div> </div>	<b>MI</b> <div style="border: 1px solid black; height: 30px; width: 100%; position: relative;"> <div style="position: absolute; top: 0; left: 0; right: 0; bottom: 0; border: 1px solid black; display: flex; flex-wrap: wrap;"> <!-- 2 empty boxes for MI --> </div> </div>
<b>Print Last Name</b> <div style="border: 1px solid black; height: 30px; width: 100%; position: relative;"> <div style="position: absolute; top: 0; left: 0; right: 0; bottom: 0; border: 1px solid black; display: flex; flex-wrap: wrap;"> <!-- 20 empty boxes for last name --> </div> </div>	
<b>Owner/Operator Signature</b> <div style="border: 1px solid black; height: 60px; width: 100%;"></div>	
<div style="display: flex; justify-content: space-between; align-items: flex-end;"> <div style="width: 60%;"> <div style="border: 1px solid black; height: 60px; width: 100%;"></div> </div> <div style="width: 35%; text-align: center;"> <b>Date</b>  <div style="display: flex; justify-content: space-around; align-items: center;"> <div style="border: 1px solid black; padding: 2px 5px;"> </div> <div style="border: 1px solid black; padding: 2px 5px;"> </div> <div style="font-size: 1.5em;">/ <div style="border: 1px solid black; padding: 2px 5px;"> </div> <div style="border: 1px solid black; padding: 2px 5px;"> </div> <div style="font-size: 1.5em;">/ <div style="border: 1px solid black; padding: 2px 5px;"> </div> <div style="border: 1px solid black; padding: 2px 5px;"> </div> <div style="border: 1px solid black; padding: 2px 5px;"> </div> <div style="border: 1px solid black; padding: 2px 5px;"> </div> </div> </div> </div> </div></div>	

--	--

/

--	--

/

--	--	--	--

	P.W. Scott	pwscott@pwscott.com
	Engineering & Architecture, P.C.	www.pwscott.com
	3871 Danbury Rd (Route 6)	(845) 278-2110
	Brewster, NY 10509	

November 28, 2023

Ms. Janet Anderson, Planning Board Chairperson  
Planning Board Members  
Town of Lewisboro  
79 Bouton Road  
South Salem, NY 10590  
[planning@lewisborogov.com](mailto:planning@lewisborogov.com)

Re: 96 Post Office Rd  
Amended Site Plan

Dear Ms. Anderson and Planning Board Members,

Please find attached an amended site plan with a 2-story residence as requested. The planter has been reduced in size to reflect the reduced site impervious. There are no longer any impacts in the wetlands due to the structures. There is minor wetland grading on the north side of the project for the well and sediment trap below the driveway. This area will be replanted. The deck to the west is now cantilevered, the deck to the south is on piers. There is no modification required for the septic system approved by WCDOH & NYCDEP.

We request, if at all possible, that the project be presented to the Board at the December meeting to review this alternative. If acceptable, our office will appear in January with the final SWPPP and completed documents for further review. Mr. Bernabo will be attending the meeting in December to discuss the proposed 2-story residence.

Thank you for your attention to this matter.

Respectfully submitted.



*Peder Scott*

Peder Scott, P.E., R.A.  
President

Attach

cc: Alex Bernabo, Owner, [info@wdesigne.com](mailto:info@wdesigne.com)






Zoning Tabulation  
Zone: RA4

	Required	Proposed
Min. Lot Area:	4.0	4.04
Lot Width (circle ft):	250.0	320.0
Min. Yards		
Front - Street Center Line	75.0	71.3*
Front - Front Lot Line	50.0	54.0
Side Setback:	50.0	78.5
Rear Setback:	50.0	439.14
Max. Building Steel		
Stories	2.5 Stories	2 Story
Feet	35 Feet	28 Feet
Max. Building Coverage:		
House & Planter		
Footprint:2,020 sf	6.0%	1.10%
Treatment Planter: 320 sf (included in coverage)		
Including Deck: 1500 sf		2.0%

Disturbances Proposed		
Wetland:	.062 acre; 2694 sf	planter & well & grading
Wetland -incl plantings	0.162 acre; 7074 sf	planter & well & grading
Upland areas:	0.462 acre, 20,124 sf	driveway & SSDS Area
Upland areas-incl plantings	0.50 acre; 21780 sf	driveway & SSDS Area



#### WETLAND IMPACT MITIGATION

THE EXISTING PROPERTY, SIMILAR TO THE ADJACENT PROPERTIES ALONG POST OFFICE RD., CONTAINS LOCAL WETLANDS ON THE REAR OF THE PROPERTY. THE SUBJECT LOT IS THE LAST VACANT LOT OF THIS SUBDIVISION APPROVED IN THE LATE 1970'S. THE WETLANDS INCLUDE A STREAM COURSE, AS NOTED ON THE SITE PLAN, WHICH IS NOT NYSDEC REGULATED. THE WETLANDS CONSIST OF A HEAVILY WOODED SITE WITH AN UNDERSTORY OF SYMPLOCARPUS FOETIDUS (SKUNK CABBAGE) AND IS IN GOOD CONDITION. ACCORDINGLY, SITE MITIGATION FOR THE DISTURBANCES IS PROPOSED AS FOLLOWS:

- SPLIT RAIL FENCE ALONG THE EDGE OF THE LOT DISTURBANCE TO PREVENT ENTRY INTO THE WETLAND.
- PERMANENT STONE OUTLET SEDIMENT TRAP TO TREAT ANY DRIVEWAY DRAINAGE.
- CONCRETE PLANTER TO TREAT BUILDING ROOF RUNOFF IN COMPLIANCE WITH NYCDEP & NYSDEC IRSP.
- BUFFER PLANTS ARE PROPOSED BEYOND THE SPLIT RAIL FENCE AS ON THE CHART PROVIDED, FOR AN AREA OF 0.13 ACRES.
- SINCE THESE PLANTS ARE WITHIN THE WETLAND, A REPLACEMENT OF 1/1 (.20 ACRES) REPLACEMENT OF WETLAND PLANTS IS NOT FEASIBLE. UPLAND AREAS ON THE WEST SIDE OF THE LOT WILL REQUIRE DISTURBANCES FOR ACCESS, THEREFOR OFFSITE WETLAND MITIGATION IS PROPOSED OR THE REMOVAL OF INVASIVE BARBERRY PLANTS ACROSS THE SITE (2 ACRES PLUS)

#### WATERCOURSE BUFFER NOTES

- REMOVE BROKEN LIMBS AND DEBRIS FROM THE WATERCOURSE.
- CLEAN UP THE BUFFER AREA TO A WIDTH OF 15' ON EACH SIDE OF THE WATERCOURSE.
- INSTALL FERNS AND SHRUBS AS NOTED ON THE PLAN.
- OVER-SEED THE FILTER STRIP AREA WITH A CONSERVATION GRASS SEED MIX.
- MULCH THE ENTIRE AREA WITH WEED FREE STRAW.
- SURROUND NEW PLANTINGS WITH DEER FENCING FOR 3 YEARS TO ALLOW GROWTH OF PLANTS.

Stream Buffer Plants					
SYM	Quant.	Botanical Name	Common Name	Caliper/Cont.	Spacing
Shrubs					
AA	6	<i>Amelanchier arborea</i>	Common serviceberry	2 gal.	5'
CA	6	<i>Clethra alnifolia</i>	Sweet pepperbush	2 gal.	5'
CR	6	<i>Cornus racemosa</i>	Gray dogwood	2 gal.	6'
IG	6	<i>Ilex glabra</i>	Inkberry	2 gal.	8'
LB	6	<i>Lindera benzoin</i>	Spicebush	2 gal.	6'
RP	6	<i>Rhododendron periclymenoides</i>	Pinkster azalea	2 gal.	8'
VP	6	<i>Vaccinium pallidum</i>	Blue Ridge blueberry	2 gal.	8'
42					


#### SUPPLEMENTAL PLANTINGS

THE PLANTINGS SHALL BE INSPECTED AND SUPPLEMENTAL PLANTINGS ADDED AFTER TWO YEAR GROWING PERIOD IF 85% COVERAGE IS NOT ACHIEVED WITH THE PLANTINGS NOTED ABOVE. THE PERMITTEE SHALL TAKE ALL NECESSARY STEPS TO ENSURE A LEVEL OF SURVIVAL AND REPLANT AND REGRADE WITH TOPSOIL, IF NECESSARY.

EXACT LOCATION OF THE PROPOSED PLANTS SHALL BE COORDINATED WITH EXISTING FOLIAGE AND TREES TO ENSURE THAT MINIMAL DISTURBANCE TAKES PLACE WITH EXISTING VEGETATION

Visual Buffer Plants					
SYM	Quant.	Botanical Name	Common Name	Caliper/Cont.	Spacing
Trees					
AB	10	<i>Arborvitae- Thuja</i>	Green Giant Arborvitae	2" (8 feet)	12'

#### LEGEND



#### PROPERTY IDENTIFICATION


OWNER: ALEX BERNABO wDESIGNE, INC.  
ADDRESS: 3867 DANBURY ROAD BREWSTER NY 10509  
E911 #: 96 POST OFFICE ROAD, LEWISBORO  
LEWISBORO T.M. SHEET 25 BLOCK 10812 LOT 3  
PROPERTY ADDRESS: 96 POST OFFICE ROAD LEWISBORO, NY 10590  
NYC DEP WATERSHED: CROSS RIVER BASIN  
AREA OF HOUSE PROPOSED: 2600 SF+ 600SF GARAGE  
# BEDROOMS: 2 BEDROOM

P. W. SCOTT		Revisions		Dwg. Title COVER SHEET		Seal	Dwg. No. CS
ENGINEERING & ARCHITECTURE, P.C.		No.	Date	Description	Project Title		
3871 ROUTE 6		A	8/16/23	REVISED PER TE MEMO	96 POST OFFICE ROAD LEWISBORO, NY		
BREWSTER, NY 10509 845-278-2110		B	9/20/23	REVISED PER TE MEMO			
		C	11/27/23	2 STORY HOUSE OPTION	Proj. No. 21-110	Drawn by MA/PWS	
					Date 5/25/23	Scale AS NOTED	

NOTE: DO NOT SCALE DRAWINGS  
DIMENSIONS SUPERCEDE SCALE

THESE DRAWINGS ARE THE SOLE PROPERTY OF P.W. SCOTT ENGINEERING AND ARCHITECTS, P.C. AND WILL NOT BE REPRODUCED BY ANY MEANS AND BE GIVEN TO ANY OTHER TRADES/PERSONS WITHOUT THE EXPRESS PERMISSION OF P.W. SCOTT ENGINEERING AND ARCHITECTS, P.C.





EROSION CONTROL LEGEND			
NO.	SYMBOL	DESCRIPTION	STATUS
1		SILT FENCE	TEMPORARY SEE DET. 1/SY1 PLACE PARALLEL TO GRADE-CONTOURS
2		CONSTRUCTION FENCE	AROUND EDGE SEPTIC FILL: SEE DET.2/SY1
3		TOPSOIL STOCKPILE AREA	TEMPORARY SEE DET. 3/SY1 RING WITH SILT FENCE
4		CONSTRUCTION ENTRANCE	TEMPORARY SEE DET. 4/SY1 PLACE @ EA. POINT OF ENTRY INTO SITE
5		STONE OUTLET SEDIMENT TRAP	PERMANENT SEE DET. 5/SY1
6		CONCRETE PUMP OUT TRAP	TEMPORARY SEE DET. 6/SY1
7		SEED & MULCH SPECIFICATIONS	TEMPORARY SEE DET. 7/SY1
8		STORAGE AREA	
9		LIMIT OF DISTURBANCE	


Maintenance Schedule – During Construction – Temporary Structures

-	Component	MINIMUM Inspection Required	After Every Storm Event	Item to Inspect	Sediment Removal Req'd	Special Inspection Items Inspect the following:	Maintenance and Sediment Removal
1	Silt Fence	Bi-Weekly	X	Woven Wire Fence Alignment	Yes	Woven Wire & Fence Stability	Remove material when a "bulge" develops, ensure fence extends into soil and fence upright, staple fencing
2	Construction Fence	Bi-Weekly		Fence Woven Wire Conditions	None	Fence posts and grid	Fix fence up right and staple as required to ensure integrity.
3	Topsoil Stockpile Area	Bi-Weekly	X	Soil Pile Condition	None	Silt Fence at Base of Pile to be inspected and seeding reviewed.	Remove material when a "bulge" develops, ensure fence extends into soil and fence is upright, staple fencing
4	Construction Entrance	Weekly	X	Stone Placement	None	Stone Placement & soil deposit between stones	Repair Top Dressing with additional aggregate and correct stone placement.
5	Stone Outlet Sediment Trap	Bi-Weekly	X	Stone Placement & Location	Yes	Stone & Sediment Accumulation	Bi-weekly, remove sediment, set stones to correct profile, fix berm blow-outs
6	Concrete Pump Out	Monthly	X	Soil Stability	None	Once filled topsoil, seed & mulch	Due to the downhill proximity of the well, it is recommended to remove the concrete off-site once cured

EXPANDED SITE PLAN  
SCALE:1"=20'

Reference the Cover Sheet CS for lot geometry and setbacks

THESE DRAWINGS ARE THE SOLE PROPERTY OF P.W. SCOTT ENGINEERING AND ARCHITECTS, P.C. AND WILL NOT BE REPRODUCED BY ANY MEANS AND BE GIVEN TO ANY OTHER TRADES/PERSONS WITHOUT THE EXPRESS PERMISSION OF P.W. SCOTT ENGINEERING AND ARCHITECTS, P.C.



- NOTES:
1. SILT FENCE SHALL BE PLACED ON SLOPE CONTOURS TO MAXIMIZE PONDING EFFICIENCY.
  2. INSPECT AND REPAIR FENCE AFTER EACH STORM EVENT AND REMOVE SEDIMENT WHEN NECESSARY. 9" (225mm) MAXIMUM RECOMMENDED STORAGE HEIGHT.
  3. REMOVED SEDIMENT SHALL BE DEPOSITED TO AN AREA THAT WILL NOT CONTRIBUTE SEDIMENT OFF-SITE AND CAN BE PERMANENTLY STABILIZED.

- NOTES:
1. SPACING MAY VARY AS PER MANUFACTURER'S RECOMMENDATIONS. MAXIMUM SPACING IS 8'-0".
  2. JOIN CONSTRUCTION FENCE SECTIONS BY OVERLAPPING END STAKES.
  3. INSPECT AND REPAIR PERIODICALLY TO MAINTAIN THE INTEGRITY OF THE CONSTRUCTION AREA.

1  
SY1

SILT FENCE- STANDARD ONLY  
N.T.S.

2  
SY1

CONSTRUCTION FENCE  
N.T.S.

5  
SY1

STONE OUTLET SEDIMENT TRAP CHART

TRAP #	LOCATION	DRAINAGE AREA	REQ'D VOL. (CF)	OUTLET WIDTH	DEPTH	TOP DIMENSION L
1	DRIVEWAY	0.10	360	1.0 FEET	3.0	12x25

VOL= .4 AREA (DEPTH)

This narrative describes the erosion and sediment controls proposed for this project, discusses the construction sequence and states the requirements for inspection and maintenance of the erosion and sediment controls. The plan has been designed in accordance with the State of New York "2016 Standards and Specifications for Erosion and Sediment Control."

The sequences provided include anticipated start dates, which are predicated on municipal and state agency approvals.

INTRODUCTION

1. Pre-application meeting with Town of Lewisboro Town Engineer/MS4 Agent, Contractor & Engineer and NYCDEP for IRSP for project scheduling and final plan coordination. There are no NYSDEC wetlands, wetland approval on local basis.
2. File NYSDEC NOI Forms with start dates
3. E.O.R. to complete NYSDEC inspections twice/week per NOI permit.

GENERAL SPECIFICATIONS

4. Surveyor to locate limits of house, planter, septic & driveway and the limit of disturbance line prior to construction..
5. Cut trees and clear - leave stumps in place.
6. Install erosion control devices including erosion control fence. Refer to Sheet SY2
7. Install construction fence around septic area as noted.
8. Remove topsoil and stockpile as noted.
9. Contractor to verify elevation at planter and limits of building (cut & fill) E.O.R. to verify with site visit.
10. Install stone outlet sediment trap on hillside below driveway to collect runoff from driveway construction.

NOTE: DO NOT SCALE DRAWINGS  
DIMENSIONS SUPERCEDE SCALE

3  
SY1

CONSTRUCTION FENCE  
N.T.S.

6  
SY1

SEEDING SPECIFICATIONS

65% FINE FESCUE @ 140#/ACRE; .3.3#/1000 SF.  
15% PERENNIAL RYE @ 33#/ACRE; .0.7#/1000 SF.  
20% BLUE GRASS BLEND @ 44#/ACRE; .1.0#/1000 SF.

- Maintenance
- All concrete washout facilities shall be inspected daily. Damaged or leaking facilities shall be deactivated and repaired or replaced immediately. Excess rainwater that has accumulated over hardened concrete should be pumped to a stabilized area, such as a grass filter strip.
  - Accumulated hardened material shall be removed when 75% of the storage capacity of the structure is filled. Any excess wash water shall be pumped into a containment vessel and properly disposed of off-site.
  - Dispose of the hardened material off-site in a construction/demolition landfill. On-site disposal may be allowed if this has been approved and accepted as part of the project's SWPPP. In that case, the material should be recycled as specified, or buried and covered with a minimum of 2 feet of clean compacted earth fill that is permanently stabilized to prevent erosion.
  - The plastic liner shall be replaced with each cleaning of the washout facility.
  - Inspect the project site frequently to ensure that no concrete discharges are taking place in non-designated areas.

11. Excavate driveway and stabilize with Item #4 due to slope.
  12. Stump the lot with access established for trucks picking up stumps.
  13. Install concrete pump out pit adjacent to driveway
  14. Install footings for residence & planter
  15. Extend power to house site
  16. Pour house walls & planter walls, allow sleeves for water, sewer out, and electrical, and propane lines.
  17. Install concrete wall, waterproof and backfill
  18. Install well by creating concrete gravel pad, install silt fence and install pump out pit for water test.
  19. Remove concrete collected in the pump out pit and remove off site.
  20. Install septic tanks and pump chamber. Install fill for septic and mechanically compact. Cut in trenches - D-Boxes for primary only. Complete as-built inspections with E.O.R.
  21. Spread 6 in to 12 in topsoil, seed and mulch
  22. Clean out stone outlet sediment trap
  23. Leave stone ring in place as permanent sediment collection point.
  24. Complete final utility connection. Electrical overhead or underground per Contractor.
  25. Construct wood deck with sonotube piers as footings, poured in cardboard forms.
  26. Once deck is complete, complete soil filling of concrete planter per specs. Connect roof leaders to planter (residence has flat roof pitching to rear and common leaders). Ensure overflows are functional in wall perimeter. Install plants between March 15th and June 15th; September 15th to October 15th . Water weekly as required if rainstorms not imminent within one week. Include planting of the northern buffer plants.
  27. When entire site is stabilized with grass cover, remove silt fence.
  28. Schedule MS4 Inspection with Town of Lewisboro
  29. File NOT with NYSDEC.
- Project complete

4  
SY1


CONSTRUCTION ENTRANCE  
N.T.S.

7  
SY1

MULCH SPECIFICATIONS

65% FINE FESCUE @ 140#/ACRE; .3.3#/1000 SF.  
15% PERENNIAL RYE @ 33#/ACRE; .0.7#/1000 SF.  
20% BLUE GRASS BLEND @ 44#/ACRE; .1.0#/1000 SF.

- SEEDING SPECIFICATIONS
- EMPIRE BIRDSFOOT @ 8#/ACRE; .20#/1000 SF.  
TREFOIL OR COMMON WHITE CLOVER @ 20#/ACRE; .45#/1000 SF.  
REDTOP @ 2#/ACRE; .05#/1000 SF.  
FREQUENTLY MOWED: SHADY DRY SITES



- NOTES:
1. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHT-OF-WAYS. THIS MAY REQUIRE TOP DRESSING, REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT.
  2. WHEN NECESSARY, WHEELS SHALL BE CLEANED PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAY.
  3. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT BASIN.

- SITE PREPARATIONS:
- RAKE OUT ROCKS ON THE SURFACE, REMOVE ANY WOOD STOCKPILE BEYOND AREA DISTURBANCE FOR DISPOSAL
- JUTE NETTING
- UNDYED, UNBLEACHED PLAINWEAVE WARP: 78 END/YD.  
APPLICATION RATE: 48" X 50 YDS./1000 SF.(60#ROLL/ACRE)  
DEPTH APPLICATION: 60 SG. YDS.  
TIE DOWN PER MANUFACTURER'S SPECIFICATIONS.
- BEST COMBINATION: FIBERS
- STRAW(SMALL GRAINED) MULCH  
APPLICATION RATE: 2 TONS (90#S/1000 SF.)  
ANCHOR WITH: WOOD FIBER MULCH(HYDRO-MULCH)  
APPLICATION RATE: 500-750#/ACRE(11#/1000 SF.)  
THE WOOD FIBER MUST BE APPLIED THROUGH HYDRO-SEEDER IMMEDIATELY AFTER MULCHING.
- ANCHORING:
- MULCH NETTING: HAY OR STRAW: STAPLE:LIGHT-WEIGHT JUTE

REFER TO SHEET SY2 FOR EROSION CONTROL NOTES

TEMPORARY & PERMANENT  
MAINTENANCE IMPLEMENTATION

THE REQUIRED PARTIES RESPONSIBLE FOR FOR THE IMPLEMENTATION OF  
STORMWATER FACILITY INSPECTION AND AND MAINTENANCE PROGRAM  
CONSISTS OF THE LAND OWNER DURING & AFTER CONSTRUCTION:



OWNER: ALEX BERNABO  
wDESIGNE, INC.

ADDRESS: 3867 DANBURY ROAD  
BREWSTER NY 10509


EMAIL: info@wdesigne.com

TELE #: (914)-906-1336

ALL SITE WORK SHALL BE COMPLETED UNDER  
THE DIRECT SUPERVISION OF A LICENSED  
ENGINEER IN THE STATE OF NEW YORK.

P. W. SCOTT		Revisions		Dwg. Title		IRSP EROSION CONTROL PLAN			Dwg. No.
	ENGINEERING & ARCHITECTURE, P.C.	No.	Date	Description	Project Title				
	3871 ROUTE 6	A	5/8/23	REVISE PER WCDON 5/8/23 MEMO	96 POST OFFICE ROAD, LEWISBORO,NY				
		B	8/16/23	REVISED PER TE MEMO	Proj. No.				
		C	9/20/23	REVISED PER TE MEMO	21-110				
		D	11/27/23	2 STORY HOUSE OPTION	Drawn by				
BREWSTER, NY 10509 845-278-2110				Date		3/30/23		MA/PWS	
				Scale		AS NOTED		SY1	





- CHANGES PER BUILDING DEPT. REVIEW
- #1 REMOVE DECK DECK
  - #2 RELOCATE STAIR
  - #3 CHANGE DECK SIZE TO 18'x24' #
  - #4 RELOCATE ROOF DRAIN COLLECTION
  - #5 REMOVE DRIVE WAY PAD DRIVE
  - #6 REMOVE PARKING / ACCESS PAD TO WELL

12.5.23

Stream Buffer Plants			
SYM	Quant.	Botanical Name	Common Name
Shrubs			
AA	6	Amelanchier arborea	Common serviceberry
CA	6	Clethra alnifolia	Sweet pepperbush
CR	6	Cornus racemosa	Gray dogwood
IG	6	Ilex glabra	Inkberry
LB	6	Lindera benzoin	Spicebush
RP	6	Rhododendron narichinensis	

LEGEND

QUANTITY

SPECIES

PLANT SYMBOL

DEER FENCING

	P.W. Scott	pwscott@pwscott.com
	Engineering & Architecture, P.C.	www.pwscott.com
	3871 Danbury Rd (Route 6)	(845) 278-2110
	Brewster, NY 10509	

December 6, 2023

Kevin J. Kelly, RA  
 Building Inspector, Code Enforcement Officer  
 Town of Lewisboro  
 79 Bouton Road  
 South Salem, NY 10590  
[kkelly@lewisborogov.com](mailto:kkelly@lewisborogov.com)  
[Planning@lewisborogov.onmicrosoft.com](mailto:Planning@lewisborogov.onmicrosoft.com)

Re: 96 Post Office Rd  
 Response to BI Comments of 12/5/23 forwarded by Planning Board

Dear Kevin,

The following is in response to the your review email dated December 5, 2023 forwarded to us by the PB.

- A. Well Pad Removal: In lieu of Grasscrete we need gravel to the well. We could place it on geotechnical fabric (Tygar 3400) and once the well is drilled remove the gravel and fabric to original.
- B. We need a backup area past the driveway in order to complete a k-turn – minimum 10 ft – could be made narrower.
- C. With regards to the rear deck of 340 sf, this is cantilevered and is 9"  $\pm$  in the air. Finish is 1¼ x 6 decking so water would extend to grade/wetland area.

Please accept this letter for the file.

With regards,

*Peder Scott*

Peder Scott, P.E., R.A.  
 President

cc: Alex Bernabo, Owner, [info@wdesigne.com](mailto:info@wdesigne.com)

ARCHITECTURE \* ENGINEERING \* SITE PLANNING

C:\Users\CiorsdanConran\AppData\Local\Microsoft\Windows\INetCache\Content.Outlook\D1YOZMAT\Response ltr to Bldg  
 Dept Review of 12.6.23.doc

	P.W. Scott	pwscott@pwscott.com
	Engineering & Architecture, P.C.	www.pwscott.com
	3871 Danbury Rd (Route 6)	(845) 278-2110
	Brewster, NY 10509	

December 12, 2023

Ms. Janet Anderson, Planning Board Chairperson  
 Planning Board Members  
 Town of Lewisboro  
 79 Bouton Road  
 South Salem, NY 10590  
[planning@lewisborogov.com](mailto:planning@lewisborogov.com)

Re: 96 Post Office Rd

Dear Ms. Anderson and Planning Board Members,

Attached is a revised site plan in response to the Building Inspector for the December meeting. The plans have been revised based upon input from the Building Inspector to minimize any encroachments into the wetlands.

The following is a comparison to the 11/27/23 submission:

1. Reduced Grasscrete to 1,950 (-512 sf). None in wetland
2. Removed the Grasscrete to well, gravel shall be used only for truck entry to well site and can be removed upon well completion.
3. Reduced deck to 980 sf (-660 sf).
4. Planter remains at 320 sf - size based upon roof size - the only impervious component on site.  
 Note: Planter must be 50.0 ft from the septic trenches as noted on the site plan.
5. House footprint remains at 1,700 sf x 2 stories including the garage.
6. SSDA – No change with this amendment.
7. There is a cantilevered deck remaining along the west side of the residence, which is 10 feet above the wetland area, with deck spacing to allow water drainage to below. This is for egress to the deck.

Net reduction of disturbance: 1,172 sf

Please accept this site plan for discussion with the Owner. Three dimensional renderings of the house and architecture shall be presented for review at the meeting.


With regards,

*Peder Scott*


Peder Scott, P.E., R.A.  
 President

Attach





**SOILS LEGEND**  
WdC- Woodbridge, 8 TO 15 PERCENT SLOPES- class C  
Sh- Sun loam- Class D  
PnC-Paxton silt Loam, 8 to 15 PERCENT SLOPES- Class C



WETLAND SPLIT RAIL FENCE DETAIL  
N.T.S.

NOTES: All wetland buffer planting shall be contained within Deer Fence for a duration of THREE (3) years minimum.  
Provide a single 3.0 ft opening for access to property.

LEGEND

PL	PROPERTY LINE	RD/VD	ROAD AND FOOTING DRAIN
468	EXISTING CONTOUR	SF	SOIL BOUNDARY
x 463.3	EXISTING SPOT ELEVATION	SF	SILT FENCE
(472)	PROPOSED CONTOUR	SF	EXISTING CATCH BASIN
HP	HIGH POINT IN GRADE	SF	PROPOSED SWALE
x (463.3)	PROPOSED SPOT ELEVATION	W	WATER LINE
PT#	PERCOLATION TEST HOLE	W	EXISTING WELL
BT#	DEEP TEST HOLE	W	STREAM 100' SETBACK LINE
W	WETLAND SPLIT RAIL FENCE	W	WETLAND LINE

WETLAND IMPACT MITIGATION

THE EXISTING PROPERTY, SIMILAR TO THE ADJACENT PROPERTIES ALONG POST OFFICE RD., CONTAINS LOCAL WETLANDS ON THE REAR OF THE PROPERTY. THE SUBJECT LOT IS THE LAST VACANT LOT OF THIS SUBDIVISION APPROVED IN THE LATE 1970'S. THE WETLANDS INCLUDE A STREAM COURSE, AS NOTED ON THE SITE PLAN, WHICH IS NOT NYSDEC REGULATED. THE WETLANDS CONSIST OF A HEAVILY WOODED SITE WITH AN UNDERSTORY OF SYMPLOCARPUS FOETIDUS (SKUNK CABBAGE) AND IS IN GOOD CONDITION. ACCORDINGLY, SITE MITIGATION FOR THE DISTURBANCES IS PROPOSED AS FOLLOWS:

- SPLIT RAIL FENCE ALONG THE EDGE OF THE LOT DISTURBANCE TO PREVENT ENTRY INTO THE WETLAND.
- PERMANENT STONE OUTLET SEDIMENT TRAP TO TREAT ANY DRIVEWAY DRAINAGE.
- CONCRETE PLANTER TO TREAT BUILDING ROOF RUNOFF IN COMPLIANCE WITH NYCDEP & NYSDEC IRSP.
- BUFFER PLANTS ARE PROPOSED BEYOND THE SPLIT RAIL FENCE AS ON THE CHART PROVIDED, FOR AN AREA OF 0.13 ACRES.
- SINCE THESE PLANTS ARE WITHIN THE WETLAND, A REPLACEMENT OF 1/1 (20 ACRES) REPLACEMENT OF WETLAND PLANTS IS NOT FEASIBLE. UPLAND AREAS ON THE WEST SIDE OF THE LOT WILL REQUIRE DISTURBANCES FOR ACCESS, THEREFOR OFFSITE WETLAND MITIGATION IS PROPOSED OR THE REMOVAL OF INVASIVE BARBERRY PLANTS ACROSS THE SITE (2 ACRES PLUS)

WATERCOURSE BUFFER NOTES

- REMOVE BROKEN LIMBS AND DEBRIS FROM THE WATERCOURSE.
- CLEAN UP THE BUFFER AREA TO A WIDTH OF 15' ON EACH SIDE OF THE WATERCOURSE.
- INSTALL FERNS AND SHRUBS AS NOTED ON THE PLAN.
- OVER-SEED THE FILTER STRIP AREA WITH A CONSERVATION GRASS SEED MIX.
- MULCH THE ENTIRE AREA WITH WEED FREE STRAW.
- SURROUND NEW PLANTINGS WITH DEER FENCING FOR 3 YEARS TO ALLOW GROWTH OF PLANTS.

Stream Buffer Plants

SYM	Quant.	Botanical Name	Common Name	Caliper/Cont.	Spacing
Shrubs					
AA	6	<i>Amelanchier arborea</i>	Common serviceberry	2 gal.	5'
CA	6	<i>Clethra alnifolia</i>	Sweet pepperbush	2 gal.	5'
CR	6	<i>Cornus racemosa</i>	Gray dogwood	2 gal.	6'
IG	6	<i>Ilex glabra</i>	Inkberry	2 gal.	8'
LB	6	<i>Lindera benzoin</i>	Spicebush	2 gal.	6'
RP	6	<i>Rhododendron periclymenoides</i>	Pinkster azalea	2 gal.	8'
VP	6	<i>Vaccinium pallidum</i>	Blue Ridge blueberry	2 gal.	8'
42					

SUPPLEMENTAL PLANTINGS

THE PLANTINGS SHALL BE INSPECTED AND SUPPLEMENTAL PLANTINGS ADDED AFTER TWO YEAR GROWING PERIOD IF 85% COVERAGE IS NOT ACHIEVED WITH THE PLANTINGS NOTED ABOVE. THE PERMITTEE SHALL TAKE ALL NECESSARY STEPS TO ENSURE A LEVEL OF SURVIVAL AND REPLANT AND REGRADE WITH TOPSOIL, IF NECESSARY.



EXACT LOCATION OF THE PROPOSED PLANTS SHALL BE COORDINATED WITH EXISTING FOLIAGE AND TREES TO ENSURE THAT MINIMAL DISTURBANCE TAKES PLACE WITH EXISTING VEGETATION

Visual Buffer Plants

SYM	Quant.	Botanical Name	Common Name	Caliper/Cont.	Spacing
Trees					
AB	10	<i>Arborvitae- Thuja</i>	Green Giant Arborvitae	2" (8 feet)	12'

NOTE: DO NOT SCALE DRAWINGS  
DIMENSIONS SUPERCEDE SCALE

THESE DRAWINGS ARE THE SOLE PROPERTY OF P.W. SCOTT ENGINEERING AND ARCHITECTS, P.C. AND WILL NOT BE REPRODUCED BY ANY MEANS AND BE GIVEN TO ANY OTHER TRADES/PERSONS WITHOUT THE EXPRESS PERMISSION OF P.W. SCOTT ENGINEERING AND ARCHITECTS, P.C.



VICINITY MAP  
1" = 500'

Zoning Tabulation  
Zone: RA4

	Required	Proposed
Min. Lot Area:	4.0	4.04
Lot Width (circle ft):	250.0	320.0
Min. Yards		
Front - Street Center Line	75.0	71.3*
Front - Front Lot Line	50.0	54.0
Side Setback:	50.0	78.5
Rear Setback:	50.0	439.14
Max. Building Steel		
Stories	2.5 Stories	2 Story
Feet	35 Feet	28 Feet
Max. Building Coverage:		
House & Planter		
Footprint:2,020 sf	6.0%	1.10%
Treatment Planter: 320 sf (included in coverage)		
Including Deck: 1500 sf		2.0%

Disturbances Proposed		
Wetland:	.062 acre; 2694 sf	planter & well & grading
Wetland -incl plantings	0.162 acre; 7074 sf	planter & well & grading
Upland areas:	0.462 acre, 20,124 sf	driveway & SSDS Area
Upland areas-incl plantings	0.50 acre; 21780 sf	driveway & SSDS Area

	5/30/2023	9/20/2023	11/27/2023
CS	COVER SHEET	✓	✓
SY1	IRSP EROSION CONTROL PLAN	✓	✓
SY2	CONCRETE PLANTER DETAILS	✓	✓
SY3	DRIVEWAY DETAILS	✓	✓
SY4	TREE PRESERVATION PLAN	✓	✓
SP1	SEPTIC PLAN - NEW CONSTRUCTION	✓	No change
D1	DRAINAGE OVERLAYS	✓	No change

PROPERTY IDENTIFICATION

OWNER: ALEX BERNABO  
wDESIGNE, INC.

ADDRESS: 3867 DANBURY ROAD  
BREWSTER, NY 10509

E911 #: 96 POST OFFICE ROAD, LEWISBORO

LEWISBORO T.M. SHEET 25 BLOCK 10812 LOT 3

PROPERTY ADDRESS: 96 POST OFFICE ROAD  
LEWISBORO, NY 10590

NYC DEP WATERSHED: CROSS RIVER BASIN

AREA OF HOUSE PROPOSED: 2600 SF+ 600SF GARAGE  
# BEDROOMS: 2 BEDROOM

P. W. SCOTT		Revisions		Dwg. Title		Seal	Dwg. No.
ENGINEERING & ARCHITECTURE, P.C.		No.	Date	Description	COVER SHEET		
3871 ROUTE 6		A	8/16/23	REVISED PER TE MEMO	Project Title 96 POST OFFICE ROAD LEWISBORO, NY		
BREWSTER, NY 10509 845-278-2110		B	9/20/23	REVISED PER TE MEMO	Proj. No. 21-110		
		C	11/27/23	2 STORY HOUSE OPTION	Drawn by MA/PWS		
		D	12/11/23	RESPONSE BUILDING INSPECT	Date 5/25/23	Scale AS NOTED	

CS





















**From:** [Janet Andersen](#)  
**To:** [Ciorsdan Conran](#)  
**Subject:** Fwd: Fwd: 96 Post Office Road  
**Date:** Friday, November 24, 2023 11:15:53 AM

---

A public comment letter.

Jan

----- Forwarded Message -----

**Subject:** Fwd: 96 Post Office Road

**Date:** Fri, 24 Nov 2023 09:51:22 -0500

**From:** John Wolff <[jawlbac@gmail.com](mailto:jawlbac@gmail.com)>

**To:** Jan Johannessen <[jjohannessen@kelses.com](mailto:jjohannessen@kelses.com)>, Janet Andersen  
<[ja.lewisboro@gmail.com](mailto:ja.lewisboro@gmail.com)>, [kkelly@lewisborogov.com](mailto:kkelly@lewisborogov.com)

FYI, from one of the neighbors.

----- Forwarded message -----

**From:** Peter Aupperle <[peteraupperle@yahoo.com](mailto:peteraupperle@yahoo.com)>

**Date:** Wed, Nov 22, 2023 at 1:08 PM

**Subject:** Re: 96 Post Office Road

**To:** [cac1chair@lewisborogov.com](mailto:cac1chair@lewisborogov.com) <[cac1chair@lewisborogov.com](mailto:cac1chair@lewisborogov.com)>

Hi Mr. Wolff - I hope that your relatives in Buffalo made it safely to your home to celebrate Thanksgiving!

It was a pleasure speaking with you after the Planning Board meeting yesterday evening, and I was hoping that I could ask you a question about the lot next door to us.

We were told by neighbors that have lived here a very long time that the lot repeatedly failed the Perc Test, which is one reason why it was deemed Unbuildable.

The engineer that is representing the Owner has stated that he has documentation that the property recently passed the Perc test, but was that test Witnessed by the appropriate Official?

Please see the photos below taken from the second floor of our home, that show at least two large "ponding areas" on the vacant lot - the property line is right where our lawn ends. This was just from Wednesday's rain.

Also note how these ponding areas are closer to Post Office Road than the stream and wetlands, directly where the proposed new house would be built. You can see the stream and Post Office Road in the photos.

You mentioned that you have a good relationship with the new head of the Building Department. Would it be possible to ask him about the veracity/proof of the Perc test that the engineer performed for the Owner?



Thank you most sincerely in advance. Your support in this matter is greatly appreciated!

Best regards,  
Peter Aupperle  
92 Post Office Road  
914-325-3703
















--

[www.lewisborotreeordinance.com](http://www.lewisborotreeordinance.com)

John

John Wolff

**TOWN OF LEWISBORO**  
**Westchester County, New York**



**Planning Board**  
**79 Bouton Road**  
**South Salem, New York 10590**

**Tel: (914) 763-5592**

**Fax: (914) 875-9148**

**Email: [planning@lewisborogov.com](mailto:planning@lewisborogov.com)**

November 18, 2022

Honorable Tony Goncalves, Supervisor and  
Members of the Town Board  
Town of Lewisboro  
11 Main Street  
South Salem, New York 10590

Re: Application of Smith Ridge Associates  
920 Oakridge Commons -  
"Villas at Vista"  
(P.B. Cal. #12-22 PB & #36-22 WP)

Dear Supervisor Goncalves and Members of the Town Board:

The Planning Board has received a formal application from Smith Ridge Associates, owner of Oakridge Commons, seeking site development plan approval and a wetland permit for proposed modifications to these premises. In sum, the application proposes the conversion of existing commercial space into eight (8) new dwelling units and the construction of six (6) new townhouses on the Oakridge Commons site.

A prior application, which was granted by the Planning Board, authorizes the conversion of commercial space within Oakridge Commons into four (4) new dwelling units. Consequently, the application now before the Planning Board, coupled with this prior approval, entails eighteen (18) new dwellings (comprised of two (2) two-bedroom units and sixteen (16) three-bedroom units). These residential units are located within and are proposed to be serviced by the Oakridge Water District.

The Planning Board will, as it must, evaluate this application under the Town Code and SEQRA. As it undertakes this review process, a threshold question is presented – namely, will the Oakridge Water District extend service connections to these new residential units? This question likewise applies to potential connections to Oakridge Sewer District wastewater services. If an impediment to these service connections exists, the Planning Board and the applicant may, in fact, be embarking upon an empty exercise.



Honorable Tony Goncalves, Supervisor and  
Members of the Town Board  
November 18, 2022  
Page 2

Accordingly, the Planning Board has authorized me, as its Chair, to submit this letter to the Town Board, which is responsible for management, maintenance, operation and repair of Oakridge Water District and Oakridge Sewer District facilities. Specifically, I have been authorized to solicit the Town Board's position as to whether service connections for these units will be provided by the Oakridge Water and Sewer Districts.

In making this inquiry, the Planning Board is mindful of the November 10, 2022 Memorandum prepared by Joseph M. Cermele, P.E., CFM of Kellard Sessions, which addresses the capacity of the Oakridge Water District Treatment Plant. Moreover, the Planning Board has received written comments from Town residents expressing concerns as to the impact of the proposed residential units upon both water capacity and the quality of water supplied by the Oakridge Water District to its consumers.

Again, the Planning Board seeks a response from the Town Board to facilitate its review of this application and avoid a commitment of resources toward a project that, absent these service connections, will not go forward.

On behalf of the Planning Board, I thank the Town Board for its consideration of this request.

Respectfully submitted,

A handwritten signature in black ink that reads "Janet Andersen" followed by two cursive "cc" characters.

Janet Andersen, Chair

cc: Gregory Folchetti, Esq.

**TOWN OF LEWISBORO  
OFFICE OF THE SUPERVISOR**

SUPERVISOR@LEWISBOROGOV.COM  
(914) 763-3151  
WWW.LEWISBOROGOV.COM



TOWN OF LEWISBORO  
11 MAIN STREET  
P.O. BOX 500  
SOUTH SALEM, NEW YORK 10590

**ANTONIO GONÇALVES, SUPERVISOR**

December 1, 2023

Janet Andersen, Chair  
Town of Lewisboro Planning Board  
79 Bouton Road  
South Salem, New York 10590

Re: Application of Smith Ridge Associates  
920 Oakridge Commons – Villas at Vista  
(P.B. Cal. #12-22 PB & #36-22 WP)

Dear Janet,

The Town Board is in receipt of the correspondence from the Planning Board dated 11/18/2022 with respect to the application of Smith Ridge Associates. Any issues or questions which are presented with respect to the capacity of the Oakridge Water District and Sewer District, to either provide the supply of potable water and/or for the treatment of wastewater and generated by the proposed application are strictly within the purview of the Planning Board.

As stated in the Planning Board correspondence dated 11/18/22, the Planning Board is mindful of the November 10, 2022 Memorandum prepared by Joseph M. Cermele of Kellard Sessions where it was concluded that there is adequate capacity in the water treatment facility to serve the project as proposed. Any additional professional guidance desired on these issues may be provided by a consultant engaged by the Planning Board. The Town Board will be taking no action with respect to this matter.

Sincerely,

Tony Goncalves, Town Supervisor

Cc: Gregory Folchetti, Esq  
Members of the Town Board



## TOWN OF RIDGEFIELD Planning and Zoning Commission

RECEIVED BY

December 06, 2023

DEC 11 2023

Town Clerk  
Town of Lewisboro

Janet Donahue, Town Clerk  
Town House, 11 Main Street  
P.O. Box 500  
South Salem, NY 10590

**Re: Referral under Section 8-7d of the Connecticut General Statutes: Application for Amendment to Section 2.2; 3.3 and 3.3-Family Day care and Child Daycare Per PA 23-142**

Dear Ms. Donahue:

Per Section 8-7d of the Connecticut General Statutes, "the zoning commission, planning commission, zoning and planning commission...shall notify the clerk of any adjoining municipality of the pendency of any application, petition, appeal, request or plan concerning any project on any site in which... any portion of the property affected by a decision of such commission, board or agency is within five hundred feet of the boundary of the adjoining municipality". Per Section 8-7d, "such notice shall be made by certified mail, return receipt requested, and shall be mailed *within seven days* of the date of receipt of the application, petition, request or plan."

This letter is to inform you, that on December 05, 2023, the Town of Ridgefield Planning and Zoning Commission (Commission) statutorily received the following Commission initiated amendments **A-23-6- Section 2.2; 3.3 and 3.3-Family Day care and Child Daycare Per PA 23-142**

Please reference the attached material and access to our online permitting system for Amendment Application A-23-6-Section 2.2; 3.3 and 3.3-Family Day care and Child Daycare Per PA 23-142:

<https://ridgefieldct.portal.opengov.com/records/94399>

**Public hearings on the proposed amendment will be held on Tuesday, January 16, 2024, at 7:00 p.m. via hybrid model at the Ridgefield, Town Hall Annex, 66 Prospect St., Ridgefield CT 06877 or registering in advance for the webinar at below link:**

[https://us02web.zoom.us/webinar/register/WN\\_-Wjc5QmJQP2BDuCKxRm4lQ](https://us02web.zoom.us/webinar/register/WN_-Wjc5QmJQP2BDuCKxRm4lQ)

If you need additional information, please contact me at 203-431-2767.

Very truly yours,

Alice Dew  
Director, Planning and Zoning

CERTIFIED MAIL: 7022 1670 0002 8151 1807

cc: Janet Donahue, Town Clerk  
Subject File

66 Prospect Street • Ridgefield, CT 06877  
Phone: (203) 431-2766 • Fax: (203) 431-2737  
[www.ridgefieldct.org](http://www.ridgefieldct.org)

# PROPOSED ZONING REGULATION TEXT AMENDMENT TO PERMIT FAMILY DAY CARE HOMES AND GROUP DAY CARE HOMES AS OF RIGHT IN RESIDENTIAL ZONING DISTRICTS AS REQUIRE BY PUBLIC ACT 23-142

## 2. DEFINITIONS

### **2.2. Defined Terms**

#### **“DAY CARE” RELATED TERMS**

**Day Care** - A program of supplementary care provided to one or more persons on a regularly recurring, but part-time basis, in a place other than the recipient's own dwelling.

**Day Care Center** - As defined in CGS 19a-77, as may be amended:

*(A facility ... which offers or provides a program of supplementary care to more than twelve related or unrelated children outside their own homes on a regular basis.) [2006]*

**Family ~~Child~~ Day Care Home** - As defined in CGS 19a-77, as may be amended:

~~(A facility ... which consists of a private family home caring for not more than six children, including the provider's own children not in school full time ...). [2006]~~ **consists of a private family home providing care for:**

**A.**

- (i) not more than six children, including the provider's own children not in school full time, without the presence or assistance of an assistant or substitute staff member approved by the Commissioner of Early Childhood, pursuant to section 19a-87b of the Connecticut General Statutes, present and assisting the provider; or
- (ii) not more than nine children, including the provider's own children, with the presence and assistance of such approved assistant or substitute staff member; and

**B.** not less than three or more than twelve hours during a twenty-four-hour period and where care is given on a regularly recurring basis, except that care may be provided in excess of twelve hours, but not more than seventy-two consecutive hours, to accommodate a need for extended care or intermittent short-term overnight care. During the regular school year, for providers described in subparagraph (A)(i) of this subdivision, a maximum of three additional children who are in school full time, including such provider's own children, shall be permitted, except that if such provider has more than three children who are such provider's own children and in school full time, all of such provider's own children shall be permitted. During the summer months when regular school is not in session, for providers described in subparagraph (A)(i) of this subdivision, a maximum of three additional children who are otherwise enrolled in school full time shall be permitted if there is such an approved assistant or substitute staff member present and assisting such provider, except that:

- (i) if such provider has more than three such additional children who are such provider's own children, all of such provider's own children shall be permitted; and
- (ii) such approved assistant or substitute staff member shall not be required if all of such additional children are such provider's own children;



- c. A Family Child Care Home shall be licensed by the State and comply with sections 19a-77 to 19a-79a, or sections 19a-82 to 19a-87a, of the Connecticut General Statutes, as amended.

**Group Child Day Care Home** - As defined in CGS 19a-77, as may be amended: ~~(A facility ...which offers or provides a program of supplementary care to not less than seven nor more than twelve related or unrelated children on a regular basis.) [2006]~~ offers or provides a program of supplementary care to:

- A. Not less than seven or more than twelve related or unrelated children on a regular basis; or
- B. that meets the definition of a family child care home except that it operates in a facility other than a private family home.
- C. A Group Child Care Home shall be licensed by the State and comply with sections 19a-77 to 19a-79a, or sections 19a-82 to 19a-87a, of the Connecticut General Statutes, as amended.

## 3. RESIDENTIAL (R) ZONES

---

### 3.2. Principal Uses and Structures

#### B. PERMITTED WITH ZONING PERMIT (ZEO)

- 2. **Group Home** - A group home as defined in these Regulations.
- 3. **Family Child Care Home or Group Child Care Home** located in a residence and licensed by the State of Connecticut.

#### D. PERMITTED BY SPECIAL PERMIT (COMMISSION)

#### 7. **Day Care (Children)** - A day care center provided that:

- a. ~~off-street parking and loading requirements shall comply with the applicable provisions of these regulations; and~~
- b. ~~there shall be safe and adequate provision for boarding and off boarding children from vehicles without hazard to pedestrians and traffic. Such provision shall be made on the lot where the facilities are located and without use of any part of the public street right-of-way for turning; and~~
- c. ~~lot size, building size, setbacks and lot coverage conform to those applicable to the zoning district; and~~
- d. ~~the use shall be located in a building on a lot having such size, shape, landscaping, screening, outdoor play yard space and parking so as to provide for the health and safety of the children using the facility; and~~
- e. ~~no area for active recreation may be located in a front yard or within ten (10) feet of a property line. A sight-obscuring and impermeable wall or fence of at least five (5) feet in height shall be installed along the entire perimeter of all recreation areas. In addition to such walls or fences, an exterior landscape buffer of at least five (5) feet in width shall be planted and maintained along the entire perimeter of any recreation areas. Buffering shall also meet the applicable requirements of these regulations; and~~
- f. ~~if the center is not located in a single use, freestanding building, the center must be adequately sound insulated so as to guard against noise interference with neighboring uses; and~~
- g. ~~the Commission shall specify the limit of the maximum number of people to be cared for and, in determining the maximum number of people permitted at the center, the Commission may consider the number of sessions per day and the impact of the overlap of two (2) or more~~

sessions on the neighborhood; and  
h. ~~all exterior lighting shall comply with the requirements of Section 7.8 of these Regulations.~~

8. **Day Care (Adult)** - A facility providing day-time care for adults provided that it shall comply with the applicable standards of Subsection 3.2.C.7 of these Regulations, unless exempted under the Connecticut General Statutes.

### 3.3. Accessory Uses

#### A. PERMITTED WITHOUT ZONING PERMIT

4. **Family Child Day Care (Children)** - Family **child** day care home accessory to a single-family dwelling.

#### C. PERMITTED BY SPECIAL PERMIT (COMMISSION)

2. **Day Care (Children)** - A group day care home operated in a residential single family dwelling by the resident of the dwelling provided that:

- a. ~~lot size, building setbacks, and lot coverage conform to those applicable to the zoning district; and~~
- b. ~~signage, if any, will conform to the requirements of Section 7.2; and~~
- c. ~~there shall be safe and adequate provision for boarding and offboarding people from vehicles; and~~
- d. ~~a safe on-site vehicular turnaround or separate entrance and exit points must be provided; and~~
- e. ~~no area for active play or play structures may be located in a front yard or within ten (10) feet of a property line. A sight-obscuring and childproof wall or fence of at least five (5) feet in height shall be installed along the entire perimeter of all play areas. In addition to such walls or fences, an exterior landscape buffer of at least five (5) feet in height shall be planted and maintained along the entire perimeter of any play areas; and~~
- f. ~~the site must be landscaped in a manner compatible with adjacent residences. The Commission retains the right to require additional screening and landscaping; and~~
- g. ~~no alterations that will alter the residential character of an existing residential structure used for a group day care home is permitted. Any new or remodeled structure must be designed to be compatible with the residential character of the surrounding neighborhood; and~~
- h. ~~if the proposed group day care home is within one thousand (1,000) feet of another currently operating group day care home, the Commission may approve the application only if it determined that the cumulative effects will not have an adverse impact on the neighborhood due to traffic, noise and safety; and~~
- i. ~~no group day care home shall be located on a shared or common driveway or accessway used by two or more residences or premises including that of the applicant; and~~
- j. ~~the applicant must show that the traffic congestion resulting from the operation of the group day care home will not impair the public health, safety and welfare; and~~
- k. ~~all exterior lighting shall comply with the requirements of Section 7.8 of these Regulations.~~

~~3. **Day Care (Children)** - A day care center accessory to a permitted use provided that it complies with the requirements of Subsection 3.2.C.7 of these Regulations.~~

4. **Day Care (Adult)** - Day care for adults when accessory to a single family dwelling.

~~**5. Day Care (Adult)** – A facility, accessory to a permitted use, providing day-time care for adults provided that it shall comply with the applicable standards of Subsection 3.2.C.7 of these Regulations.~~