

- ASSUMES NO RESPONSIBILITY FOR THE ACCURACY OF THIS INFORMATION. NO FILL WITHIN THE 100-YEAR, ZONE-A
- AVAILABLE NYSDEC ENVIRONEMTNAL RESOURCE MAPS AND GENERALLY FOLLOWS THE BANKS OF THE POND. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR THE ACCURACY OF THIS INFORMATION. HOWEVER, THIS OFFICE FIELD INSEPCTED THE WETLAND BOUNDARY AND IS IN GENERAL AGREEMENT WITH THE LIMITS SHOWN. NO DISTURBANCE TO THE STATE WETLAND IS PROPOSED BY THIS PROJECT. AN ARTICLE 24 - FRESHWATER WETLAND PERMIT SHALL BE
- . ALL CONDITIONS, LOCATIONS, AND DIMENSIONS SHALL BE FIELD VERIFIED AND THE ENGINEER SHALL BE IMMEDIATELY

- . THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE SAFETY AND SECURITY OF HIS EMPLOYEES, SUBCONTRACTORS . THE CONTRACTOR SHALL BE RESPONSIBLE TO PROVIDE 24-HOUR PROTECTION OF HIS MATERIALS AND EQUIPMENT
- SEQUENCES, AND PROCEDURES AND FOR COORDINATING ALL PORTIONS OF THE WORK UNDER THE CONTRACT. 11. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE RESTORATION OF THE EXISTING FEATURES DISTURBED BY THE

- ALL SOIL EROSION AND SEDIMENT CONTROL PRACTICES SHALL BE IN ACCORDANCE WITH THE LATEST EDITION
- 2. ALL SOIL EROSION AND SEDIMENT CONTROL PRACTICES ARE TO BE INSTALLED PRIOR TO THE COMMENCEMENT
- . ANY DEWATERING ACTIVITIES THAT MAY BE NECESSARY FOR SITE DEVELOPMENT WILL NEED TO BE REVIEWED AND APPROVED BY THE TOWN ENGINEER TO ENSURE THAT ADDITIONAL DIRECT OR INDIRECT IMPACTS TO
- . ALL TOPSOIL NOT TO BE USED FOR FINAL GRADING SHALL BE REMOVED FROM THE SITE IMMEDIATELY. ALL TOPSOIL REQUIRED FOR FINAL GRADING AND STORED ON SITE SHALL BE LIMED, FERTILIZED AND SEEDED WITHIN 21 DAYS IN ACCORDANCE WITH THE NEW YORK STATE STANDARDS FOR EROSION AND SEDIMENT
- 5. ANY DISTURBED AREA THAT WILL BE LEFT EXPOSED FOR MORE THAN 21 DAYS, AND NOT SUBJECT TO CONSTRUCTION TRAFFIC SHALL IMMEDIATELY RECEIVE AN APPLICATION OF TEMPORARY SEEDING. MULCH SHALL BE USED IF THE SEASON PREVENTS THE ESTABLISHMENT OF TEMPORARY COVER. DISTURBED AREAS
- 6. ALL AREAS WITHIN 500 FEET OF AN INHABITED DWELLING SHALL BE WETTED AS NECESSARY TO PROVIDE DUST
- RESPONSIBLE FOR ANY ROAD CLEANING THAT MAY BE NECESSARY DURING THE COURSE OF CONSTRUCTION OF



